

THE
RELIGIOUS CEREMONIES
AND
CUSTOMS OF THE PARSEES

By

JIVANJI JAMSHEDJI MODI,

B.A., PH.D., C.I.E.,
FELLOW OF THE UNIVERSITY OF BOMBAY (1887), DIPL.
LITTERIS ET ARTIBUS (SWEDEN, 1889), SHUMS-UL-ULMA
(INDIA, 1893), OFFICIER D'ACADÉMIE (FRANCE, 1898),
OFFICIÉR DE L'INSTRUCTION PUBLIQUE (FRANCE, 1902),
CAMPBELL MEDALLIST, B. B. R. ASIATIC SOCIETY (1918).

2nd Edition.

1937.

JEHANGIR B. KARANI'S SONS
BOOK-SELLERS & PUBLISHERS
"BEHRANJI MANSION"

SIR PHEEROZSHAW MEHTA ROAD, FORT, BOMBAY.

Edited by Joseph H. Peterson, 2011, avesta.org, Kasson, MN.

Updated Mar 28, 2022: Corrected footnote on p. 62.

Feb 26, 2022: Corrected typo p. 257: 'khwâm' should read 'khwân'.

June 12, 2021: Corrected typos, redid artwork, and filled in missing Gujarati, Sanskrit, Persian, Pahlavi, and Arabic passages in appropriate fonts; photo of mah-rui also added.

For search-ability, spelling of Zoroastrian technical terms has been altered to conform with F.M. Kotwal and J. Boyd, *A Guide to the Zoroastrian Religion*, Scholars Press, 1982.

Library of Congress

Cataloging in Publication Data

Modi, Jivanji Jamshedji, Sir,

1854-1933.

The religious ceremonies
and customs of the Parsees.

Includes bibliographical
references.

1. Parsees. 2. Zoroastrianism. 3. Zoroastrians – Rites and
ceremonies. 4. Iran-- Religion. 5. India – Religion. I. Title.

BL1570.M57 2011

ISBN 13: 978-1-xxxxx-xxx-x

TO
THE TRUSTEES — PAST AND PRESENT
OF
THE FUNDS AND PROPERTIES OF THE
PARSEE PANCHÂYET

Whom — and through them the Parsee Community —
I have tried to serve, to the best of my poor abilities,
For a long period of nearly 30 years,
As a Souvenir
Of my long connection with their Board as their Secretary,
And as a Token of Gratitude
For all that they have been pleased to do
to help me in my Duties and to encourage me in my Studies.

JIVANJI JAMSHEDJI MODI.

FOREWORD

Dr. Modi's monumental text has been so valuable to me over the years, that I decided to undertake the job of making an electronic edition, if only for my own use. Especially wanting in the original edition is consistent spelling of the technical terms. I have also incorporated Modi's *corrigenda*, expanded citations when I could find them, and fixed many problems with misplaced footnotes. A table of abbreviations has also been added.

Unfortunately I have undoubtedly introduced my own set of errors; I can only apologize in advance and hope readers will point them out so I can fix them.

J. Peterson, October 2011

ABBREVIATIONS

Av.	Avesta, Avestan
B.B.R.A.S.	Bombay Branch of the Royal Asiatic Society
C.	chapter
Cf.	<i>confer</i>
Fr.	French
Ger.	German
Guj.	Gujarati
Pahl.	Pahlavi
Pers.	Persian
Sans.	Sanskrit
S.B.E.	<i>Sacred Books of the East</i> , ed. by F Max Müller, Oxford, Clarendon Press, 1879-1910.
Sls.	<i>Shayest Ne-Shayest</i>
Vd.	Vendidad
Y.	Yasna
Yt.	Yasht

Contents

FOREWORD.....	i
ABBREVIATIONS.....	ii
PREFACE.....	v
By the Same Author.....	x
PART I. SOCIO-RELIGIOUS CEREMONIES AND CUSTOMS.....	1
CHAPTER I. BIRTH CEREMONIES AND CUSTOMS.....	1
CHAPTER II. MARRIAGE CEREMONIES AND CUSTOMS..	12
CHAPTER III. FUNERAL CEREMONIES AND CUSTOMS...	42
I. Ceremonies that relate to the disposal of the body.....	42
II. Ceremonies that relate to the soul of the deceased.....	61
PART II. PURIFICATORY CEREMONIES, RITES, AND CUSTOMS.....	70
CHAPTER IV. The padyab and the nahn.....	70
I. Padyab, the first form of purification.....	73
II. Nahn, the second form of purification.....	76
CHAPTER V. The Barashnom and the Riman.....	82
IV. Riman, The Fourth Form of Purification.....	123
CHAPTER VI. PURIFACTORY PROCESSES AND CUSTOMS IN DAILY LIFE.....	133
PART III. INITIATION CEREMONIES AND CUSTOMS.....	142
CHAPTER VII. (I) THE NAOJOTE [NAVJOTE]. THE INITIATION OF A ZOROASTRIAN CHILD INTO THE FOLD.	142
CHAPTER VIII. (II) THE NAWAR AND THE MARTAB.....	157
2. THE MARTAB.....	165
PART IV. THE CONSECRATION CEREMONIES.....	167
CHAPTER IX. (I) CONSECRATION OF THE SACRED FIRES AND THE FIRE-TEMPLES.....	167
(B) Consecration of the Sacred Fire of the second grade, the Atash Adaran.....	189
(c) Consecration of the Sacred Fire of the Third Grade: The Atash Dadgah.....	192

CHAPTER X. (II) CONSECRATION OF THE TOWERS OF SILENCE.....	193
CHAPTER XI. (III) CONSECRATION OF THE ÂLÂT OR RELIGIOUS REQUISITES.....	202
PART V. THE LITURGICAL CEREMONIES.....	208
CHAPTER XII. THE INNER LITURGICAL CEREMONIES. (I) THE YASNA: ITS LITURGICAL APPARATUS.....	208
I. THE PARAGNA.....	212
II. THE YASNA PROPER.....	255
CHAPTER XIII. (II) THE VISPERAD CEREMONY.....	262
CHAPTER XIV. (III) THE VENDIDAD CEREMONY.....	277
CHAPTER XV. (IV) The Baj Ceremony.....	279
CHAPTER XVI. THE OUTER LITURGICAL SERVICES. (I) THE AFRINAGAN CEREMONY.....	297
CHAPTER XVII. (II) THE FAROKHSHI.....	321
CHAPTER XVIII. (III) THE SATÛM.....	335
CHAPTER XIX. COMBINED GROUPS OF LITURGICAL CEREMONIES.....	338
1. HAMÂYASHT OR HOMÂSHT.....	338
2. THE GETI-KHARÎD.....	339
3. SAROSH.....	340
4. ZINDA-RAWAN.....	348
5. THE NIRANGDIN.....	349
6. THE GAHAMBAR CEREMONY.....	349
7. JASHAN.....	357
8. FRAWARDIGAN OR MUKHTAD CEREMONIES.....	365
IX. FIRESHTE [FARESTÂ].....	376

PREFACE

This book has grown out of the work of study, undertaken for the Dictionary of Religion and Ethics published by Dr. Hastings. In his letter dated 26th December 1905, Dr. Hastings, invited me to be a contributor to his Dictionary on the subject of Parsee Religious Ceremonies and customs. A complete compendium of all the Religious Ceremonies and Customs of the Parsees was wanting. So, on receiving the above invitation, I proposed to go thoroughly into the study of whole subject, and this book is the result. Here and there, I have re-cast the subjects as originally written.

My name was kindly submitted to Dr. Hastings by the late Dr. Mills, Professor of Iranian Languages at the University of Oxford. So, Dr. Hastings, at his suggestion, asked me to give “the closest possible description” of the ceremonies and customs. Dr. Mills also had written to me direct, to “be absolutely exhaustive as to details.” Ere this, I had found, that a detailed description of the ceremonies and customs was wanted by scholars, especially foreign, as it would help them their elucidation of some Avesta and Pahlavi texts. For I found that my paper on the Funeral Ceremonies of the Parsees, read before the Anthropological Society of Bombay, had been of some use to the late Prof. James Darmesteter in his translation of the *Vendidad*.¹ Prof. A. V. W. Jackson, when he was in Bombay in 1901, had drawn my attention to the want of a detailed description of religious ceremonies, especially the Purification Ceremonies of the barashnom. Then, in a letter dated 8th March, he wrote: “May I not urge you to write a detailed monograph of the barashnom I spoke to you on the subject that morning when I was at Colaba? Such a treatise giving an the Ceremonies would be important.” I know, that the want of such a book was felt, at times, in Courts of Justice, when there were cases [vi] in the matter of the Wills of Testators who directed certain religious ceremonies to be performed, and when there was the question of the proper significations of the ceremonies. I knew of a case, in which the learned Judge had to refer to Dr. Haug’s *Essays on the Parsees*² for the explanation of certain Ceremonies. In another case, the present Parsee Advocate General studied with some interest, for an explanation of some ceremonies, my rough copy of the manuscript sent to Dr. Hastings. So, bearing all the above suggestions and matters in mind, I have tried to be somewhat exhaustive, and hope,

1 In his Appendix A, to the eighth chapter of the *Vendidad*, entitled “Cérémonies fun-èbres chez les Parses,” he thus refers to it: “Nous grand usage dans cet exposé d’une excellente étude de M. Jivanji Modi” (*Le Zend Avesta*, Vol. II, p. 146 n. 1.)

2 Haug, Martin. *Essays on the Sacred Language, Writings, and Religion of Parsees*. Bombay: Printed at the “Bombay Gazette” Press, 1862.

that the book will be of some use to students of Comparative Religion. I am glad to observe, from the preface of *The Comparative Study of Religions*¹ by Prof. Widgery of the University of Cambridge, that the advanced proof pages of this book, of which he speaks as “an exhaustive treatise on Social and Religions Customs of the Parsees,” have been of some use to the author. Students of Comparative Religion may, in the matter of the religious ceremonies and customs of the Parsees, look to this book as a kind of a Dictionary of Parseeism. The exhaustive Index will help them to use it as such. I beg to tender my best thanks to my friend, Mr. Bomanji Nusserwanji Dhabhar M. A., for its preparation.

I think that, irrespective of the question of the want of such a book by the students of Religion and Anthropology, it will be found of some use to my community in general. The times are rapidly changing. The “new” has been springing rapidly upon the “old.” As often said, the heresy of to-day becomes the orthodoxy of tomorrow; the liberalism of this year, the conservatism of the next. The reader will find that many a ceremony, ritual, or custom has been spoken of as having become obsolete, or as being more honoured in the breach than in the observance. Many more will be obsolete in the course of a few years. Customs are often as despotic as fashions, [vii] but they also change as fashions. So, this work will, it is hoped, serve, to a certain extent, as a record of what was once, and what is now prevalent.

Some of the religious ceremonies and customs are good in themselves from a sanitary or hygienic point of view. As Prof. Max Müller says: “There is a reason at the bottom of everything, however, it seems unreasonable to us, in the customs and laws of the ancient world.”² What is said of the old symbolism stands good, to a certain extent, for some old customs: “The Symbolism of today preserves the serious belief of yesterday and what, in an age more or less distant, was a vital motive, inspiring an appropriate course of conduct, *survives in the conduct* it has inspired, long after it has itself ceased to be active and powerful.” But, we find that, at times, “too much of even a good thing” spoils that thing. This is so in the case of some religious ceremonies and customs. We find that, very particularly, in the case of some purificatory ceremonies, for example, the barashnom. The original good simple ideas of purity, *viz.*, freedom from contact with the impure, and isolation, if infection or impurity is caught or is believed to have been caught, are, at times, carried to tiresome

1 Widgery, Alban G. *The Comparative Study of Religions; A Systematic Survey*. Baroda: Luhana Mitra Steam Printing Press, 1922, p. ix.

2 Müller, F. Max. *Contributions to the Science of Mythology*. London: Longmans, Green, and Co, 1897.

extremes. No wonder, if they were so carried to extremes in olden times, when we see, that cases of that kind happen even in modern times, under an alarm or panic of a sudden epidemic, as that of Plague in Bombay in 1896-97. However, such extremes tend to obscure the original good object.

In the rituals of purification, especially in that of the barashnom, as prescribed in the *Vendidad*, and as carried on later, we find such an extreme, ending in some tiresome intricacies. It seems that, at the end of the ninth century, there was, among the Zoroastrians of Persia itself, an attempt of a kind of revolt against the multiplicity or the intricacy of the ceremonies, and the standard of that revolt was raised by a prelate, Zadspram, the high priest of Sirkan. But the revolt was suppressed by the higher ecclesiastical authority at Pars and Kerman. We find an account of this controversy [viii] in the Pahlavi *Epistles of Manuscheher*;¹ It seems, that long before this, even in the times of the Pahlavi commentators, there arose some controversies about the intricacies and the details of the ritual of the barashnom.

Goethe, that great German Hafiz, admires the view of the Purity of Elements (Fire, air, earth, and water), as observed by the ancient Persians. He admires, what he calls, "Würde der Sämmtlichen Elemente" i.e., "The Dignity of Elements." He has attached to his *Parsi-Nameh or Buch des Parsen*, which forms the eleventh book of his *West-Östliche Divan*, some "Notes and Discussions" (Noten und Abhandlungen). Therein, he says: "Their religion is clearly based on the dignity of all elements, as manifesting God's existence and power. Hence the sacred dread to pollute water, the air, earth. Such respect for all natural forces that surround man leads to every civic virtue. Attention, cleanliness, application are stimulated and fostered."² Notwithstanding this admiration of the Dignity of the Elements, he runs down the later, what he calls, "endless tedium" of consecration and purification.

Some of the intricate tedium of purification carried to an extreme from the original reasonable thoughts of sanitation and purification, has now passed off and is passing away. But as it often happens, in the rush or fashion of doing away with what was tedious or unnecessary and what formed the excrescences, some other customs, which are good from sanitary and other points of view of public utility, also are done away with. Even M. Renan of France, who was taken to be a

1 *Vide* the interesting Introduction of Mr. Bomanji N. Dhabhar in his *Nâmakîhâ-i Mânûshchîhar*. *Vide* West's Introduction S. B. E. Vol. XVIII.

2 *Vide* my Paper on "Goethe's *Parsi-nameh or Buch des Parsen*", in the *Journal of the B. B. R. A. Society*, Vol. XXIV, pp. 66-95. *Vide* my *Asiatic Papers*, Part II, pp. 119-148.

heretic for his liberal thoughts and views, and who, therefore, cannot be suspected of any kind of undue conservatism, and who, though looking hopefully to the future, looked with respect to the past,¹ looked with distrust at the attempt to [ix] throw off good with the bad. He said: "I fear that the work of the twentieth century will consist in taking out of the waste paper basket a multitude of the excellent ideas which the nineteenth century has heedlessly thrown into it." The Parsees of the present day, are, I am afraid, doing something of that kind. This book, which records all the religious ceremonies and customs of the Parsees, will, at least, show to future generations, what was the good that was heedlessly thrown off, and what was the bad that was properly thrown off.

In connection with this view of preserving what is good in the customs of the old, one may appropriately quote from Mr. Carpenter's *Pagan and Christian Creeds* (p. 266) the following passage: "Numerous instances might of course be adduced of how a Church, aspiring to be a real Church of Humanity, might adopt and re-create the rituals of the past in the light of a modern inspiration. Indeed, the difficult would be to limit the process; for every ancient ritual, we can now see, has had a meaning and a message, and it would be a real joy to disentangle these and to expose the profound solidarity of human thought and aspiration from the very dawn of civilization down to the present day. Nor would it be necessary to imagine any Act of Uniformity or dead level of ceremonial in the matter. Different groups might concentrate on different phases of religious thought and practice. The only necessity would be that they should approach the subject with a real love of Humanity in their hearts and a real desire to come into touch with the deep inner life and mystic growing pains of the souls of men and women in all ages."

In describing some of my subjects I have tried to follow a suggestion of Dr. Hastings. He had asked the subjects to be treated, both from the Iranian or the ancient Zoroastrian and the Parsee or the modern Zoroastrian point of view. I have tried to show, here and there, how the modern practice and view differ from the ancient, referred to in the Avesta, Pahlavi, Pazand, and Persian books. I have generally tried to look at various subjects from a student's point of view and have merely described them as required. But in some places, [x] where possible, I have tried to explain old beliefs and customs and to trace their origin.

Some of the subjects treated in the volume have been treated by me in various papers,² read before the Anthropological Society of

1 He said: "J'aime le passé mais, je porte envie a l'avenir."

2 These papers are the following. —

Bombay, and published in some form or another in the Journal of the Society. So I have tried to treat them, here and there, from the point of view of Cultural anthropology, and have given points of similarity with the beliefs and customs of other people.

I have treated the whole subject under the following principal heads: —

I. The Socio-Religious Ceremonies, which have been treated under the heads of (A) Birth, (B) Marriage and (C) Death Ceremonies.

II. The Purification Ceremonies, which are treated under the sub-heads of (a) Nahn, (b) Riman, and (c) the Barashnom, (d) with an additional chapter on the purification of articles supposed to have been contaminated.

III. The Initiation Ceremonies, which have been treated under the sub-headings of (a) Navjote or the Initiation of a [xi] child into the fold and (b) Nawar and Martab, which are the two grades of Initiation into priesthood.

IV. The Consecration Ceremonies, which treat of (a) the consecration of Fire-temples, (b) of the Towers of Silence, and (c) of Alat, or religious requisites.

V. The Liturgical ceremonies, which are treated under two principal heads: (A) The first head speaks of the Inner Liturgical services and treats of (a) the Yasna, (b) the Visperad, (c) the Vendidad, and (d) the Baj. (B) The second head speaks of the Outer Liturgical ceremonies of (a) the Afrinagan, (b) the Farokhshi, and (c) the Satum. An additional chapter treats of several ceremonies which are groups of more than one ceremony.

I beg to thank Rev. Hastings for the courtesy to let me use my articles in his Dictionary for the purpose of some of the subjects of this book.

FATEHMA LODGE, 1 WOODHOUSE ROAD,
COLABA, Bombay. 5th November 1922.

-
1. Birth Customs and Ceremonies (Journal of the Anthropological Society of Bombay. Vol. IX, pp. 568-82).
 2. Marriage Customs and Ceremonies (Vol. V, pp. 242-82).
 3. Funeral Ceremonies (Vol. II, pp. 405-44).
 4. Purificatory Ceremonies. The Padyab and the Nân (Vol. XI, pp. 162-185.)
 5. Purificatory Ceremonies. The Barashnom and Riman (Vol. XI, pp. 224-289).
 6. Purificatory Ceremonies. Purificatory Processes in Daily life. (Vol. XI, pp. 364-375).
 7. Initiation Ceremonies (Vol. XI, pp. 454-484).
 8. Consecration Ceremonies (Vol. XI, pp. 496-544).
 9. The Inner Liturgical Ceremonies. The Yasna (Vol. XI, pp. 996-1055).
 10. The Outer Liturgical Ceremonies (Vol. XII, pp. 39-91).

By the Same Author.

- The Religious System of the Parsees.
Catechism of the Zoroastrian Religion.
The Naôjôte Ceremony of the Parsees.
The Marriage Ceremony of the Parsees.
Marriage Customs among the Parsees, their Comparison with similar Customs of other Nations.
The Funeral Ceremonies of the Parsees.
The Parsees at the Court of Akbar and Dastur Meherji Rana.
Âiyâdgâr-î Zarîrân, Shatrôîha-î-Aîrân, va Afdya va Sahîgîya-î-Sistâ, i.e., The Memoir of Zarir, Cities of Iran, and the Wonders and Marvels of Seistân (Pahlavi Translations, Part I. Texts in Gujarati character, with English and Gujarati translations and notes) .
Jâmâspî (Pahlavi Translations, Part III. Pahlavi, Pazend and Persian texts with English and Gujarati translation and notes).
Wine among the Ancient Persians.
A Few Events in the Early History of the Parsees and their Dates.
A Glimpse into the Work of the Bombay Branch Royal Asiatic Society during the last 100 years from a Parsee point of view.
Asiatic Papers. Part I.
Asiatic Papers. Part II.
Asiatic Papers. Part III.
Anthropological Papers. Part I.
Anthropological Papers. Part II.
Anthropological Papers. Part III.
Masonic Papers.
Dante Papers. [xxv]
Memorial Papers.
Anquetil Du Perron and Dastur Darab.
Moral Extracts from Zoroastrian Books.
Education among the Ancient Iranians.
Impressions d'un Parsi sur la Ville de Paris.

La Visite d'un Parsi á la Ville de Constantinople.

La Ceremonie du Naojote parmi les Parsis.

WORKS EDITED BY THE SAME AUTHOR.

K. R. Cama Memorial Volume.

The Pahlavi Mâdigân-i Hazâr Dâdistân.

K. R. Cama Masonic Jubilee Volume.

Spiegel Memorial Volume.

Sir J. J. Madressa Jubilee Volume.

PART I. SOCIO-RELIGIOUS CEREMONIES AND CUSTOMS.

CHAPTER I. BIRTH CEREMONIES AND CUSTOMS.

The ceremonies and customs, that fall under the head of “Socio-Religious Ceremonies and Customs,” may be subdivided, according to the three principal events of man’s life, — birth, marriage, and death — under the following heads:-

- I.- Birth Ceremonies and Customs.
- II.- Marriage Ceremonies and Customs.
- III.- Funeral Ceremonies and Customs.

I.— Birth Ceremonies and Customs.

The birth of a child is a very auspicious event in a Parsee house. It was so also in ancient Persia. According to the *Vendidad*,¹ Ahura Mazda says:- “I prefer a person with children (*puthrânê*) to one without children (*aputhrâi*).” Even the very ground, where lives a man with his children, is described as feeling happy.² Cultivation and a good supply of food to people are recommended, because they make mankind healthy and able to produce a healthy progeny.³ To be the father of good children was a blessing from the Yazatas, like Tishtrya,⁴ Mithra,⁵ Haoma,⁶ and Atar,⁷ and from the Fravashis.⁸ To be childless, was a curse from the Yazatas.⁹ Domestic animals, [2] when ill-fed and ill-treated, cursed their masters, that they may be childless.¹⁰ Childlessness was something like a punishment from heaven.¹¹ Kingly splendour (*khwarrâh*)¹² was associated with those who were blessed

1 Vd. 4:47.

2 Vd. 3:2.

3 Vd. 3:33.

4 Yt. 8:15, Tir.

5 Yt. 10:65, Mihr.

6 Y. 11:4, 7, 10, 13, 22 (Hom Yasht).

7 Y. 62:10, Atash Niyayesh; Vd. 18:27.

8 Yt. 10:3, Mihr; Yt. 13:134.

9 Hom Yasht, Y. 11:3. Cf. The blessings and the curse of Cambyses (Herodotus III, 65). Cf. also those of Darius (Behistun Inscriptions, IV, 10, 11).

10 Y. 11:1-2.

11 Y. 11:3; Yt. 10:38, 108, 110, Mihr.

12 Av. *Kavaêm Kharêno*.

with children.¹ According to the *Shayest Na-Shayest*, one of the advantages of having children was “that the duty and good works which a son performs are as much the father’s as though they had been done by his own hand.”²

A Zoroastrian woman often prayed for a good, healthy child.³ A Zoroastrian man and woman prayed before their sacred fire for a good, virtuous child.⁴ A woman without a child felt as sorry as a fertile piece of land that is not cultivated.⁵ She prayed for a husband who could make her a mother of children.⁶

Among the Achaemenians, a wife who gave birth to many children was a favourite with her husband, who did not like to displease her in any way.⁷ Children being the choicest gift of God, their lives were, as it were, pledged by parents for the solemn performance of an act.⁸ We read in Herodotus:⁹ “Next to prowess in arms, it is regarded as the greatest proof of manly excellence to be the father of many sons. Every year, the king sends rich gifts to the man, who can show the largest number: for they hold that number is strength.” Strabo also says a similar thing.¹⁰ We learn from the writings of the Christian Martyrs of Persia, that the ancient Persians, did not, for the above reasons, like the prohibition against marriage among the Christians in the case of holy young Christian girls.

Pregnancy.

In the Avesta itself, we find no references to any ceremony or rite during the state of pregnancy. The only allusion we find is this:- Women on finding themselves *enceinte* prayed before Ardwisura for an easy delivery,¹¹ [3] and then for a copious supply of milk at their breast for their children.¹² The allusion to these prayers suggests, that there may be some formal ceremonies accompanying those prayers,

1 Yt. 19:75, Zamyad.

2 Chap. 10:22; 12:15. S.B.E. Vol. V, pp. 325, 345.

3 Y. 9:22.

4 Atash Niyayesh, Y. 57:5.

5 Vd. 3:24.

6 Yt. 5:87, Aban.

7 Herodotus, IX, 111.

8 Herodotus, IX, 10.

9 *Ibid* I, 136. Rawlinson’s Translation, Vol. I, p. 277.

10 Bk. XV, 11.

11 Yt. 5:87, Aban.

12 Ardwisur Niyayesh, 3.

but we do not know what they were.

Coming to later Pahlavi and Persian books, we find, that the *Shayest ne-Shayest* directs, that, when it is known that a lady of the family has become pregnant, a fire may be maintained most carefully in the house.¹ The *Saddar* also gives this direction.² We have the remnant of this injunction in the present custom of some of the modern Parsees, who on the occasion of the completion of the fifth and seventh months of pregnancy, light a lamp of clarified butter in their houses. The reason, assigned for this in the Pahlavi and Persian books, is that the fire, so kindled in the house, keeps out *daevas*, i.e., evil influences from the house. Again, a fire or a lamp is even now taken to be symbolical of the continuation of a line of offspring. For example, it is not rare to hear, even now, words like these "*Tamâro cherâg roshan rahê*" i.e., "May your lamp be always burning." This benediction is meant to say: "May your son live long, and may your line of descent continue." The ancient Iranians believed that there were many chances of the children to be born being males, if the males were stronger than the females at the time of conception. (*Bundahishn*, Chap. 16).³

According to the *Avesta*, in the state of pregnancy, a woman is to be looked after very carefully. It is wrong for the husband to have sexual intercourse with her in her advanced state of pregnancy, which, according to the *Rivayats*, commences with the fifth month.⁴ She is to abstain from coming into contact with any dead or decomposing matter, even with a thing like one's tooth-pick which may contain germs of one's disease.⁵ [4]

The fifth and the seventh months of pregnancy, observed as days of rejoicing.

During pregnancy, the modern Parsees have no religious ceremonies or rites. On the completion of the fifth month of pregnancy one day is celebrated and known as "*Panch mâsiûn*," i.e., the day of the fifth month. Similarly, a day is observed on the completion of the seventh month, and is known as *Agharni*. These days are observed as auspicious days of rejoicing only in the case of the first pregnancy. They are observed not in accordance with any

1 Chap. 10:4; 12:11. S.B.E. Vol. V, pp. 316, 343.

2 Chap. 16:1. S.B.E. Vol. XXIV, p. 277.

3 *Vide my Anthropological Papers*, Part II, p. 207.

4 Four months ten days. *Vide* Anquetil Du Perron, *Zend Avesta*, Vol. II, p. 563. (Paris, N. M. Tilliard, 1771.)

5 *Shayest ne-Shayest*, Chap. 10:20; 12:13. (S.B.E., Vol. V, pp. 323, 344); *Saddar*, 17:2 (S.B.E., Vol. XXIV, p. 278).

religious injunction or with religious ceremonies or rites. The expectancy of a child being a joyful event as said above, these days — especially some day after the completion of the seventh month — are observed as joyous occasions, when the lady who is *enceinte* is presented with suits of clothes by her parents, relatives, and friends and especially by the family of her husband. The husband, in turn, is presented with a suit of clothes by the wife's family. Sweets are sent out as presents by the husband's family to the bride's house and to near relations and friends. In these sweets, one prepared in the form of a cocoanut,¹ has a prominent place. A cocoanut typifies a man's head² and so it is a symbol of fecundity. Some of the customs observed on these occasions are more Indian in their origin and signification than originally Persian or Zoroastrian.

Place of delivery, and its temporary consecration.

In the case of the first delivery, it generally takes place in the house of the wife's parents. A room or a part of a room, generally on the down-floor, is prepared and set apart for the purpose. As the *Vendidad*³ says, the place for delivery must be very clean, [5] dry and least-frequented by others. It appears, that in former times, such places were specially provided in Parsee houses on the down-floors. Parsee houses in those times had generally spacious down-floors that were used for all purposes. The upper floors were low, and were rather like lofts. So, the down-floors provided proper places for delivery, as enjoined in the *Vendidad*. But, as, with changed circumstances, Parsee houses of today are not what they were before, and as, at present, in storied houses in big towns, the down-floors are generally the worst part of the houses, places of delivery at the down-floor are now-a-days properly condemned as unhealthy. In the case of a house or a place where no delivery has taken place before, religious-minded persons generally take care that a religious ceremony may be performed there before the delivery. In other words, they get the place consecrated. A priest or two say and perform the Afrinagan prayer

1 Among the Rajputs of India, the acceptance of a cocoanut is a symbol of the acceptance of a proposal for marriage (*vide* Tod's *Annals of Rājasthān*, edited by C. H. Payne, p. 25). [i.e. James Tod, *Annals and antiquities of Rajast'han, or the central and western Rajpoot states of India* (London, Smith, Elder and co. [etc.] 1829-32.)

2 The following story connects the cocoanut with a man's head. An astrologer once said to a king that, whatever was sown or planted on such and such a coming auspicious day, would grow well. The king said: "Suppose somebody sows a man's head on a stony ground, will that also grow up into a luxuriant tree?" "Yes," said the astrologer. The king, thereupon, cut off the head of the astrologer and sowed it in a stony ground. The cocoanut palm grew out of it. (*Journal of the Ceylon Asiatic Society*. January 1891.)

3 Vd. 5:46.

and ceremony over the place. At times, even the Baj prayer is recited. It seems that one of the lost *nasks* (books), the *Husparam*, had special chapters on the subject of parturition.¹

A lamp lighted on the birth of a child.

On the birth of a child, a lamp is lighted and kept burning, for at least three days, in the room where the lady is confined. The *Saddar* says: "When the child becomes separate from the mother it is necessary to burn a lamp for three nights and days — if they burn a fire it would be better — so that the demons and fiends may not be able to do any damage and harm; because when a child is born, it is exceedingly delicate for those three days."² Some people keep the lamp burning for ten days and some for forty days, the latter number being generally observed as the period of confinement. [6]

Period of confinement on delivery, 40 days.

On delivery, the mother is enjoined to remain apart from others. She is not to come into contact with fire, water, and other furniture of the house.³ In the case of those that give birth to still-born children, it is enjoined in the *Vendidad*,⁴ that they must thus remain apart for 12 days. This period has been latterly extended, as described in the later Pahlavi and Persian books, to forty days in all cases of delivery. Now-a-days, a Parsee lady has generally forty days of confinement after delivery. The *Saddar* says: "During forty days it is not proper that they should leave the child alone; and it is also not proper that the mother of the infant should put her foot over a threshold in the dwelling (i.e., leave the house) or cast her eyes upon a hill, or it is bad for her menstruation."⁵

Some families, following the Hindu custom, observe the fifth day after birth, known as *pachory* (i.e., the fifth day), and the tenth day, known as *dasori* (i.e., the tenth day), as gala days, but these days have no religious signification.

Perfect isolation and purification.

During the above forty days, the lady is in a state of isolation. She

1 *Denkard*, Bk. VIII, Ch. 31 and 35:9, S.B.E., Vol. XXXVII, pp. 100 and 109. Dastur Darab Peshotan [Sanjana]'s *Denkard*, Vol. XVI, pp. 20 and 28. The second of the above two chapters, refers to various subject, of obstetrics.

2 Chap. 16:2; S.B.E. Vol. XXIV, p. 277; *vide* also the Persian *Farziât-nameh* of Dastur Dârâb Pâhlan; *vide* the Gujarat *Farziât-nameh* (1843), p. 5.

3 Vd. 5:45-49.

4 Vd. 5:55-56.

5 Chap. 16:4, S.B.E., Vol. XXIV, p. 277.

is not to come into contact with anybody and with any part of the ordinary furniture of the house, especially wooden furniture and linen articles. Her food is to be served to her on her plate by others. Those who have to come into contact with her have to bathe before they mix with others. Even the medical attendants had to do so, but, now-a-days, this sanitary rule is more honoured in the breach than in its observance. The original injunction may, among some other reasons, have been intended to observe “purity” in order to prevent the spread of the diseases to which women in this state are subject.¹ [7]

At the end of forty days, which is the period of confinement, the lady has to purify herself by a bath before ordinarily mixing with others. At first she takes an ordinary bath and then goes through what is called ‘nân,’ a contraction of the Sanskrit word “snân” which is a sacred bath.² A priest, generally the family priest, administers that bath with consecrated water.

All the bedding and clothes of the woman, used during the forty days of her confinement after delivery, are rejected from ordinary use. They are enjoined to be destroyed, lest they carry germs of disease among others. But, now-a-days, that injunction is not strictly followed. They are given away to sweepers.

The first drink after birth.

Formerly, a mother in child-birth first drank a few drops of the sacred Haoma-juice, which was squeezed and consecrated in a fire-temple. The Persian *Farziât-nameh* of Dastur Darab Pâhlan says, that a new-born child should be made to drink a few drops of this juice. If the consecrated Haoma-juice (*para-Haoma*) may not be had, one may pound at home a few Haoma twigs and a few leaves of the pomegranate tree (*urvarâm*) in water with the recital of an *Ahunwar*

1 *Vide* the chapter on “Maternity and its Perils” in Mr. Havelock Ellis’s *The Nationalization of Health* (1892), pp. 123-143. It says that in England and Wales, where 4,500 women die every year in child-births “about 70 percent of this mortality is due to puerperal fever” and that “almost the whole of this mortality might be avoided.” It is the careless medical practitioners and midwives, that are responsible for this mortality, because they do not take sanitary care, and therefore carry germs from one woman in confinement to another. The midwifery writers of old said to their disciples: “Thine is a high and holy calling; see that thou exercise it with purity.” In the enjoined isolation of the Parsee women during their confinement, the original intention seems to be that of observing *purity*. Some of the later Pazand and Persian writers have not properly understood the original good object of the early writers, and so, have carried the rigour of isolation too far. But anyhow, the origins injunction of isolation is intended for the purity referred to by old midwifery writers. *Vide* Dastur Jamaspji’s *Sad-dar* (સદદર યજ્ઞેરે તત્ત્રીણ), pp. 142-46, for some further medical opinion.

2 *Vide* below, Chap. IV, Purificatory Ceremonies.

and give the juice for the first drink. In the Hom Yasht,¹ Haoma is said to give fine healthy children to women. Haoma was emblematical of immortality. Anquetil Du Perron² refers to this religious custom as prevalent in his time. But now-a-days this custom is rarely observed, and in place of the Haoma-juice, a sweet drink made of molasses or [8] sugar is given to the child as a first auspicious drink. The *Farziât-nâmeh* asks the mother to feed the child with her own milk for 18 months if the child be male, and for 15 if it be a female.

Naming the child.

Herodotus³ refers to the custom of naming the child among the ancient Persians. We infer from what he says, that the parents waited for some time after birth, and then, watching the physical and mental characteristics of the child, gave them such names as indicated their characteristics. In the case of modern Parsees, many name the child after an immediate deceased ancestor. A Parsee name is made up of three names. The first is his own personal name. The second is his father's name and the third is his surname or family name. Now, it is the first of these three, that is the proper name of the child; and in the case of that name, many prefer to call a child by an immediate ancestor's name. Suppose a person named Jivanji had his father named Jamshedji, and his mother named Âwânbâi. Then, on the birth of a child, if it is a male child and if his own father (Jamshedji) was dead, he would prefer to name it Jamshedji. If it were a female child, he would like to name it Âwânbâi after his deceased mother. Some resort to a so-called astrologer and name the child as advised by him.

This process of naming the child has one particular religious significance, and it is this: In all religious ceremonies, during life or after death, a person's name is recited as he or she is named at the time of his or her birth: This name is called *Janam-nâm* or birth-name. In his or her Naojote [navjote], i.e., sacred shirt and thread ceremony, marriage ceremony, or any other ceremony enjoined by him or her during lifetime (*Zindeh-ravân*), the birth-name is recited together with the father's name. In all the ceremonies after death (*Anôsheh-ravân*), the name is similarly recited. In the case of a female, her personal name is recited together with that of her father as long as she is not betrothed. But after betrothal, her name is recited together with that of her husband.⁴ As a lady's name is recited with her husband's [9] in all ceremonies after betrothal, the ceremony of

1 Yasna 9, p. 22. *Vide* my paper on "Haoma in the Avesta" for the health-giving properties attributed to the plant. *Vide* my *Asiatic Papers*, Part I, pp. 225-43. *Journal of the Anthropological Society of Bombay*, Vol. VII, pp. 203-21.

2 *Zend Avesta*, II, p. 564.

3 Bk. I, 139.

betrothal is known as “*Nâmzad shudan*” in Persian, meaning “to be named,” or *nâm pâdvun* in Gujarati meaning “to give a name.”

Herodotus says of the old Achaemenian times, that “their names, which are expressive of some bodily or mental excellence, all end with the same letter.”¹ Looking to the names as given in the Avesta, we find that they mostly end in ‘a’. The same or similar names when given by Greek writers end in ‘s’. This can be easily seen from a list of Iranian names given by Rawlinson² with their corresponding forms in Greek writings.

We find from stray allusions here and there in the Pahlavi and Persian writings, that, at times, children were named after, or in memory of, some particular events at the time of their birth. For example, names like Rustam and Kobâd are associated with some particular events at the time of their birth. Herodotus³ speaks of Persian names as expressive of their physical form. Thus we read in the *Khushro Shirin* of Nizami that the father of Khusro Parviz named the child Khusru, because he saw him “king-like” (*Khusravi*) in appearance.

Most of the modern Parsee names end in *ji* (જી, Avesta “ji,” Persian *Zîstan* “to live”). In the recital of prayers in honour of the dead, this suffix “ji” is generally dropped, especially among the priestly class. It is taken to be a suffix-appellation of only the living. Modern Parsee names can be traced to certain few sources. For the males they are the following:- (1) Some of them are derived from the names of some of their Yazatas or angels. They are Hormusji (from Avesta Ahura Mazda, Hormuzd, the first Yazata), Bahamanji (Avesta Vohumana, Persian Bahman, the 2nd Yazata), Adarji (Adar, the 9th), Khorshedji (Avesta Hvare Khshaeta, the 11th), Meherji (Avesta Mithra, Persian Meher, the 16th), Behramji (Avesta Verethragna, Pahlavi Varahram [Varharam], Persian Behrâm, the 19th), Din (Avesta Daena, the 24th), and Homji (Avesta Haoma the 32nd in the list of the Siroza). (2) Some names are derived from some [10] precious jewels; for example, Dhanji, Hirji, Manockji, Ratanji.⁴ (3) Some names are adopted from those of their Iranian ancestors, as mentioned in the *Shah-nameh* and in other Iranian writings; for example, Ardeshir, Burjorji, Bezonji, Dârâshâh, Dârâbji (Dorabji), Edalji (Adalji), Erachji, Fardunji

4 Among the present Zoroastrians of Persia and those of the Kadmi sect in India, who follow them, her name is recited with that of her father.

1 Bk. I. 139. Rawlinson’s *Herodotus*, Vol. I, p. 279.

2 *Ibid*, Vol. III, pp. 550-63.

3 Bk. I. 139.

4 *Vide* for their meaning, the similar names of women on the next page.

(Fredun), Firozji (Pirozeji), Frâmji (Framroz), Godrezji, Gustâdji, Jâlbhai, Jamshedji, Jâmâspji Jehângirji, Kaikusru, Kekkâdji (Kaikobâd), Kerbâdji, Kâvasji, Khodâbux, Minochehrji (Mancherji), Meherwânji (Meherbân), Nâdirshâh, Nowrozji, Nushirwânji, Pâhlanji (Pâhlûm.), Pestonji (Peshotan), Rustamji, Shiâvakshâh, Shâpurji, Shehriârji, Sohrâbji, Tehmulji (Avesta Takhma-Urupa, changed in Pahlavi into Tahamurasp, then contracted by dropping the final *asp*, into Tahmur, then changed into Tahmul). (4) Some names have been taken bodily or with slight changes from the Hindus. For example, Bapuji, Bhikhâji, Dâdâbhai, Dâjibhâi, Dosâbhai, Fakirji, Ghândibhâi, Jijibhâi, Jivâji, Jivanji, Kuvarji, Lavji, Limji, Motâbhâi, Nânâbhâi, Pochâji, Santok, Suklâji, Ukarji.

Coming to the names of the female sex, “Bâi” the last part of their names corresponds to the last part “ji” of the males. One can divide them under the following groups:- (1) Names derived from the names of the Zoroastrian Yazatas or angels. These are Bahmanbâi, Adarbâi, Âvânâi (from Awân the tenth Yazata), Khorshedbâi, Meherbâi, Dinbâi, Hamâbâi (from Homa or Haoma. (2) Names derived from wealth or precious metals or jewels. They are Dhanbâi (wealth), Hirâbâi (diamond), Jarbâi (Persian *Zar* gold), Manockbâi (ruby), Motibâi (pearl), Ratanbâi (jewel), Rupâbâi (silver), Sunâbâi (gold). (3) Names derived from old Persian names: Bânubai (Persian *Bânu* lady), Freni, Gulbâi (Persian *Gul* flower), Navazbâi (contracted from Persian Arnavâz, a sister of King Jamshed), Pirozbâi, Pourouchisht, Tehminâ. (4) Names derived from expressions for sweets: Mithibâi (sweet), Shâkarbâi (sugar), Shirinbâi (Persian *Shirin* sweet, also an Iranian name). (5) Names taken from the Hindus: Âimâê, Âlibâi, Bachubâi, Bhikhibâi, Chândanbâi, Dosibâi, Jâibâi (Jâiji), Kuwarbâi, Nâlibai, Sukhlibâi, Virbâi. [11]

We find from these above lists, that some names are common to males and females. It is only the suffix “ji” or “bai” that makes it a male or a female name.

As for the names derived from the Zoroastrian Yazatas or angels, children are at times named after some particular Yazatas, if they are born on the days of the month bearing the name of those Yazatas. For example, a male or female child born on the day Mihr, the 16th day of a Parsee month, may be named Meherji or Meherbai respectively.

Birth day.

The birthday of a Parsee child — and especially the first birthday — is an important day. No religious rites are enjoined as necessary. But the parents generally like to celebrate the day in what one may call, a religious way. After a bath and a new suit of clothes, the child is

generally sent with some sandalwood to an adjoining Fire-temple. There, the ash of the sacred fire is attached to its forehead. Some of those, who can afford, get a religious ceremony, known as Fireshte,¹ performed. That is generally done on the first birthday. This ceremony consists of the recital of prayers in honour of the 33 different Yazatas or angels, and indicates, that God's blessings are invoked upon the child, and that it is wished that it may be blessed with all the physical characteristics and mental virtues over which God has directed these Yazatas to preside. According to Herodotus,² "of all the days in the year, the one which the ancient Persians observed most was their birthday."

Childhood.

From a strictly religious point of view, there is nothing special to be remarked in the case of the childhood of a Parsee child. It is held to be innocent and not liable or subject to the performance of any religious duties or rites. If God forbid, the child dies before the navjote or the investiture of the sacred shirt and thread, its [12] funeral ceremonies are on a lower scale. In the recital of the funeral prayers, the child is spoken of as "Khûrd," i.e., small or young. This appellation signifies that the deceased person was too young and that it had no responsibility for duties or rites as a Zoroastrian.

At or about the age of six, the child has to learn by heart a few religious prayers — especially those falling under the head of, and attached to, the Nirang-i-Kusti,³ i.e., the recital for putting on the sacred thread. These must be learnt by heart for the coming occasion of its navjote, when it is to be invested with sacred shirt [sudre] and thread [kusti]. After this investiture, the child's name ceases to be recited as *Khûrd* in the prayers accompanying religious ceremonies but is recited as Behedin or Oshta as the case may be, i.e., as it belongs to the layman or the priestly class.

According to the *Farziât-nâme*h, when the child first begins to speak, the first word to be taught to it is the name of God and the next that of Zoroaster. At the age of seven, it may be entrusted to a Mobad or priest for religious instruction. At first, the Srosh Baj prayer, then the Niyayeshes, and then the Yashts may be taught to it.

1 Or Fareshta. Pers. فرشته "fîreshteh," i.e., angel.

2 Bk. I. 133. *Vide Ibid.*, Bk. IX. 110-14, for the king's birthday feast "Tykta." The king soaped his head and gave gifts on this day. He refused no demands of gifts on that day. For the meaning of the word "tykta," see my *Asiatic Papers* Part II, p. 242 (Bombay, British India Press, 1905).

3 Spiegel, translated by Bleek, Vol. III., p. 4, *Le Zend Avesta*, par Darmesteter, Vol. II., p. 685.

The Pahlavi *Aerpatastan*¹ has a chapter on the subject of the childhood of a Zoroastrian child of old and of the responsibilities of its Mobed preceptors. The latter were to take no children under their charge without the permission of their parents or guardians.² There seemed to be a custom whereby some children lived with their preceptors, whose fee for the whole period of tuition is mentioned in one place as 500 drachms, or about 600 rupees. The preceptors had, as it were, a kind of lien on the children if the stipulated fee was not paid. If, at the end of the stipulated time, they found that the guardians were not the proper persons to whom the children could be safely restored, [13] they withheld the restoration.³ The Pahlavi *Andarz-i kutakân* speaks of a few duties of children from a religious point of view (Dr. Freiman's Text and Translation, *Dr. Hoshang Memorial Volume*, pp. 482-89). [14]

1 *Aerpatastan and Nirangastan*, by Mr. Sorab Jamshedji Bulsara, M.A. *Aerpatastan* Bk. I., Chap. IV.

2 *Ibid.*, Chap. IV. I.

3 The following subjects are referred to in the *Denkard* as the contents of a section of the lost *Husparum nask* on the subject of childbirth and children: "Begetting a son; conception; tokens of a sex; formation of the limbs; Fravahars' power of making the sexes; childbirth and care of a child; spiritual vision of the child; habits tending to beauty and other good qualities." I (Dastur Darab Peshotan [Sanjana]'s *Dinkard*, Vol. XVI, contents, p. V).

CHAPTER II. MARRIAGE CEREMONIES AND CUSTOMS.

Marriage, a good institution, according to Parsee books.

According to the Parsee books, marriage is an institution that is favoured by the Almighty God. According to the *Vendidad* (4:47), Ahura Mazda says: “O Spitama Zarathushtra! Indeed, I thus recommend hereunto thee, a man with a wife above a Magava (i.e., an unmarried man) who grows up (unmarried), a man with a family above one without any family, a man with children above one who is without children.” The very ground where a married man lives is represented as feeling happy. Zarathushtra asks: “O Creator of the physical world! Which is the second place on the earth that feels happy?” Ahura Mazda replies: “That (place is happy), over which a holy man builds a house with fire, cattle, wife, children, and good followers.” (Vd. 3:1.)¹

The reason why marriage is recommended in Parsee books is that there is a greater likelihood for a married person than for an unmarried one to be able to withstand physical and mental afflictions and to lead a religious and virtuous life (Vd. 4:48, 49). We read in the Gathas (Y. 53:5): “I say (these) words to you, marrying brides and bridegrooms! Impress them in your mind. May you two enjoy the life of good mind by following the laws of religion. Let each one of you clothe the other with righteousness. Then assuredly there will be a happy life for you.”

To help marriage is a meritorious act.

Marriage being thus considered a good institution and well-nigh a religious duty, recommended by religious scriptures, a Parsee considers it a meritorious act to help his co-religionist to [15] marry. The *Vendidad* (4:44) says: “If a co-religionist — be he brother or friend — comes to thee with a desire for a wife, get him married to a wife.”² To bring about the marriage of a maiden, who has reached her

1 Compare with this, the following lines, wherein also the poet describes the house of a married couple as feeling happy:-

“What a delicious breath marriage sends forth
The violet’s bed not sweeter! Honest wedlock
Is like a banqueting house built in a garden,
On which the spring flowers take delight
To cast their modest odours.”

2 It is not unusual for Parsees to enjoin by their last testament or by a Trust, that a certain amount of their wealth may be spent in charity in the way of helping poor brides to marry. A similar provision has been made by the first Sir Jamsetjee Jejeebhoy, Baronet, in his charitable Institution known as the Sir Jamsetjee

puberty, with a good righteous man, is considered to be very meritorious and an act of atonement for a sin (Vd. 14:15).

The authority of Herodotus.

We learn also from Herodotus (Bk. I., 136), that in ancient Persia, the State encouraged married life. He says: "Next to prowess in arms, it is regarded as the greatest proof of manly excellence to be the father of many sons. Every year the king sends such gifts to the man who can show the largest number, for they hold that number is strength."¹ Thus, from very ancient times, marriage is considered among the Parsees to be a most important event in one's life.

The religious part of the marriage ceremonies is originally Persian.

After the several vicissitudes of fortune that the community has passed through, it is difficult to determine how many and which of the present several marriage customs of the Parsees are originally Zoroastrian or Persian. But this much can be said with well-nigh a certainty, that the strictly solemn or the religious part of the ceremony, wherein the priests take part, is more or less originally Persian. M. Harlez seems to be correct when he says on this point: "Nous ne trouvons pas non plus, [16] dans ce qui nous reste des livres avestiques, de cérémonies particulières pour le mariage; il est probable cependant que l'origine de celles qu'observent encore les Parses modernes remonte aux temps les plus reculés."²

In the very commencement of the Ashirwad [*asirvad*] or the marriage Blessing-prayer, known as the *Paêvand-nâmeh*, and recited at the wedding ceremony, the officiating head priest says that the ceremony is "according to the rules and customs of the Mazdayasni religion (avar dâd va âin-i-Din-i-Mazdayasni)." We gather from stray references in Herodotus (Bk. IX. 108) that the Achaemenians observed some ceremonies for marriage. Ferdowsi also refers to the existence of some marriage customs (*âin va kîsh*. Mecn's Calcutta

Jejeehhoy Parsee Benevolent Institution; and even now, about 60 years after his death, poor brides are helped to be married. The Parsee Punchayet funds also have a similar provision. At present, about Rs. 75 are given to help the marriage of every bride. When parents lose by death a young son of marriageable age, they take consolation in this special kind of charity. This custom can be compared to that of the "funeral doles" of the ancient Christians, wherein pious Christians provided for the marriage of poor unmarried girls. Among the ancient Greeks, the State thought it its duty to provide dowries for the marriage of the poor maidens of the country.

- 1 Among the Romans, the State encouraged marriages. A tax known as uxorium was imposed upon the unmarried. Celibacy was an affliction among the ancient Jews (Judges 11:37; 1 Samuel 1:11; Proverbs 17:6).
- 2 Harlez, *Avesta*. (Introduction) p. CLXXI.

edition, Vol. I, p. 320).

The marriageable age.

According to the Avesta, a person came to manhood in ancient Iran at the age of fifteen (Yt. 8:13-14, Tir; Yt. 14:17, Warharan; Y. 9:5). The Pahlavi *Bundahishn* also gives the same age (Chap. III., 19, S.B.E. Vol. V., 16). So, fifteen was the marriageable age for males. For the females also it was 15 (Vd. 14:15). The very fact, that in the Avesta we find brides praying for suitable husbands, shows that there were no early marriages (Yt. 5:87, Aban; Yt. 15:40, Ram; Y. 9:23). The Paywand-nameh, recited at present at the marriage ceremony, also shows that early marriages were never contemplated. The bride and bridegroom are asked to express their consent after "truthful consideration" (*Tâ andâzandi paêmân pa râst manashni pasand kardehid*). The book of Herodotus also points to a grown-up age for marriage. The marriageable age at present is generally after 21 for the males and after 16 for the females. The Parsee Marriage Act enjoins 21 for the males and 18 for the females. When they are not of that age, the marriage-certificate must be signed by the parents.

The betrothal.

The nuptial ceremonies of the marriage-day are preceded by several other ceremonies. When the match is arranged, an auspicious day is fixed for the betrothal. The new moon day, or the first day (Ohrmazd) of the [17] Parsee month, or the twentieth day, over which Warharan, the angel of Victory, is believed to preside, are generally considered to be auspicious days. Now-a-days, the parties generally fix such auspicious days or the days most convenient to them. But still it is not rare, especially in the Mofussil towns, for the parties to resort to Hindu astrologers to name one or more auspicious days for the betrothal or marriage or such other auspicious events.

Matches are generally arranged by the parents with the consent of the children, though, now-a-days, there are many cases of marriages where marrying parties make their own choice. In the latter case, they generally consult the parents. Mutual friends of the two families generally carry messages and bring about the arrangement. The Pahlavi Pand-nâmeh of Adarbad Mahraspandan recommends this process (§ 42). The marriages of the three sons of Faridoon and the marriages of Rustam with Tehemina and of Kaus with Soudabeh were, as we learn from Ferdowsi, thus arranged. Upto late, and even now to a certain extent, professional match-makers were not unknown.

On the betrothal day, at first, the ladies of the bridegroom's family

go to the house of the bride and make her a money present in silver coins. Then the ladies of the bride's family go to the house of the bridegroom and make him a similar present. These reciprocal presents of silver coins form the only important part of the ceremony.

The ladies return to their houses, after a little refreshment, mostly consisting of fish, sweets, curd, plantains and sugar. The modern Parsee term for this ceremony is *Adrâvvûn*, but the older¹ term is *Nâm pâdvûn*, which is derived from the Persian [18] term "*Nâmzad kardan*," i.e., to name. It is so called from the fact that after the betrothal, the brides took the names of the bridegrooms.² According to the Parsee custom, a girl's name is always connected with her husband's in religious ceremonies after the betrothal, even if, by some chance or accident, marriage does not take place. This shows that betrothal³ was considered to be a solemn ceremony for a marriage contract. Nuptial songs are generally sung on this occasion.⁴

The Divô, or the kindling of a lamp.

The next ceremonial occasion is that of Divô, i.e., a light. It is so called because early in the morning of a day fixed for the occasion, an oil lamp is lit in the house of each party.⁵ The ladies of each of the two

1 An unbetrothed girl was said to be "unnamed," (*nâ kardeh nâm*). Cf. Ferdowsi's statement about the daughters of the king of Yeman, *mar ân har sê râ nûz nâ kardeh nâm*. (Mecan's Text, Vol. I, p. 51). According to Anquetil du Perron (Tome II, p. 557), the marriage ceremonies of the Parsees in Surat, at the time of his residence there (A.D. 1760), were of two kinds, (I) *Nâmzad* (betrothal) and *Nekâh* (marriage). Now-a-days, in Bombay, the priests do not take any active part in the first ceremony, but it appears from Anquetil (II, p. 557) that they did so in former times. The intended bridegroom and the bride, and their families, met together, and the family priest of the bridegroom said that "That was the will of God." He then recited the Tan-Dorosti and the Profession of Faith prayer and gave the hand of one into that or the other. In some of the Mofussil towns like Naosari, the family priest or a friendly priest still takes an active part in the betrothal. On the day of betrothal, he carries a formal message from the family of the bridegroom to that of the bride and asks for the bride to be given in marriage to the bridegroom. The parents express their pleasure to do so, and stamp, as it were, their pleasure to do so, by presenting the priest with a few rupees. Afterwards, a priest from the bride's family goes on a similar errand to the family of the bridegroom.

2 *Vide* above, p. 9, the section of "Naming the child" in "The Birth Ceremonies."

3 Betrothal is so called, because in it a "troth" or a promise of truthful adherence to a marriage contract is given; *cf.* the promise of *Mithro virô mazô* (Vd. 4:2), which is considered by the Rivayats to be a marriage promise, to break which is considered to be a great sin.

4 For some marriage songs, *vide* my *Marriage Customs of the Parsees*. *Vide* Journal, Anthropological Society of Bombay, Vol. V of 1899.

5 *Cf.* the custom among the ancient Greeks, according to which the bride's mother carried in her hand the bridal torches kindled at the family hearth, and the bridegroom's mother carried torches and awaited the procession from the bride's house.

families go in turn to the house of the other, and place a silver coin in the lamp there. This occasion is considered more important than that of the betrothal, because, on it, formal presents of clothes and rings are made. When the matches are arranged, the betrothal is hastily determined upon, to give a formal stamp, as it were, to the arrangement, The parties then [19] have no time to prepare mutual presents and gifts; so, this second occasion, the day for which is fixed leisurely, is more important than the betrothal, for the formal presents of gifts, The first wedding rings are generally presented by both the parties on that day.

The Âdarni.

The next important occasion is that of Âdarni, It is the occasion, on which, the dowry given by the bride's father, is presented to the bride-groom's family. On several other occasions of holidays between the betrothal day and the marriage day, several presents are sent to each other's family, mostly from the family of the bride to that of the bridegroom. The marriage occasion is one, when the mothers of the bride and the bridegroom, expect presents of clothes from their own parents. If the parents are dead, it is considered to be the duty of the brother or brothers to present a suit or suits of clothes to the sister. A nuptial song is generally sung on such an occasion.

The fixing of an auspicious day.

An auspicious day is fixed for the marriage. In some families, even now, it is the astrologer who determines which day is auspicious for the marriage.¹ The new moon day and the full moon day are auspicious. Tuesdays are inauspicious.² The [20] marriage festivities

(The Home Life of the Ancient Greeks, by Blümner, pp. 139-140).

- 1 In some families an astrologer's services are engaged before the marriage also. When matches are being arranged by the intercession or mutual friends, the horoscopes of the intended bride and bridegroom are submitted to him to observe whether there was or not any *râç* between the two, i.e., whether the stars predicted or not that there would be harmony between the two. If that harmony is declared not to exist, nothing further is done.
- 2 According to Strabo, the vernal equinox was considered to be the best season for marriages among the ancient Persians, because it was, as it were, the birthday of Nature. Among the ancient Greeks, weddings took place in the winter. "A favourite time was the month Gamelion (the end of January and beginning of February) which hence received its name. Certain days regarded as auspicious were generally chosen, and the waning moon was specially avoided." (*The Home Life of the Ancient Greeks*, by Blümner, p. 136). "The Athenians preferred the time of the new moon, while some of the Greeks considered the period of full moon as the most favourable" (*The Knot Tied* by W. Tegg, p. 63). Among the ancient Jews, "the fourth day of the week, i.e. Wednesday, was an auspicious day for the marriage of virgins and Thursday for that of widows." (W .Tegg, p. 53). Among the ancient Romans, "certain days were reckoned unfortunate for the marriage as the Kalends, Nones,

generally last for four days. The first of these is called *mândav-saro*, when a twig of a tree, generally a mango-tree, is planted near the door, symbolic of a wish for fertility.¹ The second and the third days are known as *Varadh-patra* days when religious ceremonies in honour of the dead are performed.

The sacred bath.

Coming to the ceremonies of the day of marriage itself, the bride and the bridegroom take in the morning or in the afternoon, a sacred bath with consecrated water.² This sacred bath is known as *nân*.³

The time of the performance of the religious ceremony.

The Parsee marriages are generally performed in the evening, just a little after sunset.⁴ The bridegroom generally sits in the compound of the house or *bungalow* in a promiscuous place in the midst of a company of several male friends and relations. The bride and the lady guests are accommodated with seats within the building. [21]

Marriage performed with éclat in ancient Iran.

Marriage is considered to be an event which must be celebrated, not quietly, but with some éclat. It must be celebrated in the presence of an assembly⁵ (anjoman) who can bear witness to the event.

and Ides, and the days which followed them, particularly the whole month of May. But widows might marry on these days. The most fortunate time was the middle of the month of June" (*Ibid*, p. 174).

- 1 Cf. The custom referred to by Mrs. Philgot in her *Sacred Trees*, pp. 88-91.
- 2 We learn from Ferdowsi, that this seems to be an old custom. King Behram Gour took his Indian wife Sepinoud to the Fire temple of Adar Gushnasp for the purpose. Among the ancient Greeks, "among the ceremonies bearing religious character which preceded the wedding, an important part was played by the bath. Both bride and bridegroom took a bath either in the morning of the wedding day, or the day before, for which the water was brought from a river or from some spring regarded as specially sacred, as at Athens the spring Callirhoe. (or Enneacrunoe) at Thebes the Ismenus." (*The Home Life of the Ancient Greeks*, by Prof. Blümner, translated by Alice Zimmern. p. 137).
- 3 *Vide* below Chapter IV. The Purificatory Ceremonies.
- 4 It is just the time when day and night unite together. So, perhaps that hour is chosen to indicate, that just as day and night, light and darkness, unite together and melt into each other, so the marrying couple may unite together in prosperity and adversity, in happiness and grief, in danger and safety. The ancient Romans also performed their marriages at night-fall, because they said it was the time when Venus, the goddess of beauty, which personified beauty in the marrying bride, shone.
- 5 In ancient Rome and Greece also, a similar view was held about marriage. But the assemblies began to be very large, and consequently extravagance in marriage expenses crept in. Hence, it was found necessary to limit the number of guests invited. Plato allowed 10 guests to each side, i.e., in all 20 guests were allowed at the

According to the *Denkard*, marriages were performed in ancient Iran, with éclat. It says that the drums and fifes which played at marriage gatherings announced the marriage to the people of the town or village. The assembly of males that gathers on marriage occasions is called *Shâhjan*, (i.e., the assembly for the royal bride).

The dress of the bridegroom.

The bridegroom puts on the usual ceremonial dress — *Jâmâ-pichhori* — of the Parsees, which is a loose flowing dress, full of folds and curls.¹ This flowing dress is always white in colour.² The bridegroom holds a shawl in his hand, a shawl being considered in India a symbol of respect and greatness.³ [22] He has the mark of a *Kunkun*⁴ (red pigment) on his forehead.

The signification of the mark of *kunkun* on the forehead and of flowers.

The red pigment mark on the forehead of a bride is always round

marriage gatherings. A law of the fourth century fixed that number to be 30. A censor had the right of going into a house where the marriage took place and he removed out of the house any number that exceeded 30.

- 1 A loose flowing dress is, in all ages, considered to be necessary for solemn and state occasions. In courts, churches, and universities, the gowns and robes, which were similar flowing dresses, played an important part. The folds of such dresses carried the idea of a kind of mystery, respect, and rank. Women, therefore, generally put on such flowing dresses.
- 2 White colour is generally the symbol of purity, innocence and faith, fulness. The Roman bride used to wear a white gown on the occasion of her marriage. The ribbon-knots which the guests put on among the Romans on marriage occasions were also white in colour.
- 3 Fifty years ago the chief leaders of the Parsee community used to carry shawls over their shoulders. The head-priests of the community still carry shawls as the insignia of their office. The presentation of shawls to friends on important ceremonial occasions, as marriages, is still common to a certain extent.
- 4 *Kunkun* or the red pigment plays an important part on marriage, and such other gay occasions in India. Various explanations are given about its use. Some say that this red pigment is the symbol or substitute of blood, and that its use is the remnant of the custom of using blood on such occasions. They say that formerly they used to sacrifice animals on gay occasions like marriage, to avert evil from the married life of the couple. The blood of such sacrificed animals was applied to the forehead of the marrying couple. The application of the red pigment is considered to be a remnant and substitute of that custom. I have heard a story of a Divân of a native State, that on the coronation of his Prince, he made a slight cut on his thumb, and with the blood oozing from the wound, made the usual mark (*tilâ*) on the Prince's forehead. That was a prevalent custom among the Rajputs of Oodeypore (*vide* Tod's *Râjasthân*). In old Christian art also, an angel is shown stamping a mark on the forehead of the elect (*vide* *The Life of Christ as represented in Art* by Dr. Farrar). The legend explains the subject as the sign of the letter T which was originally a + (cross) and was a symbol of felicity, safety, and salvation.

and that on the forehead of a bridegroom always long and vertical. The reason is this: the long vertical mark of the male symbolizes a ray of the sun, and the round mark of the female symbolizes the moon. A handsome man is compared by Oriental writers with the sun, but the beauty of a woman is always compared with that of the moon. The sun is always represented in ancient pictures, as a round disc with shooting rays. Again, the sun, through his rays, is a fructifying agent, but the moon is represented as a conceiving agent. She absorbs the rays of the sun. Just as the sun is a fructifying agent, and the moon a conceiving agent, so is man in his relation to woman. Hence it is that the mark on a man's forehead is long and vertical like the rays of the sun, and that on a woman's forehead round like the moon.

The bridegroom has a garland¹ of flowers round his neck as a symbol of sweetness and geniality. The bridegroom is [23] called *var-râjâ*, i.e., husband-king. For this particular occasion of marriage his position is taken to be elevated.²

Presents to the bride and bridegroom and to their parents.

Some of the assembled friends and relations then make their presents to the bridegroom and his father. The presents mostly consist of shawls or rings or money in cash. The bride and her parents receive similar presents from their friends. Up to a few years ago, these presents, especially those in cash, were very common. Small presents of cash up to Rs. 5 were not necessarily paid into the hands of the parties, but were given into the hands of a friend or relation, who acted as a receiver or collector for the occasion. He put down in a book the names of the donors and the amount of their money-gifts. Such money-presents used to payoff a part of the marriage expenses.³

1 Garlands play a prominent part in the marriage customs of many nations. They were common among the ancient Greeks, Romans, and Jews. In old Anglo-Saxon churches, the priest blessed the pair, and put garlands of flowers round their necks.

2 They say, that in ancient times, among several nations, the marrying couple put on crowns. Among the ancient Greeks, the priest put crowns on the heads of bridegrooms. In Athens, the friends of the bride carried a crown for her. In Egypt also, the bride put on a crown. Among the Hebrews the marrying couple were made to walk under a canopy resembling a crown. In Norway, the bride put on a jewel resembling a crown. In ancient churches, they kept a metallic crown, which was lent to the marrying couple for the occasion.

3 This custom reminds one of the "marriages of contributions" of ancient Wales and the "penny weddings" of ancient Scotland. In Wales, a herald went round in the town, announcing the marriage, and saying that presents would be received very thankfully and returned on similar occasions. Individual givers of small cash presents did not feel the burden of the small payment, but to the marrying couple and their parents, the total amount of these individual small presents was most welcome, as it enabled them to payoff the wedding expenses, and to put up a new house. In the case of the penny-weddings of Scotland, at times, the people of the

The memo kept by the receiver proved to be of use to the parties when, on similar occasions of marriages in the family of their friends, they had to make similar presents in return. [24]

Marriage gift and dowry.

It appears from the Avesta, that in old Iran, it was more customary for the bridegroom to give marriage gifts to the bride than for him to take from her. The duty of the father of the bride, and in his absence or death, that of the brother, was confined to that of presenting an ear-ring (*gaoshâvarê*) to the bride. The sum of 2,000 silver *dinars* and two gold *dirhems*, referred to in the Pahlavi *Paêwand-nâme*h, recited at the marriage, seems to be the average standard which an ordinary bridegroom of moderate means was expected to provide for his bride.

Marriage processions.

An hour or two before the celebration of the marriage, the ladies of the bride's family and the bride's friends, form themselves in a procession, and carry for the bridegroom, to his place, presents of clothes and some other valuables. The houses of the bridegroom and the bride have a kind of wedding powder called *chauk* spread over their thresholds on such merry occasions.¹ A nuptial song is again sung on such an occasion. They return to their place after this presentation. The assembly, then, forms itself into a procession, headed by the officiating priests and the bridegroom and followed by the ladies who carry with them what is called *varni*, i.e., a present from the *var*, (i.e., the bridegroom) to the bride. The procession is sometimes preceded by a band of music. According to the Pahlavi *Denkard*, one of the objects of playing music on the occasion of a marriage is to inform the whole town, especially the neighbourhood,

whole village paid in their small contributions, and took a part in the wedding festivals. In some cases, the neighbours collected among themselves and presented to the marrying couple, sufficient corn that would last during the whole of the first year of their married life. In old England, they say, the nobleman in possession of the adjoining estates presented meat, and the milk-men milk, cheese, eggs, etc., for the wedding feasts. The schoolmasters and the priests generally lent their cooking utensils. The parties receiving these presents kept a note of such presents, and were generally ready to give similar presents on the occasions of marriages in the families of those who had given them those presents. In Cumberland, they placed a plate in a prominent place at the place of marriage, and the assembled friends put into it their mite. In ancient Europe, on the marriage day, the bride used to sell ale to her friends and to her husband's friends at fancy prices. The money so acquired helped them in putting up a new house. In ancient Egypt, the bride held in her hand a soft substance called *henâ* and the friends put in silver coins in that substance.

1 *Vide* my paper on "The Wedding Sand in Knutsford (Cheshire, England) and the Wedding Sand (𑀘𑀓𑀭) in India" (Journal, Anthropological Society of Bombay; 1912, Vol. IX, pp. 471.80). *Vide* my *Anthropological Papers*, Part II, pp. 31-39.

that a marriage has been celebrated.¹ [25] The procession² goes to the house of the bride, where the marriage generally takes place. A nuptial song is generally sung on this occasion.

The procession goes to the place of the bride, and its members are accommodated with seats, the males in the compound and the females within the house. The door of the house of the bride is decorated with a hanging string of flowers, called *toran* (i.e., arch) and the sideposts which support the doors are marked with *Haradh* (turmeric) mixture.³ This kind of decoration is observed on the door

- 1 Dastur Peshotan's *Denkard*, Vol. II., p. 96. Vide "Notice Sur lez Yezedis," Journal Asiatique of January-February, 1896, p. 119.
- 2 Such marriage processions played an important part in many nations. In the Isle of Man, the marriage processions entered the church after going round three times. In ancient Greece, marriage processions were generally accompanied with musical bands and torches. The whole procession went on foot to the house of the bride, but the marrying couple were seated in a carriage. Up to about 70 years ago in Bombay, and about 45 years ago in Naosari, and such other Mofussil towns, it was common to see the husband — generally boy-husbands — riding on horses. In Naosari, some marriage processions were accompanied by men carrying guns which were fired at intervals. It is said that this is the case even now in some parts of Scotland. This seems to be a remnant of the ancient custom of marrying by capture when tribes attacked other tribes, and carried off marriageable girls.
- 3 Among the ancient Romans, the door of the house of the bridegroom was similarly decorated with flowers when the bride first went to her husband's house. She herself applied oil to the door-posts, oil being considered a symbol of prosperity. In Indian and other architectures, the *toran* (archway) played a very prominent part (vide *History of Indian Literature* by Harrowitz, p. 72). It is a symbol of marriage, suspended at the portal of the bride (Tod's *Râjasthân*, p. 26).

The custom of applying *Haradh* (turmeric) to the door-posts is common in India. The word *Haradh* comes from the Sanskrit root *har*, which means "to be yellow, to shine." Its colour is like that of sunlight. So turmeric and other drugs of its colour are taken to be the symbols of sun's light, and also of the prosperity and plenty brought about by his fertilizing power. Hence, the marks made with turmeric are considered auspicious. Instead of the red pigment (*Kunkun*), some use turmeric for the auspicious marks on their foreheads. It is for its being a symbol of plenty and prosperity that the new account books, commenced to be used on the Dewali New Year's day by the Hindus, are marked with turmeric marks.

According to Dr. Dymock, one of the different Indian words for turmeric is *Rajni*, i.e., light. They say that in ancient times young wives decorated their foreheads with auspicious marks of turmeric, a little before sunset, when they expected their husbands to return to their homes from outdoor work. This was intended as an auspicious thing, signifying that, as the sun, whose symbol the turmeric was, fructified the creation, so they may be fructified and blessed with children at the hands of their husbands. This custom is said to prevail even now in some of the Indian villages. Even young ladies, when visiting lady friends in the evening, have their bodies marked with turmeric. These visitors are then allowed to return to their husband's houses after sunset, which is considered to be the auspicious occasion for the coming of the goddess Laxmi, which presides over wealth and prosperity. According to the *Iliad*, Juno, in order to entice Juno, had her bed prepared of turmeric-coloured saffron.

of the bridegroom's house also. A nuptial song is sung on this occasion. [26]

Welcoming ceremonies before crossing the threshold.

After the assembly is seated, the bridegroom enters the bride's house. He is welcomed at the door by the mother of the bride. He is made to stand at the threshold where several ceremonies are performed to welcome him and to wish him good luck. A fresh *Kunkun* mark is made upon his forehead, and a little rice is stuck upon the moist *Kunkun* mark and thrown over his head. Rice is considered to be the symbol of plenty and prosperity. Hence the sprinkling of rice plays a prominent part on many occasions of joy for wishing good luck. The officiating priests also, in performing the religious ceremony, and in invoking the blessings of God upon the couple, sprinkle rice over them.¹ Before the recital of the marriage blessings, the bride and the bridegroom also throw upon one another a handful of rice. Some fond mothers make the bride and the bridegroom eat a few grains of rice thus besprinkled over them in the marriage ceremony.

An egg is then passed round his head three times, and then thrown upon the ground and broken. This seems to be the [27] remnant of the old custom of animal sacrifice.² It signifies that if there be any evil destined for the person it may pass off to the egg and be destroyed with it.

A cocoanut is then similarly passed round the head three times and then broken.³ A little water is then poured in a tray, which is

1 In Poland, the father of the bridegroom, after the nuptial benediction, welcomes the married couple into his house by throwing over them grains of barley corn. The grains are picked up again and sown, and, if they grow well, that is considered very auspicious. Among the Hebrews also, grains of barley were thrown in the front of the couple, and that was meant "to denote their wishes for a numerous progeny." In Nottinghamshire and Sussex, the sprinkling of rice on the couple was a prevalent custom. In ancient Spain, not only the parents of the couple, but other passers-by in the streets, also sprinkled corn. According to Dalton's *Ethnology* (p. 148), among the Buniyas, the bride and the bridegroom threw over each other seven handfuls of rice, and moved seven times round a pole buried in the midst of a hut.

2 Among the ancient Romans, on similar occasions, "a hog was sacrificed. The gall of the victim was always taken out, and thrown away, to signify the removal of a bitterness from the marriage."

3 In Scotland, they used to break a cake over the head of the bride at the threshold of her husband's house, when after marriage, she entered it for the first time. Among the Hebrews, after the marriage ceremony, they present before the bridegroom a wineglass which he breaks as a sign of good omen. All present then shout out "mazzletown, mazzletown" (*mazel tov, mazel tov*), which means "good luck, good luck." This ceremony among the Hebrews is variously explained. Some say, it is to remind the Hebrews that their people are all scattered in different countries, just as

passed round the head three times, and then the water is thrown at the feet of the bridegroom. Once in the evening, the ladies of the bride's family present before the bridegroom a water-pot (called *var-behendoo*, i.e., a pot presented to the husband, (*var*), as a part of the dowry), and make him dip his hand in it. While doing so, he drops a silver coin into it as a return gift, and as a mark of his appreciation of their gift.¹ At one time it was customary that the feet of the couple were washed with water just after the performance of the marriage ceremony. When Parsees began to put on English-fashioned boots, it being a little [28] troublesome to remove the boots, the custom was to wash the tip of the boots with a little water.²

After the welcoming ceremonies on the threshold, the bridegroom is made to cross the threshold without placing his foot upon it. The bride also, when she goes to her husband's, is made to cross the threshold.³ The threshold is crossed with the right foot, which is always considered auspicious.⁴

the pieces of the glass lie scattered over the ground. Others say that it is to remind the marrying couple of the transitory state of this life, which may be as easily broken as the glass.

- 1 Water is considered to be a symbol of prosperity and also of humility. According to Herodotus, the ancient Persians, when they went to conquer foreign countries, asked for dust and water from those countries as tokens of submission. The act of the Athenians and Spartans of throwing the Persian messengers into a pit and into a well respectively, to receive with their own hands therefrom the desired earth and water, was one of the immediate causes of the Persian invasion of Greece, which led to the famous battle of Marathon. In one of the tribes of Bengal, they give earthen pots full of water and rice to the marrying couple, and sprinkle water over them from those pots. A person going out on an important business, considers it a good omen, if he meets one with a pot full of water.
- 2 In Scotland, in the last century, the unmarried friends of the bride washed her feet on the evening preceding the marriage. The custom is still known in some parts of Scotland as that of "feet-washing." It was known among the ancient Hebrews and is known among the modern Hindus. Among the ancient Romans also they washed the feet of the couple. Among the Persian Zoroastrians, they still wash the feet of the couple, and make them dip their hands in earthen water-pots.
- 3 According to Plutarch (*Life of Romulus*), among the ancient Romans, the bride, when she first went to her husband's, was lifted up over the threshold. A similar custom is said to prevail in Lincolnshire. They say, that in old England, when the couple first left the house after marriage, the house servant washed the threshold with hot water "to keep the doorstep warm." This was to indicate a wish that another marriage may soon take place in the family.
- 4 In some countries of Europe, the bride, while entering the Church to be married, is asked to put her right foot first into the building and then to leave it also with the same foot. In former times, when some royal marriages took place by proxy, the nobleman representing the royal bridegroom placed his right foot on the bed of the royal bride. The right hand side is always considered auspicious. Among the Dhankar tribe of Mahableshwar, to determine whether the time for marriage is auspicious or not, a calf in the hut is let loose to be fed by the cow which is kept

The waiting for the bride.

When the bridegroom enters the house to be married he is further welcomed with a song. Having entered the house, the bridegroom takes his seat first, and waits for the bride, who comes in after a short time, to take her seat.¹ The bridegroom sits on [29] the right hand of the bride. The right hand side is a place of honour, and so it is occupied by the husband who is considered to be the leader of the bride.²

The bridegroom and the bride take their seats facing the East.³ There are two stools on one side of each of the chairs. On these are placed two metallic trays full of rice, which is to be thrown by the officiating priests over the couple while reciting their marriage benedictions. On the stool by the side of the chair on which the bride is to take her seat, stands a small metallic pot containing ghee (clarified butter) and molasses.⁴ [30]

outside the hut. If the calf, while going to the cow, passes by the right-hand side of the marrying couple sitting in the compound, the time is auspicious. If it passes by the left-hand side it is inauspicious, and the marriage is postponed for some time.

- 1 To make the bridegroom wait for the bride for some time, seems to be a custom prevalent among many people. Among the Zoroastrians of Persia, when, at the marriage time, the members of the bridegroom's family go to ask her to be present for the marriage, the bride does not go at once. Her relatives keep her away and say that "She has gone to the garden for picking flowers," or that "She has gone to her brother's." When the match is arranged, a few members of the bridegroom's family go to the bride's house to have her final consent. When they ask her, "Are you willing to marry such and such a person?" she is not expected to reply at once. The question is repeated several times, and then finally she replies in the affirmative in a low voice. In some tribes, when the bridegroom's party goes to the bride's, the latter's house is kept closed for sometime and opened after some knocking. Such customs and evasive answers are intended to signify, that it is the husband who seeks the wife and is anxious to have her, and not the wife.
- 2 In Christian marriages also, the bridegroom stands on the right hand of the bride.
- 3 "We modern Christians perpetuate this custom of Orientation in the position given to our churches and in turning to the East when we recite the creeds or general assent to the articles of the Christian Faith." (Mrs. Ainsley's *Symbolism of the East and West*, p. 33). This custom is a relic of the ancient Sun worship that was generally prevalent.
- 4 Ghee being a soft, slippery substance made out of milk, is considered to be a symbol of gentility, courtesy and obedience. The ancient Roman bride, for similar reasons, applied oil on the threshold of her house when welcoming the bridegroom into her house. Even now, some fond Parsee mothers, while giving a bath to their children on their birthdays apply milk to their bodies. "Have a bath with milk, and be the parent of many sons," is a common form of benediction among Parsee ladies on marriage occasions. Curd, which is a kind of milk production, also plays a prominent part on joyous occasions like birthdays and marriages. Molasses being a sweet substance is a symbol of sweetness and good temper. So these two substances are produced by the family of the bride as symbols of good omen, wishing gentleness, peace and contentment to the couple. After the ceremony, the pot

Fire.

A servant stands there holding a censer with burning fire in one hand, and a little frankincense in the other.¹ On the two stands there are two burning candles, one, by the side of the bridegroom, and the other, by the side of the bride.²

Marriage witnesses.

Then two persons are made to stand before them, one by the side of the bridegroom and the other by that of the bride. These are the marriage witnesses.³ The nearest relations generally stand as witnesses. It is usually married persons, not bachelors, who stand as marriage witnesses.⁴

The ceremony proper.

As to the ceremony itself, we find, both from the ancient writings and the modern customs, that the following are requisite for a proper marriage:-

(1) The marriage should be celebrated before a specially-called assembly (*anjoman jasta-isted*)⁵ which need not be very large. As the later tradition says, five persons may for the purpose form an *anjoman* or assembly. The assembled guests served, as it were, as further witnesses to the marriage. [31]

containing these substances and the remaining rice are presented to the family priest.

- 1 Fire is held as a sacred and most important symbol among the Parsees. So, it is present in most of the Parsee rituals. It is a symbol of purity and plenty. Among the ancient Greeks, fire and water were held as symbols of purification, and the bridegroom himself held them in his hand while welcoming his bride in his house. According to some, the Roman bridegroom held fire and water before his bride as "necessaries of life," signifying thereby that he would supply her with all necessaries of life. Among the Romans, the marriage ceremony was performed before the altar of their Atrium where their sacred fire was burning. In some parts of Australasia, the brides carry fire to the houses of their bridegrooms.
- 2 These burning-candles remind us of the "bridal torches" of the ancient Greeks, among whom the mother of the bride carried these torches in marriage processions. They were kindled from their family hearths.
- 3 It is the custom of many nations to have witnesses to testify to the event of marriage. The ancient Hebrews also had two witnesses. The Christians also have two. Among the Romans, the Pontifex Maximus performed the marriage ceremony before the witnesses. In ancient Persia, the nearest relations stood as witnesses. According to Ferdowsi, in the marriage of Siavash with Firangiz, Afrasiab, the father of Firangiz, stood as a witness for his daughter.
- 4 In the Greek Church of Russia, it is only married priests that can perform the marriage ceremony.
- 5 Pahlavi Paywand-nâmeh.

(2) The officiating priest questioned the marrying couple whether they consented to be united in marriage.

(3) He united them by joining their hands, a process known as *Hâthêvârô*, i.e., hand-fastening. A symbolic knot also played a prominent part in the ceremony.

(4) The process uniting them was followed by a benediction which was accompanied with a sprinkling of rice or such other things.

Preliminary ceremonies. Tying the marriage-knot.

Before being seated by each other's side, the bride and the bridegroom are first seated opposite each other, separated by a piece of cloth held between them as a curtain. Now begins what we may call the religious ceremonies. Two priests present themselves for the performance of these ceremonies. The senior officiating priest gives the right hand of one into the right hand of the other. Then a piece of cloth is passed round the chairs of both so as to enclose them in a circle. The ends of the cloth are tied together. This is, as it were, strictly speaking the tying of the marriage-knot. This is done with the recital of the sacred formula of "Yatha Ahu Vairyo."¹

***Hathêvârô*, i.e., hand-fastening.**

After tying the knot of the ends of the cloth, which, as it were, encloses them into a circle of unity, the priest fastens with raw twist their right hands which are grasped by each other. This rite is called *Hathêvârô*, i.e., hand-fastening.² The above [32] sacred formula is recited during this rite also. It is the family priests who are entitled to

1 A knot is a symbol of love, friendship and faithfulness. In old England, the bride carried, on her gown, a number of ribbon knots which the guests plucked off from her body and carried them with them as tokens of the event. That the custom of tying marriage knots among the Parsees is very ancient appears from Ferdowsi's *Shah Nameh* where Zal's marriage with Roudâbeh is said to have been celebrated by tying marriage knots. (*Bê bastand bandi ba âin o kîsh.*)

2 Up to the eighteenth century, there was a custom in England that the marrying couple went to the river adjoining the town, washed their hands, and each, grasping the other's hand, took the oath of marriage. This was known as hand-fastening. Among the Christians also, it is the priest who joins the hands of the couple. Among the ancient Greeks, the ceremony of hand-fastening was considered as the ratifying agreement of marriage. Among the ancient Romans, the priest made the marrying couple sit on chairs which were put together, and on which wool was spread, and then fastened their hands. The modern Hindus also unite the hands of the couple. In Finland, it is the father of the bride who fastens the hands. Among some tribes, slight cuts are made on the hands before their being fastened, so that the blood of one may flow into that of another. It is the right hand of each that is fastened because the right hand is considered to be the witness of one's faith. Among the Assyrians, it was the father of the bridegroom who fastened the hands of the couple with a woollen thread.

the fee of hand-fastening, even if the ceremony is performed by other priests.¹

In the ceremony of hand-fastening, the raw twist is put round the hands seven times.² After fastening the hands, the raw twist is passed round the pair seven times, and then, finally, it is passed seven times round the knot of the cloth which passes round their chairs. During all this process, the sacred prayer of *Yatha Ahu Vairyo* is recited.

The union.

At the end of this ceremony, at a signal given by the senior priest, the servant who holds the fire-vase places frankincense on the fire. At this signal, the curtain of cloth, which is held between the couple, is dropped, and the couple throw on each other a few grains of rice which they hold in their left hands. This throwing of rice is accompanied by a clapping of hands by the friends and relations who have assembled there.

The above ceremony of holding the cloth-curtain between the bride and the bridegroom, and then dropping it after the fastening of the hands, signifies that the separation that hitherto existed between them no longer exists now, and that they are [33] now united into the bond of matrimony.³ As long as the curtain was held, they sat opposite each other, but on its removal, they are made to sit side by side. This also signifies that they, who were up to now separate, are now united together.

The putting on of raw twist round the couple seven times also indicates union. The raw twist itself can be easily broken, but when several threads are twined into one, they cannot easily be broken. So it signifies that the tie of union into which the couple is now bound may not easily be broken.

1 This reminds us of the custom among ancient Christians, that the marriages generally took place in the parishes in which the couple lived. But when they were performed in other parishes, it was the priest of the parish in which they lived, that took the marriage fee.

2 The number 7 plays a prominent part in this ritual of hand-fastening. Seven was a sacred number among the ancient Persians. There are seven Amesha Spentas, or archangels, seven heavens, and seven Keshwars, i.e., the zones or regions [or continents]. Cf. the seven archangels of the Hebrews and the seven Spirits of the Christians.

3 Among the Hebrews, the bride at first put on a veil which was removed immediately after they were united in marriage. Among the ancient Christians, when the couple was kneeling in the sanctum, four of the assistant clergy held over their hands a poll or care-cloth which was afterwards removed. Among the Russians of the Greek [Orthodox] Church, "a curtain of crimson taffeta supported by two young gentlemen, now parts the lovers, and prevents them from stealing any anxious glances from each other's eyes." (*The Knot Tied* by W. Tegg. p. 106).

The throwing of rice.

The throwing of the rice by the marrying couple upon each other is watched with great interest by their friends, especially by the ladies, who urge their respective friends, the bridegroom or the bride, to look sharp and throw the rice first when the signal is given. The one that throws rice first over the other is said to win. This is, as it were, a race of love. "Who won, the bridegroom or the bride!" is a question often heard in the assembly.¹ This is to signify that one who throws rice first, thereby indicates that he or she will be the foremost in loving and respecting the other. The clapping of hands expresses the approval and good-will of the [34] assembly for the union.² The priests also, during the recital of the benedictions, throw rice over the marrying couple. To throw rice or some such other thing over the marrying couple as a symbol of good luck and prosperity seems to be an old custom. Ferdowsi refers to it in the case of Zal's marriage (*akik va zabarjad bar afshândand*).

The strictly religious part of the ceremony.

Then follows the most important or the solemn part, or, what can be called, the strictly religious part of the ceremony. Two officiating priests stand before the couple. The senior priest at first blesses the couple in the following few words:

"May the Creator, the omniscient Lord, grant you a progeny of sons and grandsons, plenty of means to provide yourselves, heart-ravishing friendship, bodily strength, long life and an existence of 150 years!"

Then, he puts the following question to the person, who stands by the side of the bridegroom as a witness to the marriage, on behalf of the bridegroom's family:- "In the presence of this company that has met together in the city of.....³ on day of month of the

1 In some parts of Wales, the friends of both parties went after marriage at the church to an adjoining inn to partake of the marriage repast. A few members of both parties ran to an inn. There was a kind of running race between them. The party who ran first and reached the inn first, guaranteed, as it were, that the bride or bridegroom, whom they represented, would be the first to show all love and respect to the other. In some parts of the south of France, when the couple is kneeling at the altar after the marriage, a lady goes before them, and pricks them with a pin. Both try to bear that as much as they can. The one that bawls out or expresses the feeling of pain first, is believed to be the one that would turn out less patient than the other in suffering the troubles, if any, of married life in particular, and of this world in general.

2 This corresponds to the custom of saying "Amen, Amen" in some of the village churches of England, when, after the third reading of the banns, the clerk of the church says, "God speed them all."

3 Here, the name of the town where the marriage takes place is mentioned.

year¹ of Emperor Yazdegird of the Sasanian dynasty of auspicious Iran, say, whether you have agreed to take this maiden.....² by name, in marriage for this bridegroom, in accordance with the rites and rules of the Mazdayasnians, promising to pay her 2000 *dirams* of pure white silver and two *dinars* of real gold of the Nishapur coinage.”³

The witness replies: “I have agreed.” [35]

Then the following question is put to the witness on the side of the bride: “Have you and your family, with righteous mind, and truthful thoughts, words, and actions, and for the increase of righteousness, agreed to give for ever this bride in marriage to?”⁴

Reply: “We have agreed.”

Then the priest asks the consent of the couple in the following words: “Have you preferred to enter into this contract of marriage up to the end of your life with righteous mind?”

Both reply: “We have preferred.”

To make the matter doubly or trebly sure, the questions are repeated three times.⁵

The *Ashirwad*, i.e., benediction.

Then follows the recital, by both the officiating priests, of the *Paêvand-nâmeh* or *Ashirwad* (i.e. benediction), which is an address made up of admonitions, benedictions, and prayers. Here is a translation of the address.⁶

1 Here, the particular Parsee day, month, and the year on which the marriage is performed are mentioned.

2 Here, the name of the bride is mentioned.

3 This sum seems to have been fixed in ancient Persia as the sum to be generally presented by the family of the bridegroom to the bride.

4 Here the name of the bridegroom is mentioned.

5 Among the Christians, the banns are proclaimed three times. Among the modern Greeks, the priest, after putting on the blessed ring, declares the marriage three times. He repeats the benediction three times. In some of the tribes of Central Asia, e.g., in Dardistan, the priest asks the marrying couple and the assembled company three times, whether they all consented. In the Greek Church in Russia also, the priest puts a similar question to the couple three times. His question is “Whether they sincerely consent to and approve their marriage, and whether they will love each other for the future as is their bounden duty so to do?” *The Knot Tied*, by W. Tegg (p. 107).

6 I had the pleasure and honour of contributing the translation of a large part of this address to Mr. Doshabhoy Framji Karaka’s very excellent book, *The History of the Parsees* (Vol. I., p. 182). So, I quote it from that work. The rest, I had translated specially for my paper “Marriage Customs” before the Anthropological Society of

Admonitions.

The first part of the address, consisting of admonitions to the marrying couple, is as follows:-

By the helping name of Ahura Mazda may your happiness increase. May you be brilliant. Try to do good deeds. Be increasing. Be victorious. Learn to do deeds of piety. Be worthy to do good deeds, Think of nothing but the truth. Speak nothing but the truth, Do nothing but what is proper. Shun all bad thoughts. Shun all bad words. Shun all bad [36] actions, Praise deeds of piety. Commit no acts opposed to piety. Praise the Mazdayasnian religion. Do nothing without mature consideration. Acquire wealth by good means. Say what is true before your superiors, and act according to their orders. Be courteous, sweet-tongued, and kind towards your friends. Do not indulge in scandals. Avoid being angry. Do not commit sins for the sake of avoiding shame. Do not be ambitious. Do not torment others. Do not entertain wicked jealousy. Do not be haughty. Avoid evil thoughts. Avoid evil passions. Deprive not others of their property. Keep yourselves away from the wives of others. Be industrious in following good professions. Do good to the pious and to the virtuous. Do not quarrel with the revengeful. Never be a partner with an ambitious man. Do not become a companion of a back-biter or a scandal-monger. Do not join the company of persons of ill-fame. Do not cooperate with the ill-informed. Fight with your enemies only by fair means. Treat your friends in a way agreeable to them, Do not enter into any discussion with persons of ill-fame. Speak in an assembly after great consideration. Speak with moderation in the presence of kings. Be more glorious than your father. In no way annoy your mother. Keep yourselves pure by means of truth. Be immortal like Kaikhosru. Be well informed like Kaus. Be as brilliant as the Sun. Be as pure as the Moon. Be as illustrious as Zarathushtra. Be as strong as Rustam. Be as fertile as the Earth. As soul is united with body, so may you be united and friendly with your friends, brothers, wife, and children. Always keep good faith, and preserve a good character. Recognise only Ahura Mazda, the Omniscient Lord, as your God. Praise Zoroaster as your spiritual

leader. Treat Ahriman, the evil spirit, with contempt.

Benedictions invoking the favour of virtues over which the Yazatas preside.

After the above admonitions, follow a few benedictions, in the first part of which the priests pray to God to confer upon the couple, certain moral and social virtues which are said to be the characteristics of the Yazatas (yazads, angels) who give their names to the thirty days of the month. [37]

May Ahura Mazda bestow upon you good thoughts through Vohuman, good words through Ardwahisht, good actions through Shahrewar, perfect thought through Spandarmad, sweetness through Hordad, fruitfulness through Amurdad. May God bestow upon you increasing lustre through Adar, purity through Aban, exalted position through Khwarshed, increase through the cow-like Mah/Mohor, liberality through Tir/Tishtar, temperate habits through Goshorun. May God bestow upon you pure justice through Mihr, obedience through Srosh, truthfulness through Rashnu, increase of strength through Frawardin, victory through Warharan, constant delight through Ram, strong power through Gowad. May God bestow upon you knowledge through Den, collection of wealth through Ashishwangh, a number of good talents through Ashtad, great activity through Asman, firmness of place through Zam/Zamyad, good sight through Mahraspand, and nourishment of body through Anagran.

Then follow a few other benedictions:

Oh, you good men! May that come to you which is still better for you than good, since you find yourself worthy as a Zaota (a pious and virtuous man). May you receive the reward which is earned by the Zaota as one who thinks, speaks, and does much good. May that come to you which is better than good. May that not come to you which is worse than evil. Oh good men! May that accrue to you which is better than good. May your relations be worthy of goodness. May you get that reward of which you have made yourself worthy. May good accrue to you as the result of perfect good thought, perfect good words, and perfect good actions. May that piety come to you which is better than good. May not that sinful life, which is worse than evil, come to you. May it be so as I pray.

May the much desired Airyaman come for joy to the good mind of Zoroastrian men and women. May he grant the desirable reward according to the law of an purities. I prefer that purity which is considered the best by Ahura Mazda. Righteousness is the best gift and happiness. Happiness to him who is righteous for the sake of best righteousness.

May they (i.e., the marrying couple) have light and glory, physical strength, physical health and physical victory, wealth [38] that may give a good deal of happiness, children blessed with innate wisdom, a very long life, and the brilliant happy paradise, which is due to the pious. May it be so as I wish it.

Benedictions in the name of the departed worthies of Iran, etc.

Then are recited a few benedictions in which certain departed worthies of ancient Iran are mentioned by name, and it is wished, that the pair may be blessed with the virtues and characteristics which had made them famous. Certain grand objects of Nature also are mentioned, and it is wished that the couple may be blessed with the physical qualities manifested by them. The following is a free translation of these benedictions:-

By the name of God, I bless you in the City of Bombay¹ as was the wont of our forefathers in Iran. May all your desires be fulfilled as were those of God in the creation of the world. May you be as great in dignity as king Kaikhosru.² May you be as friendly as angel Mihr, as victorious over your enemies as Zarir, as handsome as Siavakhsh, as splendid as Bejan, as pious as King Gushtasp, as strong as Sam Nariman, as powerful as Rustam, as good a lancer as Aspandiar, as good a helper of religion and far-seeing as Jamasp, as holy as the Holy Spirits, as generous as Tishtrya, as sweet as rain-water, as brilliant as the Sun, as righteous as Zoroaster, endowed with a life as long as Time that rules over the world, as fertile as the Earth, as united as a river united with a sea, as full of joy as Winter, as gay as Spring, as fragrant as musk, as well-known as gold, as current (i.e. favourite) as a coin, as good a doer of virtuous deeds as God in his creation. May these good wishes be fulfilled.

1 Or, any other city, where the marriage is performed, may be mentioned.

2 Kavi Husrava of the Avesta. For this and other proper names mentioned here, *vide my Dictionary of Avesta Proper Names.*

May you be as useful as the Sun, the Moon, Water, Fire, Wine, Myrtle, Jasmine, Rose, and the sweet Marjoram. May and.....¹ with their children and their progeny [39] live for a thousand years. Be fragrant and good as the basil and the amber. May you have such pious children as may be illustrious, and victorious over enemies, and as may add to the glory of the family. May it be so as I wish it.

The address in Sanskrit.

A part of the address is, if so desired by the family, repeated in Sanskrit: They say, that when the Parsees first emigrated to India, in order to make it intelligible to the Hindu Raja and his courtiers who had given them a home on the Indian soil, they repeated the address in Sanskrit, which was then the language of the Court. That practice they have continued up to now, though there is no longer any necessity to do so at present. There is no written authority about the above statement.

Tan-dorosti, i.e. Benedictions for the vigour of body.

Then follow another set of benedictions in the Pazand language known as Tan-dorosti. The following is a free translation of these benedictions:-

By the name of the bountiful, merciful and kind God, who is a kind and just Lord, May² have health and long life. May they be worthy of piety and splendour. O Omniscient Lord! let joy and pleasure, ease and plenty reach them and let Divine light and royal justice reach them. May they have courage and victory. May they be firm in their knowledge of the good Mazdayasnian religion by means of honest endeavour and good demeanour. May good relationship, the birth of children and long happy life be their lot. May their body be blessed with happiness and their soul with good government. O Omniscient Creator! May the religion of Zoroaster prosper. — Amen. O Great God! May you grant long life, happiness and health to the ruler of our land, to the community and to Grant them all these for many years to enable them to help the worthy. Give them a long life for many generations. May there be thousands of blessings upon them. May the year be happy, the

1 Here are mentioned the names of the bride and the bridegroom.

2 Here are mentioned the names of the marrying couple.

month auspicious and the day propitious. Grant that for several years, several days, and several months, they may be found worthy and fit to perform religious rites and [40] deeds of charity. Keep them pure for works of righteousness. May health, virtue, and goodness be their share. May it be so. May it be more so, as is the wish of God and His Archangels.

The marriage ritual repeated at midnight.

The marriage ritual is repeated at midnight. Anquetil du Perron says that it is a remnant of the old custom of Persia where, in the town of Kerman, the marriage ceremony was performed at midnight. In many families, the practice of repeating the ceremony at midnight and of the address in Sanskrit is not resorted to now. The performance of the above ceremonies and the recital of the address, complete, what we should call, the solemn part of the celebration of marriage. But there are certain other customs and observances, which, though very rare in Bombay, are observed to a certain extent in the Mofussil towns. It is the ladies who observe them. Moreover, they are now rather looked on more with an idea of merriment than with that of any solemnity.

***Chheda cheddi*, i.e., fastening the skirts of the garments.**

The first observance of that kind is that of uniting *Chheda cheddi*, षड् षड् i.e. of fastening the skirt of the garments of the couple.¹ The nearest friend or relation of the couple ties the skirts of the *jâmâ* (the flowing dress) of the [41] bridegroom with that of the *sâree* of the bride. Thus united, the bride goes to the house of the bridegroom. The process of fastening the skirts is accompanied by a song. This custom

1 Among the Hebrews, the bride and the bridegroom were made to walk under a canopy or a sheet of cloth. This signified unity of protection. This custom seems to be another form of the custom of fastening the skirts of each other's garments. The Hebrew spouse in the above custom said: "His banner over me was love." (W. Tegg, p. 55). A Hebrew bridegroom at one part of the ceremony also spread the skirt of his garment over the head of his bride. That was meant to signify that the bride was now under his protection. The old Aztec priest used to ask the consent of the bride for the marriage. Having received it, he fastened the end of a part of her long veil to the skirt of the bridegroom's coat, and thus united, the bride went to the house of the bridegroom. This custom prevails also in Nicaragua. In some tribes the officiating priest gently knocked the head of the bridegroom against that of the bride. This also had the same signification of unity. According to Dalton (*Ethnography*, p. 148), among the Buniyers, on the appearance of the stars at nightfall, the skirts of the garments of the couple were joined together and they passed the night alone in this way. The next morning both were taken to an adjoining tank for a bath and the knot was untied there. On their return home, they stood at the threshold of their house with pots of water over their heads. A part of the water was then poured over their heads.

also signifies the act of uniting the two into the bond of marriage.

“Washing the feet.”

The next rite is that of “washing the feet” of the couple with water.¹ That was more practicable about forty years ago, when almost all Parsees put on native shoes without stockings. But now, owing to the inconvenience of taking off English shoes and stockings, only the front tip of the shoes is washed with a little water. The signification of the custom may be that of washing away all past mistakes and driving away all evils and misfortunes. More probably, it signifies a kind of welcome. In India, visitors who come from some distance, are first given some water to wash their feet soiled by a long walk. At times, a lady hid the shoe thus removed and did not return it unless paid a rupee.²

Dahi-Koomrô.

The next rite was that of making the couple partake of food from the same dish.³ In doing so, each gives to the other, morsels of food of

-
- 1 In Scotland in the 18th Century, according to an old custom, the maids of the bride washed the feet of the bride on the eve preceding the marriage. Among the ancient Romans, “both she and her husband touched fire and water, because all things were supposed to be produced from these two elements; with the water they bathed their feet.” (W. Tegg, p. 75). The custom of washing the feet is prevalent among the Zoroastrians of Persia also. This custom of feet-washing prevailed among the ancient Hebrews also. It is now prevalent among the Hindus.
 - 2 “At Hindoo weddings, the brother or nearest relative of the bride hides the bridegroom’s shoes and will not restore them until the bridegroom pays him at least a rupee and a quarter.” (*The Shoe, a Moral Essay*, by Mr. Tribhuvandas Mangaldas, p. 5).
 - 3 Among the ancient Romans, one of the forms of marriage was *confarreatio* which was “a ceremony in which the bridegroom and bride tasted a cake made of flour with salt and water in the presence of the high priest and at least ten witnesses. This rite was said to symbolize the community of life, of property, of family worship, that henceforth united them.” Among the Roman Patricians, many generally resorted to this form of marriage, and the couple was made to sit on one and the same piece of leather prepared from the skin of a sheep killed for the marriage sacrifice. The bridal cake of Christian marriages seems to be a relic of the ancient Roman custom. Colonel Dalton in his *Ethnography*, gives several instances of tribes that have still prevalent among them this custom of making the couple eat together. As the Romans sat on one and the same piece of leather in their “*confarreatio*,” so, some of the tribes sit together on one and the same piece of cloth. Among the ancient Hebrews, the couple were made to drink from one and the same cup of wine which was consecrated and blessed by the Rabbi (W. Tegg, p. 54). In Russia and Scandinavia also, the couple are required to drink wine from the same cup. In Hesse, the couple eat from the same plate and drink from the same cup. According to a writer of the *Asiatic Quarterly Review*, in old Lombardy, the only marriage rite was this, that the marriage couple drank from the same cup and kissed each other. Latterly, when the clergy protested against this simple rite without any religious element in it, the benedictions from the priest and a sermon were added to it.

which *dahi* or curd form a part. This rite signifies that now, being [42] united in the bond of marriage, they have to board together and to share each other's happiness and grief. This repast is known as "*Dahi-Koomro*" from the fact that *dahi* (curd), which is considered an auspicious substance of food on gay occasions, formed the essential part of the dish.

Eki Beki, i.e., odds and even.

Another peculiar custom, now almost obsolete, is that of making the couple play *Eki Beki* which is a form of play. Both have several rupees in their hands. One, without letting the other know, takes a certain number in the right hand, and asks the other whether the number is *eki* (odds) or *beki* (even). If the other guesses the number right, he or she is said to win. Perhaps the signification is the same as that in the rite of throwing the rice referred to above, wherein the one who won, guaranteed, as it were, his or her desire to love the other more ardently than she or he would do.

The bride taken to her husband's house.

A nuptial song is sung at the close of the wedding ceremony. After the celebration of the marriage, the bride accompanies the husband to his house. A nuptial song is sung by the ladies, when the bride is taken to her husband's house, and another is sung when the bride enters the house of her husband. [43]

Entertainment of the assembled guests.

After the celebration of the solemn part of the marriage ceremony, most of the guests were entertained at a marriage feast. The following were the toasts generally proposed at Parsee marriage feasts:-

1. *Yazdân-ni yâd*, i.e., In remembrance of God.
2. The married couple.
3. The sacred fire temples. May their Sacred fires burn for ever. May they be the means of helping all.
4. The guests.
5. The host.
6. His Majesty the King.

All, or some of these, except the fifth, are proposed according to the directions of the host, and some one among the guests proposes that of the host. At some marriage feasts, a piously inclined host adds to the above list that of the dear departed ones as "*Asho Farohar ni*

Among the Melanesians, the couple gave each other three morsels from a dish called "*sagomash*." The bride then gave a little tobacco to the bridegroom who, in his turn, gave a betelnut to the bride. (Featherman, p. 32).

yâd," i.e., "the remembrance of the pious departed ones." In other communal feasts, while proposing this toast, and the first on the list, *viz.*, that in remembrance of the sacred name of God, fragrant frankincense is ordered to be placed on the family hearth. No speeches are made while proposing them. At large gatherings, there are professional health-proposers. Loud and clear voice is their only qualification for the work. They simply give out the toast with a loud voice, and at times, when the dining parties are very large, they go round the tables, repeating the words for giving the toasts several times, so that all may hear. These toasts are drunk generally while dining, not at the end of the dinner.

The menu.

As to the menu, fish, which is considered a symbol of good omen and luck, is essential. No marriage feast can be complete without it. Again, a course of some kind of sweets is essential. Meat is not generally eaten in marriage feasts. It appears from Anquetil that the reason why meat was prohibited in India, was, that formerly, at Surat, which was at first the head-quarters of the Parsees, a large number of Hindoo guests was invited. As Hindoos consider it [44] irreligious to slaughter animals for food, to spare their feelings, meat was prohibited. But, from an account of the proceedings of a meeting of the community, held in Bombay on the 18th of October 1823, and convened to consider some steps to regulate funeral and marriage expenses, it appears that meat was prohibited on marriage occasions from the point of view of economy.¹ Meat courses were thought to be expensive.

Divorce.

In connection with this subject of marriage, we will say a few words here on the subject of divorce and on that of adultery, which generally leads to it.

It appears, that in ancient Iran, a husband was entitled to have a divorce from his wife in case of adultery. Besides adultery, aggravated perpetual quarrels also seemed to be a legitimate cause of seeking divorce. The parties had to go to court for a divorce.² There seemed to be a set form of speech for the husband to give divorce.³ The Pahlavi word for divorce is *zan-tajâ*.⁴

1 *Parsee Prakâsh*, by Khan Bâhâdur Bomanji B. Patel, Vol. I., p. 172.

2 Dastur Peshotan's *Denkard*, Vol. II, Chap. LXXX, 16 pp. 98-99. S.B.E., XVIII, pp. 406-47.

3 S.B.E. XVIII, p. 407.

4 *Ibid.* p. 419.

Another cause of divorce on the part of the husband was the sterility of the wife. To be the father of children, being considered a good, important and religious act, it is natural that this was thought to be a valid cause. It was considered a valid reason, even in India upto so late as about 50 years ago. There was no clear divorce, until the wife wished to have one in such a case, but there was a permission for the husband to marry a second wife. Even upto 50 years ago, the Parsee Panchayet of Bombay permitted such husbands to have second wives during the lifetime of their first wives, but on one condition, that they were to maintain their first wives. At times, the first wife finding herself sterile, of her own accord asked her husband to have a second wife, and continuing to act as the mistress of the house, treated the second wife with affection and kindness. [45]

A passage in Herodotus also leads us to the same conclusion (Bk. IX, III). Xerxes asks his brother Masistes to divorce his wife. Masistes urges, as a reason not to do so, that she had borne him many children.

The Parsees, now-a-days, are governed by the Parsi Marriage and Divorce Act (Act No. XV of 1865) passed on the 7th April 1865. According to that Act, the following serve as grounds for a divorce (sections 27-30):-

“1. Lunacy or mental unsoundness, at time of marriage, of which one of the contracting parties did not know.

2. Impotency.

3. Continual absence of one of the parties for seven years, without being heard of as alive.

4. Adultery of the wife.

5. Adultery, or bigamy with adultery, or adultery with cruelty, or adultery with wilful desertion for two years or upwards, or rape or unnatural offence, of the husband.”¹

Adultery

Adultery is the principal cause that leads to divorce. “The Avesta raises its voice with great force against misconduct in every form and lays down very wise restrictions to assure lawful birth.”² It looks with dislike even at marriages between persons of unequal positions, from moral and religious points of view. (Vd. 18:62). The very fact that the ancient Iranians attached much importance to marriage, shows that they looked upon adultery with horror. In the case of a maiden who had lost her father, it was incumbent on the brother to give her in

1 *Parsee Law*, by Mr. F. A. Rana, p. 57.

2 *Avesta*, par C. De Harlez, Introduction, p. CLXXI.

marriage at the proper time. That was accounted an act of righteousness on his part. It was considered inadvisable or almost sinful to allow a girl of marriageable age to remain unmarried.

In the Gatha Wahishtoisht (Y. 53:7), there is a carefully worded warning against, what Dr. Mills calls, "solicitations [46] to vice."¹ There, it is said: "But yours be the recompense, (O ye righteous women!) of this great cause. For while lustful desire heart-inflamed from the body there beyond goeth down where the spirit of evil reaches (to ruin, still) ye bring forth the champion to help on the cause, (and thus conquer temptation), etc."²

The female Yazata Ashi (Yt. 17:47-60) complains bitterly against this vice. She says that it "is the worst deed that men and tyrants do,"³ when they seduce maidens from their path of virtue. In some parts of the Avesta and in the Pahlavi books, this vice is personified as "Jahi."

The Yazata Haoma is entreated to withstand the evil influence of vicious women, whose lustful wavering soul is like a cloud which often changes the direction of its motion according to the direction of the wind (Y. 9:32). The Amesha-Spenta Asha Vahishta (Best Righteousness) is similarly entreated. (Yasht 3:9). An adulterer or adulteress is, as it were, an opponent of Gao, the good spirit, of the Earth or of the animal creation, the idea being, that such a person comes in the way of the progress of the world (Vd. 21:1). The progress of the world in the different spheres of activity, physical and mental, acts against the influence of this class. (Vd. 21:17). Eredhat Fedhri is the name of a good pious maiden, who is considered as a prototype of maidenly virtue, and whose guardian spirit is invoked to withstand the evil machinations of Jahi, the personification of this vice (Yt. 13:142). In the Pahlavi Bundahishn (Chap. 3), this Jahi is said to be an accomplice of Ahriman himself. Her work is said to be "to cause conflict in the world,"⁴ wherefrom the distress and injury of Ohrmazd and the archangels will arise.

In the Pahlavi *Dadestan-i Denig* (71st question),⁵ adultery is spoken of as one of the most heinous sins. The mother of [47] Zohak is said to be the first woman in the world, who committed this offence. It is said to be a sin which disturbs all lineage, which puts an end to all control upon one's desires and to the legitimate authority of a

1 S.B.E. XXXI, p. 189.

2 Ibid, p. 193.

3 S.B.E. XXIII, p. 281.

4 S.B.E. Vol. V, p. 15.

5 S.B.E. Vol. XVIII, Chap. 72:5.

husband. It is more heinous than theft or spoliation (77th question).¹ It is a crime which leads at times to murder, because the woman brings about abortion at times.² There is another way in which adultery leads to murder. It is noted in our account of pregnancy,³ that sexual intercourse during pregnancy is prohibited, because it is thought that it leads to an injury to the life of the child in the womb. Now, a woman, who yields to lust and gives herself up to an adulterous life, is likely to commit adultery, even in pregnancy. Such sexual intercourse may cause the loss of the life of the child in the womb.⁴

Again, adultery is a canker in society in another way. When a man commits adultery with a woman, he, according to the injunction of the *Vendidad*, is bound to support the woman whom he has seduced and the children that may be born of the illicit intercourse. It is his duty to bring up his illegitimate children along with his legitimate children. In that case, the company of the illegitimate children is likely to spoil the good manners and morals of the legitimate children.⁵ But, if he does not bring up the illegitimate children properly, if he does not give them proper training, he is responsible for, and guilty of, all the wrongful acts and sins that the children may commit in their childhood or in their grown-up age.⁶

Atonement for the sin.

The sin of adultery is very heinous in itself. But what little atonement can be done for it can be done by the following good acts:-

(a) The guilty person, especially the adulterer, must help by money or otherwise, in bringing about the marriage of four poor couples. (b) He must assist with money poor children [48] who are not cared for by others and bring them up decently and educate them. (c) If he sees others in society leading a vicious life, he must do his best to retrieve them. (d) He must perform certain religious rites like those of the *Dvâzdeh-Homâst*.

In the *Viraf-Nameh* the adulterer is represented as punished by being thrown in a steaming brazen cauldron (Chap. 60), and the adulteress as gashing her own bosom and breasts with an iron comb. (Chap. 62).⁷ The adulteress who brings about abortion, meets with

1 Ibid, Chap. 78:3.

2 Ibid, p. 5.

3 Vide above, p. 3, "Birth Ceremonies."

4 *Dadestan-i Denig*, 77th Question, Chap. 78:6.

5 Ibid, 8-9.

6 Ibid, 1-9.

7 Hoshang-Haug-West, *Viraf-Nameh*, pp. 186-87.

worse punishment. (Chap. 64).

In all cases of adultery, the *Vendidad* (15:18) enjoined, that the person seducing a woman, whether married or unmarried, should maintain her, and the children that may be born of her, until they come to age. Any attempt at desertion was considered a great sin (Vd. 15:11-14).

The Pahlavi *Madigan-i-Hazar Dadistan* named the *Social Code of the Parsees* by Prof. Darmesteter, and proposed to be called a Law-book (Rechts buch) by Prof. Bartholomae is a book of a judicial type containing old Iranian Laws on marriage and cognate subjects. [49]

CHAPTER III. FUNERAL CEREMONIES AND CUSTOMS.

We will treat the subject of the Funeral Ceremonies and observances under two heads: (I.) The Ceremonies that relate to the disposal of the body, and (II.) Those that relate to the soul.

I. Ceremonies that relate to the disposal of the body.

The main principle at the bottom of the customs and ceremonies for the disposal of the body.

The main principle, at the bottom of the Parsee custom of disposing of the dead and at the bottom of all the strictly religious ceremonies enjoined therewith, is this that the body, when the immortal soul has left it, should, preserving all possible respect for the dead, be disposed of in a way the least harmful and the least injurious to the living. For properly understanding the Parsee ceremonies that relate to the disposal of the body, one must look to the ancient Zoroastrian ideas of sanitation, segregation, purification, and cleanliness as expressed in the *Vendidad*, one of their Avesta Scriptures.

The object of observances summed up in two words.

As Prof. Darmesteter (*Zend Avesta* II) says, all the ceremonies of this order can be summed up in two words, which are the same as those which sum up today all the prophylactic measures in the case of an epidemic, viz., (1) to break the contact of the living with the real or supposed centre of infection; (2) to destroy this centre itself. Though all do not die of an infectious disease, it is dangerous and difficult to leave it into the hands of all, to distinguish which case is infectious and which not. So, for the sake of precaution and safety, it seems to have been enjoined, that all cases of death should be supposed as infectious, and that people should come into as little contact as possible with dead bodies. [50]

The idea of simplicity and equality.

Again, an idea of simplicity is observed in these ceremonies. Sâdi, the Persian poet, says:

*Chun âhang-i-raftan kunad jân-i-pâk
chê bar takht murdan chô bar rui-i-khâk.*

i.e., when the pious soul thinks of departing, it is all the same, whether one dies on a throne or on bare ground. The Parsee custom of the disposal of the dead illustrates, as it were, the above words of the

poet. The method of carrying the body for disposal, from beginning to end, is the same for all.

Washing the shroud, and the part of the house where the body is placed.

When a person's case is given up, the relations begin to make preparations for the disposal of the body. At first, a part of the house on the down-floor, where the body is to be placed before its removal to the Towers, is washed clean with water. The shroud or the dress with which the body is to be covered is also washed beforehand in the house. The shroud or the dress with which the body is covered is white and made of cotton. It need not be new. Old clothes may be used for the purpose after being washed. Unnecessary wastage of clothes over the dead bodies is forbidden (Vd. 5:60).

Akhiânah.

When a case is given up as hopeless, the relations send for two or more priests, who assemble round the sick bed of the dying person and say, for his benefit, the *patet*, which is a prayer for the repentance of one's sins. The priests are paid in money and corn for their services. This is called the *Akhiânah*¹ ceremony because during this ceremony, priests are presented with grain. This part of the funeral ceremonies is not generally performed. The origin of this custom seems to lie in the fact that a person must always say his repentance prayer [*patet*], and repent of his [51] sins. If he is conscious and able, he must do so at the approaching moment of death. His near relations and friends may join in the last prayers. If the recital of the whole *patet* is not possible, the recital a short time before death, of the Ashem-Vohu formula by the dying person himself, if he is able, or by some relation, if he is unable, is considered meritorious. The *Hadokht Nask* (1:31-32) says that the recital of the Ashem-Vohu formula² at the very end of life, praising good thoughts, good words, and good actions, and condemning evil thoughts, evil words, and evil actions is, in point of greatness, goodness and excellence equal in value to the whole or the region of Khwaniras with its cattle and leading men. The purport of all this is to say that if a man at his dying moment could honestly say that he led a pious life and repented of all his sins, that life is worth more than the country of Khwaniras with all its riches.

In the *Vendidad* (12:1-19), a shorter period or mourning is

1 The grain presented to priests, both on unhappy occasions like death, and happy occasions like Naojote [navjote] or Marriage, is called *Akhiânah*, (perhaps corresponding to Av. *akhehaëna*. i.e., that which prevents weakness).

2 The Ashem Vohu prayer may be thus translated: "Righteousness is the best gift and happiness. Happiness to him who is righteous for the sake of best righteousness."

enjoined to the surviving relations of a righteous person (*Dahma*) than to those of a sinful person (*Tanu-peretha*). According to tradition, the *Dahma* or the righteous in this case is one who has said his repentance prayer or recited the Ashem Vohu; and the *Tanu-peretha* or the sinful is one who has not said that prayer or recited that formula. A longer period of mourning is enjoined for the sinful, because, in his case, the surviving dear ones have not only to mourn his loss, but have to mourn for the fact that he has not led a good life, and as such has to meet with punishment.¹ [52]

Communion with a few drops of the sacred haoma juice.

Upto a few years ago, a short time before death, a few drops of the consecrated haoma juice were poured into the mouth of the dying person. The haoma² plant being an emblem of immortality, its juice is poured to impress an idea that, after all, the soul of a man is immortal. The haoma plant reminds one of "The Tree of Life" of the Christian scriptures (Genesis, II, 9) in the garden of Eden and of the Sidra or Lotus of the Mahomedan scriptures (The Qurân, LIII, 14-20: S.B.E., IX, p. 252). As the Tree of Life is guarded by the Cherubim and the Sidra by 70,000 angels, so the *haoma-i saphid*, or the White Haoma, is guarded by 99,999 Fravashis or the guardian spirits. Sometimes, instead of the juice of the haoma plant, if it was not available at hand, the juice of a few grains of pomegranate, the leaves of which are considered essential in some of the Parsee ceremonies, is dropped into the mouth of the dying person.

The final bath.

A short time after death, the corpse is washed throughout, first with a little application of *gomez* and then with water, generally with well-water. A clean suit of clothes, washed at home, is then put over the body. It is afterwards destroyed and never used for any other

1 Cf. the words of Hamlet's ghost:-

"Cut off even in the blossoms of my sin,
Unhousel'd, unanointed, unanel'd
No reckoning made, but sent to my account
With an my imperfections on my head. (Act I, Sc. V).

Cf. "Tears for the dead, who die in sin,
And tears for living crime;
Tears for the lost — but Heaven's own voice
Says for the Christian dead — Rejoice." - *Fewsbury*.

Cf. "Come, come; no time for lamentation now;
Not much more cause.
Nothing is here for tears, Nothing to wail,
.... Nothing but well and fair. And what may quiet us for death so noble."

2 Vide below, the Haoma Ceremony.

purpose. The *kusti* or the sacred thread is then put round the body by some near or dear one, with the recital of the Nirang-i-kusti, or the *Ahura Mazda Khudae* prayer.¹ The corpse is then placed on a cot. Then two persons keeping themselves in touch with the body sit close by, and somebody recites the Ashem Vohu prayer very close to the ear of the deceased. The relations then meet or embrace the deceased for the last time. In Persia, the person washing the corpse puts on woolen gloves. [53]

Contact stopped to prevent infection.

After this time, the dead body is supposed to fall under the influence of *Druj-i-Nasush*, i.e., the evil influence of Decomposition or Destruction. It is considered that to touch the body then is dangerous for the living, lest they should catch contagion and spread disease. Only the corpse-bearers are allowed to come into contact with the body. If somebody else touches the body, he has to go through a process of purification or a sacred bath taken under the directions of a priest.

Putting on of the shroud.

The body is now given in charge of two persons who are generally trained to their work. They are first required to take a bath and put on a clean suit of clothes. They perform the *kusti*,² i.e., ungird the sacred thread and put it on again with a prayer, and then recite a part of the Srosh-baj prayer. Then holding a *paywand* between them they enter the room where the corpse is placed.

The Paywand.

To hold a *paywand* means to be in close contact or touch with each other. This is done when two persons hold a piece of cloth or cotton tape between them. This is intended to show that they are associated or united in doing a thing and are ready to co-operate and sympathise with each other. When these two persons enter into the room, holding the “paywand” between them, the two relations who are sitting by the side of the deceased leave their places and entrust the body to them. They place the body on the ground on a clean white sheet of cloth and put on the shroud over it. The whole of the body except the face is covered with cloth. In some parts of Gujarat even the face is covered with a *padan* (Avesta, *paitidana*).³ [54]

1 In some cases, generally those of old men, when they were given up as hopeless, the final bath was, upto a few years ago, given during the last moments of life.

2 *Vide* below, the *navjote*.

3 The *padan* is a piece of white cotton cloth put over the face. It is also put on by the Parsee priests when they say their prayers before the sacred fire or other sacred

Laying on the slab.

The corpse is then lifted from its place by the above-mentioned two persons and put on slabs of stones in a corner of the front room. The hands are arranged upon the chest crosswise. In some of the towns of Gujarat, the old Avestic method of placing the dead body on a plot of ground previously dug in the house, instead of on slabs of stone is still in practice. The ground is dug out a few inches deep and a layer of sand is spread over it. The corpse is placed on the ground thus prepared (Vd. 5:11; 8:8). The body is placed on the ground or on the slabs in a position which would avoid the head pointing towards the North.

The north side always avoided.

In all the ceremonies of the Parsees, the north side is as a rule generally avoided. The children while going through the navjote ceremony for the purpose of putting on the sacred shirt (sudre) and thread (kusti), the marrying couple going through the *Ashirwad* or marriage ceremony, and the priests in all their religious rites and ceremonies never face the North. This is due to the fact that the ancient Iranians, the ancestors of the Parsees, had a natural hatred for the North, from which side proceeded all kinds of dangers and evils whether climatic, physical or mental. The *Vendidad* (7:2, 5) says that the *Druj-i-Nasush*, i.e., spirit of Destruction runs from the northern direction in the form of a fly. Even the wind from the northern direction was believed to be stinking (Yasht Fragment, 22, Hadokht Nask, 3:18).¹ The winds from the northern cold regions brought sickness and death in Persia. Again, the marauders from Mazendaran, Gilan, and other adjoining regions in the North brought destruction and death in many Iranian families. These people of the North were depraved and wanting in many moral qualities. On the other hand, the South was considered a very auspicious side. The winds from the South were healthy and invigorating. Coming from the South, they brought rain and plenty. The wind blowing from the south purified the atmosphere all round (Vd. 3:42). the wind blowing [55] towards the soul of a virtuous man, when it (the soul) passes on to Heaven on the dawn of the third night after death, was said to be sweet-scented and fragrant and to have come from the south (Yasht Fragment 22, Hadokht Nask 2:19). Owing to the belief based on these facts and considerations, the North was always avoided.²

things of offerings. This is intended to prevent particles of saliva falling over the body or over the sacred things and thus to save them from defilement.

- 1 Haug's text and translation in the *Book of Arda Viraf*, p. 315.
- 2 Cf. the ancient Egyptians, while mummifying the dead bodies, pointed the head towards the South (Maspero's *Egypt and Assyria*).

Drawing the *kasha*, or the boundary lines.

After placing the corpse on slabs of stones, one of the two persons, draws round the body three *kashas*¹ or circles with a metallic bar or a nail. This is intended to show that the ground within the circle is temporarily set apart for the corpse, and that nobody is to go to that part of the ground lest he should catch infection.

Separate apartments for the dead bodies.

In ancient Persia, almost all houses were provided with separate apartments for placing the corpse before its removal to the Towers of Silence (*dahkmas*). In the case of the poor who could not afford to have such separate apartments there was a separate house for the purpose in every street. The poor carried their dead to such houses before removing them to the Towers. "Ahura Mazda said: 'In every house, in every street, they should make three *katas* (separate parts of ground) for the dead.'" (Vd. 5:10).

It is said that even now, such separate houses are provided in the Parsee streets in Persia where the parties take their dead and perform the funeral ceremonies before removing them to the Towers of Silence. Such houses are known as "*margzâd*" [mortuary]. Up to late, some of the mofussil towns of Gujarat had such separate houses for the dead in Parsee streets. They were known as *Nasâkhânâs*, i.e., the houses for the dead bodies. Every Parsee town has a *Nassâ-Khânâ*, but now it is generally used as a depot for the biers, the slabs of stones above [56] referred to, the shrouds and such other requisites for the removal of the dead. The Vohuman Yasht (2:36) speaks of it as *Nasâi-kata*² (corpse-chamber).

Their sanitary isolation.

It is enjoined that the place to be chosen for such apartments or houses for the dead should be free from dampness, should be the least frequented by men and animals, and should be far away from the place where religious ceremonies are performed. The *Vendidad* (8:5) says: "Ahura Mazda said that (they must choose) in the house of a Mazdayasnian the cleanest and the driest place which is the least frequented by cattle and beasts of burden, by the fire of Ahura Mazda, by the *barsom* spread through piety and by the holy man." After having placed the body on one side of the ante-room, either on slabs or on a part of the ground dug and specially prepared, the two persons, who were up to now arranging all these things, now leave the

1 *Vide* my paper on "Iranian *kashas* and the Boundary lines of the Roman Lustrum" (Journal of the Anthropological Society of Bombay, Vol. VIII, pp. 520-30. My *Anthropological Papers*, Part I., pp. 331-39).

2 Dastur Kaikobad Adarbad's Text, p. 7. S.B.E., Vol. V., p. 205.

house, still holding the *paywand* between them. They then finish the Srosh Baj prayer, a part of which they had recited before commencing their work.

The Sagdid. Its object.

One of the ceremonies is that of the *Sagdid*. The word "Sagdid" is made up of *sag*, a dog, and *did*, sight, and means "the sight of a dog." A dog, usually a four-eyed (*Chathru-chashma*) dog, i.e., a dog with two eye-like spots just above the eyes, is made to see the corpse.¹

As regards the purpose why the *sagdid* is performed, various reasons are assigned: (a) Some say that the particular class of the spotted (*chathru-chashma*, or the four-eyed) dog had the characteristic of detecting whether life in the body of a man [57] was extinct or not. It stared steadily at the body if life was extinct, and did not look at it at all if life was not altogether extinct. Thus the purpose for the *sagdid* among the ancient Iranians was to ascertain, before the disposal of the body, whether life was really extinct. (b) Others, as Dr. Haug says, attributed the *sagdid* to some supposed magnetic influence in the eyes of the dog. (c) There were others who connected the *sagdid* of the dog, which of all animals is the most faithful to his master, with the idea of loyalty and gratitude that must exist between the living and the dear departed ones. (d) M. Abel Hovelacque thinks that the respect which the Mazdayasnians professed for the dog may be due either to a recollection of ancient belief of which the correct meaning may have been lost or to a special motive. That motive may be the expression of the recognition of the dog's valuable services in a society where the country life, agriculture, and the breeding of the cattle played a role of great importance.² (e) Again, others considered

1 It appears from the customs of several ancient nations that the dog played a prominent part in the funeral ceremonies of these nations. (a) Compare the *Chathru-chashma* of the Avesta with the "four-eyed dogs" of the Rig-Veda (tenth Mandala) which guarded the way to Yama's abode; "Fear not to pass the guards — The four-eyed brindled dogs — that watch for the departed". Mon. Williams *Indian Wisdom* (1876, p. 22). (b) Among the ancient Romans, Lares of the departed virtuous, were represented in pictures with a dog tied to their legs. This was intended to show, that as the dogs watched faithfully at the door of their masters, so the Lares watched the interests of the family to which they belonged, (c) The people of the West Indies have a notion among them of the dogs accompanying the departed dead. Cf. the following lines of Pope; "Even the poor Indian whose untutored mind / Sees God in clouds or bears him in the wind; / Thinks admitted to yon equal sky / His faithful dog shall bear him company."

2 Ce respect que le Mazdéens professaient pour le chien avait-il un motif spécial; était-il le souvenir d'anciens événements, d'anciennes croyances dont on pouvait bien avoir perdu déjà le véritable sens, c'est ce que nous ne pouvons assurer. Faut-il simplement en voir la cause dans la reconnaissance à laquelle le chien devait avoir un si juste titre pour ses bons offices, dans une société ou la vie de campagne, la culture de la terre, l'élevage du bétail jouissent un rôle si considérable? Peut-être les

the dog to be symbolical of the destruction of immoral passions. Death put an end to all passions; so, the presence of a dog near the dead body emphasized that idea. Cf. Dante's following lines:— [58]

For that fell beast whose spite thou wailest o'er,
Let no man onward pass along her way.

.....

Many the creatures are that with her wed,
And will be more until the greyhound come;
Who with sharp agony shall smite her dead.

(*Divine Comedy*, Hell, Ch. I, ll. 94-102; Dr. Plumptre's translation.)

In these lines, the greyhound is considered as the deliverer of Italy. He is the symbol of the destroyer of the passions of sensual enjoyment, pride and avarice which are represented by the leopard, the lion, and the wolf.¹

(f) Some connect the idea of the *sagdid* with the symbolic idea of the two dogs — the *Canis major* and the *Canis minor* in the Orion at the Chinwad bridge, which is the Milky Way.²

The *sagdid* is performed twice during the process of putting on the shroud and is repeated in every Gah,³ as long as the corpse is in the house. It is repeated just when the new Gah begins. It is enjoined that in case a dog is not procurable, the *sagdid* of flesh-devouring birds like the crows and vultures may be allowed; that is to say, it will do, if a flesh-eating bird happens to pass and see the corpse from above.⁴ [59]

Fire kept burning in the room.

After the first *sagdid*, fire is brought into the room in a vase and is

deux opinions ont-elles ici, comme bien souvent, une égale raison d'être." (*L' Avesta, Zoroastre et le Mazdéisme*, par Abel Hovelacque, (1880) p. 337).

- 1 For the various beliefs about the dog, *vide* "The Dog in Myth and Customs" by E. T. Leith (Journal of the Anthropological Society of Bombay, Vol. III, pp. 302-306 and pp. 360-362). *Vide* my paper on "The Tibetan Mode of the Disposal of the Dead. Some side-light thrown by it on some of the details of the Iranian mode as described in the *Vendidad*. A study" in the *Sir J. J. Z. Madressa Jubilee Volume*, edited by me, pp. 347-35.
- 2 *Sir J. J. Z. Madressa Jubilee Volume*, p. 317.
- 3 The *Gahs* are the five different periods of the day. The first Gah, Hawan, begins with the dawn of the day and ends at twelve noon or midday. The second, Rapithwin, runs from twelve noon to three o'clock in the afternoon. The third, Uzerin, begins at three and continues until it is dark. The fourth, Aiwisruthrem, commences from when it is dark, and lasts upto midnight. The fifth Gah Ushahin, commences from midnight, and lasts upto the dawn of the day.
- 4 "Or, the flesh-eating birds fly in the direction." (Vd. 7:3.)

kept burning with fragrant sandalwood and frankincense. This is done with a view to destroy the invisible germs of disease that may be floating in the air in the room where the corpse is placed before its removal to the Tower of Silence [dakhma]. We read the following in the *Vendidad* (8:79, 80) about this sanitary use of fire: “O holy Zarathushtra! If one carries with purity (for the fire) the *aêsma* (i.e., the wood) of the plant *Urvâsna*, or *Vohugaôna*, or *Vohukêrêti*, or *Hadhânaêpata*.¹ or any other fragrant tree, the fire of Ahura Mazda goes to fight a thousand times against the invisible evil daevas² in all the directions in which the wind spreads the fragrance of the fire.”

Prayers by a priest.

Then a priest sits before the fire and recites the Avesta till the time of the removal of the corpse to the Tower (dakhma), and keeps the fire burning. It is not absolutely necessary that a priest should recite prayers at this time. Any person in the house can recite prayers and keep the fire burning. The priest and all other persons are enjoined to sit at a distance of at least three paces from the corpse, so that in case the deceased died of an infectious disease, there may be no danger or risk to the health and life of the living. We read the following about this enjoinder: “O Creator of the material world! At what distance from the holy man (should the place of the corpse be)?” Ahura Mazda replied, “three paces.” (Vd. 8:6, 7.)

Time for the removal of the body to the tower.

The corpse may be removed to the Tower (dakhma) at any time during the day. As it is enjoined that “the Mazdayasnians should expose the body to the Sun,” (Vd. 5:13), the removal of the body at night is strictly forbidden. If death takes place early at night, the body is removed the next morning; but, if it takes place late [60] at night or early in the morning, it is removed in the afternoon. In the case of an accidental death, a long interval is generally allowed. The *Vendidad* (7:4-5) says, that in a such a case, the decomposition does not commence as early as in the case of a body that was suffering from illness, but commences after one Gah, or one period of the day; and so, it is not detrimental to the health of the living to keep the body some time longer.

The corpse-bearers.

About an hour before the time fixed for the removal of the body to

1 All these are species of fragrant plants, the burning of the wood of which destroyed germs of disease.

2 The word “*daêva*” is used in the Avesta for all evil influences or things, whether physical, mental, or moral.

the Tower (dakhma), two — or four if the body is heavier — *Nassâsâlars*,¹ i.e., corpse-bearers, clothed in perfect white, enter the house, after having said and performed the Padyab-Kusti. All the parts of the body except the face are covered up. They put on *dastânek* (i.e., covering for the hand) over their hands. The exposed parts of the body are covered up to ensure their safety against catching infection through any uncovered part, should the deceased have died of an infectious disease. They enter the house holding a *paywand*² between them and carry an iron bier, called *gekân*,³ to remove the body. Wood being porous and therefore likely to carry and spread germs of disease and infection, its use is strictly prohibited in the funeral ceremonies. So, the bier is always made of iron. [61]

The number two plays a prominent part in all funeral ceremonies.

The corpse-bearers must be at least two, even if the deceased were a mere infant that could be carried by a single person. “Nobody should carry the dead alone” (Vd. 3:14). If the body is heavy, it must be carried by four, six, eight, ten, or any such even number. A pair, or the number two, plays a prominent part in all the ceremonies for the disposal of the dead body and that pair always holds a *paywand* between them. After death, the body must never be left alone or in the company of only one person. After washing it, there must be always two persons sitting by its side. Again the persons, who put on the shroud and place it on slabs of stone in a corner of the house before its removal to the Tower (dakhma), must be two. We will see further on, that the priests who say the last funeral prayers at the house are also two. The persons who attend the funeral procession to the Tower also go in pairs of two and two, holding a *paywand* in the form of a handkerchief between them. A single individual should never attend the funeral. The injunction of having pairs in all these funeral ceremonies is intended to create a view of sympathy and mutual help.

1 The *Nasu-Kashas* of the *Vendidad*. In large towns or centres of Parsee population, there are generally two classes of corpse-bearers, (a) The *Nassâsâlars*, who go to the house and place the corpse on the bier, and who afterwards enter the Tower [dakhma] and expose the corpse there. (b) The *Khândhâs* (lit., those who carry the body on their *Khândh*, i.e., shoulders) whose business is to carry the bier of the corpse from the house to the Tower. In small towns where the Parsee population is scarce, one and the same persons perform both the works. In smaller towns where the Parsee population is more scarce, there are no paid professional carriers of this type and the corpses are disposed of by the relations and friends of the deceased. In Bombay, it being the head-quarters of the Parsees, there is a paid staff of about 50 professional corpse-bearers of both the classes.

2 *Vide* above, p. 54.

3 Perhaps from Pers. *gâh* bed, meaning the last bed.

The recital of the Bâj.

The corpse-bearers, on entering the house, place the bier by the side of the corpse and then “take the *Baj*.”¹ They then recite a formula in a suppressed tone which says:

(We do this) according to the dictates of Ahura Mazda, according to the dictates of the Amesha Spentas, according to the dictates of the holy Sraosha, according to the dictates of Adarbad Mahraspandan,² and [62] according to the dictates of the Dastur of the age.³

By the recital of this formula, known as the Dasturi formula, they declare that they undertake to perform all the ceremonies for the disposal of the dead as enjoined in the religious books and as directed by the Head-priest of the time. Then they sit silent by the side of the corpse. If they have at an any occasion to speak, they speak with a kind of suppressed tone, without opening the lips, which is said to be speaking in *baj*.

The *geh-sarnu* prayer.

Then follows the *geh-sarnu* (*Gêh-Sârânâ*) ceremony, i.e., the recital of the Gatha. Its recital was intended as a sermon and exhortation to give moral courage to the survivors to bear up with fortitude the loss of the deceased and as a protection against the spread of disease. We read the following on this point in the *Vendidad* (10:1, 2): “Zarathushtra asked Ahura Mazda: ‘O Ahura Mazda! Most beneficent Spirit! Holy Creator of the material world! How are we to stand against the *druj* (evil influence) which runs from the dead to the living? How are we to stand against the *nasu* (evil influence) which carries infection from the dead to the living?’ Then Ahura Mazda replied: ‘Recite those words which are spoken twice in the Gathas.’” The words referred to in this quotation occur in a passage in the beginning of the Ahunawad Gatha.

In this *geh-sarnu* ceremony, two priests perform the *Padyab-Kusti*, and, after reciting the prayers for the particular Gah, go to the

1 “To take the Baj” is to recite the Srosh-baj prayer up to the word “Ashahé” in the Kem-na Mazda prayer which forms a part of the Srosh-Baj (Darmesteter, *Le Zend Avesta* II, pp. 686-88). When the particular work of a person in connection with the disposal of the dead body is finished, the baj is also then finished, i.e.; the remaining part of the Srosh-baj is recited. This baj is also taken by the priest at the time of bathing and in the barashnom ceremony.

2 He was a well-known Dastur or Head priest of the Sasanian times, and took an active part in the renaissance of the Zoroastrian religion after the long period of ignorance in the times of the Parthians.

3 Here they recite the name of the Head-priest, if there be one, of the time at the town.

chamber where the dead body is placed, and standing at the door or inside the door at some distance from the body, and holding a *paywand*¹ between them, put on the *padan*² over their face, take the *baj*³ and recite the Ahunawad Gatha (Y. 28-34) which treats of Ahura Mazda, his Amesha Spentas or immortal archangels, the future life, resurrection, [63] and such other subjects. After reciting nearly half of the Ahunawad Gatha (up to 31:4), they stop for about a minute. The corpse-bearers now lift the corpse from the slabs of stone on which it is lying and place it over the iron bier. The two priests now turn towards the bier and recite the remaining half of the Ahunawad Gatha.⁴

Geh-sarnu ceremony of pregnant women.

If the deceased person is a pregnant woman in the fifth month of her pregnancy when the child is supposed to have some life, the *geh-sarnu* ceremony is enjoined to be performed by two pairs of priests. The *sagdid*, above referred to, is also by two dogs, one for the woman and the other for the child. Again the body also is to be carried out of the house by two pairs of Nassasalars (Sls. 10:10;⁵ Sad-Dar 70:5).⁶

The last look.

When the recital of the Gatha is finished, the final *Sagdid*⁷ is performed, and then the relations and friends of the deceased who have by this time assembled at the house, have a last look of the deceased. In such an assembly, the females assemble in the house, and the males outside the house or in the street. The males, one by one, pass before the corpse, have a last look, and out of respect make a bow, which process is called *sijda*.

Removal from the house.

When all have had their last look and paid their respects, the

1 *Vide* above, p. 53.

2 *Vide* above, p. 53n.

3 *Vide* above, p. 61.

4 It seems, that at one time, in Persia, and even in India, the Geh-sarnu prayer at the house was finished at this part of the recital and the body was removed to the Tower [dakhma], the rest of the prayer being recited on the way to the Tower. (*Vide* my paper on "The Geh-sarna Recital as enjoined and as recited about 150 years ago," in the *Sir J. J. Z. Madressa Jubilee Volume*, edited by me, pp 415-20.)

5 S.B.E., Vol. V, p. 319. It is said that when the body of a pregnant woman has to be carried, in unavoidable circumstances, by two persons, these two persons must go through the barashnom purification (Sls, 2:6. S.B.E., Vol. V. p. 247).

6 S.B.E., Vol. XXIV. p. 335.

7 *Vide* above, p. 58.

corpse-bearers cover up with a piece of cloth the face of the deceased which was up to now open, and secure the body to the bier, with a few straps of cloth [64] so that it may not fall on being lifted up and carried. They then carry the bier out of the house and entrust it to the Khândhiâs who are, as said above,¹ another class of corpse-bearers whose only business is to carry the bier of the corpse on their shoulders from the house to the Tower (dakhma). The number of these carriers varies according to the weight of the body to be carried. Before lifting up the body, these carriers also “take the baj” and arrange themselves in pairs of two holding the *paywand* between them.

Gomez, or cow’s urine as a purifier or disinfectant.

Immediately after the removal of the body from the house, Gomez, i.e., the urine of the cow, is be-sprinkled over the slabs of stone on which the body was placed and over the way by which the corpse-bearers carried the body out of the house. The slabs of stone are now generally removed from the house immediately after the removal of the body.²

The gomez or cow’s urine is spoken of as *nirang*, because its application or use is generally accompanied by the recital of a *nirang*, i.e., a prayer formula. Cow’s urine was believed by the ancient Zoroastrians to possess disinfecting properties. So, in order to destroy the germs of impurity and disease, if any, it was besprinkled on the place where the dead body was placed.³ For the same reason, cow’s urine played a prominent part in cleaning impurities attached to things that came into contact with the decomposing matters of men and animals. Such things are first asked to be purified or washed with cow’s urine and then with water (Vd. 7:74-75). Utensils or articles of furniture made of wood, clay, or porcelain that come into contact with a decomposing body are condemned altogether. Being porous, they are held to have possibly caught the germs [65] of disease from the dead body and are therefore considered to be unsafe for further domestic purpose (Vd. 7:75).⁴

1 *Vide* above, p. 63, note 19.

2 In some of the Mofussil towns, at least in the orthodox families of the towns, the slabs are kept in the house for 10 days or 30 days according as the season of the year be winter or summer. This injunction seems to have been based upon the *Vendidad* (chap. 5:42).

3 Vd. 19:21.

4 According to Dr. Eugene Wilhelm, many other ancient nations besides the Persians used cow’s urine as a disinfectant. *Vide* Dr. Wilhelm’s paper “On the use of Beef’s

The Funeral Procession.

When the bier leaves the house, out of respect for the deceased, all the male relations and friends of the family that have assembled at the house of the deceased, or at times only the elders, follow the bier for some distance from the house or upto the end of the street. There, they make a last bow to the deceased and stand aside, giving way to those relations and friends who wish to accompany the funeral procession to the Tower of Silence (dakhma). These follow the bier at a distance of, at least, thirty paces. The rest of the assembly now disperse. Before entering into their houses or places of business, they wash their face and other exposed parts of their body and perform the *kusti*. All those who go with the funeral procession to the Tower are clothed in full white dress. They arrange themselves in pairs of two, hold a *paywand* between them, take the *baj* and silently march to the Tower. The procession is headed by two priests. On this point we read in the *Vendidad* (8:14, 19-21): “O Holy Creator of the material world! How does the road over which a dead man is carried become passable for cattle, etc.?” ... (Reply) “First, the Athravan (i.e., the priest) should pass by the road, reciting the victorious words (of *Yatha Ahu Vairyo* and *Kem-na Mazda*).”

The Disposal in the Tower.

When the bier reaches the Tower, at first it is put on the ground outside and the Nassasalars uncover the face of the body. Those who have accompanied the funeral procession pay their respects and have a last look from a distance of at least three paces. Then *sagdid* is once more performed and that for the last time. In the [66] meantime, the gate of the Tower which is kept locked with a metallic lock is opened. The Nassasalars who had fetched the corpse out of the house and entrusted it to the carriers and who have accompanied the corpse, now resume charge of the body. They lift up the bier and carry it into the Tower. They remove the body from the bier and place it on one of the “*pâvis*.”¹ They then tear off the clothes from the body of the diseased and leave it (the body) on the floor of the Tower. We read on this point in the *Vendidad* (8:10) “Two powerful persons may carry him and place him naked without any clothes on this earth, on clay, bricks, stone and mortar.” The body must be exposed and left partly

Urine, according to the precepts of the Avesta and on similar customs with other nations.” According to Dr. Haug, the peasants of several parts of Europe, even now, use cow’s urine for a similar purpose. (Haug’s *Essays on the Parsees*, second Edition, p. 286). “The use of *gomez* has been lately found to be known in Basse-Bretagne (Luzel, *Le Nirang des Parsisen Basse-Bretagne*, *Melusine*, 493)” Darmesteter. S.B.E. IV, first ed. Introd. p. LXXXVIII n. 3.

1 The platform of the Tower is divided into separate sections named *pâvis*. Each corpse is placed on a separate *pâvi*.

uncovered, so as to draw towards it the eye of the flesh-devouring birds and to fall an easy prey to them. The sooner it is devoured, the lesser the chance of further decomposition and the greater the sanitary good and safety. The clothes removed from the corpse are never used for, any purpose whatever, but are thrown in a pit outside the Tower, where they are destroyed by the combined action of heat, air, and rain. In Bombay they are further destroyed with sulphuric acid.

On the Nassasalars completing their work in the Tower and on their locking the Tower, notice is given, by a clapping of hands by a servant, to all those who have accompanied the funeral procession and who have by this time taken their seats at some distance from the Tower, to say that the body is placed in the Tower. They all get up from their seats and finish the *baj*, i.e., recite the rest of the Srosh-baj, of which, before joining the procession, they had recited only a part. They now leave off the *paywand* and recite a short prayer which says: "We repent of all our sins. Our respects to you (the souls of the departed). We remember here the souls of the dead who have the spirits of the holy." They then apply cow's urine (*gomez*) to the exposed portions of their body and then wash them with water. They untie and regirdle the *kusti* with its usual formula, of prayer. Then some, especially the priests, say the *patet* or [67] the Repentance prayer, mentioning the name of the deceased in the last portion of the prayer and thus ask the forgiveness of God upon the deceased. As said above, the *Vendidad* enjoins that only two priests must attend the funeral procession with a view to direct and advise the adoption of the necessary rites and ceremonies. But generally, the family invites more than two priests to accompany the procession and to say the prayers at the Towers. All of them are paid for their services. This being done, all return home and generally take a bath before following their ordinary vocations.

The Tower (*dakhma*).

A short description of the Tower of Silence¹ will not be out of place

1 The Parsee word for a Tower of Silence is *dakhma*, which is used in the general sense of a receptacle for the dead. The English phrase "Tower of Silence" seems, as pointed out by Sir George Birdwood, to have been first used by the late Mr. Robert Zavier Murphy, who was for some time the Oriental Translator to the Government of Bombay. The round tower-like construction of the building seems to have suggested to him the use of the word "Tower." Then, in Persian and also in Hindustani, the word *Khâmush*, i.e., silent or *Khâmushi*, i.e., silence, is often used in connection with the dead. The dead are alluded to as being *Khâmush*, i.e., silent. Hence this Persian word *Khâmush* seems to have suggested to Mr. Murphy, who was versed in oriental learning, the word "silence" in connection with the word Tower.

here. The Tower of Silence wherein the dead bodies are exposed to the sun and to the flesh-eating birds, is generally built on the top of a hill or on an elevated ground. We read on this point in the *Vendidad*: "O Holy Creator of the material world! where are we to carry the bodies of the dead? O Ahura Mazda! where are we to place them?" Ahura Mazda replied: "O Spitama Zarathushtra! on the most elevated place" (Vd. 6:44-45). On such an elevated place, an isolated spot, away from human dwellings, is chosen for the Tower. Its construction all along is just in accord with the view held in the performance of the ceremonies for the disposal of the dead, *viz.*, the sanitary view, which enjoins that, while disposing of the dead body with all respect due to the deceased, no injury or harm should be done to the living. The Tower is a round massive structure built throughout of solid stone. A few steps from the ground lead to an iron gate which opens on a circular platform of solid stone with a [68] circular well in the centre. The following is a short description of a Bombay tower as given by Mr. Nusserwanjee Byramjee, the late energetic Secretary of the public charity funds and properties of the Parsee community.

The circular platform inside the Tower, about three hundred feet in circumference, is entirely paved with large stone slabs well-cemented, and divided into three rows of shallow open receptacles, corresponding with the three moral precepts of the Zoroastrian Religion — "good deeds," "good words," "good thoughts." (The three rows are used as follows:)

- First row for corpses of males.
- Second row for corpses of females.
- Third row for corpses of children.

The clothes wrapped round the corpses are removed and destroyed immediately after they are placed in the Tower — "Naked we come into this world and naked we ought to leave it."

There are footpaths for corpse-bearers to move about. A deep central well (*bhandâr*) in the Tower, about 150 feet in circumference (the sides and bottom of which are also paved with stone slabs) is used for depositing the dry bones. The corpse is completely stripped of its flesh by vultures within an hour or two, and the bones of the denuded skeleton, when perfectly dried up by atmospheric influences and the powerful heat of the tropical sun, are thrown into this well, where they gradually crumble to dust, chiefly consisting of lime and phosphorus;— thus the rich and the poor meet together on one level of equality after death.

There are holes in the inner sides of the well through which the rain water is carried into four underground drains at the base of the Tower. These drains are connected with four underground wells, the bottoms of which are covered with a thick layer of sand. Pieces of charcoal and sandstone are also placed at the end of each drain, which are renewed from time to time. These double sets of filters are provided for purifying the rain water passing over the bones before it enters the ground — [69] thus observing one of the tenets of the Zoroastrian religion that “The Earth shall not be defiled.”

The vultures (nature’s scavengers) do their work much more expeditiously than millions of insects would do, if dead bodies were buried in the ground. By this rapid process, putrefaction with all its concomitant evils, is most effectually prevented. According to the Zoroastrian religion, Earth, Fire, and Water are sacred and very useful to mankind, and in order to avoid their pollution by contact with putrefying flesh, the Zoroastrian religion strictly enjoins that the dead bodies should not be buried in the ground, or burnt, or thrown into seas, rivers, etc.

In accordance with their religious injunctions the Parsees build their Towers of Silence on the tops of hills if available. No expense is spared in constructing them of the hardest and the best materials, with a view that they may last for centuries without the possibility of polluting the earth or contaminating any living beings dwelling thereon.

However distant may be the home of a deceased person, whether rich or poor, high or low in rank, he has always a walking funeral — his body is carried to the Towers of Silence on an iron bier by official corpse-bearers and is followed in procession by the mourners, relatives, and friends, dressed in white flowing full-dress robes, walking behind in pairs and each couple joined hand in hand by holding a white handkerchief between them in token of sympathetic grief.

In the compound of the Tower, at a short distance from it, there is a small building called *sagri*, where a sacred fire is kept burning day and night. In mofussil towns, where it is not convenient to keep fire burning, at least, a light is kept burning.

The Consecration of the Tower.

The construction of a Tower is accompanied by religious ceremonies¹ which are performed at different times during the

¹ *Vide* below, Consecration ceremonies.

progress of the structure and are therefore divided into three classes:- (1) The ceremony of digging the ground. (2) The “Tana” ceremony, or the ceremony of laying the foundation. (3) The [70] consecration ceremony after which the Tower is laid open for public use.

The solicitude for the living at the bottom of all the ceremonies.

We have described at great length the funeral ceremonies upto the time of the disposal of the body in the Tower. It appears, that at the bottom of a good many of them lies a great solicitude, on the part of the lawgivers who framed the rules and dictated the ceremonies, to attend to the sanitary good of the survivors. At first sight, the details may appear irksome, but from the standpoint of sanitation and health, most of them, though enjoined about 3,000 years ago, appear essential. Every precaution is enjoined, so that, in disposing of the dead body, no contamination or injury may result to the living. After a certain time after death, no man except the official corpse-bearers, is allowed to touch the dead body or to come into any contact with it. If somebody accidentally or unavoidably touch the body, he is enjoined to keep himself aloof from and not touch them before he bathes and undergoes a prescribed ceremonial of different washings.

Segregation and Disinfection.

Not only should a man not come into contact with the dead body, but even utensils and other articles of furniture should be kept away from the corpse. If wearing clothes have been defiled by the sweat, vomit, etc., of the dead, they should be altogether rejected and destroyed (Vd. 7:13). If not defiled, they may be purified by the “Gomez” and water. If the clothes are made of leather they must be washed thrice with “Gomez,” rubbed with dry earth thrice, washed with water thrice, and exposed for three months in the air before being used again. If they are made of woven cloth, which is more porous than leather and therefore likely to carry more germs of disease and infection, the above process of cleaning and washing must be repeated six times, and they must be exposed to the air for a period of six months (Vd. 7:14-15). Even the clothes thus purified cannot be used again for religious purposes or for ordinary domestic purposes, but they can be used for other petty purposes. (Vd. 7:18-19) [71]

Utensils for domestic purposes, if they have come into contact with a dead body, require to be washed several times according to the specific gravity of the metal of which they are made. If the utensil is made of gold, it requires one washing with “Gomez” and water and a rubbing with dry earth. An utensil of silver, which is more porous than gold and therefore likely to carry more contagion, requires two similar cleanings and washings. An iron one requires three, a zinc one

four, and a stone one six washings. An utensil of porcelain, wood or clay is to be condemned altogether (Vd. 7:73-75). In the same way, if accidentally a dead body happens to come into contact with stores of grain (Vd. 7:32-35) or of drinking water (Vd. 6:26-41), it is enjoined to reject and condemn a certain quantity in the near vicinity of the body.

Thus, at the bottom of all religious injunctions and restrictions in connection with the funeral ceremonies and the disposal of the dead body, lies the sanitary principle of segregation, prevention of contamination and infection, and the idea of observing simplicity and equality.

We will now speak of some of the observances attended to in the house after the removal of the corpse. They also point to the same end.

A few observations attended to in the house. Fire kept burning.

After the removal of the body to the Tower [dakhma], all the members of the family are required to bathe. Fire is generally kept burning for three days at the spot where the body was placed before removal. Fragrant sandalwood and incense are burnt over it. We have spoken above, about the good attributed to the fire in destroying the germs of disease lurking at the spot where the decomposing body was placed.

Spot set apart.

Again the spot, where the body was placed before removal, is generally set apart and not used for some time. Nobody is allowed to go on the spot for a period of ten days if the season at the time be winter, or for a period of thirty days, if the season be summer, when [72] the decomposition and contamination are generally more rapid. (Vd. 5:42).

Lamp and flowers.

Near the spot where the body was placed, a lamp is kept burning for a period of ten days or thirty days, according as it is winter or summer. In a small pot full of water fresh flowers are kept and changed every morning and evening. On the expiry of the above period, the chamber is washed throughout.

Abstinence from meat diet.

For three days after death, the family abstains from meat and takes food chiefly consisting of vegetable and fish which is called "*parhîzi*" i.e., abstinence. Not only do the family, but even nearest and dearest friends abstain from meat diet. The abstinence is observed as

a sign of mourning. Generally, no food is cooked in the house where death has taken place. The nearest relations of the family prepare the food for the bereaved family and send it over to their place.

On the custom of abstaining from meat diet during the first three days after the death of a member of the family, we find the following injunction in the *Shayest Ne-Shayest* (17:1-3). "In a house where a person shall die, until three nights are completed, nothing whatever of meat is to be placed on a sacred cake (*dron*) therein and its vicinity; but these, such as milk, cheese, fruit, eggs, and preserves, are to be placed; and nothing whatever of meat is to be eaten by, his relations."¹ The *Saddar* says "In every habitation where anyone departs ... the relations should not eat meat for three days." (*Saddar* 78:1-2).²

II. Ceremonies that relate to the soul of the deceased.

We will now speak of the funeral ceremonies performed for the soul after the disposal of the body. A short epitome of some of these is given in the 17th chapter of the *Shayest Ne-Shayest* (S.B.E. Vol. V, pp. 382-84). [73]

The soul sees a picture of its deeds.

According to Parsee Scriptures, the soul of a dead person remains within the precincts of this world for three days.³ In this state it sees before itself a picture of its past deeds. If it is the soul of a pious person, it sees a beautiful picture of its deeds in the past life in the form of a handsome, well-formed, strong damsel and feels happy and joyful. If it is the soul of a wicked person, it sees a horrible picture of its past deeds in the form of an ugly, ill-formed, weak woman, shudders and feels unhappy at the sight and is at a loss where to go.⁴ We read in the *Hadokht Nask*: "Zarathushtra asked Ahura Mazda, 'O

1 S.B.E. V. (1880) p. 382.

2 *Ibid* XXIV, pp. 341-42.

3 Cf. The Christian idea of the resurrection of Christ at the end of three days.

4 Dr. Cheyne calls this "a very noble allegory." He says, "Heaven and hell are not primarily the localities appointed for souls after death; the one is 'life,' 'the best mental state;' the other is 'life's absence,' 'the worst life,' a high doctrine which is embodied in a very noble allegory in the *Vendidad*.... Conscience, in fact, according to the fine allegory, appears to the soul of the deceased man and conducts it to its place." (*The Origin and Religious Contents of the Psalter* by Rev. Dr. Cheyne (1891), pp. 398-99. The Bampton Lectures of 1889). *Vide* Rev. Dr. Casartelli's paper entitled: "Outre-Tombe – A Zoroastrian Idyll" in the *K. R. Cama Memorial Volume*, pp. 74-78. Dr. Haug thought that this allegory suggested to Mohamed "the idea of the celestial Huris." Dr. Cheyne says, "At any rate this Zoroastrian allegory suggested the Talmudic story of the three bands of ministering angels who meet the soul of the pious man, and the three bands of wounding angels who meet the bad man when he dies." (*The Origin of the Psalter*, p. 437).

Ahura Mazda, Beneficent, Spirit, Holy Creator of the material world! when a pious man dies, where dwells his soul for that night? ... Where for the second night? ... Where for the third night?' ” (Yasht Fragment 22; *Hadokht Nask*, Chap. 2:1-18). Then Ahura Mazda replied, “It remains at the place of his body, singing the Ushtawad Gatha (song of congratulation), asking for blessedness thus: ‘Blessedness to him to whom Ahura Mazda of his own will grants blessedness!’” (Yasht Fragment, 22; *Hadokht Nask*, Chap. 2:5. *Vide* Haug’s Text and Translation in *The Book of Arda Viraf*, pp.309-10).

If it is the soul of a wicked man it remains within the precincts of this world for three nights, remembering all the [74] wickedness of its past life and feeling at a loss where it should go. It clamours: “Oh Ahura Mazda! To what land shall I turn? Where shall I go?” (Yasht Fragment, 22; *Hadokht Nask*, Chap. 3. *Vide* Haug’s *Book of Arda Viraf*, p. 315).

Number three symbolically sacred.

The soul of a man thus remains within the precincts of this world for three days. The number three is a sacred number, because it reminds one of the three principal precepts of the Mazdayasnian religion upon which the moral philosophy of the Zoroastrian religion turns. Think of nothing but the truth, speak nothing but the truth, and do nothing but what is right, and you are saved. Your good thoughts, good words, and good deeds will be your saviours in the next world. Therefore it is that, three days after death, the soul of a good man directs itself towards the paradise with three steps of *Humata*, *Hukhta*, and *Hvarshata*, i.e., good thoughts, good words, and good deeds. On the other hand, the soul of a wicked man directs itself to hell with three steps of *Dushmata*, *Duzukhta*, and *Duzvarshata*, i.e., evil thoughts, evil words, and evil actions. We read in the *Hadokht Nask*: “The first step which the soul of the pious man advanced, he placed in *Humata* (good thoughts). The second step which the soul of the pious man advanced, he placed in *Hukhta* (good words). The third step which the soul of the pious man advanced, he placed in *Hvarshata* (good deeds).” (Yasht Fragment, 22:15; *Hadokht Nask* 2:34, *Ibid*, p. 314).

Sraosha as the protecting angel.

Now for the three days and nights that a soul is believed to remain within the precincts of this world, it is under the special protection of Sraosha (Srosh). The Yazata or the angel Sraosha is a guardian angel guiding the souls of men. He is a guardian angel whom the Almighty has appointed to guide the souls of men while living and even when dead. The Yasna says: “O beautiful, holy Sraosha! protect us here in

these two lives, in these two worlds, in this world which is material, in that which is spiritual.” (Y. 57:25).

As Sraosha is the protector of the soul in this world, all the prayers of a Zoroastrian begin with a *Srosh-baj*, which is a [75] prayer for the *Khshnuman* of (lit., for the pleasure of, i.e., for thanking) Sraosha. It is for this reason, that *Srosh Yasht* (Y. 57) is generally recited by a Parsee at night before going to bed, to pray that his soul be under the protection of the angel when he is asleep.

The first three days’ ceremonies at home.

As the soul is under the protection of Sraosha for three days after death, when it is still within the precincts of this world, the religious ceremonies for the soul of the dead during the first three days are performed in the name of, or with the *Khshnuman* of Sraosha. This angel is specially implored by the relations of the deceased to protect his soul. The *Shayest Ne-Shayest* says: “In all the three days, it is necessary to perform the ceremonial (*Yazishn*) of Srosh, for this reason, because Srosh will be able to save his soul from the hands of the demons for the three days; and when one constantly performs a ceremonial at every period (*gah*) in the three days, it is as good as though they should celebrate the whole religious ritual at one time.”¹ We will now describe these ceremonies performed for the first three days in honour of Sraosha.

At the commencement of every *gah*, two or more priests and the relatives of the deceased say the Srosh-baj and the prayers of the particular *Gah*, and the *patet* or the repentance prayer with the *Khshnuman* of Sraosha. At night, at the commencement of the *Aiwisruthrem Gah*, two priests perform the Afrinagan ceremony in honour of Sraosha. They sit on a carpet face to face with a vase of fire and a metallic tray between them. The senior priest, who has the tray before him, is called “*Zaoti*” (from *Zu*, to perform a ceremony), or performer of ceremonies. The other, who has a vase of fire before him, is called the *Atravakhshi*, or the fire-priest. The metallic tray contains a pot of pure water and a few flowers, eight of which are arranged in a particular order. Two of them point to the fire and the remaining six are arranged in two rows of three each, pointing to one another and in a line at right angles to the line in which the first two are arranged. [76]

The *Zaoti* begins the Afrinagan with what is called a *dibache*, i.e., introduction, which is a prayer in the Pazand language, wherein he invokes the protection of the angel Sraosha upon the soul of the

1 Chap. 17:3, S.B.E. Vol. V. (1880) pp. 382-83.

deceased, whom he names in the prayer. When the *dibache*¹ is finished, both the priests recite together the seventh *Kardah* (Av. *Kereta*) or section of the Srosh Yasht, (57:15-18), which sings the praise of the angel for the protection it affords.

The first three days' ceremonies at the Fire-temple.

Besides these prayers and ceremonies, which are performed for three days and nights at the house of the deceased, the Yasna prayers, and sometimes the *Vendidad* with the Khshnuman of Sraosha are recited at an adjoining Fire-temple for three successive mornings and nights. These Yasna prayers and the Baj ceremonies with the Khshnuman of Sraosha, can be performed only at the Fire-temples.

The Uthamnu ceremony

In the Uzerin Gah of the third day, a ceremony is performed which is called the Uthamnu (*Oothamnâ*). The friends and relatives of the deceased and a few priests meet together in an assembly. The particular prayers of the Gah, the Srosh Hadokht (Yt. 11.) and the patet are recited. A Pazand prayer with the Khshnuman of Sraosha is recited, wherein the name of the deceased is announced and the protection of Sraosha is implored for him. This is an occasion for the announcement of charities. This ceremony and this assembly are very important, because, at the end of the ceremony, the relations and friends of the deceased generally announce donations to charity funds in the *naiyat* or memory of the deceased and to commemorate his name. The Parsee community of India has given many lacs of rupees in public charity. Of this sum, a large part was announced at these funeral gatherings of the third day after death.

The custom of commemorating the name.

The Parsees have another custom of commemorating the name of a deceased person if he be a great public benefactor. At the conclusion of the above Uthamnu ceremony on the third [77] day, the head priest generally, or in his absence an "*akâbar*," i.e., a leader of the community, proposes before the assembled anjoman, i.e., the public assembly, that the name of the deceased public benefactor, whose benefaction or good deeds he enumerates, be commemorated by the community consenting to remember the name of the deceased in all the public religious ceremonies in the Dhup-nirang recital. This proposal is sometimes seconded by somebody, or very often it is just placed before the assembly without any formal seconding. When nobody opposes that proposal, silence is taken as consent, and thenceforth the name of the deceased is recited and his soul is

1 Spiegel-Khordeh *Avesta* (Bleek's Translation). Vol. III, p. 172.

remembered in all public religious ceremonies. If the deceased public benefactor has done benevolent acts for the good of the whole Parsee community, in whatever part of the world they be, his name is recited and remembered by the whole community. If the deceased has done good and benevolent acts for the good of the community of his own particular town or district, the anjoman of that town or district alone begins to invoke his name in the religious ceremonies. For example, the name of Sir Jamsetjee Jejeebhoy, the first Parsee Baronet, who rose from very poor circumstances to be a merchant prince of India, and who gave large sums of money in charity, not only for his own co-religionists but for all sections of the mixed community of India, is remembered in the religious ceremonies by the whole Parsee community of India.

This custom¹ is a very old one. It had its origin in the old Avesta times. The Frawardin Yasht contains a long list of the departed worthies of old Iran who had, before the time when the Yasht was written, done some benevolent acts for the good of the Mazdayasnian community. The Afrin-i Rapithwin, written, [78] later on, in the Pazand language, contains a few names of such illustrious departed worthies.

The different formulae for commemorating the names of the deceased.

The formulae used for this purpose have varied at different times. The formula used in the Frawardin Yasht is: "We invoke the Fravashi...." For example, "We invoke the Fravashi of the holy Yima of Vivanghana." The formula used in the Pazand *Afrin-i Rapithwin* is, "May the holy spirit of ... be one with us." For example, "May the holy spirit of Emperor Kai-Vishtasp be one with us in ceremony." The formula used now in the Pazand *Dibache* of the Afrinagan is, "May ... so and so ... of pious soul be remembered here." For example, "May

¹ I am told that a somewhat similar custom prevails at the University of Oxford, where during the bidding prayer, they make "a long statement recalling the gifts of benefactors to the University in times past. It is really a thanks giving to Almighty God for the gifts of the worthies of old who gave lands and money to endow the Colleges and University. The list of benefactors is read out in full on the high festivals in the University Church only." (Dr. L. Mills in a letter).

Behedin¹ Jamshed Behedin Rustam² of pious soul be remembered here. The honour of thus remembering the name of a deceased person in public religious ceremonies was considered to be the greatest honour that a grateful community could bestow upon a person after his death for the good that he had conferred upon his fellow-brethren.

The adoption of a son.

If the deceased is of the age of fifteen and has left no son, it is necessary that a son should be given to him in adoption. The adopted son generally belongs to a nearly-related family. The name of the son thus adopted is declared publicly before the assembly. We [79] find no reference to the system of adoption in the Avesta books. It is the Pahlavi works that refer to it. But the desire to have a son adopted if there is no son of one's own, naturally follows from the desire to have a son of one's own, as alluded to in the Avesta. An Iranian was to aim at a married life and to have a son, and not only to have him but to educate him well. If he did his duty towards his children well, and if being well brought up morally, they performed good acts, he, as a consequence of, or as a recompense for, his carefulness to do his duty, was to participate in the righteousness which resulted from the good deeds of the children. The *Shayest Ne-Shayest* says, "one is to persevere much in the begetting of offspring, since it is for the acquisition of many good works at once; because in the Spend and Nigadam Nasks, the high priests have taught that the duty and good works, a son performs, are as much the father's as though they had been done by his own hand." (Sl. 12:15).³ Thus a son was considered a blessing from several points of view. His good actions were expected to shed lustre upon the good name of the father. Again, he would look after the family interests. He would perform the necessary religious rites of his parents. For all these reasons, an Iranian looked at a son as a great blessing. So, failing a son, he generally wished to adopt one.

1 "Behedin," i.e., "of good religion," is a term applied to the name of a Zoroastrian layman. If the deceased belongs to the priestly class, and has gone through the initiating ceremony of nawar, he is spoken of as "Ervad," which is another form of Herbad, which itself is the later form of Avesta *Aethra-paiti*. If the deceased belongs to the priestly class, but has not gone through the initiating ceremony of the nawar, he is spoken of as "Ostâ" which is the contracted form of Avesta "Hâvishta." If he is a head priest, he is spoken of as Dastur. If the deceased is a female of the priestly class, she is spoken of as "Osti."

2 The second name is the name of the father. If the deceased was adopted, his adoptive father's name is mentioned instead of his own father's. In the case of females, the name of her father is mentioned with hers, if she is unmarried, and that of the husband if she is married. In case of a second marriage, the name of the first husband is mentioned with hers. The Zoroastrians of Persia, and following them the Parsees of the Kadmi sect in India, mention the name of her father.

3 S.B.E., Vol. V., p. 345.

The passage of the soul to the other world on the fourth day.

The dawn after the third night after death is considered a great and solemn occasion. As we said above, the soul of a man remains within the precincts of this world for three days. On the dawn after the third night, it goes to the other world. The soul passes over a bridge called Chinwad.¹ We read in the *Vendidad*: "The soul goes to the holy Chinwad Bridge created by Mazda, which is an old path of immemorial times and [80] which is for the wicked as well as for the holy. There, they ask the soul (to account) for its deeds done in this material world." (Vd. 19:29).

The Chinwad Bridge and Mithra the Judge.

The bridge is guarded by the angel Mithra. The *Vendidad* says: "(When) the third night ends and the dawn shines, the well-armed Mithra appears at the sufficiently happy mountain." (Vd. 19:28). This angel who is known in the later books as *Mihr Dawar*, i.e., Mihr the Judge, is assisted by Rashnu, the Angel of Justice, and Ashtad, the Angel of Truth. They judge a man's actions done in the past life.² If his good deeds outweigh even by a small particle his misdeeds, his soul is allowed to pass over the bridge to Paradise. If his good deeds are equal to his misdeeds the soul goes to a place called hamistagan (hameshta-gehân).³ (Vd. 19:36). If his misdeeds outweigh his good deeds, even by a particle, he is cast down into hell.

Ceremonies at the dawn of the fourth day.

Thus, the dawn after the third night after death is the occasion when the soul of the man is judged by Mihr Dawar, the Judge, assisted by Rashnu Rast, the Angel of Justice, and Astad, the Angel of Truth. Therefore it is considered a very important and solemn occasion for the performance of religious ceremonies for the soul of the deceased. The ceremonies performed in the Uzerin gah on the previous day are repeated, and the Afrinagan and Baj prayers and

1 The Chinwad Bridge reminds one of the "Sirat" of the Arabs, the "Wogho" of the Chinese, the "Gjoell" and "Bifröst" of the Scandinavians. Cf. *the Belief of the Ancient Egyptians*. Vide my paper, "The Belief about the Future of the Soul among the Ancient Egyptians and Iranians" (Journal, B. B. R. A. S., XIX, pp. 365-374. Vide also my *Asiatic Papers*, pp. 137-146).

2 St. Michael is also represented as weighing a man's actions in a scale. Vide my paper on "St. Michael of the Christians and Mithra of the Zoroastrians. A Comparison." (Journal of the Anthropological Society of Bombay, Vol. VI, pp. 237-54. My *Anthropological Papers* Part I, pp. 173-90). For a similar notion among the ancient Egyptians, Vide my paper on "The Belief about the Future of the Soul among the Ancient Egyptians and Iranians." (Journal, Bombay Branch Royal Asiatic Society, Vol. XIX, pp. 365-374. My *Asiatic Papers* Part I, pp. 137-146).

3 The Hameshta-gehan of the Parsees reminds one of the Purgatory of the Christians and the "Aerâf" of the Mahomedans.

ceremonies are performed in addition. This being the time of the judgment of the man's deeds, his relations and friends pray for God's mercy on the soul of the deceased. Man is liable to err, and therefore they implore the [81] blessing and mercy of the Almighty on this particular occasion, when his deeds are judged by the angel Mihr assisted by Rashnu and Astad.

The Baj ceremonies on this occasion are recited in honour of the angels who have an important share in connection with the occasion. The first Baj is in honour of the angels Rashnu and Astad together, who help the angel Mihr. The second is in honour of Ram-Khvastra, who is the angel presiding on the rarified atmosphere or ether. This is because when a man dies, the soul of a good pious man passes away to the higher regions through, or with the help of, rarefied air. The third Baj is in honour of Ardafarosh, i.e., in honour of the spirits of all the departed souls, whose rank the particular deceased, for whom the ceremony is performed, has joined. The fourth Baj is in honour of Srosh who has guided and guarded the soul of the deceased in its sojourn to the other world after death. When the Baj of Ardafarosh is recited, a suit of white clothes, together with the sacred bread and other sacrificial articles, is consecrated by the priest. This suit of clothes is called "Shiâv." It is the *Vastra* in the word *Vastra-vata* of the Frawardin Yasht: "Who will praise us ... with clothes in hand?" (Yt. 13:50). This suit of clothes is generally given to the priest or to, the poor.

Ceremonies on, and after, the fourth day.

The other principal occasions, on which the Afrinagan-Baj ceremonies are enjoined to be performed in honour of the dead, are the "*Chehârum*," "*Dehum*," "*Siroz*," and "*Salroz*," i.e., the fourth day, the tenth day, the thirtieth day and a year after death. The following passage of the *Shayest Ne-Shayest* speaks of the above-said ceremonies of the dawn after the third night and of subsequent ceremonies:

"And after the third night, at dawn, one is to consecrate three sacred cakes (*dron*), one for Rashnu and Astad, the second for Vae, the good, and the third for the righteous guardian spirit (*ardâi fravard*); and clothing is to be placed upon the sacred cake of the righteous guardian spirit... And the fourth day the ceremonial (Yazishn) of the righteous guardian [82] spirit is to be performed; and afterwards are the tenth day, the monthly, and, then, the annual ceremonies." (Sl. 17:4-5. S.B.E., Vol. V, 1880, p. 383).

According to the Zoroastrian belief, the relation between a pious deceased and his surviving relations does not altogether cease after

death. His holy spirit continues to take some interest in his living dear sons. If the surviving relations cherish his memory, remember him with gratefulness, try to please him with pious thoughts, pious words, and pious deeds, it is likely, that these invisible departed spirits will take an interest in their welfare, and assist them with an invisible helping hand. The most essential requisite, by which a surviving relative can please the holy spirits of his departed dear ones, is this, that he should be pious in thoughts, words, and deeds, and that he should perform meritorious charitable deeds. We read in Yasna (16:7): "We praise the brilliant deeds of piety in which the souls of the deceased delight." For this reason, it is not unusual among the Parsees, that on the above-mentioned occasions of the third, fourth, tenth, and thirtieth day, and on the anniversaries after death, they give food and clothing to the poor of their community, and sometimes give various sums in charity. These occasions are further the occasions on which the surviving relatives remember the deceased with feelings of gratitude, respect, and love, and pray to God that his soul may rest in peace and tranquility.

It appears from all the above description, that the funeral ceremonies are intended to produce in the minds of the survivors a great solicitude for the health of the living, respect for the dead, feelings of gratitude and love towards the deceased, and ideas of morality and virtue, inculcated by the thought that death levels everybody, and that one should always be prepared for death which may overtake him at any moment. [83]

PART II. PURIFICATORY CEREMONIES, RITES, AND CUSTOMS

CHAPTER IV. The padyab and the nahn.

Introductory.

Rev. W. F. Blunt¹ in his article on the words “Clean and Unclean,” thus introduces the subject of Purification: “The words ‘clean’, ‘unclean’, ‘purity’, ‘purification’ have acquired in the process of religions development a spiritual annotation which observes their original meaning. Their primitive significance is wholly ceremonial; the conceptions they represent date back to a very early stage of religious practice, so early indeed that it may be called pre-religious, in as far as any useful delineation can be established between the epoch in which spell and magic predominated, and that at which germs of a rudimentary religious consciousness can be detected. In a conspectus of primitive custom, one of the most widespread phenomena is the existence of ‘taboo.’ Anthropology has yet to say the last word about it, and its general characteristics can be differently summarised.” These introductory words of Rev. Blunt on the subject of “purification” suggest the question, whether in the matter of the progress of the world, there was at first, the revelation of truth and then degeneration, or whether there was at first a low state of ideas and then with the advance of time, there was progress and elevation. That is a very large question, and in its consideration, one must remember, that the world has progressed in what may be called cycles of time. From a broad consideration of the question on this special subject of ‘purification,’ we may say that the ancient Iranians had, from remote antiquity, the idea of mental or spiritual purity connected with that of physical purity. The number of different intricate purificatory ceremonies, referred to in the *Vendidad*, may be the result of a later development, existing side by side with the first idea of mental purity, Goethe in his “Notes and Discussions” (Noten und [84] Abhandlungen) connected with his *Parsi-nameh* or *Buch des Parsen*, seems to take that view.²

As said by Dr. Rapp,³ “the Iranians had a cultivated sense for

1 Rev. Hastings' *Dictionary of the Bible*, p. 144.

2 *Vide* my Paper on “Goethe's *Parsi-nameh* or *Buch des Paraen*” *Journal B. B. R. A. S.*, Vol. XXIV, No. 1. (pp. 67-95) p. 93. *Vide* my *Asiatic Papers*, Part II (pp. 119-48) p. 146.

3 “Die Religion und sitte der Perser ünd übrigen Iranier nach den griechischen und römischen Quellen.” (Religion and Customs of the Persians and other Iranians,

purity and decency; whatever has in the slightest degree anything impure, nauseous in itself, instils into them an unconquerable horror. This has a connection in part with the fact, that the impure is mostly even unhealthy and harmful, but in several cases the cause of the impurity does not allow of being traced back to that fact. The Iranians had in a certain measure a distinct sixth sense for the pure. All of that sort has, according to their view, their origin in darkness, in obscurity; in such substances, according to their conceptions, the evil spirits dwell, and when they let such sorts to approach near to them, they thereby offer to the evil spirits admission into, and domination over, themselves.” This view explains the origin of some purificatory rites and ceremonies, which cannot easily, from their surface, be connected with physical purity, sanitation, and health.

Reason, why importance is attached to Purificatory Ceremonies.

Among the ancient Iranians, a good deal of importance was attached, to what we may term, the purification of the body. The reason was, that it was believed — and it is a very reasonable belief — that the physical purity, or the purity of the body, is a step towards the purity of the mind, the purity of the soul. Purity is as essential for the good of the body as for the good of the soul. “*Yaozdâo masyâi aipî Zânthem vahishtâ*”¹ i.e., “Purity is best from the (very [85] beginning of one’s) birth” is one of the most excellent sayings of the Avesta.

Relation of Religion to body and soul.

Religion, has a good deal, a great deal to do with the soul — with the soul of man, with the soul of the universe. And as soul has a close relationship with the body, no religion, no religious system ignores the health of the body. Physical health comes as much into the domain of religion as spiritual health. It is for this reason, as well as for other reasons, that among all ancient nations, it was the priests who were Doctors of Medicine as well as Doctors of Divinity. It was so in ancient Egypt, in ancient Greece, in ancient India, and it was so in ancient Iran.² As Thomson says:—

Even from the body’s purity, the mind
Receives a secret sympathetic aid.

The purity of body is an emblem of the purity of mind. As a writer says: “So great is the effect of cleanliness upon man that it extends

according to the Greek and Roman authors). German Oriental Society’s Journal, Vol. XVII (Leipzig 1863) pp. 52-56. Translated from the German of Dr. Rapp by Mr. K. R. Cama in his “Zoroastrian Mode of Disposing of the Dead,” p. 10.

1 Y. 48:5 (Gatha); Vd. 5.21.

2 Vide my paper on “Education among the Ancient Iranians,” p. 3.

over to his moral character.”

Health of Mind dependent on Health of Body.

According to the Parsi books, upon the harmony of the bodily elements depends the health of mind. Diseases, which are introduced by Ahriman, or the Evil Spirit, disturb the harmony. So, as it is the bounden duty of a Zoroastrian to oppose Ahriman, it is also his bounden duty to oppose that which introduces disease in the body, and to seek that which keeps up health. That is the original object at the bottom of all Zoroastrian Purificatory Ceremonies. Purification was intended to keep the body strong and healthy, so that the strength of the body may act upon the mind and make it strong, healthy and pure. It is with this view that the *Denkard* says “The removal of the sin pertaining to the soul and rendering it precious depends upon the strength of the body; (for) it is owing to the existence of the body that there is cleansing of the sin of the soul.”¹ ‘Mens sana in corpore sano’ is an oft-quoted maxim; but, as Dr. Casartelli says, “It [86] has always been one of the most favourite maxims of Mazdeism.”² Again as Prof. Darmesteter says, “The axiom that ‘cleanliness is next to godliness’ shall be altogether a Zoroastrian axiom, with this difference, that in the Zoroastrian religion ‘cleanliness is a form itself of godliness.’”³ Such being the case, it is no wonder, that in the Avesta, and among the followers of the Zoroastrian religion, a good deal of importance was attached to Health laws and to the purification of the body as a step towards the preservation of health. As religion powerfully impresses upon the mind of the masses the necessity of preserving laws of health and purification, their observation has taken the form of religious ceremonies. An enormous multiplication of these has led and leads, at times, to the frustration of the original good object. A good deal has become mechanical.

A sort of *Padyab* or purification, common in all nations.

A ceremonial *Padyab* or ablution is seen practised in almost all ages and by almost all nations. It was deemed essential, both from the health point of view and from a symbolic point of view. Moses enjoined such ablutions. The ancient Greeks and Romans had them. The modern Mahomedans and Hindus⁴ have them. The Christians

1 Dastur Peshotan’s *Dinkard*, Vol. IV. p. 228.

2 *La Philosophie Religieuse du Mazdéisme sous les Sassanides* par L. C. Casartelli, p. 128.

3 *Le Zend Avesta*, II. Introduction, p. X.

4 *Vide* the *Manu Smriti* and *Nirnaya Sindhu*. *Vide* Mr. Krishnalal Mohunlal Jhaveri’s Paper on “The Cult of the Bath” (*Journal of the Anthropological Society of Bombay*, Vol. IX. pp. 217–24).

have them symbolically in their baptismal rites. The sacred water placed at the doors of Christian churches, in which people dip their hands before entering, is a kind of “Aqua Lustralis” or the water of purification of the ancient Romans.

Two objects of the purification ceremonies.

Purification is held essential among the Zoroastrians from two points of view: (1) Physically, from a Health point of view and (2) Symbolically, from a Moral point of view.

Firstly, from the point of view of Health. Men come into contact with impurities hovering in the air, water, and on the [87] earth. When they know that they have so come into contact, they must purify themselves, and that, not only for their own good, but for the good of others among whom they are likely to spread the contagion. Not only should they purify themselves, but also purify their household things or utensils that may have come into contact with impurities. Again, there are times and cases, when they know, that they have not come into actual visible contact, but there are chances that they may have come into contact with some impurities. So, from a ‘protective’ point of view it is better that they wash or clean or purify themselves.

Secondly, as mind receives some sympathetic aid from the purity of the body, and as the effect of cleanliness extends to one’s moral character, purification of the body seems to be an emblem of the purity of mind.

Four kinds of Purification Ceremonies.

There are four kinds of purificatory ceremonies among the Parsis. They are the following:— I. Padyab. II. Nahn. III. Barashnom and IV. Riman. The first is very simple and is the work of a minute or two. It is performed by all without the help of a priest. The second takes a long time. It takes from about twenty to thirty minutes and one requires the services of a priest in it. The third is a longer affair. It is accompanied by a kind of Retreat, and lasts for ten days, and one has to go through three ceremonial baths. It requires the services of two priests. The fourth requires the services of two persons, one of whom must be a priest. The other may be a priest or a layman. It lasts for about half an hour. Nowadays, it is strictly confined to those who have come into contact with dead bodies. We will first describe the Padyab.

I. Padyab, the first form of purification.

What is the Padyab?

The padyab is the simplest form of purification or ablution which a

Parsi has to go through several times during the day. The word *padyab* is the modern Persian form of Avesta *paiti-â* whose Pahlavi rendering is *pâdyâv*. It means “throwing water (*âb*) over (*paiti*) [88] the exposed parts of the body.” The following is the process of the *padyab*: There are three parts of the process, which all together are known as *padyab-kusti*. The central or the second part is the *padyab* proper, which is preceded and followed by a prayer, (a) The first part of the process or the ceremony is to recite a short formula of a small prayer. The person performing the *padyab* says at first *Khshnaôthra Ahurahê Mazdâo*, i.e., “I do this for the pleasure of Ahura Mazda.”¹ Then he recites the short formula of *Ashem Vohu*.² (b) Having recited it, he washes his face and the exposed portions of his body, such as the face, hands and feet. This is the *padyab* proper. He then wipes off his face and the other parts of the body, (c) Then he finishes the process by performing his *kusti*,³ i.e., he unties and re-ties the *kusti* with the recital of its formula.

Occasions for performing the *padyab*.

The following are the occasions on which a Parsi has to perform the *padyab*:— (1) Early in the morning after rising from his bed. (2) On answering calls of nature. (3) Before taking his meals. (4) Before saying his prayers.

1. The early morning *padyab*.

The first thing that a Parsi has to do on rising from his bed is to recite the short formula of *Ashem Vohu*. This recital is held to be very meritorious as it reminds him as to how to move during the whole of the day in the path of purity and piety. The Hadokht Nask says:

Question.— “What is the one recital of the *Ashem* which is worth a thousand of the other recitals of the *Ashem* in greatness and goodness and excellence”?

Reply.— “Ahura Mazda answered him: O holy Zarathushtra! That, indeed, which a man recites, standing up from sleep [89] praising good thoughts, good words, and good deeds, renouncing evil thoughts, evil words and evil deeds.”⁴

Then he has to apply *gomez* or cow’s urine to the exposed portions

1 This short invocatory formula is recited by a Parsi at the commencement of all his sets of prayers. It signifies that he undertakes to do all his actions for the pleasure of God, i.e., so as to please Him, and for His Honour and Glory.

2 It is a short prayer formula in praise of purity and piety.

3 *Kusti* is the sacred thread put on after the initiation of the Navjote.

4 H1.10-11. *The Book of Arda Viraf*, etc., by Haug. p. 308.

purification was enjoined among the Parsis. The first point of view was that of Health and Cleanliness, and the second that of physical purity or cleanliness reflecting upon the mind as an emblem of mental purity. On the above three occasions, and especially on the first two occasions, the padyab was performed from the first point of view, *viz.*, Health or Cleanliness. On this last occasion, i.e., on the occasion of prayers, it is generally performed with the second point of view, *viz.*, that physical purity is a reflex or an emblem of mental purity, though the first point of view is not altogether absent. A man when he says his prayers, has the idea of the purity of mind before him. Prayer is a process to purify his mind. So, physical purification at the commencement reminds him of that mental purification.¹

II. Nahn, the second form of purification.

The nahn: Meaning of the word.

Nahn is a higher form of purification. The padyab is a daily form of Purification. The nahn is gone through on certain occasions, and therein, the help of a priest is necessary. The word *nâhn* is a contraction [91] of a word *snân* which, though we do not find it in that form in the Avesta, is found in the Sanskrit as स्नान (*snân*). *Snân* means "ablution, bathing." The word comes from the Avesta root *snâ* Sans. स्ना (*snâ*), Latin *Nare*, Fr. *Nager*, meaning 'to bathe.' So, while the padyab is a purification of only the exposed portions of the body, the nahn, being a bath, is the purification of the whole body. The process of this second and higher form of purification consists of several parts. They are the following: (1) The ordinary padyab-kusti. (2) The symbolic eating of a pomegranate leaf and the drinking of the consecrated *gomez* or cow's urine. For the sake of convenience, we will call this process "symbolic communion." (3) The recital of the patet or prayer of repentance. (4) The final bath. Thus the nahn or *snân*, i.e., the bath proper, is preceded by three preliminary processes. We will speak of them in their order.

1. The preliminary padyab-kusti.

At first, the person who has to go through the nahn ceremony performs the padyab-kusti.² The priest, who officiates or makes the person pass through the ceremony, has also performed the padyab-

1 We see this custom of purifying the body, at least as a symbol, among many nations. A Mahomedan performs his *wuzu* (وضو), i.e., ablution before saying his *nimâ* or prayers. A Hindu has his *snân* or bath before his *pujâ*. A Christian's application of the sacred water on entering his church is a relic of the same custom.

2 Vide above, p. 92.

kusti. After the performance of this, the candidate for the ceremony is made to sit on a stool generally made of stone. Wood is generally avoided in these higher forms of purification, because, being more porous, it is supposed to be likely to contain some germs of impurity. The priest who officiates at this ceremony must be a barashnomwala priest, i.e., a priest holding the barashnom,¹ and must be “with the Khub.”²

The alat or the requisite things for the nahn.

He takes with him, in a metallic tray or vessel the following consecrated things known as *alat* (*lit.*, instruments or means) to the house of the person undergoing the nahn ceremony or to the place of the ceremony in the Fire-Temple, if the ceremony takes place there. (a) Nirangdin, i.e., the consecrated *gomez* or cow’s urine. (b) Cow’s urine for application to the body. A small portion of both of these is poured in small cups. (c) Bhasam, [92] i.e., the consecrated ash of the Atash Bahram or the sacred Fire Temple of the first grade. (d) A little sand. (e) A pomegranate leaf.

2. Symbolic communion. (a) The pomegranate leaf.

After the padyab, he makes the candidate “take the Baj,”³ i.e., recite the prayer of grace said before meals. After the recital of this prayer of grace, the candidate is made to eat or rather chew the leaf of the pomegranate tree. The candidate takes the leaf not directly in his hands but on a *paywand*, which, in this case, is a handkerchief or the skirt of his sacred shirt [sudre].

The Pomegranate as a Symbol.

The pomegranate tree leaf, which is technically known among the Parsi priests as “*urvaram*,” (Sanskrit *urvarâ*, Lat. *arbor*, Fr. *arbre*, a tree) or “the tree” is considered as the representative of the vegetable world which supplies sustenance to man. Among the ancients, the pomegranate symbolized the ‘arc,’ the allegorical story of which was compared with the various versions about argus, Arguz, Aren, Arene, Arne, Theba, Baris, Laris, Boutus, Boeotus, and Cibotus of the ancients (*Vide A New System or an Analysis of Ancient Mythology* by Jacob Bryant, Vol. III, p. 73). The ‘arc’ had something like its parallel in the “Damater or Demater” (i.e. the mother) of several ancient nations, which word typified “The womb of Nature.” The “arc” gave forth a number of men and living creatures just as mother earth or the

1 We will speak of this later on. *Vide* below, p. 148.

2 A liturgical qualification.

3 *Vide* Spiegel, translated by Bleek. *Khordeh Avesta*, p. 185.

womb of Nature gives them forth. The pomegranate contains, within the area of its small size, hundreds — nay, thousands — of grains, and so typifies or symbolizes the womb of Nature. It is a symbol of fecundity and fertility. Again, the pomegranate tree is almost ever green. It bears leaves during the whole of the year. So, it is a symbol of all everlasting life. It was held to be sacred by the ancient Babylonians. From all these facts, we can understand why the leaves of a pomegranate tree were given to a child or to an adult at the nahn or the sacred bath ceremony. When used in the Navjote ceremony of a child, its signification reminds one of the words used by a Christian child's god-parents in the baptism ceremony, [93] viz., "It (the child) may so pass the waves of this troublesome world, that finally it may come to the land of everlasting life."

(b) The nirangdin.

Then the candidate is asked to drink from a metallic cup a few drops of the nirangdin or the consecrated urine of the bull. In that consecrated urine,¹ the priest adds a pinch of the *bhasam*² or the consecrated ash of the Fire-Temple. Before drinking it, he is made to declare why he drinks that. He says in Baj, i.e., in a suppressed tone:

In khuram pâki-i-tan, yaôzdâthra-i-ravân râ,

i.e., "I drink this for the purification of my body, for the purification of my soul." The words indicate that the few drops of the nirang are drunk to signify symbolically, that the drinker undertakes to preserve during his life, not only physical purity but also mental purity, purity of life and action. He recites these words three times, and after each recital drinks a drop or two of the nirangdin. This finishes what one may call, the symbolic communion. So, the person now completes or finishes the Baj, i.e., recites the prayers which follow a meal. Having finished it, he performs the *kusti*.

Then the candidate says his patet or the repentance prayer.

3. The recital of the patet or the repentance prayer.

As he has to go through a purifying or expiatory ceremony, he has to confess before God his sins and to repent for them. He purifies his body symbolically of its impurities. This purification is emblematic of the purification of the mind. So, for that mental purification, he must repent for all his sins. The word patet is the contracted form of Avesta "paiti-ita," literally meaning "going back" (from paiti, Sanskrit, prati, Lat., *re*, 'back' and 'i,' Lat. *i-re*, to go). So the word *patet* means 'going back' or 'receding from the transgression of the Law.' It corresponds

1 *Vide Haug's Essays*, second ed., p. 400, n.

2 *Vide Ibid.*, pp. 570-71.

to the Hebrew word *t'shubah* which also means 'returning or going back.'¹ It is a formula of [94] confession, answering to the Buddhists' Patimokkha which literally means "the disbursement."²

4. The Bath.

After reciting the patet, the person retires to the bathroom. After reciting the short prayer formula of *Khshnaothra Ahurahê Mazdâo Ashem Vohu*, he undresses himself. Then placing his right hand over his head he takes the Baj.³ The priest then hands him from outside, with a spoon tied at the end of a long stick having nine knots and called *naogar* or *navgireh* (i.e., a stick with nine knots), the following articles believed to have purifying effects. At first, he hands him three times the consecrated urine of the bull. It is rubbed over the body thrice. Then he gives him thrice a little sand. That also is rubbed thrice over the body.⁴ Then lastly he gives him thrice a little consecrated water called *Âv* (i.e. the water). That also is rubbed over the body thrice. A few drops of the consecrated water is generally sprinkled over the new suit of clothes which the candidate has to put on after the bath. At times, for example, in the case of female candidates, the priest leaves in the bathroom the above three things beforehand and gives instructions to the candidate how to apply them to the body before the bath.

After the application of these consecrated purifying articles, the person bathes with water which itself is consecrated. A few drops of the water consecrated in the nirangdin ceremony, when added to a pot full of water, consecrate the whole water. Having finished his bath and having put on his trousers, the sacred shirt [sudre] and the cap, placing his *kusti* on his shoulders, he [95] finishes the baj which he had commenced before the bath. Then he puts on his *kusti* with the recital of the necessary formulae of prayers. This finishes the nahn ceremony of the sacred bath of purification.

The occasions on which the nahn ceremony is gone through.

The following are the occasions on which a Parsi goes through this

-
- 1 *The Origin and Religious Contents of the Psalter*, by Rev. Cheyne, p. 369.
 - 2 *Vide, Buddhism* by Rhys Davids (1882), pp. 162-63.
 - 3 i.e., recites the Srosh Baj, beginning with three Ashem Vohu and *fravarâne* prayers. A Parsi was enjoined not to speak when bare-headed. Hence the necessity of covering the head with the hand while reciting the formula.
 - 4 It is believed that, at first, sand was used only as a substitute for water where water cannot be found. The Mahommedans are permitted to use sand for their "Wuzu." That sand is known as *khâk* (خاك). The Parsis also use the same word *khâk* for the sand. Sale, in his *Koran*, say that the early Christians also used sand in Baptism when water was not procurable. (Sale's *Koran* (1891) Preliminary Discourse, p. 75.)

form of sacred bath:— (1) The navjote or the investiture with the sacred shirt [sudre] and thread [kusti]. (2) The marriage. (3) Woman at the end of their period of accouchement, (4) The Frawardigan holidays.

1. On the occasion of navjote.

Of the above four occasions, the fourth was always voluntary. The third is the one with which women alone are concerned. The first two occasions, being the occasions of the two most important events in the life of a Parsi, are very important, and so all go through this form of the sacred bath. The sacred bath at the navjote of a child is indispensable. The only difference in its case is, that, as the child has no sacred shirt and thread [sudre and kusti] over its body before this occasion, its preliminary padyab consists of simply reciting the introductory formula and washing the face and the other uncovered parts of the body. It does not perform the kusti.

2. On the occasion of the marriage.

The second most important event in the life of a Parsi, when he goes through this form of the sacred bath, is his or her marriage. Both the bride and the bridegroom go through this on the marriage-day, either in the morning or in the evening, before the celebration of the marriage itself. This Parsi custom of having a sacred bath on the occasion of the marriage reminds us of the sacred bath among the ancient Greeks. Among them, among the ceremonies bearing religious character which preceded the wedding, an important part was played by the bath. Both bride and bridegroom took a bath either in the morning of the wedding day or the day before, for which the water was brought from a river or from some spring regarded as specially sacred, as at Athens, the spring of Callirrhoe (or Enneacrunos), [96] at Thebes, the Ismenus.¹ The Hindus also have a ceremonial bath before marriage.² We learn from Firdausi that this custom of having the sacred bath at marriage is an old Iranian custom. King Behram Gour had taken his Indian wife Sepinoud to the Fire-Temple of Adar Gushnasp for the purpose.³

3. The occasion of Accouchement.

The women at the end of the period of 40⁴ days of their

1 *The Home Life of the Ancient Greeks* by Prof. Blümner, translated by Alice Zimmern, p. 137.

2 *Journal of the Anthropological Society of Bombay*, Vol. IX, p. 219.

3 *Le Livre des Rois*, par M. Mohl, VI, p. 65.

4 The Hindus also have a bath for women at the end of 40 days after delivery (*Jour. Anthr. Sty. of Bombay*, IX, p. 218).

accouchement, go through this purification. Before doing so, they do not touch the domestic fire or go to the Fire-Temples or attend ceremonial gatherings. Not only do those who have been in child-birth, but others who have come into contact with them, also go through this purification. Women among the ancient Greeks¹ and Hebrews, and the early Christians² had such purifications.³

4. Occasion of the Frawardigan Holidays.

The ten days of the Frawardigan Holidays fall at the end of the of the Zoroastrian year. On any one of these days, and especially on any one of the last five days, a Parsi went through this ceremony of purification. Up to a few years ago, these holidays were generally the occasions for this ceremony of purification; but now-a-days it is a custom more honored in the breach than in its observance. Very few practice it in Bombay, but in the Mofussil towns, there are still some who go through this form of purification every year. These annual general occasions remind us of the general occasion for lustration (Lat. *lustrare*, 'to purify') or purification among the ancient Romans. [97]

1 *Vide, The Home Life of the Ancient Greeks* by Prof. Blümner. Among the Greeks, both the mother and those who had come into contact with her, went through a solemn sacred bath.

2 Luke 2.22.

3 *Vide, Dalton's Ethnology of India* (Bengal, the Meshmites) for a similar custom. *Vide also A. Featherman's Social history of the Races of Mankind*, second division, p. 87.

CHAPTER V. The Barashnom and the Riman.

III. Barashnom, the third form of purification.

The subject of the barashnom is very large and intricate. Its description varies a little in the different parts of the *Vendidad*.

I will treat the subject of the barashnom under the following heads:— 1. What is the barashnom? Its meaning. Its original and present object. 2. A description of the barashnom, as given in the *Vendidad*. 3. Barashnomgah, or the place of the barashnom. The ancient barashnomgah and the modern barashnomgah. 4. The process of giving the barashnom. We will treat this third part under two heads:— (a) The preliminary preparation, and (b) The process proper. 5. The retreat of nine full days after the barashnom purification.

1. The barashnom. Its meaning and object.

What is barashnom. Meaning of the word.

Firstly we will speak of: What is barashnom? How it differs from the first two forms of purification? What is its meaning? What was the original object? What is its modern tendency?

Barashnom is the highest form of purification. It differs from the first two forms in several respects:— (a) While the padyab is a work of one or two minutes, and the nahn, of about half an hour, the barashnom, which originally had the object both of purification and segregation, lasted nine days. So, it is, at times, referred to in Parsi books as the *Barashnom-i-Noh Shab*, i.e., the barashnom of nine nights, (b) While the padyab requires no help of a priest, and while the nahn requires the help of one priest, the barashnom requires the services of two priests, (c) While the first two can be performed in any ordinary house or in a temple, the barashnom purification must be gone through in a particular open-air place. Such a place is called barashnomgah, i.e., the place of the barashnom. We will describe this place later on. [98]

This form of purification has taken its name from the word *bareshnu* which means, 'top, head,' from Av. *barez*, Sans. 'to be pre-eminent.' In the description of the process of the particular form of sacred bath gone through in this ceremony, as given in the *Vendidad* (8:40), it is enjoined, that the purification of the different parts of the body must begin from the head or the top (barashnom). The water is first required to be poured over the head from which the impurity passes down step by step. Hence the name. We will speak of these different parts of the body later on.

The original and the modern objects of the barashnom purification.

The original object of the barashnom, as referred to in the *Vendidad*, seems to be to purify those who had come into contact with a worse form of impurity — impurity which, from the sanitary point of view, may be deemed dangerous or infectious. For example, a man, who became unclean by coming into close contact with the dead or, through, what Dr. West calls “any other serious defilement,”¹ was, in ancient Iran, required to go through this purification. Some deaths occurred from infectious diseases, and so, the “contacts,” i.e., the persons who had come into long close contact with such dead, were likely to spread contagion. They were, therefore, required not only to go through purification, but through segregation for nine days. Thus, it was a joint form of *purification* and *segregation*. The original object seems to have been latterly widened, perhaps from a point of view of greater caution. At times, it is difficult for medical men to determine, whether the disease of which a man dies is infectious or not. If it is difficult for an expert medical man to determine that, it must be more so for the ordinary class of people. So, for the sake of caution or safety, it seems to have been enjoined that the living, a short time after death, must keep themselves at a distance from all the dead, whether they died of infectious or of non-infectious diseases. Those, who had, for some purpose or another, to remain in a very long contact with the dead, had to go through the long form of barashnom purification and segregation. [99]

Darmesteter’s view.

While considering the subject of the barashnom or the great purification, in order to have a clear grasp of the purification as originally intended, we must bear in mind what Prof. Darmesteter says on the subject of the ceremonies about the disposal of the dead among the Parsis:² “The principle which governs the ceremonies of the first order is the fear of contagion, or, as the Avesta says, of the Druj Nasu, the Druj of Carrion. Death, that has once come, rests. The

1 S. B. E. Vol. XVIII, p. 431.

2 “Le principe qui domine les ceremonies du premier ordre est la crainte de la contagion ou, comme dit l’Avesta, de la Druj Nasu, la Druj-Charogne. Lamort, une fois venue, reste: la preuve visible en est donnée par la corruption qui bien vite s’empare du oadavre et répand l’infection autour de lui: on se la représentait sous la forme d’une mouche horrible, la mouohe qui bourdomie sur les cadavres (Cf. Farg. VII 2). Toutes les cérémonies de cet ordre peavent se résumer en deux mots, ceux-là même qui résument aujourd’hui toutes les mesures prophylactiques en cas d’épidémie: 1^o interrompre les communications des vivants avec le centre d’infection, réel ou supposé: 2^o détruire ce centre même.” — *Le Zend Avesta*, Vol. II, pp. 146-147; *vide* also *Ibid.* Introduction, page XII.

visible proof of it is given by the corruption which at once goes on in the body and spreads infection round about. It is represented in the form of a horrible fly, the fly which hovers over the corpses. All the ceremonies of this order can be summed up in two words, which are the same as sum up to-day all the prophylactic measures in the case of an epidemic:— (1) to cut off the communications of the living with the centre of infection, real or supposed; (2) to destroy the centre itself.”

On the subject of purification itself, Prof. Darmesteter says: “Purity is, after birth, the greatest good for man’ (*Yaozdâo mashyâi aipi zânthem vahishtâ*) is the principle which dominates the *Vendidad*. This word, ‘purity’ (*Yaozdâo*), though it associates with itself a moral idea or impression, has equally, before all, at least in the *Vendidad*, a conception purely physical; and the word *propreté* (cleanliness) shall be the most exact, if it has taken the moral reflex which the Zend expression has, and which, for example, the English word “cleanliness” has. The axiom ‘Cleanliness is next to godliness’ shall altogether be Zoroastrian, with this difference, that in Zoroastrianism ‘Cleanliness is a form itself of Godliness.’ [100]

“Lawful impurity has always physiological causes. Above all, the corpse is an impure object . . . But he who speaks of impurity speaks of contagion: because the corpse engenders putridity and pestilence..... The purification has for its object the expulsion of this contagion which passes from the dead to the living, and from one living person to another; and the theory of impurity and of purification reduces itself in fact to a theory of hygiene.”¹

Further on, Prof. Darmesteter says: “During the purification, the impure remains isolated from the faithful (i.e., from other Zoroastrians), whom he would (otherwise) defile, in a sort of lazaret. . . . One sees, that they (i.e., the funeral ceremonies) are summed up in two words—two words of hygiene: (*viz.*) to isolate the centre of infection, (and) to destroy that centre. What distinguishes the Zoroastrian conception from the European conception is this, that we busy ourselves in isolating and destroying the dead element only in case of diseases said to be infectious; (but) in Zoroastrianism death is always infectious and contagious.”²

The present object.

Latterly, the original object of the barashnom purification was still further widened. At times, it was enjoined for the physical purification originally intended, and, at times, it was intended to serve as a symbol for mental purification. It served as a kind of purification, both

1 *Le Zend Avesta*, Vol. II, Introduction, pp. X-XI.

2 *Ibid*, p. XII; *vide also Ibid*, p. 147.

physical and mental, which qualified one for some higher religious ceremonies. Now-a-days, the persons who go through this barashnom ceremony are the professional corpse-bearers, who go through it, both before joining the profession and on leaving it. They come into contact daily with dead bodies of men, some of whom may have died of infectious diseases. Of course, after the removal of every corpse to the Towers, they are required to bathe, but, when they leave for good, or at least for a long time, their daily line of business, it is thought to be good and safe that they may go through this [101] higher form of purification, before they mix freely with others. So, one can understand the object of a corpse-bearer gang through the purification and segregation on retiring from his professional work. Looking to the original object of the purification as referred to in the *Vendidad*, it is not easy to understand why he has to go through this purification before he joins his profession. But, in order that he may be prepared for his business which requires extreme caution so as not to spread infection, or that he may be given an idea of the form of purification necessary in case of those who come into direct contact with the dead. It may be with a 'protective' view. In the matter of the purificatory ceremonies of various nations anthropologists occasionally speak of "the purificatory ceremony" as the protective theory. This may be an instance of the latter.

As to the priests, the barashnom is necessary, both for a person who wishes to be initiated for the priestly profession, and for a full-fledged priest, when he wants to officiate in, what may be called, the inner circle of higher ceremonies. In these cases, there is not the origin idea of purification from impurities caught by having come into contact with dead bodies, but the idea of a sentimental and symbolic point of view or a protective point of view. Another reason, which may have, at first, led to the custom, may be this: It was one of the functions of a priest to purify those who had come into contact with the impurities of a corpse. He was, therefore, also known as an *yaozdâthragar*, i.e., purifier. That being the case, it was held advisable that he himself should have at first gone through this purification. Thus, latterly, the original object of the barashnom as enjoined by the *Vendidad*, viz., purification from the highest form of impurities like those arising from coming into long and close contact with the dead, especially the dead who died of infectious diseases, assumed also a symbolic signification. Thus, purification became a priestly function and was thought to be necessary for those priests who wanted to officiate within the inner circle of the Fire-temple and at some of the higher forms of ritual. The original object, latterly, in process [102] of time, took another form. For example, a priest takes a barashnom, and while doing so, declares that he does so for the "*tan pâk*"

(purification of the body) of A, B, or C, who may be living or dead, i.e., he goes through the ceremony, so that the physical or the spiritual body of that person, who is named in the ritual, may have the efficacy of the purification.¹ All this seems to be a later diversion from, or degeneration of, the original sanitary object of the *Vendidad*.

2. Description of the barashnom as given in the *Vendidad*.

Three references to it.

We find references to the barashnom in three chapters of the *Vendidad*:— (a) The first and principal reference is in the 9th chapter (§§ 1-57),² where it is treated at some length. To have a clearer grasp, this chapter must be read with its Pahlavi rendering and commentary.³ (b) The second reference is in the 8th chapter (§§ 35-72).⁴ (c) The third reference is in the 19th chapter (§§ 20-25).⁵

These three references seem to refer to three different forms of pollution, i.e., to three different forms of greater or lesser contact — direct or indirect — with corpses, which, when going through decomposition, are centres of disease and infection. Of course, all persons have to come into some contact with the corpses of their dead relatives or friends for some time after death. But then, they must observe some rules or laws of health, so as not to endanger their own lives, and through themselves, the lives of others. If they do not observe these, there is a likelihood that they may, by some close contact with the dead bodies, catch some germs of disease or infection and transfer them to others. In case they fail to observe those rules by accident or for some unavoidable purpose, in order to avoid any danger, they must go through some purification which may lessen the chance of their infecting others and spreading the disease. [103]

The first reference (Vd. 9) seems to be an account of the purification of an extreme case of contact with a corpse — so extreme, that it requires to be carefully purified and isolated for ten⁶ days, so

1 “In the *taurobolium* purification of the Romans also, the priests went through the purification for ‘the benefit of others’” (*vide* below, p. 163).

2 S. B. E. IV (1880), pp. 119-130.

3 S. B. E. XVIII, pp. 431-454.

4 S. B. E. IV, pp. 103-110.

5 S. B. E. IV, pp. 209-11.

6 It may be remembered here, that the period of 10 days is even now considered by medical men to be the period of incubation for an infectious disease. We speak of 10 days’ quarantine (which originally was of 40 days). If a ‘contact,’ i.e., a person who has come into contact with a person suffering from an infectious disease, is isolated for 10 days and, if he, within that period does not develop that particular disease, he is considered to be safe to mix with others.

that the least chance for the spread of infection may be avoided.

The first reference (9:1-57) in the *Vendidad*.

The following is an outline of the account:— When a person has become polluted or defiled by coming into contact with a dead body, he must seek a purifier who must be (a) righteous, (b) speaker of truth, (c) versed in the *manthras* or holy scriptures, and (d) who has learnt from experienced persons how to purify others. The righteous man with these qualifications must find out a sanitary piece of ground. He must cut off the trees, if there be any, on that ground. The ground chosen must be dry, clean, without vegetation and the least frequented by cattle and men.

On the ground thus selected, nine *magas* or pits may be dug. Then these nine pits must be marked out by 13 *karshas* or furrows which have to be drawn by a sharp metallic instrument. Of these 13 *karshas*, the first must be drawn equidistant from the line of the pits. Then three *karshas* must be drawn round the first three pits. Then other three *karshas* round these first three and second three pits, i.e., round the first six pits. Then, other three, round the nine pits together; lastly, the remaining three *karshas* round the central three pits. Then, the ground thus selected and marked out, or symbolically enclosed, must be covered over with sand or some such kind of drying or disinfecting earth.

Now follows an account of the purification. The purifier is to stand out of the *karshas* drawn as above, and is to ask the infected person or the candidate for purification to advance to [104] the pits. When the candidate has advanced to the first pit, the purifying priest is to say the words

“*Nemaschâ yâ ârmaitish izâchâ*”¹

and is to ask the candidate to repeat them. Each repetition of these words is said to weaken the influence of the infection. The purifying priest has to hold a *naogar* or a nine-knotted stick in his hand and to fasten an iron or leaden receptacle or spoon at its end. He is then to get, at first, the two hands of the candidate washed thrice by means of *gomez* or the consecrated urine poured on his hands by means of the above spoon. If that is not done carefully, the purification that may follow will not be effective or complete. The hands with which the candidate is to clean his whole body must be at first thoroughly cleaned and purified. Then the whole body may be cleaned and purified in a particular way, beginning with the head and gradually coming down to the feet. By this purification from head to foot, the

1 i.e., Praise and commendation to Armaiti, i.e., to the Purity of thought.

evil power of pollution or infection, is said to run away from one part of the body to another, lower down, and, at last, it leaves the body through the lowest parts of the body, *viz.*, the toes of the feet, in the form of a stinking fly. Then, when this is done, the purifying priest is to recite the *Ahunwar* and then the *Kem na Mazda* prayers up to the words "*Astvaitish ashahê.*" The recital of these formulae of prayers is said to be very efficacious and is said to have its good effect on the health of the body.

The above process of purification and the recital of prayers are to be repeated at each of the first six pits, to each of which the candidate is to advance step by step, and at each of which the evil power of pollution decreases step by step and the candidate gets purer. Having gone through this process of purification at each of the first six pits, the candidate is to advance towards the seventh pit, and is to sit at a distance of about $3 \frac{1}{5}$ in. from it. The purification here is with sand or some sand-like substance. He is to rub his body with it 15 times. He is to wait there till the moisture — if any — of the application of the consecrated urine dries off. The sand is supposed to [105] be a purifying substance and it serves to dry the moisture as well. Then he is to go to the seventh pit where he has to purify his body once with water. Then he is to advance to the eighth pit and purify his body twice with water. Then he is to advance to the ninth pit and there purify his body thrice with water. Then his body is to be fumigated with the smoke of the fuel of the wood *Urvâsna*, *Vohû-gaona*, *Vohû-kêrêti*, and *Hadhânaêpata* which were species of fragrant wood whose smoke was believed to have the quality of killing germs.

This finishes the purification proper. The candidate is now to put on his clothes and to retire to a house where he is not to come into physical contact with other persons. He is to remain aloof and away from fire, water, cultivated land, trees, cattle, men, and women. He is to pass three days and nights in such isolation. On the fourth day, he is to wash his body at first with urine and then with water. Then, he is to continue in the retreat, as said above, for three nights more. On the seventh day he goes through a bath again as on the fourth day. He then again remains aloof for three nights more, and then, on the tenth day, has again a bath. Thus, for nine days and nine nights after the first barashnom purification, he is to remain in a kind of isolation and retreat. After the final bath on the tenth day, he is deemed to be perfectly purified and can then mix with all men and women.

The person who purifies must be properly paid by the person who goes through the purification. His fee depends upon the position of the candidate. The purifying person on his part is required to be proficient in his work. If he is not, he is guilty of doing harm to others

and is liable to great punishment.

The second reference in the *Vendidad* 8:35-72.

The second reference to barashnom in the 8th chapter of the *Vendidad* applies to cases, not so serious as in the first reference. While in the 9th chapter, the case is that of a person who is already supposed to have been defiled by a long contact with the dead (*hâm nasûm paiti-iristem*), here, in the 8th chapter, [106] the case refers only to one who has accidentally come into slight contact with (*yâ, nasâum ava-bereta*) a dead body. So, in this second case, the purification is not so irksome as in the first case, both, in point of length of time and in the number of baths or purifications. The process enjoined in this case is as follows:— If the flesh of the dead body has been devoured off by a flesh-eating bird or animal before the person touches it, i.e., if the body is a mere carcase of bones without the flesh on it, then, the most harmful parts of the body being done away with, there is less risk of catching any germs of disease from the corpse. So, in this case, he is simply to wash his body with gomez and water. A simple bath of this kind is sufficient to purify him. But, if the flesh of the corpse is not eaten off and the body is there with all its decomposing parts on it, then, the chances of risk being somewhat greater, the process of purification is as follows:— Three *magas*, i.e., pits must be dug, and the person is to purify his body with gomez on each of them. Then a dog is to be taken near him. This process is to be repeated at a second set of three pits. He is then to wait for some time till the moisture of the urine, applied to his body and head, especially that on the head, dries up. Then, the person is to advance to a third set of three pits. He is to purify his body there, with water. The water must be poured over the different parts of his body from head to foot in a particular way which is the same as that described in the case of the great barashnom purification. Then, finally, he is to recite one Ahunwar and the Kemna Mazda prayer upto the words “*Astvaitish ashahê*.” The person then puts on his clothes and the kusti or the sacred thread, reciting its allotted prayer. This finishes the purification.

The third reference (Vd. 19:19-25).

There is a third reference to a higher form of purification, but it cannot strictly be called barashnom, because, therein, it is not enjoined that the bath should begin from the “*bareshnu*” (head) which word has given the purification its name. It says that if a person has come into contact with a dead body,¹ or if a [107] person has come

1 In modern parlance, such as was used during plague operations in Bombay, such a

into contact with a "contact"¹ he is to go through a process of purification. No pits are mentioned in this purification. He is to wash his body four times with gomez and twice with consecrated water. He is to recite 200 Ashem Vohus and 200 Ahunwars. He is to pray for nine nights.

The difference in the ritual. Its cause.

We find that there is a difference in the ritual, described in the three parts of the *Vendidad*. The tendency is to reduce the rigour and intricacy and to make the ritual simple. The difference may be due to various causes. It may be due (a) to the different views of different priestly writers (b) or to the changed times, when it was found permissible to reduce the rigour, (c) or to the change in places, the priests of one part of the country thinking it advisable to reduce the rigour. When we find that in a limited Parsi population of India, there are differences in ritual in places so close as Bombay, Udvara and Naosari, Surat and Broach, we must be prepared to find them in a large population like that of Iran. As a matter of fact, the Pahlavi Epistles of Manushchihir do point to such differences in later times, in the matter of the barashnom. Zadspram, the high priest of Sukan in the South of Kirman, was found fault with by his brother Manushchihir, the high-priest of the western country, for having made some changes in the ritual of the barashnom.²

I have spoken above of a *karsha*³ or a furrow, of a *padan*, and of a *naogar* or nine-knotted stick, and shall have to speak of them frequently later on. So, I will describe them here. [108]

A *karsha* or *kasha*.

A *karsha* (Sanskrit कर्ष : *karsha*) from the root, "*karesh*" (Per. *kashidan*, to draw) means "a trench or a furrow." The word has a technical meaning in Zoroastrian rituals. At times, sacred or consecrated things or materials are to be kept, for the time being, within a limited space or enclosure, so that persons other than the officiating priests may not come into contact with them. The person in charge of the things, placing the things on the ground, draws round it

person is called a "contact."

- 1 In the language of plague operations, a person who came into contact with a "contact" was known as an "evict," and he also was asked to leave his house and to go to camp.
- 2 Vide *Namakihā-i Manushcheher* by Ervad Bamanji. N. Dhabhar. Vide *S. B. E.* Vol. XVIII, p. 279, *et seq.*
- 3 Cf. The Boundary Lines of the Roman Lustrum. Vide my paper "The Kashas of the Iranian barashnom and the Boundary Lines of the Roman Lustrum" (Journal of the Anthropological Society, Vol. VIII, pp. 520-35).

a temporary circle, trench, or furrow. Suppose, it is the consecrated urine or water that he carries, and, in travelling, he has to place these things aside for a time. Then, he places them on the ground and immediately draws, with a nail, a circle or furrow or trench round it. It need not be very deep. This process, *viz.*, placing the things within the circle so formed, indicates, that it is free from the contact of other undesirable persons or things. If somebody else steps within the circle — or touches it even from without the circle, in which case also the line of isolation is broken — the thing is said to have lost its efficacy of consecration. This *karsha* (or *kasha* as it is ordinarily spoken now) or circle of limit, has a double efficacy. Just as, when you shut a door of a room, you stop a person within from getting out and a person without from getting in, so when you draw a '*karsha*' or the sacred circle, you not only stop — anyhow symbolically — the pollution from without affecting the purity of the consecrated substance within, but, in case the substance itself is undergoing decomposition and is impure, you stop the impurity from going out of the circle and spreading round about. For example, in the barashnomgah, *karshas* having these two different significations are drawn, (a) The officiating priests take into the barashnomgah '*nirang*,' i.e., the consecrated urine, '*âv*,' i.e., the consecrated water, and '*bhasam*,' i.e., the consecrated ash of the Fire-temple. The priest who takes these there, first makes a circle on the ground with a nail or even at times with his forefinger, and then places the consecrated things within the ground thus enclosed. Now, in this case, the circle is believed to protect the consecrated things from the pollution outside or to preserve the efficacy of [109] the consecrated things from being lost. (b) Then take the case of the *karshas* round the pits or holes, where the person to be purified is to go through the different washings and the final bath.

In this case, the *karshas* are meant to limit the circle of pollution. Here, a person who is considered to have been polluted or, to speak correctly, supposed to have been infected with an infectious disease, goes through his washings and baths, and the circles were originally intended to keep the infection confined within the limit, so that it may not spread. The furrows are supposed to be trenches which would prevent the polluted water from his infected body to run beyond that certain limit. The *karsha* that a corpse-bearer draws round about the corpse in the house before removing the body to the Towers¹ is of a similar kind.

Most of these *karshas* are of a temporary kind, but in the Fire-temple, they are of a permanent kind. In the Yazashna-gah, where the Yasna, Vendidad, and Baj ceremonies are performed, such

1 *Vide* above, p. 57, The Funeral Ceremonies.

karshas are necessary. So, there, they are of a permanent kind. There, the stone slabs, which form the pavement, have furrows, about two inches deep and two inches wide, cut in the stones. In the chamber of the Sacred Fire also, there are such permanent furrows cut in the stones of the pavement. These furrows are of the first kind, i.e., they are intended to preserve the efficacy of the consecrated fire or articles and of the sacred ceremonies within them.

Pavi.

A *karsha* of this kind is generally known as a “*pâvi*.” *Pav*¹ means sacred. So a *pavi* means a furrow which preserves the sacredness of the consecrated things or of the sacred ceremonies. When the efficacy [110] of the consecrated things is encroached upon by somebody else going within the circle or within the limit pointed out by the *pavi*, then the thing is said to be *avâ*, (*apâv*) i.e., desecrated. In the phraseology of the ritual, the words “*pâvi karvi*” are at times used to signify the preparation of temporary furrows or the performance of religious ceremonies.

Paiti-dâna or padan.

The word *padan* is Avesta *paiti-dâna*, lit., that which is kept over (the mouth). It is *padân* in Pahlavi, *panâm* or *penûm* in Pazand, *padân* in Persian. It is a piece of white cloth of cotton with two strings at the top to be fastened over the nose. It is a kind of mouth-veil put on at different times with different purposes. The priests put it on, when saying prayers before fire and the *myazd* or sacred things, so that their breath or saliva may not defile the sacred things before them. In this case, it resembles the covering which the ancient Flamines, the Roman fire-priests, were required to put on. At other times, it is put on, as it were, for a contrary purpose, i.e., to prevent the outside defilement from coming to the person who puts it on.² For example, the priest put it on, in the *barashnomgah*, to prevent the defilement of the infected person, whom he purified, coming towards him. Some put it on even over the face of a corpse. Here also the

1 Lit. *pavan âv*, i.e., (that which is washed) with water. In the language of the ritual, they often speak of “making a thing *pâv*,” i.e., ceremonially clean. This is done by washing the thing from within and without three times. To make the water to be used in the ritual *pâv*, they first wash thrice the vessel which is to contain the water, then fill the vessel upto the brim with water, and then, lastly, pour thrice, with the recital of *Khshnaoithra Ahurahê Mazdâo Ashem Vohû*, further water and let it overflow.

2 This fact seems to be illustrated by what I saw in October 1918. The Medical authorities of the Parsi Fever Hospital directed, that nurses and other male and female volunteers, who attended influenza patients at the Hospital during its epidemic, may put on a mask or a double-layered cloth-cover over their mouth and nose, so that they may not catch infection from the patients.

object seems to be to prevent the defilement from the nose and mouth of the corpse spreading out. The Pahlavi *Vendidad* (18:1) says that it may be prepared of any material (*kolâ mandavami*). It may be two fingers (*angusht*) broad and should be of two layers of cloth.

***Naôgar*, the nine-knotted stick.**

Naogar, or to speak more correctly, *Naô-gireh* is the technical name of a nine-knotted stick (*graom nava-pikhem*, Vd. 9:14). The use of such a stick in the purifying ceremony as a symbol, seems to [111] have been suggested by a passage of the *Vendidad* (19:4). Zoroaster advances against Ahriman holding an instrument in his hand (*asâno¹ zasta drajimmô*). In the portraits of Zoroaster, drawn from some sculptures on the rocks in Persia supposed to be those of Zoroaster, he is represented as having a stick in his hand. This is perhaps in reference to the above passage of the *Vendidad*. Some translators of the above passage of the *Vendidad* speak of this instrument as a nine-knotted stick. Another instrument, with which Zoroaster is said to have advanced against Ahriman, is Ahunwar, i.e., the short prayer of *Yathâ Ahu Vairyô*. That prayer is the spiritual weapon with which the prophet fights against the Evil Spirit, and the stick is the material symbol of it. In all religions, priests or bishops are made to hold some weapons, mostly the sword. These weapons are symbols of religious authority. Now Zoroaster's fight against the Evil Spirit is a kind of spiritual or mental purification. He fights to free or purify the world from his evil influences. So, the weapon also came to be used as a symbol in the barashnom ceremony of purification, wherein also the purifier fights against the pollution brought upon by the Evil Spirit.

Now, as to the number nine, it was a sacred number among the ancients. It was supposed to be a symbol of a kind of perfection, because when multiplied by any number, the addition of the digits of the product always gives nine as the product. So, it was held sacred even amongst the ancient Zoroastrians. In the barashnomgah, the pits are, as we said, nine. The *karshas* or the furrows round the nine pits are nine. The isolation or the retreat after the barashnom lasts for nine nights, So, the number nine also plays its part in the stick used in the purifying ceremony. The priest gives the consecrated articles to the candidate for purification by means of a spoon attached to such a nine-knotted stick. Perhaps, it was thought, that, in case the infection escaped from the infected person who is a candidate [112] for purification, it might not reach the purifying priest and might be stopped at every knot of the stick. It might pass through the fibres of

1 Harlez (*Zend Avesta*, p. 192) takes it to be an "arrow." Some take it to be "stones." Aspandîârjî (Edition of 1900, p. 269) takes it to be 𐬀𐬎𐬌𐬎 *nogar*. Others take it to be symbolical for Ahunwar. (*Ibid*).

the stick but might be stopped at each of the knots. All this is symbolic, however we may try to understand it.

3. Barashnom-gâh or the place for the barashnom.

The locality for the barashnomgah as enjoined in the *Vendidad* and the sanitary condition of the ground.

Having spoken at some length on what is barashnom and on its description in the *Vendidad*, I will now speak of the Bareshnom-gâh. The barashnom being a form of purification for a person who came into close contact with a dead body — perhaps the dead body of a person who died of an infectious disease — it is natural that the place for this purification should be enjoined to be away from thickly populated parts of a town. It ought to be in a sequestered or the less frequented part of the town. The *Vendidad* (9:1-11) enjoins, that it ought to be at a place, less frequented by cattle, beasts of burden and men. Again, it must be at the distance of at least 30 steps (*gâya*) from fire, 30 steps from the *barsom*¹ and 3 steps from the holy man. What is meant is, that it must be in a less frequented place and in a place away from religious places which are frequented by people.

Let us determine the distance mentioned here. It is required to be at the distance of at least 30 *gâya* from a religious place where liturgical services are performed. Now, according to the ancient Parsee books, each *gâya*, i.e., step, is made up of 3 *pâdha*, (Sans. *pâdha* Lat. *ped-s* or *pés*, Fr. *pied*, Germ. *fuss*, Pers. *pâi*, foot) i.e., feet. Now each *pâdha* or foot is equal to 14 *êrêzu*, i.e., fingers. Each *êrêzu* or finger is about 4/5 of an inch.² So each *pâdha* (foot) comes to about 11 1/5 in., and each *gâya* (step) comes to about 2 ft. 9 3/5 in. Thus, when it is said that the [113] barashnomgah must be at least 30 *gâya* from a place where religious services are performed, it means, in modern measures, that it must be at least (30 by 2 ft. 9 3/5 in.) 84 feet. In other words, there must be no place of worship near the barashnomgah for about 84 feet. Holy men are required to keep themselves away from it by three steps, i.e., by 8 ft. 4 4/5 in.

The above figures from the *Vendidad* speak about the distance of the nearest frequented place. The *Rivayats* follow the spirit of the *Vendidad*, but increase the distance, and say, that it must be about 300 *gâyas* (steps), (*Bareshnûmgâh dûr az sheher si-sad gâm*

1 [Originally twigs, now] Sacred metallic rods used in ritual. [See p. 261.]

2 For a comparison of the Avesta measures with the Iranian measures mentioned by Herodotus and with modern measures, *vide* the tables given by me, in my *𐬀𐬀𐬎𐬎𐬎𐬎 𐬀𐬎𐬎𐬎𐬎𐬎𐬎𐬎 𐬀𐬎𐬎𐬎𐬎𐬎𐬎𐬎* 'The Ancient Iranians according to Herodotus and Strabo' pp. 93-95. *Vide* Rawlinson's *Herodotus*, I, p. 315.

shâyad)¹ i.e., at the distance of about 280 yards from the city. 22. *Burjor Kamdin's Revayet*: Mr. Maneckji R. Unvala's MS., dated 1061 A. Y. (A.D. 1602).

Again it is further enjoined, that, after having chosen a distant or less frequented locality, one must select there a piece of ground "where there is least water and where there are fewest trees, the part which is the cleanest and driest" (Vd. 9:3).² In short, the driest and the cleanest place is enjoined for the purification, so that the impurities or germs of infection from the infected person may not increase and develop, and thus be a source of danger. In case, a place free of trees is not near at hand, the trees on the ground must be cut off to meet the requirement. The ground round about the barashnomgah must also be cleared of its trees, for a distance of about nine *vibâzu*. As each *vibâzu* is spoken of as containing 8 *vitashitis* and as each *vitashiti* is about 10 in.,³ the ground so cleared off must be about $9 \times 8 \times 10 = 720$ in., i.e., about 60 feet from all sides.

Laying out of the barashnomgah.

Having chosen the locality at a safe distance from the city, and at the distance of at least about 84 feet from the nearest inhabited or frequented place, and having made the place dry and devoid of trees the next business is to lay out or arrange the barashnomgah. It should be laid out in the centre of the above-mentioned area of 60 feet. The arrangement consists of 3 kinds of work:— [114]

- (a) Digging *magas* or pits at fixed distances from one another.
- (b) Drawing out the *karshas* or the furrows round the pits.
- (c) Covering the barashnomgah with sand or earth.

(a) At first nine *magas*, i.e., pits or holes are to be dug in the centre of the ground beginning from the West and ending in the East. Each of these pits was to be two fingers (*êrêzu*), i.e., about $1 \frac{3}{5}$ in. deep, if the time of the purification was summer, but 4 fingers, i.e., about $3 \frac{1}{5}$ inches deep, if it was winter. At first, six such pits are to be dug at the distance of one step, i.e., about 2 ft. $9 \frac{3}{5}$ in. from one another. Then, at the other end of this set of 6 pits, a space of 3 steps, i.e., about 8 ft. $4 \frac{4}{5}$ in. is to be left undug. Then follows another set of 3 pits of the same depth and at the same distance from each other as those of the first set of six. The breadth of each of the nine pits is not given in the *Vendidad*; but the depth being, as said above, $1 \frac{3}{5}$ in. in summer and $3 \frac{1}{5}$ in. in winter, let us suppose that the width

1 *Burjor Kamdin's Revayet*: Mr. Maneckji R. Unvala's MS., dated 1061 A. Y. (A.D. 1602).

2 S. B. E. IV, (1880) p. 120.

3 *Vide my Kadim Iranians*, p. 94.

also is the same, *viz.*, in summer $1 \frac{3}{5}$ in., and in winter $3 \frac{1}{5}$ in. The reason, why different sizes were enjoined in the different seasons, seems to be, that in summer, the heat being great, the ground, moistened by the water in the purification process, dries up earlier than in winter.

(b) The next important work in the preparation of the *barashnomgah* is that of drawing the *karshas* or furrows round the pits, to mark out the ground, beyond which the pollution or infection may not pass. The infected person is to have his baths in such a way that the water running from his infected body may not run further from the place and not pollute further ground. So, the ground must be marked out and proper channels or furrows for the water must be made. These channels may serve as limits for confining the pollution or infection in a particular place.

At first, one large *karsha* is to be drawn round the whole limit of the *barashnomgah* with a sharp metallic instrument. (Vd. 9:10). It must be at the distance of 3 steps (*gaya*), [115] i.e., about 8 ft. $4 \frac{4}{5}$ in. from the long row of pits. Then, 12 *karshas* must be drawn round the pits themselves in the following order: Firstly, 3 *karshas* round the first three pits; secondly, 3 *karshas* round the first six pits; thirdly, 3 *karshas* round all the nine pits. Then, lastly, 3 *karshas* round the inner, i.e., central three pits.

(c) Having prepared the pits, on each of which the candidate has to purify his body, and having enclosed the ground, the *barashnomgah* must be covered with some earth or sand. The candidate for purification has to go through the purifying process on each of the pits. Going through that, he has to cross that pit and go to the other or the purer side of the pit, leaving behind, in the pit just crossed, any pollution that had passed away from his body. So, he must have purer and cleaner ground to stand upon, after crossing the pit. This was secured by having the ground covered with sand or such other moisture-absorbing clay or earth.¹


Taking the distances as given in the *Vendidad* and as described above, the figures for the length and breadth of the *barashnomgah* and for the space occupied by the pits, the intervening spaces, and the furrows come to these:—

The breadth of each pit is $3 \frac{1}{5}$ in. in winter and $1 \frac{3}{5}$ in. in summer. We take the largest breadth of winter months in our calculations. As there are altogether 9 pits, they occupy altogether ($9 \times 3 \frac{1}{5}$ in.=) $28 \frac{4}{5}$ in. = 2 ft. $4 \frac{4}{5}$ in. Then, the distance between each pit being 2 ft. $9 \frac{3}{5}$ in., as there are 7 intervals or distances between

1 Vd. 9:11.

these 9 pits, they occupy in all ($7 \times 2 \text{ ft. } 9 \frac{3}{5} \text{ in.} =$) $235 \frac{1}{5} \text{ in.} = 19 \text{ ft. } 7 \frac{1}{5} \text{ in.}$ Then, the distance between the first set of 6 pits and the second set of 3 pits being $8 \text{ ft. } 4 \frac{4}{5} \text{ in.}$, the length of the ground occupied by the whole set of pits comes to ($2 \text{ ft. } 4 \frac{4}{5} \text{ in.} + 19 \text{ ft. } 7 \frac{1}{5} \text{ in.} + 8 \text{ ft. } 4 \frac{4}{5} \text{ in.} =$) $30 \text{ ft. } 4 \frac{4}{5} \text{ in.}$ Then, the first and the most distant *karsha* or furrow being $8 \text{ ft. } 4 \frac{4}{5} \text{ in.}$ from all sides of the pits, allowing the space of $8 \text{ ft. } 4 \frac{4}{5} \text{ in.}$ from the space ($30 \text{ ft. } 4 \frac{4}{5} \text{ in.}$) between the first and the ninth or the last pit, i.e., on the East and on the West, the whole length of the [116] ground from East to West comes to ($30 \text{ ft. } 4 \frac{4}{5} \text{ in.} + 8 \text{ ft. } 4 \frac{4}{5} \text{ in.} + 8 \text{ ft. } 4 \frac{4}{5} \text{ in.} =$) $47 \text{ ft. } 2 \frac{2}{5} \text{ in.}$ Coming to the breadth, (north and south), as the first and most distant *karsha* or furrow is to be $8 \text{ ft. } 4 \frac{4}{5} \text{ in.}$ on both sides from any one of the pits, taking the pit to be a square and therefore its length to be the same as its breadth, i.e., 3 ft. , we have the breadth of ($8 \text{ ft. } 4 \frac{4}{5} \text{ in.} + 8 \text{ ft. } 4 \frac{4}{5} \text{ in.} + 3 \text{ ft.} =$) $17 \text{ ft. } 4 \frac{4}{5} \text{ in.}$

From all these calculations, we learn that the barashnomgah, as enjoined by the *Vendidad*, must have the surrounding ground of the distance of about 60 ft. from all its sides, cleared off of its trees, and that the space in it to be occupied for the purpose of the purification ceremony itself should be $33 \text{ ft. } 2 \frac{2}{5} \text{ in.}$ in length from East to West, and $17 \text{ ft. } 4 \frac{4}{5} \text{ in.}$ in breadth from North to South. The accompanying sketch presents a plan of the barashnomgah, enjoined as above by the *Vendidad*.



Plan of the Bareshnomgah as enjoined in the Vendidad.

A modern barashnomgah.

Now, as the modern barashnom purification has changed somewhat from the original one of the *Vendidad* times, in its object and in the matter of the persons who should take the barashnom, so has the modern barashnomgah changed from the original barashnomgah of the *Vendidad* times. Again, even at present, some of the rigid injunctions are more honoured in their breach than in their observance. We will here examine the changes, which are especially in the following points: (a) Its locality. (b) Its area. (c) The form of its *magas* or pits. (d) The distance between the pits.

(a) Firstly, as to locality, the present barashnomgahs are not always away from the city. It is only at Naosari, the old head-quarters of the Parsi priesthood, that the old injunction of the *Vendidad* is

followed and the barashnomgah is situated at some distance from the closely inhabited part of the town. Even at Naosari, the ground round about, of the distance of about 60 ft., is not cleared off of its trees. Now-a-days, the barashnomgahs are attached to many Fire-temples, because the original purpose of the barashnom, *viz.*, that of purifying only the infected, has lost much of its importance, and the barashnom is looked at, as [117] a form of purification necessary for the performance of liturgical services and ceremonies in the Fire-temple. It is mostly the priests that now-a-days take the barashnom. So, the original requirement of the infected person being kept apart from frequented quartets of the town no longer exists. Thus, the barashnom being a more frequent form of purification, and being the requirement for a priest, the barashnomgahs are now attached to the Fire-temples.

(b) The area of the modern barashnomgah also is much smaller than that described in the *Vendidad*. It varies in different towns. According to the *Vendidad*, the row of pits was in the centre of the area. In the modern one, it is nearer to the northern boundary.

(c) As to the form of the *magas*, we have no pits at all. They are replaced by sets of small stones. Each set consists of 5 stones. The space between each set of pits as enjoined by the *Vendidad* was 9 $\frac{3}{5}$ in. That space is now replaced by sets of 3 stones each.

(d) The *magas* or the pits having been done away, the distances, mentioned in the *Vendidad*, between each of the pits, *viz.*, 9 $\frac{3}{5}$ in., and between the first set of six pits and the second set of three pits, *viz.*, 8 ft. 4 $\frac{4}{5}$ in., are not observed. The omission of the small distances between each of the pits or their modern substitutes, *viz.*, the sets of stones, is not noticeable; but the omission to observe the greater distance between the first six; and the second three pits is easily marked. In the modern barashnomgah, all these sets of stones — both those representing the original pits, *viz.*, sets of 5 stones, and those representing the original empty spaces between the pits, *viz.*, sets of 3 stones — are only about 6 in. apart.

Sets of small stones in the modern barashnomgah.

Taking the replacement of the *Vendidad* *magas* by sets of stones at present, there must be nine sets of stones, each of 5 stones, to represent the 9 pits of the older barashnomgah, and nine sets of stones, each of 3 stones, to represent the intervening [118] spaces between the pits — in all, 18 sets of stones. But instead of these 18, we have 21 sets in the modern barashnomgah. The extra three are made up of two sets, each of 3 stones, and one of 5. The first extra set of 3 stones is in the front of the long row of stones, i.e., in the west end of

the row, and it is on this set, that the purifying priest places his nine-knotted stick, and commences the process of preparing the barashnomgah or drawing the *karshas*. The second extra set of 5 stones is at the other end of the long row on the east, and it is on this set that the candidate takes his final bath. These 5 stones are generally replaced by a broad large stone, so that the person can conveniently stand or sit on it and have his bath. The third or the final set of three stones forms the furthest end of the row on the east. It is provided for the bather to stand upon, after his final bath on the large stone, to dry his feet before putting on his shoes.

It seems, that, according to the *Vendidad*, in ancient times, at each time that there was a case of a person who had become infected by coming into contact with a dead person in a prohibited way or in a way other than the proper or prescribed way, a barashnomgah was laid out. A piece of ground was selected, pits were dug, and the *karshas* or furrows were drawn. It appears, that the cases were rare, and so, the necessity of preparing the barashnomgah arose rarely. But latterly, when the original object of the purification was changed, and its use and object were extended, a permanent thing was wanted. Now-a-days, the barashnom purification is a rare and uncommon thing for the laymen, but common with the priests, who want to qualify themselves for performing religious ceremonies in the inner circle of the temples. So, in the modern barashnomgah, much of the arrangement enjoined in the *Vendidad* is given a permanent form. As said above, they have done away with the digging of the nine *magas* or pits and replaced them by 9 sets of stones; and the intervening spaces between the pits are permanently replaced by sets of stones. It is only the *karshas* or the furrows that are newly made on each occasion of the barashnom, and that part of the process only is now-a-days [119] technically known as "preparing the barashnomgah." Again, in the modern ritual, there is no fumigation.

Plan of the barashnomgah.

Plans of the barashnomgah are given by Anquetil du Perron,¹ Harlez,² Spiegel,³ Darmesteter,⁴ and West.⁵ But they all are faulty in one respect. They point the arrangement of the pits in the direction North to South, thus indicating, that the candidate for purification comes in from the North and advances to the South. But as a matter

1 *Zend Avesta*, Tome II, p. 546.

2 *Avesta*, Introduction, p. CLXXVI.


3 *Avesta*, Erster Band, *Vendidad*, p. 295.

4 *Le Zend Avesta*: Deuxième volume, p. 162.

5 S. B. E., Vol. XVIII, p. 435.

of fact, the direction is from West to East. The candidate enters from the West and advances to the East. Again, the plans of Prof. Darmesteter and Dr. West are further faulty, in this, that they point out the last 3 *karshas* to be round the last set of pits. But this is not so. These last three *karshas* are round the central set of the three pits.

The plans given by all these scholars do not give clear separate ideas of (a) what a modern permanent barashnomgah is, and (b) what it appears to be when prepared at the time of giving a barashnom to a candidate. I give a plan which gives a view of both, and I will illustrate the process of giving the barashnom by references to it.



4. The process of giving the barashnom.

Now we come to the subject of the process of giving the barashnom. I will at first speak (A) of some requisite preliminary preparations and then (B) of the process itself.

(A.) Preliminary Preparations.

The preliminary preparations consist of the following:— (a) Preparing or consecrating the requisites for the purification. (b) Preparation on the part of the particular priest who gives the purification. (c) Preparation of the barashnomgah. (d) Preparation of the candidate. [120]

(a) Preparing necessary requisites for the barashnom.

At first, two barashnomwalla¹ priests who have previously performed the great *Khub*² ceremony, carry to the barashnomgah, the following consecrated articles required for the barashnom:— (a) The Nirangdin, i.e., the consecrated urine of the cow. (b) The *Āv*, i.e., the consecrated water, (c) The Bhasam,³ i.e., the consecrated ash of the Sacred Fire of the Atash Bahram. Besides these consecrated things, the following utensils and articles are required in the barashnomgah:— (a) Two pots-ful of water. (e) Two metallic cups. (f) The leaf of a pomegranate tree, (g) Two *naogars*, i.e., sticks having nine knots. One of these two sticks has a metallic spoon at one end tied with a *kusti* or sacred thread. Another stick has a metallic nail similarly tied at one end. The first three consecrated things are placed within a *pavi*.⁴ This *pavi* is on the south side of the barashnomgah (place marked Z in the plan).

The purification of the utensils and of the water.

Having placed the above consecrated articles and other necessary things into the barashnomgah, the two priests perform the *kusti-padyab*, of the water. and put on the *padan*. Then one of them first makes *pāvu*,⁵ i.e., cleans ceremonially the two small metallic cups. In one of the cups, he pours the consecrated urine and throws into it a pinch of the bhasam or the consecrated ash. Then he makes the two

1 i.e., the priests who have themselves gone through the barashnom purification and who observe all the required observances.

2 The *khub* ceremony requires the recital of the Yasna and the observance of certain ceremonies.

3 भ्रम रनान is said to be a special purification ceremony among the Hindus. भ्रम शयिन is one of the several names of Shiva, because he sprinkled ashes over his body. विमूर्ति is their sacred ash (Calcutta Review of Jan'y. 1905).

4 Vide above, p. 115.

5 Vide above, p. 115.

water-pots *pâv* and pours into them a few drops of consecrated water. A few drops of consecrated water consecrate all the water in the pots. [121]

(b) Preparation on the part of the particular priest who gives the purification-bath.

After preparing the requisite things as said above, the priest himself takes a bath in the barashnomgah. He purifies himself with consecrated water before purifying the candidate. One of the above two pots of water is for his use and the other for the subsequent use of the candidate. He goes to an adjoining place enclosed by a *pâvi* (marked C on the plan), recites the formula of *Khsnaothra Ahurahê Mazdâo Ashem Vohû*, and then unclothes himself. He places his clothes at a little distance from himself on a set of three stones. In doing so, he removes his turban with the *padân* hanging over it. Then, sitting on a big stone, he bathes with the consecrated water contained in one of the two pots placed before him by the other priest on a set of three stones. The other priest sprinkles a few drops of the *âv* or the consecrated water on the clothes of the priest. Thus, he symbolically purifies with the consecrated water his clothes also. On finishing his bath, he puts on his clothes and in so doing, he puts on his turban with the *padân* hanging over it. Then throwing his *kusti* on his shoulders, he recites the *Kemna Mazda* prayer and then puts on the *kusti*, reciting the Nirang-i-Kusti.

(c) The preparation of the barashnomgah.

Having bathed with the consecrated water, the priest now proceeds to “prepare the barashnomgah.” As said above, in the modern barashnomgah, the place is all ready with the 9 pits, now-a-days replaced by 9 sets of 5 stones each and with the intervening sets of 3 stones each. What is left undone is the drawing of the *karshas* or the furrows which is technically known as “preparing the barashnomgah.” He proceeds to draw the *karshas* as follows: He takes the two Naogars or the nine-knotted sticks, in his hands, the one with the metallic nail at the end in his right hand, and the other with the spoon in his left hand. Then, going to the place where the sets of stones commence, he places the nailed end of the first stick on the first set of 3 stones — the first extra set marked D in the plan — and stands facing the East. He then recites what is [122] technically called the Dasturi, i.e., he declares, that he performs the ceremony as enjoined by the Dasturs. In this recital, he first recites *Khshnaôthra Ahurahê Mazdâo*, one Ashem Vohu and five Ahunwars, and then recites in *baj*, i.e., in a suppressed tone, the Dasturi formula.¹ Then he

1 Herein, he says, that he performs the ritual as enjoined by the Dasturs. *Vide* above,

recites loudly three Ashem vohus, and takes the *baj* of Srosh upto the words “*Vidhvao mraotu.*” Then saying the word Ashem, once loudly, and for the second time in a suppressed tone, he goes to the north-west corner of the limit of the barashnomgah (marked E in the plan) and draws one *karsha* with the nailed end of the nine-knotted stick round the whole boundary, beginning with the northern side. Some draw this *karsha* within the permanent *pâvi* which shows the inner boundary of the barashnomgah and others draw it out of the *pâvi* on the inside of the boundary. He slowly proceeds from West to East (E to F in the plan), reciting four Ahunwars during the process. Then he continues on the eastern side (F to G), then on the southern side (G to H), and lastly, on the western side (H to E), reciting three Ahunwars each time. Thus, completing the quadrangle, he draws the first large *karsha* referred to, as said above, in the *Vendidad*. Then, he goes back to the row of stones and draws 12 *karshas* round about them. At first, he draws three *karshas* round the first set of the three pits (I J K L), each represented in the modern barashnomgah by three sets of 5 stones and shown in the plan by 5 dots. Then, he draws 3 *karshas* round the first six pits, as marked M N O P in the plan; then, thirdly, round all the nine pits as marked Q R S T in the plan. Lastly, he draws three other *karshas* round the middle set, as marked U V W X. When these 13 *karshas* are drawn, the barashnomgah is technically said to have become *taiyâr* (تیار) i.e., ready for the purification ceremony of the candidate. The priest, who thus prepares it, finishes the *baj* of Srosh, the first portion of which he had recited at the commencement of the work of preparing the barashnomgah. [123]

(d) Preparation of the candidate.

The candidate for purification first takes his ordinary bath in the morning with the necessary ritual, either at his house or at the Fire-temple. At Naosari, he takes this preliminary bath at his own house, and then goes to the barashnomgah. As it is a small town, and there are quarters which are strictly Parsi quarters, and the distances to the barashnomgah and the Fire-temples are not great, one can easily walk from his house to the barashnomgah, and from there to the Temple, where he has to pass nine days in a kind of retreat. But Bombay being a large city, it is not quite possible to go from one's house to the barashnomgah in a Temple without running the chance of coming into contact with non-Zoroastrians, from whom he is to keep aloof. So, in Bombay and in other large centres of population, the candidate — and when one speaks of a candidate, he is almost always a priest who goes through the ceremony to qualify himself for the performance of certain religious ceremonies — takes the preliminary

bath at the Temple. He puts on a newly washed set of clothes. Then, he goes to the Barashoumgah. If a long interval has passed since his preliminary bath, he performs the padyab-kusti; if not, he need not perform that.

Then he takes his seat on a piece of clean cloth on the ground within an enclosed *pâvi* (A in the plan) outside the barashnomgah proper. Then, he is made to say the Baj, or prayer of grace, and is given a pomegranate leaf to chew, and a little consecrated urine to drink in one of the two small metallic cups referred to above. He then finishes the Baj and recites the patet. The process is the same as that in the Nan ceremony or in the second form of purification. So, I need not describe it in detail here.¹ He goes through this preliminary preparation before the technical “preparation of the barashnomgah.”

(B) The process proper of the barashnom.

Now, we come to the subject proper of the process of the barashnom ceremony. Two priests are required for the purpose.² As said above, one of the priests, the purifier, has himself [124] gone through a purification with consecrated water. He has ‘prepared’ the barashnomgah for the purification. The candidate himself is now ready. The second priest now goes in a *pâvi* (Y) outside the barashnomgah proper, and holds a dog by a chain in his hand. The candidate is now about to enter into the barashnomgah; but before he does so, the priest who is to purify him retires into the *pâvi* (Z) wherein the consecrated articles are kept. An infected person is supposed to step into the barashnomgah; so, not only should the consecrated things, but also the priests who are to purify him and to give him a bath of purification are supposed to keep themselves out of the chances of infection and pollution. The *pâvi*, which is prepared by drawing a *karsha* or a furrow round about, protects them.

The candidate now rises from his seat on the ground, leaves the *pâvi* wherein he ate and drank the consecrated things, and steps into another *pâvi* (B). Coming in there, he takes the Baj. He recites *Khshnaothra Ahurahe Mazdao, Ashem Vohu*.³ Then he recites in baj, i.e., in a suppressed or muttering tone, “*Humata, hukhta, hvarshta, hu-manashnê hu-gavashnê, hu-kunashnê*⁴*tan pâk*,” i.e.,

1 Vide above, p. 96 et seq.

2 *Yaôshdâsragar dô gan âvâyad* (Pahl. Vd. 9:32); one of them has performed the *khûb*.

3 Amat Yaôshdâsragar Yasht la kard Yekvimunet la Shayad (*ibid.*) Dastur Jamaspi takes the word “Yasht” here for *khûb*, ખુબા પેહેલવી વંદીદાદજુ ગુજરાતી વાંચણ તથા ઠરજમી by Dastur Kaikhosru, p. 106.

4 Here, he names the person, for whose *naiyat* or intention he takes the barashnom.

“(I go through this ceremony) with good thoughts, with good words and good deeds,¹ and I do this with the intention that the good of this may result to the body of (such and such a person).”

This is a later change, development, or rather, degeneration. The original object of the purification, *viz.*, purification from a kind of pollution or infection, was lost, and the ceremony became a kind of qualification for the performance of some ceremonies. The priests go through this, and are paid for that and for the subsequent ceremonies, Yasna, &c. At first, they recited the name of the person who had asked them to perform the ceremonies in certain formula recited in the prayers. But, latterly, they began to recite his or her name in the purification ceremony itself. [125]

The candidate then unclothes himself. He is not to speak anything now. If he has to say anything, he must speak in *baj*, i.e., in a suppressed tone. Having unclothed himself, he seats himself on the first set of 5 stones (*a* in the plan) which represent the first *maga* or pit of the original barashnomgah of the *Vendidad*. While proceeding to the seat, he covers his head with his right hand, because a Zoroastrian is enjoined not to walk bear-headed. With another hand, he tries for decency to cover his private part.

The candidate for purification having taken his seat in the *pâvi* or enclosure formed by the *karshas* or furrows, the cause of infection is, as it were, confined within that space. As the infection is not expected to spread, the purifying priest now comes out of the *pâvi*, where he had taken his refuge for the sake of safety. He goes to the candidate to purify him, but always takes care to stand out of the *pâvi* formed by the furrows in which the candidate is seated. He holds the nine-knotted stick with the spoon in his right hand, and the second stick with the metallic nail in his left hand. Then, the candidate places his right hand on his head. The reason why he now puts his right hand on his head is that a Zoroastrian is asked not to speak with an uncovered head.² When he has to say [126] anything with an uncovered head, for

If it is for himself, he says so. *Vide* above p. 107, n. 5.

- 1 The words are here repeated in their Pazand form.
- 2 We learn from Herodotus, that the ancient Persians always kept their heads covered. He speaks (Bk. III, 10-12), of the battle, which the Egyptians fought with the Persians at the Pelusio mouth of the Nile, and in which Psammenitus, son of Amasis, was defeated, and of his visit of the battlefield. There he says, “Here I saw a very surprising fact, which the people of the country informed me of The skulls of the Persians were so weak, that if you should hit them only with a single pebble, you would break a hole in them; whereas those of the Egyptians are so hard, that you could scarcely fracture them by striking them with a stone. The cause of this, they told me, is as follows, and I readily assented; that the Egyptians begin from childhood and shave their heads, and the bone is thickened by exposure to the

example, during the bath, he places his right hand over his head, and then says what he has to say. Now, as the candidate has to speak something, as we will see later on, he has to cover his head temporarily with his hand.

The priest who has advanced to purify him now places the spoon-end of the nine-knotted stick on his hand which covers the head. The candidate then places his left hand over the spoon. Care must be taken that the hands of the candidate only touch the spoon, i.e., the metallic part of the stick, and not the wooden part, which, being porous, is likely to catch germs of infection from him. The priest then recites three Ashem Vohus and the Baj of Srosh up to “*vidhvao mraotu*,” and with the word “*ashem*,” (i.e., Purity), removes from the head the spooned stick. Then going to the *pâvi* where the *âlat* or the consecrated things are placed, and taking, in one of the small metallic cups above referred to, a little of the *nirang*, goes to the candidate again, pours a little of it in the spoon,¹ and drops it in the hand of the candidate who applies it to his whole body. He repeats this three times.

The *Vendidad* (9:15-26) enjoins that the application must not be haphazard, but in a particular way beginning from the top of the head to the tip of the toe. It says, that, at first, both the hands must be cleaned or purified with the *nirang*, so that, with those clean hands, he may clean all the other parts of the body. It says (9:15): “At first, both his hands must be washed. If both his hands are not washed at first, he makes his whole body unclean.” The *nirang* after its application to the hand, must be applied to the other parts of the body in the following order: The head, the front part of the face between the brows, the back part of the head, the cheeks, the right ear, the left ear, the right shoulder, the left shoulder, the right arm-pit, the left arm-pit, the chest, the back, the right nipple, the left nipple, the right rib, the left rib, the right hip, the left hip, the sexual parts, (if the candidate [127] for purification is a male, the application must first be on the hind part and then on the front part; but if a female, it must begin on the front and then on the hind part), the right thigh, the left thigh, the

sun. And the reason why the Persians have weak skulls is this; they shade them from the first, wearing tiaras for hats. Now, I myself saw that such was the case; and I also observed the same thing at Papremis, with respect to those who were slain with Achæmenes son, of Darius, by Inarus the Libyan.” Bk. III, 12. H. Cary’s Translation. Bohn’s S is (1889). p. 174.)

While saying prayers or performing religious ceremonies, a decent head-dress was unavoidably necessary. Herodotus says: “When any one wishes to offer sacrifice he invokes the god, usually having his tiara decked with myrtle.” (Bk. I, 132, *Ibid*, p. 60.)

1 Vd. 9:14.

right knee, the left knee, the right shin of the leg, the left shin of the leg, the right ankle, the left ankle, the right instep, the left instep, the right sole of the foot, the left sole of the foot, the right toe, the left toe.


The *Vendidad* adds, that, with such an application, the Druj-i-Nasu, i.e., the Evil of infection or — to speak in modern scientific language — the microbe of infection leaves the particular part of the body thus cleaned and runs down to the next named part, and, at last, leaves the infected person at the foot, making good his escape in the northern direction.

Now-a-days, the application is not so systematic and not in the same successive order as enjoined in the *Vendidad*. It differs in several points:—

(a) Firstly, it is a hasty application or rubbing of the Nirang from head to foot, (b) Secondly, the *Vendidad* enjoins the priest who purifies the candidate to throw or sprinkle the Nirang gradually upon the different parts of the body, one after another. That process would require a very large quantity. But in practice now, the priest gives at once a little quantity, about a tea-spoonful the most, in the hollow of the hand of the candidate who applies that quantity over all the parts of the body, (c) Thirdly, in modern practice, the priest drops the nirang in the hands of the candidate three times at each pit. This triple process of dropping it is, perhaps, to replace, and to make up for, the abandonment of the very long and intricate process of the application as enjoined in the *Vendidad*. (d) Fourthly, it is enjoined, that the words “*nemaschâ, yâ Ârmaitish izhâchâ*” (i.e., praise and commendation to Armaiti, i.e., to the Purity of thought) are to be recited by the priest and repeated by the candidate before the first application or washing, but, in practice, they are recited after the first triple application.

Then, to proceed in our description of the process of the barashnom, the priest, after dropping the nirang into his hands, [128] retires again into his *pâvi* or enclosure where the *âlât* or the consecrated articles are placed. The candidate is isolated within the *karshas* or the furrows. The isolation is shortly to be broken or dissolved by the other priest who is to present a dog before the candidate.¹ If that is done, the purifier himself, coming within the

1 The isolation of the *pâvis* is said to be broken or dissolved when a contact is made between a person or persons or a thing or things within the *pâvi* and between a person or persons, or a thing or things outside the *pâvi*. For example, suppose the adjoining A figure represents a space enclosed in a *pâvi*. The lines AB, BC, CD, DA represent the four furrows of the *pâvi* on the four sides. Now suppose a stick or a handkerchief falls on one of the *pâvis* in the way shown at E. Then, the *pâvi* is said



circle of pollution or infection, is likely to catch infection. So, he retires within his enclosure (Z) of isolation for safety. The other priest then advances with a dog held by a metallic chain, and keeping himself at a distance beyond the *pâvi*, — in this case the first and distant *karsha* or furrow, — presents the dog before the candidate who then touches with his left hand the left ear of the dog.

The dog in the barashnom ceremony.

I will say a few words here on the use of the dog in this purification ceremony. In the 9th chapter of the *Vendidad*, where a lengthy description of the barashnom purification is given, we find no reference to the dog. But it is in its Pahlavi commentary that we find it. There, on the authority of the later commentators, it is said, that “when they (the candidates for purification) pass from one pit to another, the dog may be held before them once.”¹ The 8th chapter of the *Vendidad* (§, 37-38) also enjoins the presentation of a dog before the candidate. The description of the 8th chapter, though it refers to the barashnom purification, refers specially to the case of an inferior kind of pollution or infection. It is the case of a person who has merely “touched the corpse of a dog or of a man.” But the case in [129] the 9th chapter is rather a more serious case — the case of a person who has not simply touched the body but is actually “defiled by the dead.” In this latter case, he is supposed to have come into greater contact with the corpse and to have disregarded the observances and restrictions enjoined by the then sanitary authorities in the matter of isolation. So, when in the first case (Vd. 8), *viz.*, that of merely touching the body either accidentally or for some purpose under proper observances, he is to go through mere purifications and baths, in the latter case (Vd. 9) of an actual defilement, he is not only to go through the purification, but also through an isolation for 9 days and nights. He was to remain aloof, as we will see later on, for a period of full 9 days and 9 nights, *i.e.*, about 10 days.

Now, the question is: why was it enjoined that a dog should be presented before the candidate for purification? One cannot speak with authority or certainty, but can advance a probable reason by analogy or inference. The reason seems to be the following:— Of the several means or ways to be adopted to do away with the spread of disease or infection, one was the speedy consumption of the body that was the centre of disease or infection. Consumption by the flesh-

to be connected D and so the isolation is said to be dissolved or broken.

1 “*Amat min magh gan magh vazlûnd ayokbâr kalbâ vakhduniyen*” Pahlavi *Vendidad* 9:32. *Vide* the Pahlavi Text of the *Vendidad* by Dastur Darab P. Sanjana, p. 186, l. 6; S.B.E. XVIII. p. 451.

devouring animals was one of such ancient prevalent ways. In the *Vendidad*, we find a reference to the old primitive way when corpses were exposed on tops of mountains, so that flesh-eating birds and animals, like vultures and dogs, who served as scavengers of Nature may devour the flesh. The dog was a domestic animal useful to the ancient Iranian in many ways. He served as a policeman to guard his house, to guard his fields, to guard his flock. Not only that, but it served him, as said above, as a scavenger of Nature in eating away the flesh of the corpse of a deceased person which otherwise would have gone on decomposing, and then endangering the health of his town. So the dog was, in the eyes of an ancient Iranian, a very dear and useful animal. What is very dear and useful whether that be a man, an animal, or a thing is, as it were, in one sense, sacred. The dog therefore became a useful and sacred animal in the eyes of an Iranian. [130] His great and important services were those of stopping decomposition and of stopping the spread of disease and infection. Such being the case, one of the several objects, why on the death of a person, the dog was brought before the corpse for *sagdid*, was, that the dog may see, that a person was dead and that a prey was ready for him. He may, by instinct, know, what was waiting for him. The second object, which arose from the first object and from all the above considerations, was rather more symbolic. The dog, being the scavenger of Nature, and as such, as said above, one of the means for the prevention of the spread of disease and infection, one of the means for keeping pure the earth, air, and ground of God, was the symbol and type of purification. Other thoughts and ideas seem latterly to have been associated with the dog, on account of his other characteristics as a faithful domestic animal. So, from all these considerations, he was brought before a corpse and made to see the corpse. His very eyesight was, as it were, a means of purification. So much for his presence before the corpse.

From the view of his presence before a corpse which was a great centre of putrefaction, infection and disease, the view of his presence before a person who was polluted and infected and who was therefore another, though lesser, centre of infection and disease, was only one step. The dog was a means, a channel, an instrument for purification, for keeping the air, earth and water of God pure. Here, in the *barashnomgah*, there is a candidate, who coming into contact with a corpse, seeks purification, so that, being purified, he may not continue to be a source of danger to those round about him. So, the dog's presence there was thought necessary to emphasize the original object of purification. The dog was one of the instruments of Nature in keeping its products pure. Here is a person, who to avoid any chance of infection, lest his infected condition may be a source of danger,

goes through a form of purification. [131] Thus, the presence of the dog before the person, who very likely was as infectious as a corpse, was symbolic and significant.¹

Now there does not seem to be any particular significance in the candidate touching the *left* ear of the dog with his *left* hand. As we said above, the candidate had now and then to keep his head covered with his right hand. Again, the dog had to be presented to him from beyond the furrows on his left. So it is only his left hand that was conveniently available. It is perhaps to preserve harmony or uniformity, that he touches the left ear of the dog. Perhaps, it is convenient also on account of the position of the dog. As we said above, the west is the side from which they enter the barashnomgah, and the candidate proceeds to the east. The priest who fetches the dog also comes in from the west. So, the dog, when it is made to stand on the left side of the candidate, with its face towards him, has his left ear conveniently near. There seems to be no other particular signification for this. As to the reason, why the candidate touches the ear, it seems to be only to draw its attention to himself. In the East, they generally twist the ear of a person to make him look a little sharp if he is careless or indolent. The [132] ear of a child is twisted by a parent or teacher to make it look a little sharp.

The candidate is not to let his left hand touch his body. His hands were cleaned in the above process of the first purification by the nirang. Having come into contact with something else, which, in its turn has not been washed, a part of the purity of the hand is said to have been lost by a touch to the dog. So, he must not apply it to his body before purifying it. This he does at the early stage of the next or second stage of purification at the second set of 5 stones which represent the next *maga* or pit.

1 It appears, that among some other nations also, the dog was used in the ceremony of purification. "The Boeotians had a custom to pass between a dog cut in half, as a means of purification. Liebrecht (*Liebrecht zur Volkskunde*, p. 350) sees here a purifying new birth brought about by a sacrifice. He points out that dogs were often employed as Purification-Sacrifices among the Greeks and Romans" (Journal of the Anthropological Society of Bombay, Vol. III, p. 360: "The Dog in Myth and Custom Extract from Mr. E. Tyrrel Leith's Notes.") Mr. W. W. Fowler, in the paper on the Roman Lustration (Purification) in his *Anthropology and Classics*, describes, on the authority of Livi, a Macedonian method of the lustral process for purifying an army. He says that the method was "to march the whole host in spring before a campaign between the severed limbs of a dog" (p. 108). Cf. The primitive way of making covenants in the Old Testament (Gen. 15:10, 17, Jeremiah 35:18 et seq.), wherein the contracting parties passed between the two parts of a sacrificed animal. Some attribute this to what they call a "purificatory theory" and others "a protective theory". Vide Sir James Frazer's *Folklore in the Old Testament*.

Repetition of the application of *nirang*, etc.

On the dog being removed from near the candidate, the isolation of the candidate within the furrows is secured and the priest gets out of his *pâvi* or enclosure with the spooned nine-knotted stick in his hand, and recites the *Kem na Mazda* prayer upto the word *Ashahê*. Then while reciting the next word '*nemaschâ yâ Ârmaitish izâchâ*' points with his above stick to the second set of 5 stones (marked b, in the plan) which represent the second *maga* or pit referred to in the *Vendidad*. That means an intimation that he should now advance further. The candidate thereupon repeats the words '*nemaschâ yâ Ârmaitish izâchâ*,' and advances, towards that set. On his taking his seat there, the priest repeats thrice the above described process of handing some *nirang* for fresh application. The candidate applies it to the whole of his body as described above. The priest again retires to his *pâvi* (Z). The second priest again advances towards the candidate with the dog. The candidate again touches the left ear of the dog. The priest with the dog retires and the first priest again gets out of his *pâvi*, advances towards the candidate, recites the abovesaid *Kem nâ Mazdâ* prayer as described above, asks the candidate to advance to the third set of 5 stones and gives him the *nirang* for application. Then the priest with the dog again advances. Thus the same process, with the above details and particulars, is gone through altogether for six times on the first six sets of pits which are represented [133] in the modern barashnomgah by the first six sets of 5 stones (a, b, c, d, e, f in the plan).

Application of sand.

On coming to the seventh *maga* or pit (*g*) or the seventh set of 5 stones, the application to the body is not that of the *nirang*, but that of mere sand (*khâk* خاك).¹ The details of the process are the same as those described above in the case of handing the *nirang*. This is done 18 times, i.e., the sand is given 18 times for application. The modern barashnomgah is covered over with sand which is renewed occasionally. So, it is some of this sand that the priest gives to the candidate. Having given this 18 times, the priest again retires to his *pâvi* (Z) and the other priest with his dog advances and the same process of touching the dog is gone through.

Application of consecrated water.

Then the first priest again gets out of his *pâvi* for the 8th time. At this time, before reciting the *Kem nâ Mazdâ* prayer as described above, he utters "*Ahunem varirîm tanûm pâiti*," (i.e., "the prayer of

1 Vide above p. 99, n. 2, for the use of sand as a purifier among the Mahomedans also.

Ahunwar or *Yathâ Ahû Vairyô* protects the body”) and then recites the *Ahunwar* formula once. He then asks the candidate, as before, to advance to the 8th pit or set of 5 stones (*h*). On the candidate taking his seat there, the application to the body is neither that of *nirang* nor of sand but of *âv*, i.e., consecrated water. This he does three times. The candidate applies the consecrated water to his body as he had previously applied the *nirang* and the sand. The first priest retires into his *pâvi* (*Z*) and the second priest with the dog advances, and the same process is gone through as before. Then, the first priest getting out of his *pâvi* recites “*Ahunem Vairîm tanûm pâiti, Yathâ Ahû Vairyô, and Kem nâ Mazdâ*” as at the eighth stage of the process and asks the candidate to advance to the ninth pit or the 9th set of 5 stones (*i*). Here again he gives him thrice the consecrated water for application as at the 8th set of stones. The whole of the process is the same. But there [134] is this difference, that at this 9th pit or set of stones, the whole process is repeated or gone through twice.

Then again the first priest gets out of his *pâvi*, recites “*Ahunem Vairîm tanûm pâiti, Yathâ Ahû Vairyô, and Kem nâ Mazdâ*” prayers, as he did three times before (once at the 8th stage and twice at the 9th stage), and asks the candidate to advance to the final stage, i.e., the final or the tenth set (*j*) of 5 stones, which, in the modern barashnomgah, is generally replaced by a large broad stone on which one can conveniently sit and bathe. Here again, the priest gives thrice the consecrated water for application and the same process is gone through. But, the process of the recital of the prayers by the first priest and the application of the consecrated water by the candidate is repeated or gone through thrice. The process of the presentation of the dog before the candidate by the second priest is gone through twice.

The bath at the last stage.

The first priest, after giving the consecrated water for application for the last time on the last stage, places the small metallic cup on the ground out of his *pâvi*, and makes a small *pâvi* round the cup. He then brings out of his *pâvi* the second pot of water which is consecrated by the addition of a few drops of *âv* or consecrated water and pours a little water out of it into the above-named small metallic cup. Then, taking the pot before the candidate, he pours gradually the water out of the pot upon his body. He must take care, that, in doing so, he himself is not besprinkled with water. He must stand beyond the *karsha* or the furrow. This is the final bath. He then once more retires to his *pâvi* and the other priest presents the dog again before the candidate for the last time. He touches it, keeping his hand thus touched, apart. The dog being removed and the contact broken, the

first priest gets out of his *pâvi* and recites once more “*Ahunem Vairîm tanûm pâiti*” and “*Yathâ Ahû Vairyô*” and the “*Kem nâ Mazdâ*” prayer upto *Nemaschâ yâ Ârmaitish izâcha*. The candidate repeats these last words after the priest. [135]

The following table gives a list of the above details of the applications, &c, in the process of the barashnom purification, according to the modern practice:—

A table showing the number of applications.

No. of the Maga (pit), or the stage, or set of 5 stones.	Kind of the con-secrated substance applied.	No. of applica-tions	Prayer recited.	The pre-sentation of the dog.
1st stage ..	Nirang	3	Kem nâ Mazdâ 1	Once.
2nd ,, ..	Do.	3	Do. 1	”
3rd ,, ..	Do.	3	Do. 1	”
4th ,, ..	Do..	3	Do. 1	”
5th ,, ..	Do..	3	Do. 1	”
6th ,, ..	Do..	3	Do. 1	”
Intervening space represented in the modern barashnomgah by 3 stones.				
7th stage ..	sand ..	18	<i>Ahunem Vairim tanûm pâiti, Yathâ Ahû Vairyô</i> and <i>Kem nâ Mazdâ</i> . 1. ...	”
8th ,, ..	âv (water) 3	3	Do. 1	”
9th stage. Process repeated.	âv 3 âv 3	6	Do. 2 repeated twice.	Twice.
10th or the final stage.	âv 3 âv 3 âv 3	9	Do. 3 repeated thrice.	Thrice.

This table shows that there were altogether 18 applications of *nirang* or consecrated urine of the ox, 18 *khâk* or sand and 18 of *âv* or consecrated water. The first priest recited the *Kem nâ Mazdâ* prayer only six times and recited that prayer with *Ahunem Vairim Tanûm*

pâiti and *Yathâ Ahû Vairyô* seven times. The dog was presented before the candidate 13 times. [136]

Consecrating the clothes.

After the recital of the final *Kem nâ Mazdâ*, as said above, the priest fetches the candidate's new set of clothes before him. It was placed aside in the barashnomgah beforehand. He pours over that suit a few drops of consecrated water from the small metallic cup which he had filled up just a little while ago. Thus, he consecrates the candidate's clothes before he puts them on. He pours the rest of the water out of that cup upon the left hand of the candidate, which had remained uncleaned since he had touched the dog for the last time with that hand. The priest then retires to his *pâvi* again. The candidate now puts on his suit of clothes and places his *kusti* or sacred thread over his shoulders. He then puts on his *jâmâ* or a loose linen overcoat which forms the upper garment of a Parsee's full dress. This garment has always long sleeves. While putting it on in the barashnomgah after his bath of purification, he is not to pull up these long sleeves, but is to keep them hanging. Then the priest comes out of his *pâvi* with his two nine-knotted sticks in his hands. The candidate then throws the loose low skirt of the right-hand side of his loose hanging gown (*jâmâ*) on his left shoulder, placing his left hand under it over the shoulder. The priest places the spooned end of one of his knotted sticks over the above-said skirt of the gown. The candidate places his right hand covered with its hanging sleeves over the above spooned end of the priest's knotted stick. In all this, care must be taken that the candidate's sleeves and clothing touch only the metallic spoon but not the wooden part of the stick. Then the candidate finishes the *baj* which he had taken when he had just entered the barashnomgah for purification and just before removing his clothes.¹

When the candidate has individually finished the *baj*, he and the priest jointly again finish the *baj*. Having done so, the priest makes the candidate recite the following formula:—

“Zadeh nasash, sar o tan pâk ashahê ravân (he repeats the words three times), sag asho harbad pâk.” (These words also [137] are repeated thrice). The words mean, “The Nasu, i.e., the Evil Spirit of pollution is put down. The head and the body, (i.e., the whole body) have become purified. The soul has been purified. The dog is holy, the priest is holy.”

When these words are repeated, the priest lifts up his knotted stick from the shoulder of the candidate who now puts on the sacred thread

1 *Vide* above, p. 125.

[kusti] that was hanging over his shoulders, reciting the Nirang-i-Kusti. This finishes the ceremony of the barashnom purification.

5. Retreat after the barashnom.

Retreat of 9 days.

Though the purification proper is finished, the candidate has still to wait for full nine days and nights before he goes to his usual avocation.¹ After the purification, he retires from the barashnomgah to the Dar-e Mihr or Fire-temple. Some temples, for example the temples at Naosari, have a separate place for the purpose, which is called *nâhnhâneh* (نان خانه i.e., the place for *nâhn*). It is so called because the barashnom also is ordinarily known as *nân*, the name by which the second purification is known. There, he has still to remain aloof from others. He is not to come into contact with anything. His food and water are to be served to him in his plates and cups by other persons. He has to take his meals during the day-hours. He is to eat with a spoon in a gloved hand and not to use his fingers. He has a separate suit of clothes for the purpose of his meals. He has to say his prayers for the most part of his time, especially at the commencement of the 5 *gâhs* or periods of the day. The first three nights must be, as it were, nights of "vigils," i.e., when he sleeps, he must sleep in a watchful or wakeful mood, so as not to let his sleep be disturbed by worldly thoughts. If he is disturbed by a nocturnal pollution during the first three nights, he has to repeat the whole of the barashnom purification referred to above.

If the barashnom is gone through for being qualified to perform the Nirangdin ceremony which is the ceremony for [138] the consecration of the gomez or cow's urine, a nocturnal pollution during any of the nine days and nights of the Retreat vitiates the whole barashnom, which, in that case, is to be repeated. The priests in this ceremony are expected to pass their time in pure mental thoughts, in devotion, and prayer. A wet dream is a proof that they have not done so. So, they are disqualified to perform a religious ceremony in which *gâomez* (urine) and *âv* (water) are consecrated for the purification — both physical and mental — of others. If those who consecrate a thing are not mentally pure, the things consecrated by them are not expected to have the influence of purifying the body and elevating the mind of others. He only, who is himself pure — both physically and mentally — can make others pure, both physically and mentally. In the case of the initiates or candidates for priesthood (*nâvar*), a similar state of mental purity is expected for a much longer time.

1 The Old Testament (Num. 19) seems to enjoin seven days.

Again, the candidates are not to sit, rest, or sleep on wooden chairs or benches or beds, when in the Retreat. They spread their beds on the floor. Wooden things are all avoided. They are not to use water for any purpose except for drinking. They are to perform their *pâdyâb* also with the application of a little *gomez*. They observe the dry system and use a kind of clay instead of sanitary paper.

The *navshu* baths.

On the fourth day, after their great barashnom purification, they are to go through a bath which is known as the first *navshu*, i.e., the first bath (or, wash 'shu') out of the nine nights of the Isolation or Retreat. The process is as follows:—

In the barashnomgah or in any other clean place covered over with dry sand, a *pâvi* or enclosure is made by drawing three *karshas*. A set of three stones is placed therein for the candidate to sit on to bathe. Then a priest with the barashnom, who has performed the Khub, makes *pâv*, a water-pot and a small metallic cup. The water-pot is then filled with ordinary pure water. A few drops of the consecrated water are put into it. This consecrates all the water. In the metallic cup is poured a little of the consecrated *gomez*. The candidate [139] then goes to the place and undressing himself, puts his clothes in an adjoining *pâvi*. He then takes his seat on the above-mentioned set of three stones, facing the east. Then the priest who is to give him the supplementary sacred bath, brings the metallic cup containing *gomez* before him, and places it out of the *pâvi* of the candidate drawing a *pâvi* or *karsha* round about the cup. The candidate then places his right hand over his head and takes the Baj of Srosh, beginning with 3 Ashem Vohus. Reciting the *Kem nâ Mazdâ*, upto the word *Ashahâ*, he takes the metallic cup before him and applies the *gomez* thrice over his whole body. Having done so, he removes the cup out of his own *pâvi*. The priest then brings the pot of the consecrated water and places it before him, drawing a *pâvi* round it. He pours a few drops of the consecrated water out of the pot upon the newly washed set of clothes which the candidate is to put on after his bath. He thus consecrates the clothes also. The candidate then bathes himself. Then, putting on his clothes and placing his sacred thread over his shoulders, he finishes the baj, facing the sun. He then puts on his sacred thread. This finishes the first *navshu* bath. If the candidate has gone through the first great barashnom purification in the Hawan gah, i.e., in the morning he must have his first *navshu* in the morning of the fourth day. If he has gone through it in the Uzerin gah, i.e., in the afternoon, his *navshu* bath must be had in the afternoon.

After the *navshu* bath, the candidate again returns to his place in

the Fire-temple and observes the regulations in the same way as during the first three days. He then has a second *navshu* bath on the seventh day. The process is all the same, but with this difference, that at this second *navshu* he is given two pots of water. The second pot need not be as large as the first. A small one is generally given. Then again, three more days of retirement are observed. The above process is gone through on the tenth day, but with this difference, that in this third *navshu*, three pots of water are given him to wash his body with. After this final bath, he is free to come into contact with all. [140]

The *Khûb* after the barashnom.

We said above, that it is generally the priests now-a-days who go through the barashnom purification ceremony, and that, that ceremony is held to qualify them for the performance of several liturgical ceremonies. So, to qualify themselves for these, they perform, in the morning of the 11th day,¹ what is called the *Khub* ceremony. It consists in the recital of the whole of the *Yasna*, accompanied by its ritual. A priest who has himself performed the *Khub* previously, makes him get through this *Khub* ceremony. This finishes the whole of the barashnom.

The time of the barashnom ceremony.

The barashnom purification, as well as the *Nân* purification, can be gone through the day-time only, and not at night.² Again the barashnom purification, in modern practice, is gone through, only during the dry season³ and not during the rains. The Naosari priests stop it from roz Warharan (or Behram), month Aban (the 20th day of the 8th month), up to roz Warharan, month Frawardin (the 20th day of the 1st month), of the next year. Among the priests of other towns, the days vary somewhat. The reason seems to be this. As said above, it is enjoined that the place of the barashnomgah must be dry and free from moisture. But the rains prevent the ground from assuming this state of dryness. Even in the ordinary dry season, if it rains out of season, the purification ceremony cannot be gone through. Not only that, but even if it rains continually for a day or two, during the nine days and nights of the Retreat, one is to abandon his course of Retreat and to repeat the whole barashnom from the very commencement when the weather gets dry and the barashnomgah gets free of moisture. The reason for vitiation is, that, owing to the continuous rain, he

1 In Some towns, they do this in the morning of the 10th day itself after the third or final *navshu* and then an ordinary bath.

2 Pahl. Vd. 9:32 *amat shap patas dayan yatunet la shâyad*, Dastur Darabji's Text, p. 187.

3 *Ibid. amat dayan mag-i pavan gomiz vârân vâdumyen la shâyad.*

is not likely to avoid rain water falling upon him while going out for purposes of nature to the proper places which are generally [141] detached from the Temples, and while going to the barashnomgah for his first, second or third *navshu*.

A barashnomwala priest. Causes that vitiate the barashnom.

A priest, who has gone through the complete barashnom purification including the final Khub ceremony, is said to be a barashnomwala priest, i.e., a priest with the barashnom qualification. He is said “to hold” that qualification as long as he observes certain rules and observances enjoined by custom to be held. A priest may hold that qualification for years together, or his qualification may be vitiated or made defective in a short time. When holding the barashnom, he is qualified to perform the religious ceremonies of Baj, Yasna, Visparad, and Vendidad, which are generally performed in a Fire-temple. If he does not hold the barashnom, he cannot perform these, but can perform ordinary ceremonies, such as the Naojote, Marriage, and Afrinagan.

The non-observance of the following regulations and observances vitiate the barashnom: 1. Eating of food cooked by non-Zoroastrians. 2. Non-observance of the Baj. 3. Long travels and voyages. 4. Swearing or taking oaths. 5. Falling off of the turban from over the head.

1. Food cooked by non-Zoroastrians.

Barashnomwala priests are required to abstain from food cooked, and water fetched, by non-Zoroastrians. Custom in India has gone even further and has enjoined that they must be cooked and fetched by a member — male or female — of the priestly class. Even the holy bread (*Dron*) which they consecrate in the Baj, Yasna, and Vendidad ceremonies must be prepared by members of the priestly class. Upto a few years ago, even the laymen abstained from food cooked by non-Parsees.¹ [142]

2. Observance of the Baj.

They must commence and finish several daily functions of necessity, with the recital of the baj. Some of these functions are the meals, baths and calls of nature, which all have their proper bajs or recitals to be made at the beginning and end. These recitals do not take a long time, but they generally begin and end with the padyab-

1 It is said, that about 50 years ago, when the late second Sir Jamsetjee Jejeebhoy, Bart., entertained H. R. H. the late Duke of Edinburgh, the uncle of His Majesty King George, at his bungalow at Khaadala (thereafter named as the Duke's Retreat), he had separate tables for His Royal Highness and party and for himself.

kusti. The non-observance of these regulations vitiates the barashnom.

3. Long travels and voyages.

Long travels vitiate a barashnom. It is generally so, in the case of long railway travelling. The reason seems to be that while so travelling, it is not possible for the barashnomwala priest to observe the above rules and regulations about saying the bajs on the necessary occasions or functions. For example, he must perform the padyabkusti before his meals. To do that, he must have pure clean water fetched by himself or by a Zoroastrian. He must tie and untie his sacred thread. While doing so he must avoid contact with a non-Zoroastrian. All these cannot be done in a long journey by railway train.

Long voyages also vitiate a barashnom; not only that, but they are held to disqualify a priest on his return to his town from performing the Yasna, Vendidad, Baj, and such other higher liturgical ceremonies.

The version of Tacitus on the subject of long voyages.

This is an old Iranian custom referred to by Tacitus, in his account of the Parthian King Valkhash (Vologeses) and his brother Tiradata (Tiridates), the King of Armenia, who lived in the time of Emperor Nero and who belonged to an orthodox priestly family. They were both kings as well as priests. When called to Rome by Nero, to receive his crown as King of Armenia from his own hands, Tiridates refused on account of his religious scruples to go by sea. Tacitus says on this point: "Neither would his (Vologeses') brother Tiridates refuse coming to Rome to receive the Armenian diadem, but that the obligation of his priesthood withheld him: he would, however, go to the standards and images of Cæsar, and there, in [143] presence of the legions, solemnly receive the Kingdom."¹ Subsequently when Tiridates did go to Rome, he went by land instead of by sea. It is said that even Valkhash (Vologeses) refused to go to Rome by sea, when called by Nero.

Reason for this prohibition suggested by the *Vendidad* and supported by the writings of Heroditus and Strabo.

The reason seems to be this: The Zoroastrian books, and among them, the *Vendidad* especially, enjoin that no impurities may be thrown into water. If a Zoroastrian finds some rotten thing thrown in water, it is his duty to get into the water and remove it (Vd. 6:26-27), lest it may infect the water and endanger the health of the living.

¹ *Works of Tacitus* (The Oxford Translation), Vol. I, *The Annals*, Bk. XV, 24. Vide the translation of A. J. Church and W. J. Brodier (1891), p. 296.

Herodotus refers to this old Iranian view when he says: "They (the Persians) neither make water, nor spit, nor wash their hands in a river, nor defile the stream with urine, nor do they allow anyone else to do so."¹ Strabo also refers to this custom and says: "The Persians never pollute a river with urine, nor wash, nor bathe in it; they never throw a dead body nor anything unclean into it."² In long voyages by sea, a Zoroastrian priest has to commit nuisance therein and throw impurities in the sea. So, he is prohibited to go on long voyages. If he does, not only is his barashnom vitiated, but he is prohibited from going through it again. This prohibition seems to stick to the letter and not to the spirit of the original commandment. The prohibition to throw impurities in water was originally in the case of the fresh water of streams and rivers. Herodotus and Strabo refer to the fresh water of rivers. So far, it was good and sanitary. But as it generally happens in the matter of many commandments, the field of operation for the above wholesome regulation was widened and made unduly strict in later times, even as early as in the times of the Parthian dynasty. [144]

4. Prohibition to take oaths.

If a priest holding the barashnom has to go to a court of justice, and there to swear or take an oath, his barashnom is vitiated, and he has to go through it again if he wishes to continue his profession. This custom also seems to be a very old Iranian custom. We find references to it in old Parsee books. Adarbad Mahraspandan³ asks his readers not to swear. The prohibition seems to rest on the oft-spoken characteristic of an ancient Iranian, *viz.*, to speak the truth and nothing but the truth — a characteristic referred to by Herodotus,⁴ Xenophon,⁵ Strabo,⁶ Plato,⁷ and Nicholas Demoscenes.⁸ To speak the truth was considered, as it were, the birth-characteristic of an ancient Iranian. His word must be taken as true by the opposite party. If it was not, and if he had, in order to support it, to swear or to take an oath, that was, as it were, a slur upon his character. If he yielded and swore, he, as it were, showed his want of self-respect. That being the view, an ancient Zoroastrian was prohibited from taking an oath. The

1 Bk. I, 138. Carey's translation (Bonn's series 1889), p. 52.

2 *The Geography of Strabo* (translated by Hamilton and Falconer, 1857). Vol. III, p. 137; Bk. XV, chap. IV, 16.

3 Pand-nameh, 42.

4 Bk. I, 136, 137.

5 *Cyropædia*, I. 20.

6 XV, ch. III, 18.

7 Alcibiades, I, 121.

8 Fragment, 67.

modern custom seems to be a relic of the old idea. So, if a priest has to go to court and unavoidably to take an oath, he is supposed to have gone against an old commandment, and therefore, his barashnom is vitiated. Hence, Parsee priests generally avoid going to courts, especially during the monsoon months, when, owing to the rains, they cannot go through the barashnom ceremony again to qualify themselves for the performance of the inner ceremonies of the Temple. They are very careful to avoid any action that may vitiate their barashnom during the rainy months, because the Frawardigan holidays, during which their services are in greater demand and better paid, occur at the end of the season.

5. Falling off of the turban. The turban and the *padân*, the insignia of priesthood.

The Parsee priests generally wear white turbans. If the turban falls off from their head, even accidentally, that vitiates the barashnom of the priest. The reason seems to be this: Firstly, all Zoroastrians are required to have [145] their heads covered. It is improper to remain with head uncovered. So the falling off of the hat interrupts the observance of the custom. But the most important thing is this, that the turban and the *padân* are, as it were, the insignia of the office of priesthood. When that insignia falls off from the head, he is, as it were, deposed from his sacred office. So, his barashnom, which qualifies him for that office, is considered to be vitiated, and he has to repeat it, if he wishes to continue to perform that sacred office. This custom seems to be an old custom common among some other ancient nations. "In the old religions, one so often finds that the celebrant and assistants officiated with shrouded heads The Flemins of Jupiter were forbidden to present themselves in public or even to go out into the open air without their skull-caps, and that, too, by a law so stringent that Sulpicius, when the tuft of his fell off accidentally, was deposed from his sacred office."¹

The *padân* or the piece of cloth, which a Parsee priest puts on over the face while performing religious ceremonies, is also held as an insignia of the qualification of the barashnom. Though it is put on by the priests in other ceremonies also wherein the barashnom qualification is not necessary, still, in the phraseology common among the priests, "*padân bândhvu*," i.e., to put on the *padân*, means to be qualified to officiate with the barashnom. When the head-priest permits the subordinate priests to go and officiate in the Yazashnagâh of the Temple, he says, "Put on the *padân*." When he wants to prohibit somebody from officiating there, he says, "Do not put on the *Padân*."

1 "Good Words," June 1893, p. 389: Article on "Hats and Caps" by Geoffrey and Winterwood.

So when one pulls off the *padân* from over the face of a priest, or when he takes off or throws off the turban from over his head, he deprives him of his qualification and is responsible for the action. The barashnom of the priest, so deprived, is vitiated.

IV. Riman, The Fourth Form of Purification.

Riman purification. Its process.

As said above, the barashnom purification, though originally a purification for those who had come into contact with the dead, especially the dead who died of infectious diseases, has, now, [146] with its accompanying retreat and Khub ceremony, come to be a form of purification for the priests who wish to perform the religious ceremonies of the inner circle of the Temple. So, now-a-days, those who have come into contact with dead bodies, in ways that have been prohibited, have to go through a comparatively simpler form of purification. It is known as *Riman* purification. We will describe it here shortly:—


The word *Riman* ریمان Pers. comes from ‘rim,’ (Pahl. ریم)

Pers. ریم or رِم from Av. root *ri* ریم Sans. र्लि to ooze, to be foul, to desecrate) i.e., pus, filth. This word seems to be the same as English “rheum” meaning “serous fluid secreted by mucous glands.” So “*riman*” is one that has become polluted by coming into contact with filth from dead bodies. In this form of purification, the services of two persons are required, one of them must be a priest, the other may be a layman. In order to be qualified to purify a *riman* (i.e., the person supposed to be polluted or infected) by this process of purification, the priest must perform the Khub ceremony. The efficacy of his Khub ends with the purification. If he has to perform other ceremonies which require the Khub, he must repeat the Khub ceremony. In the *riman* purification, the alat, i.e., the consecrated things and the other requisites required, are the same as those in the barashnom.

The place for this purification.

The place of the purification must be one which is the least frequented by people. On such a place, the priest has to prepare altogether nine *pâvis* or enclosures. While preparing these, he is to bear in mind the position of the sun and the direction of the wind. The *pâvis* must be so drawn as not to let the shadow of the *riman*'s body fall over the purifier, and thus deprive him of the heat and light of the luminary. Again, they must be so arranged that the direction of the wind may not be from the *riman* to the purifier, lest it may carry any

germs of disease from the infected person to the priest. The *pâvis* may be prepared either by digging in the ground, or by spreading sand on the ground in a way which may form a [147] furrow. Generally it is done in the second way. Seven of the *pavis* must be in one line and two others in a line by the side of this row adjoining the central part of the row. A tenth circular *pâvi* must be drawn at a distance with six circular furrows. A set of three stones are to be arranged outside this circular *pâvi*.



Description of the plan.

The above plan gives an idea of the place. In the *pâvi* A, the priest first places all the *alat* or the consecrated requisites. He then performs the *padyab* and then fetches water from a well in two pots previously made *pâv* or purified by three washings. One of these two pots is large and the other small. Then he puts on tight trousers known as *ijâr* and also the *padân*. Then, as in the case of the barashnom, he makes two small metallic cups *pâv*, and, after having dried them, pours in one a little of the *nirangdin*, i.e., the consecrated urine and the *hasam*, i.e., the sacred ash, and into another a little of the urine for external application. He then makes the two water-pots *pâv* and throws a little of the *âv* or consecrated water into them. The priest then retires to his *pâvi* wherein the *alat* are placed. Then the *riman*, i.e., the person who seeks purification, undresses himself at a distance and buries his clothing in the ground. He then comes and takes his stand in the *pâvi* G allotted to him. The [148] second person who has accompanied the priest and whose standing place is somewhere about L gives to the person who is *riman* all the necessary

instructions as to where to seat himself etc. He gives these instructions by a show of hands and signs. He is not to speak anything.¹ He must not go so near the *riman* as to let his shadow fall upon himself or to let the wind blow from his direction towards himself. The priest then pours the consecrated urine from the small metallic cup into an empty shell of an egg. This is done to avoid even a drinking cup coming into contact with the lips of the person supposed to be infected. He places the shell so filled and a leaf of the pomegranate in the *pâvi* (marked I). The second person lifts these up and places them in the *pâvi* F. He, by signs, instructs the *riman* to chew the pomegranate leaf and then to drink the consecrated urine three times from the shell of the egg. The *riman* must avoid touching his lips with the shell but try to pour the consecrated urine into his mouth, so that even the shell of the egg may not catch any germs. Having drunk from it, he breaks the shell and buries it in the ground near his place. Then the priest advances from his *pâvi* A to the third *pâvi* C with the *navgireh* [naogar] in his right hand and the small metallic cup containing the consecrated urine for application in his left hand. From there, by means of the long *navgireh* [naogar] or the nine-knotted stick, he pours the *gomez* in the hands of the *riman*. He must avoid touching the hands of the *riman*. He must throw it quickly so that the falling liquid may not even form a current which can transfer the infection. The *riman* then applies the *gomez* to his body 15 times. Having given the *gomez*, the priest comes back to his first *pâvi* A, takes a little sand from there and goes to the third *pâvi* C again, and gives as above the sand to the *riman* 15 times. The *riman* rubs the sand over his whole body. The priest then coming back to his *pâvi*, takes the small pot of consecrated water with him and similarly pours that water to the *riman* 15 times for application as above. He then coming back to his *pâvi* takes [149] the large pot of water and places it in the *pâvi* I. The second person takes it from there and instructs the *riman* by signs to leave his *pâvi* G, and advance to the place of his final bath K. The *riman* does so. Then the second person, standing at some distance from him, pours from the pot gradually the water on his body. He is to take care that he is not besprinkled with any water from the body of the *riman*. He is to pour the water three times over his body. Thus washing his body, the *riman* puts on a new suit of clothes fetched near him by the other attendant. He then puts on the sacred thread [kusti] reciting its usual *nirang*. This finishes the process and the person is now purified.

1 Compare what is said of the restrictions in the Plague of Florence in 1310: "Nor was it (plague) given by conversation only with or coming near the sick, but even by touching their clothes or anything that they had before touched." (Quoted in the *Times of India* of 27th December 1898).

Old Iranian Purification and Modern Plague Operations.

All the Iranian injunctions about purification as enjoined in the *Vendidad*, and to a certain extent, as observed now, appear to have at first the object of securing safety from disease. They seem to have been framed in the times of a great epidemic. The plague operations of modern times in India, especially in the first two or three years of the plague, have shown, that these injunctions had their use in those early times, and have their use even now, if observed in the spirit and not in the letter. We would compare here some of the above injunctions with modern regulations, enjoined in the times of plague in its early stages in Bombay in 1897 and 1898. Some of these were enforced so strictly that they even led to public riots.

1. Purification or disinfection of infected houses.

The houses where plague cases occurred were disinfected. In case of tents, they were removed and sterilized. A number of houses were fumigated with sulphur and other substances. There is a corresponding injunction in the *Vendidad* to fumigate the house or to remove the house if removable, i.e. if it is a hut or a tent. The dwellers were to leave the houses for a time.

2. The *Hamrit* of the Parsee books and the “Contacts” of modern times.

Those who came in contact with plague cases, for example members of the family in which a plague case occurred, were called “contacts” by Plague officers. There were separate isolated “contact camps” for them. The regulations [150] for these people were at times so hard that they caused great heart-burning. In a Parsee camp at Dadar, it was enjoined by a Plague Medical Officer in charge of the district, that the inmates of the camp must not be allowed to move out of the camp and to go to the bazaar to fetch their daily things, but that a person — an outsider — may be appointed to take orders from these people and fetch things for them. As the Secretary of the Institution that erected these camps, I had to protest to the Plague Committee against too hard an enforcement of this rule, and relief was granted. But, I think that the European Medical Officer was a better follower of the *Vendidad* in this matter than myself.

3. The *Patrits* of the Parsee books and the “Evicts” of the modern times.

Those, who did not come into contact with plague cases, but came into indirect contact with the “contacts,” were called “evicts,” and they also were asked to go out to camps. Both these classes of people had to remain in camp for at least a period of 10 days known as the

“incubation period.” The “contacts” were asked to hold little intercourse with others outside the camp. The “evicts” were allowed to go out, but were carefully watched. These “contacts” of the modern plague phraseology were the “*hamrits*,” and the “evicts” were the “*patrits*” of the old Parsee books. According to the *Vendidad* also, the immediate “contacts” had to go through a purification-isolation for 10 days.

4. The baths and fumigations of the *Vendidad* and of modern times.

In the first years of the plague, people leaving infected towns and districts were made to go through a bath with disinfecting substances. On railway stations like that of Anand, passengers had to get down and go through such baths before proceeding further. In some places, they had to go through fumigation. For example, the Baroda State had ordered at one time, that people going to Naosari, one of the towns under its jurisdiction, and the headquarters of the Parsee priesthood, were, before they went to the town, to go through fumigation in a house adjoining the station. It is said, that even the Head Parsee Priest of the town, on returning to [151] Naosari from a visit to an adjoining town, was made to submit to this fumigation; and he took some offence at this compulsion, not remembering, perhaps at the time, that what he was then enjoined to do, was a form of the injunction of his own *Vendidad*, where a person, after passing through the barashnom purification, was enjoined to go through a fumigation (Vd. 9:32). The *Yaôzdâtâr*, i.e., the priest or the officer who made the person pass through the purification, was required to be a person well versed in his work of ensuring perfect purification. If he did not know his work well or if he failed in his duty, he was condemned as a man who brought disaster upon his city (Vd. 9:51).

5. Conversation with the infected.

It is said¹ that in the 14th century, at the time of the plague in A.D. 1340 at Florence, it was believed that even conversation with an infected person transferred disease from one to another. In the *riman* purification, it is a custom that the purifier and the person going through the purification must not speak, and the former must take his stand in a position which would avoid even the current of wind from the latter.

6. Destruction of things suspected of contact.

As in the *Vendidad*, so now-a-days, things, that are supposed to have come into contact with the dead body of an infected person, are

1 *Vide* above, p. 156, n. 64.

enjoined to be rejected, or if used, to be used only after certain disinfection (Vd. 6:42-43; 8:12-15; 28-35; 73-75).

7. Burial prohibited.

Scientific opinion believes that plague germs remain buried in the ground together with the dead body and thrive again after a number of years on getting an opportunity. "Even after the lapse of several hundred years microzymes, or disease-producing organisms, were found to be alive and as active as ever and became the cause of death to hundreds of workmen engaged in digging up ground which had been a burial place of some who had died of the plague of Modena, 300 years before. In fact, [152] the plague was started anew and so killed thousands more."¹ It is with this idea that burial seems to have been prohibited in the books of the Parsees. Herodotus refers to this ancient prohibition (I, 140). Strabo also refers to it (Strabo's Geography, Bk. XV, chap. III, 20). According to the *Vendidad*, the place where a corpse is buried is not considered to be pure and safe to live upon, for a period of at least 50 years from the time of the burial (7:48).

As said by Prof. Darmesteter, with the Iranians, the question of a man's death was not the question of his death alone. "In the death of a man, there is more involved than the death of one man: the power of death, called forth from hell, threatens from the corpse, as from a stronghold, the whole world of the living, ready to seize whatever may fall within his reach, and 'from the dead defiles the living, from the living rushes upon the living.' When a man dies in a house, there is danger for three days lest somebody else should die in that house."²

"The notion or feeling, out of which these ceremonies grew, was far from unknown to the other Indo-European peoples: what was peculiar to Mazdaism was that it carried to an extreme, and preserved a clearer sense of it, while elsewhere it grew dimmer and dimmer, and faded away. In fact, when the Greek, going out of a house where a dead man lay, sprinkled himself with water from the ἀρδανίου at the door, it was death that he drove away from himself. The Vedic Indian, too, although his rites were intended chiefly for the benefit of the dead, considered himself in danger and, while burning the corpse, cried aloud: 'Away, go away, O Death! injure not our sons and our men!'" (Rig-veda X, 18,1).³

I will close this subject with a short account of purification among

1 Scientific American, 1888.

2 *Sad Dar*, 78. S.B. E., Vol. XXIV, p. 341.

3 S. B. E., Vol. IV, *Vendidad*, Introduction V.3, first ed., pp. LXXXVI.

the ancient Hebrews and Romans, with a view, that the reader may see, at one glance, some points of similarity, between the Iranian purification and the Hebrew and Roman purification. [153]

The Iranian purification and the Hebrew purification.

With reference to the similarity between the purificatory regulations of the Iranians and those of the ancient Hebrews, we read in the Old Testament, of the unclean being removed out of the camp. And the Lord spake unto Moses, saying, "Command the children of Israel, that they put out of the camp every leper, and everyone that hath an issue, and whosoever is defiled by the dead: Both male and female shall ye put out, without the camp shall ye put them; that they defile not their camps, in the midst whereof I dwell."¹ We find some points of resemblance as follows:—

1. In place of the consecrated *gomez*, the Hebrews had what they called the "water of separation." It was produced as follows: An unyoked spotless red heifer was slayed in the presence of the priest who sprinkled her blood before the tabernacle seven times, and burnt her with all her skin, flesh, blood, and dung. Cedar wood, hyssop, and scarlet which, as it were, here took the place of the *urvâsna*, *vohû-gaona*, and *vohû-kereti* of the *Vendidad*, were burnt with the heifer.² A man that was clean was to gather up the ashes of the heifer so burnt, and was to "lay them up without the camp in a clean place . . . for a water of separation" which was "a purification for sin."³

2. The Iranian barashnom, the purification of one who had come into contact with the dead, lasted for full nine days. The Hebrew purification lasted seven days. "He that toucheth the dead body of any man shall be unclean seven days." As in the Iranian barashnom, so in the Hebrew purification, there was one purification on the third day (the first *navshu* of the barashnom) and the second on the seventh day. As the unclean man in the Iranian barashnom is asked to keep himself away from a place of worship, so among the Hebrews, he was to keep himself away from the holy tabernacle. Among the Hebrews, even one, who "toucheth a bone of a man, or a grave, shall be unclean seven days."⁴ [154]

3. Ashes played an important part in, the purification ceremonies in both. In place of the ashes of the burnt heifer, the Iranians had the *bhasam* or the ashes of the sacred fire of Atash Bahram.

1 Num. 5:1-3.

2 Num. 19:3-6.

3 Ibid., 9.

4 Num. 19:11 and 16.

4. Among both, if a man died in a tent, the tent became unclean. Among the Hebrews the uncleanness extended to "all the vessels, and upon the persons that were there."¹

5. Among the Iranians, the *yozdathregar* (*yaozdâiar*) or the purifier is required to take all possible care to secure himself from any contact with the unclean. Among the Hebrews also, the purifier, the person "that sprinkleth the water of separation" is required to wash his clothes. He was taken as "unclean until evening."

6. Among both, any person, whom the unclean touched, himself became unclean.

The Iranian purification and the Roman purification.

The ceremony of the *barashnom* purification of the ancient Persians and the modern Parsis reminds us of two kinds of purification known to the ancient Romans.

(1) One was that of the *taurobolium* or blood-bath in the worship of the Mother, the goddess Cybele which worship the Romans are said to have admitted into Rome from Prgia, with all possible pomp and dignity, in order to have its protection and help against Hannibal who was overrunning Italy. The *novena* or the fast of nine days in this ceremony reminds us of the nine days (*noh-shab*) Retreat of the *barashnom* ceremony. In the ceremony of Cybele, "the votary was placed in a pit covered with a grating of planks pierced with holes, on which a bull and a ram were slaughtered, so that the blood dropped through on to the recipient below."² Thus, we see, that pits or holes and bulls had their use in the Roman *taurobolium*, just as they had in the Iranian *barashnom*. The worship and ceremony of this goddess are connected by some with the worship of Mithras which had [155] spread in the West. This Mithras of the West was the Mithra of the ancient Iranians, and it must be remembered, that, even now, the temple, where the *barashnom* purification ceremony is gone through, is spoken of as the *Dar-e Mihr*, i.e., the Port or the Gate of Mithra, *Mihr* being the later Persian form of Mithra. The ancient Iranian worship of Mithra, the *Yazata* or Angel of Light, while passing to the West had much degenerated. Here, we have an evidence of this. When the Iranians used and continued to use the *gomez*, the urine (*mez*) of the cow or the bull (*gao*) after consecration, the borrowers of the mysteries or the rituals in the West resorted to blood sacrifices in which they slaughtered bulls. It is possible, that the degeneration in the West may have reacted to some extent here and there on Iran, but,

1 Num. 19:14-18.

2 *Journal, R. A. S. of 1917*, p. 704. Article on The Most Ancient Goddess Cybele, by Mr. F. Legge.

on the whole, the original object of purification, the physical, mental, and moral purification, was not lost sight of but was always in view. Of the Roman celebration of the goddess Cybele, it is said, that (a) "it was thought to have a magical effect on the votary, who often records on votive tablets and altars that he or she has been by it 'reborn unto eternity.' (b) It also seems to have been performed, like the Catholic Mass, for the benefit of others, since we hear of its being celebrated for the health of the emperor, the success of the Roman arms, and other like purposes."¹

We may say that upto about 69 or 70 years ago, as in the case of the Cybele celebration among the Romans, so among the Parsees, very young girls, of the age of about ten or under, went through the barashnom purification. Even now, some priests go through the purification for, what Mr. Legge speaks of, as "the benefits of others."

(2) The second Roman purification of which we are reminded is that known as the "lustratio." A paper on "Lustratio" by Mr. Fowler² suggests many thoughts of similarity:

(a) As among the Parsees, so among the Romans, the original idea of purification or lustratio arose from the idea of [156] removing impurities caught from "some mysterious miasmatic contamination,"³ corresponding to the Druj-i Nasush of the Iranians.

(b) Water, bull's blood, fire, sulphur, laurel, wool, and pine twigs formed some purificatory materials among the Romans. Water, bull's urine, fire or rather its product, ashes, and some fragrant plants for fumigation were the materials among the Iranians. The Romans also used "strips of the skin of a victim." The Iranians had nothing of the kind of victims or animal sacrifices. They had the consecrated urine of the bull. The Romans had a cake also as a holy ingredient. Among the Parsees, the candidate had to chew a pomegranate-leaf, but the purifying priest wanted *drons* or sacred breads for performing the *khub* which qualified him to do his work of purifying the candidate.

(c) The Romans associated their lustratio with processions, or "slow-ordered movements in procession, so characteristic of the old Roman character." In the case of the barashnom among the Parsees, in an old Parsee centre of priesthood like Naosari, we find that, at times, some parents invite their near relatives and friends at the barashnomgah to witness the purification of their son when he goes through the barashnom, which precedes his initiation into priesthood. Those assembled then follow after purification, the candidate on foot,

1 *Ibid.*, p. 704.

2 *Anthropology and the Classics* by W. W. Fowler, edited by Mr. R. R. Morett.

3 *Ibid.*, p. 170.

forming a small procession to the temple where the candidate goes through his nine days' retreat.

(d) In the case of the Roman *lustratio* Mr. Fowler draws a line "between a magical period and a religious period."¹ In the case of the Iranian *barashnom* I would distinguish the periods as physical and spiritual (*tani va ravâni*). At first the *barashnom* was meant as a purification from the contact with the dead or from physical impurities, and then a spiritual signification began to be added. Among the Romans the idea of purification was extended from men to animals and even to armies and cities. With this extension of ideas, the periods [157] of *lustration*, which came to be known as *lustrums*, came to be utilized in the case of armies, for reviews of troops, and in the case of cities, for taking the census. The ancient Hebrews also had, in their purificatory ceremonies, some connection with their system of census. The very name 'Numbers' for one of their Old Testament books signifies that.

(e) Among the Romans, February was the month of purification. The month was so called from *februare* (to purify). Among the Parsees, the last ten days of the year are generally the days for the second kind of purification, viz., the *nahn*.

(f) The Romans had, what are known as, their "boundary-lines" in their wholesale purifications of cities. These boundary-lines correspond, to a certain extent, to the Iranian *Kashas*.²

The ancient Egyptians also had some purificatory ceremonies for their priests. According to Maspero,³ the officiating priest must carefully wash — *nabu* — his face, mouth, hands and body; and so necessary was this purification, that from it, the professional priest derived his name *nibu*, i.e., the washed, the cleaned. Similarly, at times, Parsee priests were spoken of as *nâhniâs* from *nâhn*. Water, in which natron &c. had been dissolved, was used as a purifying agent, both for application and drinking. Such water was perfumed with specially prepared incense.⁴ [158]

1 *Ibid.*, p. 171.

2 *Vide* my paper on The *Kashas* of the Iranian *Bareshnm* and the Boundary-lines of the Roman *Lustrum*, *Journal of the Anthropological Society*, Vol. VIII, No. 7, pp. 520-30.

3 *Dawn of Civilization*, p. 123.

4 *A short History of the Egyptian People* by Dr. Budge (1910), p. 200.

CHAPTER VI. PURIFACTORY PROCESSES AND CUSTOMS IN DAILY LIFE.

We will now speak about the purification of things infected, or supposed or suspected to be infected, and of the purifactory processes or customs observed in daily life.

Purification of a house.

Not only is purification necessary for a man who has come into contact with a dead body, but it is necessary in the case of the house where such a death has taken place and in the case of things that have come into contact with such a dead body. In the case of the house, it is enjoined that, after the removal of the dead body, the house may be purified, or, to speak in modern terms, may be disinfected or fumigated, by burning in it the wood of trees like *urvâsana*, *vôhugaona*, *vôhu-kereti*, and *hadhânaepata*.¹ The smoke of the burning wood of these trees was believed to have possessed a disinfecting result. In the case of removable houses, such as tents and huts, it was enjoined that they may be removed from the place where death took place and then disinfected as above.²

Purification of things that have been defiled.

Besides the house, there are other inanimate things, which also get defiled, and they, in their turn, are likely to be the medium of infection. So, just as men require purification, these things also require purification, though that purification is of a simple nature. The following are the injunctions of the *Vendidad* for the purification of these things:— In the case of the bedding of the deceased, if it is spoilt by any excretions of the deceased, it must be rejected altogether. If it is not so spoilt, it may [159] be disinfected with cow's urine and used again.³ If the bedding consists of things made of leather, there must be three washings with cow's urine, three rubbings with some disinfectant clay and finally three washings with water. It must then be exposed in the air for three months before being used again. If the bedding consists of linen things, all the above cleanings and washings must be made six times and the exposure in the air

1 Vd. 8:1-2. These Iranian plants seem to have had the same properties as the *hyssop* of the Bible (Num. 19:18).

2 Vd. 8:3. Cf. the Old Testament, Num. 19:14-18, When a man dieth in a tent: all that come into the tent, and all that is in the tent, shall be unclean seven days And a clean person shall take hyssop, and dip it in the water (i.e. the water of separation made of the ashes of a red heifer) and sprinkle it upon the tent.

3 Vd. 7:12-14.

must last for six months.¹ If wooden things, fodder, and grain have come into contact with dead bodies, a certain portion of these, that may have come into direct contact with the impurities, shall be rejected, and the rest must be purified and exposed in the air before being used.² In the case of metallic utensils, the purification depended upon their specific gravity. Gold being the least porous, and so the least likely to hold infection, golden utensils required only one purification; silver ones, two; iron three, and so on.³

Some purificatory processes in daily life.

In the consideration of the principle of purification, one fact must be borne in mind, and that is that, according to the old Iranian idea, which to a great extent may be considered the modern hygienic idea, not only does death spread uncleanness, but whatever goes out of the body also spreads uncleanness. So, the following things are unclean and require a kind of purification:— (a) Breath or saliva from the mouth; (b) Nails of the fingers or toes, when separated from the body; (c) hair when cut from the body; (d) issues both from males and females.

(a) Uncleanness of breath or saliva. Pollution of drinking from the same cup.

If a person drank from a cup or vessel, touching his lips with the cup or vessel, no Zoroastrian must drink from that cup until it is washed with water. This is enjoined to avoid the risk of catching the germs if any disease, which the first drinker may be suffering from. [160] These germs may have passed with his saliva to the sides of the cup.⁴

Glass or metallic cups from which one person has drunk, touching his lips with it, must be washed and purified. It is after this washing that another person can safely drink from it. In the case of cups made of clay, the clay being porous and so likely to imbibe germs of disease,

1 *Ibid.*, 15.

2 *Ibid.*, 28-35.

3 *Ibid.*, 73-75. Cf. Old Testament, Num. 19:15, where open vessels in the tent where a man died, were taken to be unclean.

4 The following paragraph in a Medical Journal shows that the above injunction is very useful from the point of health: An educational journal contains a warning against the common drinking cup in school, as a means of infective contact. The children should be instructed to provide themselves with individual drinking-cups. Parents must be given to understand, that if the child does not have a drinking cup, it will not be possible to drink in school. The mouth of every consumptive contains the germs of the disease, and the transference of these germs from the sick to the healthy child by means of the common drinking-cup is the easiest accident possible. -*Good Health*, September 1905.

it is believed, that they are not likely to be sufficiently free from danger even after washing. Porcelain though glazed, has some risk. So, custom has enjoined that priests, observing the barashnom, who are expected to observe all forms of purity, must not eat or drink from clay, wooden and porcelain vessels or cups.

The breath or the saliva being unclean, it is a Parsee custom, that when a priest goes before the sacred fire or when he says his prayers with the *myazd*, or the sacred offerings like fruit, flowers, etc. before him, he is to put on a *paiti-dâna* or *padân* over his face,¹ so that the sacred fire or things may not be polluted. Again for this reason, the Parsees are not to extinguish the fire or a lamp by their breath, i.e., by blowing over it.² [161]

(b, c) The pollution of nail and hair.

When nails are pared or hair cut, they must not be thrown at haphazard, but they must be buried carefully in the ground. The *Vendidad* (17) enjoins, that they must be buried in a dry place at some distance from the house in a well-dug hole. It further enjoins that they should be buried with the recital of a certain formula of prayer. According to the modern practice, it is the priests only — and of those also very few — who bury the nails with the recital of the Baj. The hair are rarely buried but they are carefully cast aside. When the head is shaved or the hair cut, it is usually the practice, to bathe after the process.³

(d) Pollution after issues.

Issue makes the person, whether male or female, unclean. Not only the person, but those who come into contact with him or her, before he or she has purified himself or herself with a bath, gets unclean. In the case of a male, wet dream or sexual intercourse makes him unclean and he must bathe before he mixes with others. This practice is still observed generally. In the case of priests, wet dreams vitiate the efficacy of certain religious ceremonies in which they may

1 This custom is alluded to in the Pahlavi commentary of the *Vendidad* (Padâm-i vini ayônâk or ayotâk) i.e., the *padâm* must properly be over the nose, (18:1).

"This principle appears not to have been peculiar to the Zoroastrian Aryans, for the Slavonian priest in Arkona was enjoined to go out of the temple, whenever he wanted to draw breath 'lest the presence of the god should be defiled by contact with mortal breath.'" (Darmesteter. S.B.E. IV, first ed., p. 168, n. 7).

2 The Rivayets; Strabo Bk. XV, chap. III, 14. The Taziks still observe this custom.

3 It is likely, that some other ideas are latterly attributed to the custom of burying the nails and hair. *Vide* my paper on "Two Iranian incantations for burying hair and nails" (Journal of the Anthropological Society of Bombay, Vol. VIII, pp. 557-72. *Vide* my *Anthropological Papers*, Part I, pp. 340-354).

be engaged. Sexual intercourse necessitates a bath for women also. The monthly issue or discharge requires greater restrictions on the part of women.

Menses, and uncleanness. (Vd. 16) The *dastânistân* or the place for the women in their monthly course.

As said above, according to the Iranian views of cleanliness and uncleanness, whatever emanates from human body is dead, and so, likely to do harm to the living. So, like nails of hands and feet, and hair, women's menses fall under the same category, and fall under the heading of things that are under the influence of Ahriman, or the Evil Spirit. They are harmful to the health of the living, and harmful [162] even to the women if not properly guarded and taken care of. So, the first care is to provide proper places for women under this condition.

It appears that in ancient Iran, just as every village or a street in a large town had a separate *margzâd*, i.e., mortuary, where people took their dead from their houses, for the performance of the necessary funeral rites and ceremonies before their removal to the Towers of Silence, so every village or street had also a *dastânistân*,¹ or, a house for the women in menses. It was not convenient in every house to provide proper accommodation for them, so a common house in the village or street was provided. It was enjoined that such a place should be about 15 *kadams* (about 13 yards) distant from household fire, water, and places of worship, and 3 *kadams* (about 2.5 yards) distant from places frequented by men. (Vd. 16:2).

Isolation. Its period.

They were not to touch anything. Anything that they touched became unclean. If they had their children with them, and if these children were to be taken out of their *dastânistân*, their hands were first to be washed, and then their whole bodies to be washed with water. If a person touched a woman in her menses, he became unclean. If he did that by chance or unintentionally, he was to purify himself by a bath with *gomez*, i.e., urine and water. If he did that intentionally, he was to be punished and that punishment increased in proportion as his fault was for the first or the second time and so on (Vd. 16:14-26). If a person had sexual intercourse with a woman in menses, that was a heinous offence deserving great punishment. The 18th chapter of the *Vendidâd* enjoins the performance of several good acts of righteousness in expiation of this most heinous of crimes.

The ordinary period of menses was thought to be three days in the

1 The word *dastân* (menses) comes from Av. *dakhshta* meaning a sign. *Chithra* (चित्र), another Av. word for menses, also means a sign, a seed.

least and nine days at the most. She was, under no circumstances, to stop the issue when in the ordinary course of menses. If she stopped the issue by any artificial means, for [163] example, by the use of medicinal drugs, it was a sinful act, as it was likely to affect her health. When she found that she was free from further issue, she must wait one day more before she purified herself. If, after nine days, the woman did not find herself free, she must consider, that that was not her usual monthly course, but was some other illness. Such an extraordinary issue was supposed to be the work of Ahriman or the Evil Spirit (Vd. 1:18-19).

Women in menses were to be given only a certain quantity of food, lest any increase of it may cause greater flow or stronger issue. The *Vendidad* speaks of two *dânarês* (i.e., about 1,400 grains) of corn and two *dânarês* of animal food. The persons giving them food are to do so from a distance and not to touch them. They were to take their meals in utensils made of metal and not of clay or wood, because the latter, being more porous than the former, are likely to secrete the impurities and thus likely to do harm to the health of those who later on used these utensils again. Again, they are not to use their naked hands for eating, but they are to put on *dastânehs* (gloves) or *kissehs* (i.e., glove-like bags) over their hands and then to eat by means of spoons.

Purification from menses.

On the day after that on which the issue stops, she has to purify herself by a bath before coming into contact with other persons and things. The *Vendidad* enjoined, that she was to bathe or wash herself with *gomez* and water on three *magas* or pits like those mentioned in the purification ceremonies of the barashnom. Her bedding and outer clothing also were to be washed and cleaned. Those who came into contact with her had also to wash themselves. It seems, that in the times of the *Vendidad*, some expiatory ceremony was performed by the women in menses after their purification, e.g., that of destroying a particular number of little noxious creatures that were thought capable of doing harm to mankind. It seems, that at first, this expiatory ceremony was enjoined in the case of extraordinary issues which were the result of the work of the Evil Spirit. The woman's carelessness for [164] her health or indifference for the ordinary laws of health was, as it were, the work of the Evil Spirit. So, some punishment or expiation was necessary for such carelessness. Then, latterly, by some unknown process or for some unknown reason, the expiation was extended even to the cases of ordinary menses.

The Pahlavi books on menses.

Among the Pahlavi books, the *Bundahishn* (3:7) speaks of menstruation as the work of Ahriman. The *Shayest Ne-Shayest* (2:17, 96) considers the things used by a woman in menses as unclean. Things with which she is in contact just at the time when she knows that menstruation has begun, do not become unclean. For example, if she is on a carpet, and there feels or knows for the first time that she is in menses, the carpet does not become unclean (Chap. 3:2). Similarly, whatever objects that be on her body just at that time, — her necklace, earrings, garments, etc., — are not unclean if immediately removed; (Chap. 3:4) but if they are not removed immediately, or if they are taken in, or put on afterwards, they become unclean. Her look vitiates the purification of the *padyab* and consecrated things. When the issue stops, she must at least wait for one day before she bathes and purifies herself. Things that pass through her hand may be considered clean after being washed with *gomez* and water.

The Persian *Sad Dar* (Chaps. 41 and 48) also speaks of the above and similar other injunctions. The injunction, of the later writings are more strict. Dastur Darab Pahlān, in his Persian *Farziat-nameh*, gives the following injunction, based on what he calls Pahlavi Zand and Pazand writings. (1) On finding the symptoms, the woman is to change at once her ordinary clothings. (2) She is to seek a sequestered place and keep herself away from, or not see, water, fire, holy man, the sun, moon, sky, mountains, stars, and trees. (3) Whatever she sees, suffers harm or diminution (*jurm* جرْم) (4) While eating, she must put on, on her hands, a piece of old cloth (*raku* رَكُو) and eat with a spoon; while drinking, she must not let a single drop of water fall over her body. (5) She must thus keep herself aloof for [165] from three to nine days, and then wash herself with *gomez* and water. (6) If she has unwittingly failed to observe any of these regulations, she is to say a *patet* or repentance prayer. *Duwazdah homast*¹ is the proper atonement for her faults in this matter. She may recite that or ask a priest to recite that on her behalf. On the subject of all these notions, Prof. Darmesteter says “The origin of all these notions is in certain physical instincts in physiological psychology, which is the reason why they are found among peoples very far removed from one another by race or religion. But they took in Persia a new meaning as they were made a logical part of the whole religious system.”²

1 This ceremony, which nowadays consists of 12 times (dvāzdah دوازده) 12 recitals of the Yasna, is performed by priests.

2 S.B.E. IV (1880), introduction, p. XCII.

The present practice.

At present also, most of the Parsee women generally observe the above practices. There are no separate *dastânistâns* or houses for menses in Parsee towns or streets, but generally a sequestered part of one's own house is chosen for the purpose. The down-floor of the house was thought to be the proper place, but nowadays, in a crowded city like Bombay, the down-floor, instead of being a quiet and healthy place, such as that contemplated by the early injunctions of the *Vendidâd*, is generally quite the contrary. So, most women in menses pass the period of menstruation on their upper floors, but in an isolated way. Every family has a separate iron cot for the occasion and a separate bedding, etc. They are supplied their meals from a distance by others and they neither come into contact with others, nor do they touch other things or do household work. The very rigorous isolation enjoined by the later books is not observed, but anyhow, some kind of isolation and separation is maintained by the generality of women. In the matter of taking food, very few use spoons now, though upto about 25 years ago, that was generally the case. In the matter of purification, they observe the bath enjoined by the early books, but the *Vendidâd* injunction of bathing over the three *magas* is [166] not observed at all. A separate place of bathing and for purposes of nature for women in this condition is generally provided in Parsee houses. No expiation ceremonies as those hinted in the *Vendidâd* are observed now, but, up to twenty-five or thirty years ago, women after their purification by a bath got a *patet*, or an atonement prayer, recited by a priest, with a hope that if any injunctions enjoined to be observed in the matter of isolation may not have been observed, the fault may be pardoned.

Similar injunctions of the Leviticus.

Issues or discharges caused ceremonial impurity among the ancient Hebrews and Christians also. (Lev. 15). A difference was made between short issues, the result of sexual intercourse or wet dreams and "running issues." In the former case, an ordinary bath brought about purification. In the latter case, a strict isolation was enjoined, and persons or things, that came into contact with the person, his bed, or his things, were held unclean. Earthenware that came into such contact was to be destroyed and wooden things to be "rinsed in water." Even after the close of the running issue, the person was to remain isolated for 7 days, and, on the eighth day, he had to seek an atonement, "the atonement for her before the Lord," at the hand of a priest and to make offerings. As to the "contacts" or the persons who had come into contact with the persons who had issues or discharges, they also became unclean. Water was a purifier in their case, and in

addition, time itself was a purifier. If such unclean persons or things were left to themselves “until the even”, they got purified, as if by the action of the moving purifying air. The children, who remained with the mother during the state of her above uncleanliness, had also to be purified. The Deuteronomy (23) also speaks of these issues and their uncleanliness. It appears that the laws of the Hebrews were to a certain extent more strict than those of the Persians. For example, persons who had *polluta nocturna* were asked to pass the succeeding day out of the Hebrew camp and to return by evening. [167]

Pliny on menstruation.

We find a reflex of the notion of the ancients on this point, as given by Pliny in his *Natural History* (Bk. VII, chap. XIII),¹ in the later regulations as summed up in the above-mentioned *Farziat-nameh* (فرضیات نامه). Pliny says:

“It would indeed be a difficult matter to find anything which is productive of more marvellous effects than the menstrual discharge. On the approach of a woman in this state, must (i.e., wine pressed from the grape) will become sour, seeds which are touched by her will become sterile, grafts wither away, garden plants are parched up, and the fruit will fall from the tree beneath which she sits. Her very look, even, will dim the brightness of mirrors, blunt the edge of steel, and take away the polish from ivory. A swarm of bees, if looked upon by her, will die immediately; brass and iron will instantly become rusty and emit an offensive odour, while dogs which may have tasted of the matter discharged are seized with madness, and their bite is venomous and incurable. In addition to this, the bitumen. . . . which is peculiarly tenacious and adheres to everything it touches, can only be divided into separate pieces by means of a thread which has been dipped in this virulent matter. It is said that the ant, even an insect so extremely minute, is sensible of its presence, and rejects the grains which it has been carrying and will not return to them again.”

Pliny says in another chapter (Bk. XXVIII, ch. 23),

“Young wives ... are injured immediately by the touch of a woman in this state; and both rue and ivy, plants possessed of highly medicinal virtues, will die instantly

1 Vide Bostock and Riley's Translation (1858) Vol. II, pp. 150-52.

upon being touched by her. Much as I have already stated on the virulent effects of this discharge, I have to state in addition that bees, it is a well-known fact, will forsake their hives if touched by a menstruate woman; that linen boiling in the cauldron will turn black, that the edge of a razor will become blunted, and that copper vessels will contract a fetid smell and become covered with verdigris, on coming in contact with her. A mare big with foal, if touched by a woman in this state, will be sure to miscarry; nay even more [168] than this, at the very sight of a woman, though seen at a distance even, should she happen to be menstruating for the first time after the loss of her virginity or for the first time while in a state of virginity.... Fire itself even, an element which triumphs over every other substance, is unable to conquer this.... Indeed, so pernicious are its properties, that women themselves, the source from which it is derived, are far from being proof against its effects; a pregnant woman, for instance, if touched with it, or indeed if she so much as steps over it, will be liable to miscarry.”

The later Parsee writings attribute many of the above-said noxious effects referred to by Pliny to the menses of women. The injunctions of the *Vendidad* do not go to such an extent. Much seems to have been borrowed latterly. [169]

PART III. INITIATION CEREMONIES AND CUSTOMS

CHAPTER VII. (I) THE NAOJOTE [NAVJOTE]. THE INITIATION OF A ZOROASTRIAN CHILD INTO THE FOLD.

Two kinds of initiation.

By initiation, we mean an introduction into a certain religious organization, by the performance of certain rites and ceremonies. Of this kind of initiation, the Parsees have two: (i) The navjote (*naôjote*), which is the initiation of a Parsee child into the fold of the Zoroastrian religion.¹ (ii) The *nawar* and the *martab*, the two grades of initiation into priesthood.² We will at first speak of the navjote or the initiation of a child into the religion through investiture with a sacred shirt and thread (*sudre* and *kusti*).

Navjote [naojote]. Meaning of the word.

The ceremony of investing a child with sacred shirt and thread [*sudre* and *kusti*] is called navjote.³ A Zoroastrian may put on any dress he likes. He may dress as an European, Hindu, Mahomedan or as a person of any nationality, but he must put on the *sudre* and *kusti*, i.e., the sacred shirt and thread as visible symbols of Zoroastrianism.

The word *Naôjote* is made up of two words, Pahlavi *naô* 𐬨𐬀 (Avesta *nava*, 𐬨𐬀𐬎𐬌) Sans. नव Pers. نو Lat. *novus*, Germ. *neu*, Fr. *neuf* “new” and *zôt* (Pahl. 𐬵𐬀 Av. 𐬵𐬀𐬎𐬌 nom. 𐬵𐬀𐬎𐬌) Sans. होत) i.e. one who offers prayers, from *zu* 𐬵𐬀 (Sans. *hu* हु) to offer prayers. The initiation is so named, because, it is after its performance, that a Zoroastrian child is said to be responsible for the duty of offering prayers and observing religious customs and rules as a Zoroastrian.⁴ The

1 *The Journal of the Bihar and Orissa Research Society*, Vol. I., Part I. (for September 1915). pages 53-54.

2 *Op. cit.*, Vol. I., Part I., page 53.

3 The modern Zoroastrians of Persia call this ceremony *Shiv-Kusti*.

4 Some take the word *Naôjote* to be another form of *Naôzâd*, i.e. a new birth, meaning thereby, a spiritual birth. After going through the ceremony, the child undertakes some moral or spiritual responsibility. Hence the word (West S.B.E. XXIV. chap. V, n. 1. p. 262). The *Shayest Ne-Shayest* speaks of it as *navid zâdih* (Dr. M. B. Davar's ed., p. 72, l. 1. Chap. XIII, 2) i.e. new birth.

ceremony of *navjote* among [170] the Parsees corresponds to that of Confirmation¹ among the Christians.

The age for this investiture.

Seven is the age at which it is enjoined to initiate a child. According to Herodotus (I, 136) and Strabo (Bk. XV, chap. III. 18). the ancient Iranians commenced the education of their children at the age of five. It seems that a part of that education was religious education which prepared them for this ceremony of investiture. Plato (First Alcibiades 37) gives the age of education as seven. This then must be the age of the regular commencement of secular education after the religious investiture with the sacred shirt and thread [sudre and kusti]. The *Vendidad* (15:45) and the *Denkard* (Vol. IV, chap. 170)² support Plato's statement. In case a child is not sufficiently intelligent to understand the ceremony and to know its responsibilities, it is permitted that the ceremony can be postponed to any age upto fifteen, at which age the investiture must take place. If the ceremony is not performed and if the child is not invested with the sacred shirt and thread [sudre and kusti] at or before the age of 15, the child is said to be claimed by the druj³ as her own. The *Vendidad* (18:31, 54) represents the evil druj as claiming four kinds of men as her own. Among these, the fourth kind is that of persons who, having passed the age of 15, go about without the sacred shirt and thread [sudre and kusti]. The druj says: "He assuredly is the fourth of my those (i.e. above class of) men, he, an ill-behaved man, who, after (the age of) fifteen years, moves about without the sacred thread and shirt."⁴ The *Sad-Dar* (Chap. 10:1) says that "it is incumbent on all Behedins,⁵ (whether) males or females, who attain the age of 15 years, to bear the sacred [171] thread, because the sacred thread is the waist-belt of humility and the symbol for preserving obedience to God, may He be honoured and respected."⁶ If one moves about without the sacred

1 "The word 'confirm' is found frequently in both the Old and the New Testaments in various shades of meaning, but with the general sense of *strengthening* and *establishing*" (Hasting's Dictionary of the Bible). It is worth noting in connection with this meaning, that one meaning of *zu*, the Avesta root of the word *zaotar* is "to be strong" (Sans. *ju*; Pers. *zor*).

2 Dastur Dr. Peshotan's edition.

3 Av. *druj* 𐬔𐬀𐬎𐬎𐬀 𐬎𐬎𐬀, one who does harm, deceives, speaks lies. This is personified as a female evil power.

4 Vd. 18:54.

5 i.e. Zoroatrians. *Lit.* members of the good religion.

6 *Sad-Dar Nasar* (Chap. 10:1). Edition of Mr. B. N. Dhabhar, p. 9. According to the 46th Chapter of this book, the period of 15 years includes the nine months of the child being in the womb of the mother. Thus, the latest permissible age for the

shirt and thread after the age of fifteen, he is said to commit the sin of *vashâd dobârishnih* or *kushâd davârashni*¹ (i.e. running about uncovered or naked.)

With the age of the child, at which it is to be invested with the sacred shirt and thread, begins the responsibility of the parents to give a good religious and moral education to their children. It is enjoined, that good religious and moral education should be given to a child at an early age. According to the Pahlavi *Ganj-i Shayagan* and the *Shayest Ne-Shayest*, the parents are held responsible, if they fail in this duty and if the child in consequence commits a bad action. On the other hand, the parents are believed to take a share in the meritoriousness, if the child, by virtue of the religious and moral education given to it, does a religious act.²

Sudre, i.e., the Sacred Shirt. Meaning of the word. Its Structure and Symbolism.

The ceremony of Navjote consists of the investiture of the child with sacred shirt and thread. Before speaking of the investiture itself, I will first speak of this shirt and thread and of their symbolism.

The shirt is called *Sadreh*, *Sudre*, or *Sudreh*. Anquetil Du Perron says, that the word “*sadreh*” comes from Zend “*setehr paéschenghé*, which means “useful clothing.”³ Dastur Edalji Darabji Sanjana also derives the word similarly,⁴ and says that the word *sud-reh* [172] means “an advantageous path.” Dr. West⁵ takes the word to be Persian “*sud-reh*” meaning an advantageous path. Some derive the word from Avesta “*vastra*,” meaning ‘clothing’ and say that the word “*sadreh*” is formed by dropping the first letter “*v*.”⁶ Mr. K. E. Kanga thinks that the word is Arabic ستره *sutrah*, i.e. anything which covers

initiation is 14 years 3 months. *Vide* also the *Shayest Ne-Shayest*, Chap. 10:13. It also gives the age as 14 years and 3 months (Dr. M. B. Davar’s ed., p. 51). S.B.E. Vol. V. (1880) p. 321.

- 1 *Menog-i Khrad* 2:35. *Vide* Ervad Tehmuras’s Edition with my Introduction, p. 12, l. 9 (S.B.E, Vol. XXIV, p. 11); *Viraf-nameh* 25:6; Patet 10.
- 2 *Ganj-i Shayagan*, Dastur Peshotan’s edition, pp. 25-26; *Shayest Ne-Shayest*, chaps. 10:22, 12:15, Dr. M. B. Davar’s ed., pp. 53 and 65.
- 3 “Tapis (etofie) utile,” *Zend Avesta*, Tome II, p. 529.
- 4 𐬰𐬀𐬎𐬌𐬎𐬎𐬀 𐬵𐬀𐬎 Mojejàti Zarthoshti, p. 10.
- 5 S.B.E. Vol. V, p. 286.
- 6 The *Zend Avesta* par Darmesteter II, p. 243 n. 13. As an instance of a similar dropping of “*v*” “we have the case of 𐬵𐬀𐬎 Sans. 𐬵𐬀𐬎 *vir* Lat. *vir*, which has given us the Pers. *yal* 𐬵𐬀𐬎 i.e., hero.”

or protects (the body).¹ The *Dadestan-i Denig*² speaks of it as *pirâhan* (Pahl. 𐭯𐭥𐭥𐭥 Pers. پیراهن shirt). The Pahlavi Vendidad³ speaks of it as *shapik* (kipS). It also speaks of it as *tashkuk* (𐭯𐭥𐭥𐭥).⁴ A Persian gloss of the word is given as *sudreh*.⁵

The sacred shirt and thread are symbolic in their structure. The symbolism is explained not in the *Avesta*, but in later Pahlavi and Persian books. Some of the symbolism is explained in the *Dadestan-i Denig* (Ques. 39, Chap. 40). The Persian *Sar-nâme-h-i-râz i Yazdâni* also refers to it. The shirt is made up of white cambric, the white colour being symbolic of innocence, and as such, the symbol of the Mazdayasni religion.⁶ The *Dadestan-i Denig* enjoins that the shirt should be pure white⁷ and of only one fold,⁸ not double. The reason for the shirt to be of only one fold is said to be that Vohuman is “one creation” which is the first (*ayôk dâm i fartûm*).⁹ The [173] word Vohû-mana being variously used, the signification is not clear, but what is meant seems to be this, that the whiteness of the shirt is supposed to influence for good one’s mind. Again, the shirt must not be made up of one continuous piece of cloth but of two pieces sewn together on the sides, so that one piece may be on the right hand side, and the other on the left hand side, thus dividing the shirt into two parts, the front and the back part. These two parts — the front and the back — are said to be symbolic of the past and the future, both being related with each other through the present. It has an opening for the head and reaches down to the knees.

The most important part of the shirt is the *gireh-bân* (*lit.* that which preserves the knot), which signifies loyalty to, or faith in, the religion. The *Gireh-bân* is known as the “*kisseh-i-kerfeh*,” i.e., “the

1 He wrote of this in a letter to me.

2 Question 39:1. Ervad Tehmuras’s Text, p. 125, l. 2.

3 Chap. 18:7. Dastur Hoshang’s Text, p. 566. Dastur Dr. Hoshang says, that it is the same as Pers. شبی a night shirt (*ibid.* Vol. II Glossarial Index, p. 209.) Anquetil Du Perron (Tome II, p. 529) takes the Pahlavi word to be Chev. In that case, it is the same as Pers. شبو below, i.e., the garment below the *kusti*.

4 Pahl. Vd. 17:1. Dastur Dr. Hoshang’s Text, p. 561, l. 12.

5 *Ibid.*, note 17.

6 “*Spaêta Daênayâo Mazdayasnoish upamanem*” (Mihir Yasht. Yt. 10:126).

7 “*Darûst sapit*” (Ervad Tehmuras’s Text, p. 125, ll. 5-6). Ques. 39 S.B.E. XVIII, Chap. 40, p. 133.

8 *Ayôtâk, ayôkardeh. Ibid.*

9 *Ibid.*

purse or the bag of righteousness.” It is made in the form of a bag or purse, which rests a little below the throat. It indicates symbolically that a man has to be industrious, and has not only to fill his purse or bag with money, but also with *kerfeh* (righteousness). The *Shayest Ne-Shayest* enjoins,¹ that the sacred shirt should be put next to skin, i.e., there should be no other garment under it.² Thus, the *sudre* is a symbol that reminds one of purity of life and righteousness.

***Kusti* or the sacred thread. Meaning of the word. Its structure and symbolism.**

The Avesta word for the sacred thread is “*aiwyaonghana*,” lit. to gird round the body. *Kûsti* is its Pahlavi rendering. The word *kusti* is variously derived. (a) It may be derived from Pahlavi *kust* کشت

Pers. کشت meaning “direction or side.” Thus, the word *kusti* may mean “that which points out the proper direction or path.” *Sudre* (the sacred shirt) indicates the advantageous path, and *kusti* (the sacred thread) indicates the proper direction to proceed [174] on that path. Talting the same derivation, *kusti* may mean, “a badge distinguishing those who are on the side (*kust*) of (i.e., who believe in) Zoroastrianism.” (b) Some derive the word from *kosht* (کشت) waist, and say that it is so called because it is put on the waist.³ (c) Again *kosht* also means “limit or boundary,” so *kusti* may mean “that which keeps us, or reminds us to keep ourselves, within proper limits or bounds.” The *sudre* being, as said above, “the advantageous path of righteousness,” the *kusti*, which is put over it, is “that which confines us or keeps us within the limits of that path of righteousness.” The Avesta word for *kusti*, viz., *aiwyaonghana*, which literally means “to sit round or to limit,” renders this derivation probable. (d) Again, some take this word *kusti* to be *kishti*, i.e., a ship, and say that it signifies that, like a ship, it carries us to the safe haven of righteousness. Whatever derivation we take, the *kusti* symbolizes and indicates a direction in the path of righteousness.

The *kusti* is made up of lamb’s wool. The wool is at first combed and then spun into fine thread on a hand-spindle called *châtri*. Two such long threads are prepared on two spindles or *châtris*, and are then twisted into one. This thread is then woven into the *kusti* on a

- 1 Chap. 4:7, 8. *Amat shâpik dô patmukht ikvîmûnet va kustik madam zak i avpar yidruniyen adinash ... vanâs*, (Dr. Davar’s ed., p.30).
- 2 Cf. Jeremiah 13:11, where the waist-cloth or the girdle or linen is enjoined always to “cleave to the loins”, i.e., to be “worn next the skin,” which process of wearing signified “righteousness and faithfulness.” (Isa. 11:5). The *sudre*, to a certain extent, corresponds to “the linen ephod” of the priest (1 Sam. 2:18.)
- 3 Haug and West, Glossary and Index of the *Vîraf-nâme*, pp. 202-3.

hand-loom called *jantar* (جنتر Sans. ञ.), the ends of which are movable, so that it can be adjusted to the length required. The twisted thread is passed round the loom 72 times; so, the *kusti* consists of 72 threads, divided into six strands, each of twelve threads. A continuous thread is made to pass, in the process of weaving, through each of the six strands. When the weaving is almost finished, and when about a foot of the threads remain to be woven, the whole thread is removed from the loom and handed to a priest to be cut and consecrated. It is the privilege of the women of the priestly class to weave and prepare a sacred thread, and it is the privilege of a priest to cut and consecrate it.

To consecrate the thread, the priest first performs the *padyab kusti*. He then recites the Srosh *baj*¹ as far as the [175] word *Ashahê*. He next recites the *nirang* (the liturgical formula) for cutting and consecrating the thread, followed by the *Ashem Vohu* and *Yatha aha vairyo* (Ahunwar).² While reciting the latter, he cuts the *kusti* into two parts as he utters the word *shyaothnanam*. On finishing the *Yatha ahu vairyo*, he utters in *baj* (i.e. in a suppressed tone) the brief Pazand formula of *sraosh ashô tagi tan farman*,³ and then finishes the *baj*. The women who prepare the *kusti*, generally get it cut and consecrated by the male priest members of their own families. When they have no such members and have therefore to get it consecrated by other priests, they have to pay a small fee for it. After this consecration, the *kusti* is returned by the priest to the owner, who now completes its weaving. First, by means of a needle, she turns the *kusti*, which is hollow, inside out, and then knits by hand the remaining part of the thread. Three tassels (*lari*),⁴ each of 14 threads, are formed at each end of the woven thread. The *kusti* is then finally washed before being used.

The *kusti*, being prepared from the wool of a lamb, which is considered to be an emblem of innocence and purity, is held to remind a Zoroastrian of the purity of life which he has always to observe. The 72 threads composing the *kusti*, symbolize the 72 *has* or chapters of the *Yasna*. The 24 threads, which make up each of the three tassels at each end of the *kusti*, symbolize the 24 *kardahs* or sections of the *Visperad*, a part of the liturgical prayer; the six strands, each of twelve threads, into which the 72 threads of the *kusti*

1 Vide Darmesteter, *Le Zend Avesta* II, pp. 686-88.

2 *Yasna* 27:14 and 13 respectively.

3 Srosh Yasht, Yt. 11, (Darmesteter. *Le Zend Avesta* II, p. 482. "Vienne Srôsh ... Ormazd.")

4 Pers. *lar*. لَر ("thin").

are divided at the time of weaving, are said to symbolize the six religious duties¹ of a [176] Zoroastrian; the twelve threads in each of the six strands symbolize the twelve months of the year; the six tassels symbolize the six season festivals (Gahambar) of a Zoroastrian year; the hollow of the thread symbolizes the space between this world and the next; the doubling of the thread in the beginning symbolizes the connection between the present corporeal world and the future spiritual world; the turning of the kusti inside out symbolizes the passage of the soul from the corporeal to the spiritual world; the final uniting of all the threads into one symbolizes universal brotherhood or union. Though we have not the authority of Avesta books for an explanation of the symbolism of all the parts of the kusti, there is no doubt, that its structure had some symbolic signification from very ancient times. It symbolizes some moral precepts or ideas, just as the *Janôî* or the sacred thread of the Brahmins and the cord worn by the Franciscan fathers round their waists do. The Sudre and Kusti of the Parsees may remind one of the white garment and girdle of the Essenes, a Jewish sect.²

Just as the cross is said to have existed as a symbol from times anterior to Christ, though Christ's crucifixion added to its signification, so the kusti is said to have existed as a symbol before Zoroaster. It was Jamshed of the Peshdadian dynasty who is said to have introduced it.³ Zoroaster is said to have [177] confirmed this

1 The enumeration of these duties differ in different Pahlavi and Pazand books. The *Shayest Ne-Shayest* (Chap. 12:31, Dr. Davar's ed. p. 71, S.B.E. V, p. 351) gives the following list:— (1) the celebration of the Gâsân bârs (Gahambar) or the season festivals; (2) the celebration of the Rapithwin or the setting in of summer; (3) Sadosh (Srosh) or the performance of the funeral ceremonies for the first three days after the death of one's dear departed ones; (4) Frawardegan, i.e., the religious observances during the last 10 days of a Parsee year in honour of the dear departed ones; (5) the recital of the Khwarshed Niyayesh in honour of the sun (three times a day); (6) the recital of the Mah Niyayesh in honour of the moon (three times a month).

The *Sad-Dar* (Mr. B. N. Dhabhar's ed. p. 6, Chap. 6:2; S.B.E. XXIV, p. 264), and the *Menog-i Khrad* (Chap. IV, 8. B. E. XXIV. p. 26, Ervad Tehmuras's Text, p. 36 Ques. 3) give a slightly different list. The *Sarnâmeh-i-râz-i Yazdâni*, a much later Persian book, gives a slightly different enumeration. (*Vide* the Persian-Gujarati edition of 1255 Yazdazardi, by Mr. Pallonji Jivanji L. Hâtariâ, Persian text, pp. 38-40).

2 Josephus.— *The Antiquity of the Jews*, translated by W. Whiston (1811), Vol. III, p. 444. Bk. II, Ch. 8:7.

3 *Dadestan-i Denig*, Chap. 39:19, Tehmuras's edition, p. 120, Ques. 38:22; *Sad-Dar*, Ch. 10:3. Mr. B. N. Dhabhar's ed., p. 9. A passage in the Pahlavi *Vendidad* also seems to allude to the fact. In the second chapter, while speaking of Jamshed, it says: 𐬀𐬀𐬀𐬀𐬀𐬀 𐬀𐬀𐬀𐬀𐬀𐬀 𐬀𐬀𐬀𐬀𐬀𐬀 𐬀𐬀𐬀𐬀𐬀𐬀 𐬀𐬀𐬀𐬀𐬀𐬀 𐬀𐬀𐬀𐬀𐬀𐬀 (Vend. 2:5, Spiegel's *Pahlavi Vend.* p. 9, 1. 15) "he had given (lit. done) a symbol to men on their body."

previous custom of putting on the *kusti*, am also directed that it may be put on over a saored shirt (*vohumanich vastarg*) and with a recital of religious formulae (*dînîk niranghâ*).¹ He held it to be a symbol of the necessity of (a) obedience to God, (b) closing up the door against sin and (c) breaking up the power of destruction.

It is enjoined, that, excepting the time of bathing, a Zoroastrian must always bear the sacred shirt and thread. The thread is to be untied and retied during the day on the following occasions:— (1) immediately after leaving bed in the morning;² (2) every time after answering a call of nature; (3) before saying prayers; (4) at the time of bathing; (5) before meals. A modern Parsee sometimes neglects to do so on the first and fifth occasions, but he generally does so on the second, third, and fourth occasions. The *Dadestan-i Denig* says,³ that, from times immemorial, men turn towards light at the time of performing the *kusti* ceremony as it is connected with a form of prayer.

The first thing that one has to do on these occasions (except the first) is to perform what is called *padyab* (*pâdyâb*)⁴ or ablution. It consists of washing the face and other uncovered parts of the body like hands and feet with pure water and after reciting a short prayer-formula.⁵ Then he has to face the sun. If he is within the house and if the sun is not visible, he has to stand facing the east in the murning up to 12 o'clock noon, and facing the west from 12 o'clock to night-fall. At night, he has to face a lamp or the moon. If there is no moon or lamp, he may face the stars. We will, later on, while speaking of the investiture by the priest, describe in detail the process of putting on the *kusti*.

As to its symbolism the *kusti* is a kind of belt. “*Kamar-bastan*” i.e., “to tie the waist” or “to put on the belt” is a phrase which has come to mean “to be ready to serve, to be [178] prepared for a work.” So the *Dadestan* says, that the putting on of the *kusti* on the waist,⁶ symbolizes one’s readiness to serve God.

1 *Dadestan-i Denig*, Chap. 39:19, Tehmuras’s Text, p. 120, Ques. 38:22.

2 *Sad-Dar*, Chap. 82.

3 Chap. 39.

4 *Vide* Purificatory Ceremonies. Journal, Vol. XI, No. II pp. 169-179.

5 *Khshnaôthra Ahurahê Mazdâo Ashem Vohu*, i.e., May God be pleased. Piety is the best good and happiness. Happiness to him who is pious for the best piety.

6 The *kusti* of the Zoroastrian scriptures reminds one of the “girdle” of the Christian scriptures which varied from that of sack cloth (Isa. 3:24) to that of gold (Rev. 1:13). The Avesta also speaks of the *kusti* or belt being golden (*zaranyô-aiwyaonghanem*, Yt. 15:57). Among the Israelites and the early Christians also, the operation of girding signified energetic action.

The knots of a *kusti*.

While putting on the *kusti*, one has to fasten it with two knots, one in the front and another on the back. Knots, which signify firmness and resolution, symbolize here resolutions about certain, religious and moral thoughts. While forming the first half of the first knot in the front on the second round of the thread, a Zoroastrian has to think that Ahura Mazda exists, that He is one, is holy and is matchless. While forming the second half of this first knot, he has to remember that the Mazdayasnian religion is the word of God and that he must have full faith in it. In the third round of the thread, while forming the first half of the second knot at the back, one has to remember that Zoroaster is the Prophet of God, and that he is our guide to show us the proper path of worship. While forming the second half of the second knot, he is to bear in mind that he has always to attend to “good thoughts, good words, and good deeds.”¹

Symbolic signification of the *kusti*, as given in the Pahlavi *Dadestan-i Denig*.

The *Dadestan-i Denig* (Chap. 39, Pursishna 38) dwells at some length on the symbolic signification of the *kusti*. The purport of what it says is this:— Firstly, God wishes that man should serve Him and should follow His path. Now, there are certain conventional ways in which a man shows his service or obedience to God. For example, he falls on his knees in his prayers; he lowers his head and bows; he raises his hands towards Heaven. All these ways or rites, which symbolize service or obedience or homage to God, are done occasionally. But the *kusti* is a standing symbol to signify permanently a man’s readiness to serve God. As a kind of *kamar-band* (بند) or belt, put on in a solemn way [179] with religious meditation and prayer, it reminds a person of his perpetual obligation to stand in the service of God. Whenever a Zoroastrian sees this *kusti*, this *band* or belt on his waist, he has to consider it as a badge of service and to say to himself “I am the servant (*bandah* بندۀ) of God.” Secondly, a person puts on a badge or belt of service and stands before his superior to receive his orders. Thus, the sacred belt or *kusti* reminds a man of humiliation before God, and of his readiness to receive His orders. Thirdly, the *kusti* is a kind of a *band*, i.e., a kind of a shutter. A shutter shuts up a thing, so that neither outside influence may affect that thing nor that thing’s influence affect an outside thing. So, by putting the *band* of a *kusti*, a Zoroastrian, while reciting the words *manashni*, *gavashni*, and *kunashni*, i.e., thoughts, words, and deeds, and putting on the knots on the thread, resolves to let no outside evil influence enter into his mind and affect the purity of his thoughts, words, and deeds, and

1 *Sad-Dar*, Chap. 10.

not to let that purity of thoughts, words, and deeds leave his mind. Fourthly, we learn from the *Dadestan-i Denig*, that the *kusti* reminds one to have a high ideal of character before his mind. The waist over which the *kusti* is fastened, divides our physical body into three parts, the higher, the middle, and the lower. The upper or the higher part of our body is the seat of heart and brain which typify higher characteristics. The lower part, which contains organs like the stomach which always require something to feed it, typifies lower characteristics of appetite, thirst, lust, etc. So, the *kusti* being tied on the middle portion of the body, *viz.*, the waist, and acting as a *band* or stopper, must remind us not to let the lower passions rise above and suppress our higher characteristics.¹

The ceremony of *navjote*.

Having described the preparation and the consecration of the shirt and thread, and having explained their symbolism, we will now describe the *navjote* ceremony itself, wherein a priest puts over the child the sacred shirt and thread. [180]

Preparation before the Investiture proper. Sacred bath. Ceremonial requisites.

As a qualification of fitness to go through this ceremony, the child is expected to know a few short prayers. Of these, the knowledge by heart of the *Nirang-i kustî* (i.e., the prayer for the sacred thread) is indispensably necessary, because it is required to be recited whenever the sacred thread is to be untied and fastened again, on certain occasions during the day, of which we have spoken above, This *Nirang-i kustî* is made up of the following three prayers:— (1) *Kemna-Mazda*;² (2) *Nirang-i-kustî* or *Ahura Mazda Khodae*;³ (3) *Jasame avanghe Mazda, Mazdayasno ahmi*.⁴ Besides this prayer of

- 1 This statement of the *Dadestan* reminds us of what Dr. Drummond, in his *Stones Rolled Away*, speaks as the three stories of our body, the upper, the middle, and the lower.
- 2 This short prayer is a part of what is known as *Khorda Avesta*, i.e., the smaller Avesta:— It is made up of the following passages of the larger Avesta. (a) Y. 46:7; (b) Y. 44:16; (c) Vd. 8:21; (d) Y. 49:10. The prayer consists of an invocation to God for help and an expression of desire to throw off physical and moral evils.
- 3 his is a prayer in the Pazand language. For the text of this prayer in the Avesta character, *vide Khurdeh Avesta in Zend Characters* by Ervad Tehmuras Dinshaw Anklesaria (1887). pp 23-26, and *Khurdeh Avesta* by Mr. Framjee Minocherji Dastur (1881) pp. 5-7 For its translation, *vide* S.B.E., Vol. XVIII, p. 384; *Le Zend Avesta*, par Darmesteter, Tome II, p. 685; and Spiegel, Bleek's Translation, Vol. of *Khordeh Avesta*, p. 4.
- 4 This short prayer, which forms, as it were, a short statement of the Zoroastrian Articles of Faith or Confession of Faith, is taken from Yasna 12:9. The first four words meaning "Oh God, come to my help " are added as an invocation, from

Nirang-i-kusti, the prayers known as *Nirang-i-ab-i Zar* or *Nirang-i Gaomez*, *Srosh-baj*, and *Patet*, were, at one time, expected from a Zoroastrian child, to be known by heart for the *navjote* ceremony. But now-a-days they are not deemed absolutely necessary.

On the day fixed for the investiture, a little before the time of the ceremony, the child is made to go through a sacred bath or a kind of purification known as *nahn*.¹ Upto a few years ago, it was customary that the child should abstain from any kind of food in the morning until after the investiture. This was considered as a little sacrifice on the part of the child to testify [181] its faith in the importance and value of the ceremony. Upto a few years ago, the ceremony was always performed in the morning, but now it is performed in the evening also according to the convenience of the parties. The very fact, that it was enjoined that during the course of the ceremony the officiating priest must recite the dawn (Hoshbami²) prayer,³ shows, that it was thought necessary that the ceremony should be performed in the morning.

After the sacred bath, the child is taken to a room where the parents and their relations and friends, and the officiating priest with one or more other priests have assembled. The upper part of its body, which is to be covered with the sacred shirt at the hands of the officiating priest, is covered over with a sheet of white cloth that can be easily removed. The child is made to sit on a low wooden stool covered over with a sheet of white cloth, in front of the officiating priest, who sits on a carpet on the floor. The child is made to sit facing the East. The following requisite things are placed on the carpet:— (1) a tray containing a new set of clothes for the child, including a new sacred shirt and thread; (2) a tray of rice known as *akhiâna* which, at the end of the ceremony, is presented to the family priest; it is a remnant of the old system, when there was a payment in kind as well; (3) a tray of flowers which are presented at the end to the assembled priests, friends, and relations; (4) a lamp, generally a lamp fed with clarified butter: there may be additional candle-sticks burning; (5) fire, burning on a censer with fragrant sandalwood and frankincense; (6) a tray containing a mixture of rice, pomegranate grains, raisins, almonds, and a few slices of cocoanut, to be sprinkled, later on, by the priest over the child as a symbol of prosperity. The first tray,

Ohrmazd Yasht, Yt. 1:27.

1 *Vide* above, pp. 95-101, "Purification Ceremonies."

2 Pahl. 𐬨𐬀𐬎𐬌 Av. 𐬀𐬎𐬌 *usha*, Sans. उषस, Lat. *aurora*, and Av. 𐬀𐬎𐬌𐬀𐬎𐬌
bâmya Pers. بام *bâm* brilliant.

3 For the prayer *vide* Spiegel (Bleeck's Translation), *Khordeh Avesta*, pp 5; Darmesteter, *Le Zend Avesta*, Vol. II. p. 688.

containing the suit of clothes, also contains some [182] betel leaves and areca nuts,¹ a few pieces of sugar candy, a few grains of rice, a coconut, a garland of flowers, a metallic cup containing *kûnkûn* (a kind of red powder) and a few rupees. All these things have nothing to do with the religious part of the ceremony, but they are considered in India as emblems of good luck. All these are presented by the priest, later on, to the child. The money is, at the end of the ceremony, taken by the family priest as a part of his fee, and is spoken of as the fee for the *giryân* or *girehbân*.²

The investiture proper.

When all the priests have taken their respective seats, the head officiating priest, who is seated face to face with the child, gives in the hand of the child a new sacred shirt. They all then recite the Patet, or the atonement prayer. The child also recites the prayer or its special sections, if it knows these by heart; but generally, it recites the *Yatha Ahu Vairyo* prayers in its stead. In some families, recently, instead of the Patet, the Ohrmazd Yasht is recited. Having finished this, the officiating priest gets up from his seat and the child stands before him. Then follows the investiture proper which is made up of the following four parts:— (1) the recital of the Confession of Faith by the child, followed immediately by the putting on of the sacred shirt by the priest; (2) the recital of the Nîrangî-i kusti with a preliminary introduction from the introductory part of the Ohrmazd Yasht (Yasht 1) upto the words *vidhvao mraotû*, accompanied with the girdling of the *kusti* or sacred thread by the priest over the sacred shirt; (3) the final recital of the *Mazdayasno Ahmi* (Y. 12:8-9) formula of the Articles of Faith; (4) the recital of the Tan-darosti or the final benediction. [183]

1. The recital of the Confession of Faith, and the investiture with the Sacred Shirt.

The first part of the investiture consists in presenting to the child the sacred shirt, after making it recite the Confession of Faith. This prayer of the Confession of Faith is made up of two parts: (a) The Avesta *khshnuman* of the Yazata [yazad] Din, who presides over Religion (Din Yasht. Yasht 16).³ (b) A Pazand formula of the

1 The betel-vine gives leaves all the year round. The vine gives no fruit or flower but simply leaves which are eaten with betel-nuts. So the leaves are held as symbols of simplicity and prosperity. *Journal of the Anthropological Society of Bombay*, Vol. XI, No. III, pp. 317-18. The areca nut is symbolic of festivity and is, therefore, always used as an offering for the gods (in India). It is also an essential requisite for the ceremony of betrothal. (*Ibid*, p. 329.)

2 *Vide* above, p. 183, for the word.

Confession of Faith [Din-no Kalmo].¹ The confession made up of these two parts runs as follows:— “Praised be the most righteous, the wisest, the most holy and the best Mazdayasnian Law, which is the gift of Mazda. The good, true, and perfect religion, which God has sent to this world, is that which Zoroaster has brought. That religion is the religion of Zoroaster, the religion of Ahura Mazda communicated to holy Zoroaster.” It ends with the recital of an Ashem Vohu prayer.

On the child making this public declaration of its faith in the Zoroastrian Mazdayasnian religion, the priest clothes it with the sacred shirt. While putting it on, he recites the sacred formula of Yatha Ahu Vairyo, and the other priests join him in the recital.

2. The recital of *Nirang-i kusti* and the investiture with the sacred thread.

Then the officiating priest stands at the back of the child and both face the east if it is morning, and the west if it is evening. He at first recites the introductory part of the Ohrmazd Yasht (Yt. 1)² and then the *Nirang-i kusti*.³ The substance of this prayer of *Nirang-i kusti* runs thus: “The Omniscient God is the greatest Lord. Ahriman is the evil spirit, that keeps back the advancement of the world. May that Evil Spirit with all his accomplices remain fallen and dejected. O Omniscient Lord, I repent of all my sins; I repent of all the evil thoughts that I may have entertained in my mind, of all [184] the evil words that I may have spoken, of all the evil deeds that I may have done. May Ahura Mazda be praised. May the Evil Spirit Ahriman be condemned. The will of the Righteous is the most praiseworthy.”

The process of putting on the *kusti* over the body is as follows:— The priest holds the *kusti* from its middle or central part in his left hand. Then he holds in his right hand a part of the two strings of the thread so formed. A part of the double strings is thus held horizontally between the two hands and the remainder hangs down vertically. This posture continues upto the recital of the words “*manashni, gavashni, kunashni*” in the *Nirang-i kusti*. With the recital of these words a part of the string is then formed into circular curves in both the hands. Then, on reciting the words *Khshnaoθra Ahurahe Mazdao*, the curves are let loose, and with the recital of Ashem Vohu, the thread is passed round the child’s waist. With the recital of the first Yatha Ahu

3 S.B.E., Vol. XXIII (1883) “To the most right Chista, etc.,” p. 264. Spiegel, translated by Bleeck. *Khordeh Avesta*, p. 147. Darmesteter, *Le Zend Avesta*, Vol. II, p. 302.

1 Spiegel, translated by Bleeck. *Khordeh Avesta*, p. 191.

2 Spiegel, translated by Bleeck, *Khordeh Avesta*, p. 21. From “In the name of God ... satisfaction, etc.”

3 *Ibid*, p. 4.

Vairyo, the second round is completed, the first knot in the front being tied with the recital of the word *shyaothananâm*. With the recital of the same word in the second recital of the Yatha Ahu Vairyo, the second knot in the front is tied, and then, with the recital of another Ashem Vohu, the thread is passed round the waist for the third time and the final two knots at the back are tied. This completes the investiture of the sacred thread. During this investiture, the child recites with the officiating priest the Nirang-i kusti.

3. The Recital of the formula of the Articles of Faith.

The child, after being thus invested with the sacred shirt and thread, announces the last and the most important part of the Articles of Faith, given in the 12th chapter of the Yasna. It runs thus: "O Almighty! Come to my help. I am a worshipper of God. I am a Zoroastrian worshipper of God. I agree to praise the Zoroastrian religion, and to believe in that religion. I praise good thoughts, good words, and good deeds. I praise the good Mazdayasnian religion which curtails discussions and quarrels, which brings about kinship or brotherhood, which is holy, and which, of all the religions that have yet flourished and are likely [185] to flourish in the future, is the greatest, the best and the most excellent, and which is the religion given by God to Zoroaster. I believe that all good things proceed from God. May the Mazdayasnian religion be thus praised."

The most important part of these short prayers is that, wherein the child is made to believe in the efficacy of one's own good thoughts, words and actions. A Parsee has to believe that, for the salvation of his soul, he has to look to himself. For his salvation, he has to look to the purity of his thoughts, the purity of his words, and the purity of his deeds. The pivot on which the whole of the moral structure of Zoroastrianism turns, rests upon this triad of thought, word, and deed. Think of nothing but the truth, speak nothing but the truth, do nothing but what is proper, and you are saved.

4. The final Benediction.

The putting on of the sacred shirt and thread and the declaration of the Articles of Faith complete the ceremony proper. The officiating priest now makes a red *kunkun* mark on the child's forehead — a long vertical mark if the child is male, a round mark if female — and then gives in its hands, the cocoanut, flowers, betel leaves, areca nuts, etc., referred to above. There only remains now the recital of the Tandarosti or benedictions by the officiating priest, invoking the blessings of God upon the new initiate. He says: "May you enjoy health, long life and splendour of piety. May the good Angels and the Immortal spirits (Ameshaspands) come to your help. May the religion of Zoroaster

flourish. O Almighty God! May you bestow long life, joy, and health upon the ruler of our land, upon the whole community and upon this¹ May the child live long to help the virtuous. May this day be auspicious, this month be auspicious, this year be auspicious. May you live for a good number of years to lead a holy, charitable, and religious life. May you perform righteous deeds. May health, [186] virtue, and goodness be your lot. May all your good wishes be fulfilled like those of the immortal angels. Amen! Amen!”

While reciting this, the priest showers over the head of the child, the mixture of rice, pomegranate seed, almonds, raisins, etc., referred to above. In the end, all the assembled priests again recite together, the above *tan-dorosti* (benedictions). The priests are then paid their fees. They and the assembled friends and relations are presented with flowers. The priests then depart, and the child and the parents are presented with sums of money by friends and relations. The assembled guests generally disperse after a dinner, where “*Jarthoshti sikkâni salâmati*,” i.e., the prosperity of the Zoroastrian fold (*lit.*, the safety or prosperity of Zoroastrian coinage) is the toast of the occasion. [187]

1 Here the name of the child is mentioned.

CHAPTER VIII. (II) THE NAWAR AND THE MARTAB.

THE INITIATION INTO ZOROASTRIAN PRIESTHOOD.

It is the son of a priest only who can become a priest. This seems to be a very old custom of ancient Iran. We find it alluded to in the *Institutions of Ardashir Babakan*, the founder of the Sasanian dynasty, with whose reign commenced the Iranian Renaissance of the period. One of the innovations said to have been introduced by him, or rather one of the old customs, — more honoured in their breach than in their observance at his time, — re-introduced by him with the aid of his Dastur Taôsar or Tansar, was, that the members of different professions and trades, and their descendants, should adhere to their old professions and trades and not change them for others, except with the special permission of the king or the Government authorities. The division of the people into different professions and trades, and the regulations to restrict them to their respective lines of business, were thought to be necessary for the good of society.

“Cette répartition,” says Tansar, “des hommes en quatre classes est pour le monde une garantie durable de bon ordre. Le passage d’une caste à l’autre est interdit, sauf le cas où l’un de nous montre un talent particulier. Alors on porte le cas devant le roi. Après une épreuve et une enquête prolongée faite par les Mobeds et les Herbeds, s’ils reconnaissent le mérite du candidat ils se transfèrent dans une autre caste Le Shâhanshâh, par sa pure intelligence et la vertu de son génie, a reconstitué ces membres disjoints. Il a remis chacun à sa place distincte, l’a fait redescendre à son rang et a arrangé que personne n’exercerait un autre métier que celui pour lequel Dieu l’avait créé. Par ses mains la Providence divine a ouvert aux habitants de ce monde une porte inconnue même aux âges antiques.”^[188]

The division of the people into different professions and trades, referred to by Tansar, as having been made by Ardashir, was not quite unknown to the ancient Persians before his time. According to the *Shah-nameh*, it was made by King Jamshid of the Peshdadian dynasty. “Il (Djemschid) assigna à chacun la place qui lui convenait, et leur indiqua leur voie, pour que tous comprissent leur position et reconnussent ce qui était au-dessus et au-dessous d’eux.”² Tabari says the same thing: “Djemschid partagea toutes les créatures du monde en quatre classes et il dit: Que chacun fasse son travail et ne s’occupe pas d’autre chose Si

1 Lettre de Tansar au Roi de Tabaristan (*Journal Asiatique*, Tome III, Neuvième Serie, pp. 518-520) par Darmesteter.

2 *Le Livre des Rois*, M. Mohl, Vol. I, pp. 49-50. Small ed., p. 35.

quelqu'un s'écartait des réglemens qu'il avait établis, il le faisait mettre à mort."¹ We thus find that the rules introduced by Ardashir were rather old, and that he re-established them, and declared that people must restrict themselves to their own hereditary professions. The priesthood was especially such a profession. But, we find further from Tansar's letter that Ardashir had intended to make certain exceptions. For example, a man, by special qualifications or examinations, can qualify himself for a profession, other than that of his forefathers. We find such an exception, in the case of priesthood, made in Persia, even so late as the 17th century. One Dastur Rustam Gushtasp Ardashir "is said to have sprung from the laity and not from a priestly family."² It is said, that in the time of this Rustam Gushtasp, the then ruling Mahomedan King of Persia ordered a general massacre of the Persian Zoroastrians, unless they proved that they were monotheists and not idol-worshippers. It was this layman Rustam Gushtasp who proved this to the satisfaction of the king, and he was made a Dastur. He was a good scholar. The copy of the *Denkard* in the Mulla Firoze Library, a copy of the *Menog-i Khrad* in Mr. Tehmuras Dinshaw's possession, and a Persian Rivayat in Mr. Manekji Unwala's possession are by his pen. In India, no exception seems to have been made, and it is only [189] the son's of priests or of the members of the priestly families who can become priests. The right can be revived by any male member of the priestly family, though his immediate ancestors may not actually have been priests. For example, A may be a priest. His son B, grandson C, great-grandson D may not have entered into priesthood, but still E, the son of D, can, if he chooses, become a priest. The right can thus be revived by a descendant upto the fifth generation. It then dies and can no longer be exercised.

In order to be a thoroughly qualified priest, one has to go through two grades of initiations and their ceremonies. They are: (1) the Nawar and (2) the Martab.

1. THE NAWAR.³

The first initiatory ceremony for priesthood is that of Nawar. The word is written and read in different ways. It is also written and read as Nâbar, Nâibar, or Nâgbar.⁴ Darmesteter says of this word:

1 *Tabari*, par Zotenberg, Tome I, p. 103.

2 S.B.E., Vol. V. Introduction. p. XXXIII, West. ;For a more recent English translation of Tansar's letter see Mary Boyce, *The Letter of Tansar*, 1968. -JHP]

3 For "Nâvar in Iran," *vide* Prof. Khodayar's article in the Sir J.J.Z. Madressa Jubilee Volume, pp. 435 *et seq.*

4 S.B.E., Vol XVIII, Pahl. Texts II, Chap. LXXIX, 4 n. 1 – West. It is written نـاـوـر

“L’origine et le sens exact du mot *nâbar* نابر Pehlvi *nâpar* et *nâivar*, sont obscurs.”¹ I think the word means “a new carrier of offerings or rites.” It can be derived from Avesta 𐬨𐬀𐬎𐬀 *nawa new* (Pahl. 𐭮𐭲, Sans. नव, Pers. نسر Lat. *novus*, Fr. *neuf*, Germ. *neu*, Eng. *new*, same as in *navjote*), and 𐬨𐬀 *bar* to carry (Pahl. 𐭮𐭲 Pers. بردن *brdn*, Sans. भ्र, Lat. *Ferre*, Eng. *bear*). In the Avesta words, *hû-bereti*, *ushta-beret*, *vanta-bereti* (Y. 62:7), the word *bereti* (like the Sanskrit *bhriti*, nourishment, food, service, capital) which is derived from the above root $\sqrt{\text{bar}}$, to carry, is used for presents, offerings. So *nawar*, which is originally *naô-bar* (i.e., a new carrier of presents and offerings), means “one who is newly initiated in the work of offering prayers, rites, and sacred things to the Deity.” The fact, that it call be explained in the same way [190] as the word *navjote*, the first important initiatory Zoroastrian ceremony, is a proof in support of this interpretation.

The different stages of the ceremony of initiating a priest.

To initiate a person into priesthood, several stages of ceremonies have to be gone through. They are the following:— (a) the barashnom; (b) the *Gewrâ*; (c) the initiation proper. I give here an illustration which shows the initiate taking his barashnom.

(a) The candidate for initiation into priesthood has first to go through two barashnom purifications.² The first barashnom is said to be for his own *tan-pâk*, i.e. for the purification of his own body, the second is for the *nîyat*³ of the person in whose memory he becomes a

in an old manuscript of the *Dadestan* belonging to Mr. Tehmuras Dinshaw.

- 1 *Le Zend Avesta*,. Vol. I, Introduction, p. LIV, n. 2.
- 2 *Vide* above, pp. 102-153, Purification Ceremonies. In Persia, at present, they go through 10 barashnoms, four of which are said to be “for his soul” (“Navar in Iran,” by Prof. Khodayar Dastur Sheheryar, in the Sir J. J. Zarthoshti Madressa Jubilee Volume, edited by me, p. 435).
- 3 *Nîyat* literally means purpose, intention. Among the Parsees, many charitable deeds are said to be performed by a person in the *nîyat* of a deceased relative or friend. A may build a Fire-Temple or a Tower of Silence or such other religious edifice in the *nîyat* of B, his father or relative or friend. It is something like what we call “in memory of” in ordinary language, in case of ordinary charitable institutions, such as schools, dispensaries, asylums, or hospitals. In the case of religious buildings, when they are consecrated, or even in the case of charitable buildings like schools or hospitals when they are opened with the religious ceremony of a *Jashan*, the name of the particular person, in whole *nîyat*, honour, or memory the building or institution is founded, is mentioned in the prayers. (For the form in which the name is mentioned see above, p. 81, chapter on “Death.”) These religious or charitable buildings may be in the *nîyat* of living persons as well. In that case, the

nawar. Between the first barashnom and the second there may be an interval of a few days if it is so desired, or, otherwise the candidate may begin the second barashnom on the same day [191] when he finishes the first. In that case, both the barashnoms take 19 days in all. During these barashnom days, the candidate is to say his prayers five times during the day. He is expected to pass his time in a religious or pious mood. If, during any of the days of the barashnoms, he has a *pollutis nocturna*, that vitiates his barashnom. In that case, he must begin the barashnom again. If the case happens in the second barashnom, he has to repeat only the second barashnom and not the first. To avoid this risk, nowadays, the candidate for priesthood goes through the initiation at a very early age, before 15 or 16, when he is likely to be free from such risk. The second barashnom is, as said above, for the *nîyat* of somebody. If that somebody is a lady, he must take care that he goes through the second barashnom and the subsequent ceremonies of *gewrâ* and initiation at a time, when there is no chance of that lady's passing through her monthly course. If during these ceremonies, the lady, in whose *nîyat* he goes through the ceremony, has her monthly course, that vitiates the ceremony which must be begun again when the lady has passed through her course and purified herself. If the person, male or female, dies during the period of these ceremonies, that event also vitiates the whole thing.¹

(b) On the candidate completing the barashnom, two qualified priests (i.e., two priest who "hold the barashnom"), who have to initiate the candidate, perform, what is known as the *gewrâ* ceremony, which lasts for six days. This *gewrâ* ceremony, which qualified them to initiate the candidate, consists of reciting the Yasna with its ritual for six consecutive days. The word "*gewrâ*" comes from the Avesta root *garew*, Sanskrit *grah*, German *engreifer*, Pers. *girafan* to acquire, to take hold of. Both the priests perform the Yasna ceremony, i.e., recite the whole of the Yasna with the necessary ritual. One of the two priests who recites the whole Yasna is called Joti (Zaota), i.e., *lit.* the performer of ceremonies or the offerer of offerings. The other priest who assists him in going through the ceremony [192] is called

names of the living persons are recited in the prayers with a slight alteration. Instead of the words *Anûsheh Ravân*, i.e., 'of the dead (*lit.* immortal) soul', the words *Zindeh Ravân*, i.e., 'of the living soul,' are affixed to the name of the person in whose honour the buildings or institutions are founded. The name of the donor also is recited as فرمایشنه "farmâyashna," i.e., one at whose direction the building or institution is founded. As in the case of the *jashans* for religious buildings or charitable institutions, so in the case of religious ceremonies, the name of the person in whose *nîyat*, i.e., purpose, honour, or memory, they are performed, is mentioned in the recital of the prayer.

1 *Vide* above, p. 145.

Râthwi.¹ The priest, who performs the ceremony as the Joti, is technically said to have “taken the *gewrâ*,” i.e., to have acquired the qualification of continuing the ceremony. The priest who takes the *gewrâ* on the first day, is said to have *taken* the first *gewrâ*. He is to pass a night of vigil and watchfulness. If he has nocturnal pollution, he is said to have lost the efficacy or the qualification of his *gewrâ*. In that case, the *gewrâ* must be repeated the next day. If the efficacy continues, on the next day, in the morning, he “gives the second *gewrâ*” to his colleague. In this case, the other priest recites the Yasna as Joti and the priest who gives the *gewrâ* acts as a *Râthwi*. He, now, in his turn has to pass the night in vigil. Thus each of the two priests has to “take the *gewrâ*” on an alternate day. These *gewrâ* ceremonies are to be performed for six days. To avoid the chance of the *gewrâ* being vitiated by the failure of the vigil of the priest holding the *gewrâ* for the particular day or by some other cause, at times, three priests are made to take part in the *gewrâ* ceremonies. Instead of one priest taking the *gewrâ*, two perform the ceremony, so that, in case one fails to observe the required vigil and is disqualified for some cause, the other may serve, and the candidate may not be disappointed and the initiation not delayed. The candidate has, during these six days, to pass his time in prayers during the five Gahs and to observe all the observances of saying the grace at meals, etc. He is not to come in contact with any non-Zoroastrian.

(c) On the sixth day of the *gewrâ* ceremony, the priest who has taken the sixth *gewrâ*, i.e., has recited the Yasna with its ritual as the Joti on the sixth day, initiates the candidate. The candidate takes his bath in the morning with all its formalities and puts on a new set of white clothes. He puts on a white turban which is a symbol or insignia of priesthood. The parents of the candidate invite a few friends, both male and female, to witness the ceremony. In mofussil towns like Naosari, a general invitation to males is passed round, through [193] a crier, in the whole town. So, any Zoroastrian who chooses may attend.

At the appointed hour at about nine o'clock in the morning, a procession is formed to take the candidate to the temple for initiation. At Naosari, the headquarters of the priesthood, the assembly gathers at the house of the candidate. Gentlemen gather outside the house and the ladies inside, and they all then go to the temple in a procession. The candidate walks in the front with the head-priest of the town, or, in his absence, with his deputy, on his right. Other elders of the community follow. The ladies follow last. In Persia, the ladies throw dry fruits and silver coins over the candidate. In Bombay, the

1 *Râthwi* or *Râspi* [raspi]. Av. 𐬵𐬀𐬯𐬀𐬎𐬎𐬀𐬎𐬀 *rathwiskara* lit. one who arranges the religious requisites at their proper (*rathwya*) places (Gah Uzerin, 5).

Parsees not having quite separate quarters, and the city being too thickly populated to arrange for the ceremonial procession, the candidate stays in the fire-temple itself, for the six days of the *gewrâ*. So, the gathering assembles at the temple itself and the procession also is formed there. It formally moves from one part of the temple to another. The candidate is dressed in his full dress consisting of *Jâmâ* (Pers. *جامه jâmeḥ*), which is a loose gown-like dress of white linen, and *pichori*, a kind of linen-belt, put round the waist. All the male members of the gathering are similarly dressed in their full dress. The candidate carries a shawl in his left hand, it being an insignia of an office or function which a person holds for the time being.

The *gurz* or the mace.

The candidate carries in his right hand a *gurz* or a mace. *Gurz* is the Avesta *vazra*, Sans. *वज्र*, a mace or club. It symbolizes that the candidate is now going to be a member of the church militant and undertakes to fight against all evils, physical or moral. In the Khwarshed Niyayesh, Mihr Yazad or the Angel Mithra, the God of Light, Justice, and Truthfulness is represented as carrying a *vazra* or mace to strike it over the heads of the *Daevas* or the evil powers (*Yazâi vazrem hunivikhtem kameredhê paiti daevanam*).¹ The Fire-temple where the candidate is going to be initiated is called *Dar-e Mihr*, [194] i.e., the Port or the Gate of Mihr (Mithra). So, he carries the *gurz* with him as the insignia of his coming office, in which he has to fight against the enemies of Light, Justice, and Truthfulness and has to make his way for the church triumphant in Heaven.²

Preparation in the temple.

On the procession arriving at the Fire-temple, the candidate goes to the *Yazashna-gah*, where he is to perform the *Yasna* ceremony. The assembled priests are generally seated on carpets spread on the floor. The candidate removes his upper garments which form his full dress, performs the *padyab-kusti*, and puts on the *padân* (mouth-veil).³ Thus prepared, he is brought before the assembly by one of the two priests, who asks for permission to initiate him. He asks: "Gentlemen of this gathering (*Anjuman*, Avesta *Hanjumana*), doth it

1 Ny1.15.

2 For further particulars about the *gurz*, *vide* my paper, "The *Gurz* as a Symbol among the Zoroastrians" (*Journal of the Anthropological Society of Bombay*, Vol. VIII, No.7, pp. 478-96). My *Anthropological Papers*, Part I, pp. 313 *et. seq.*

3 In Persia, the *Padân* hangs from a crown or a turban, decorated with gold and silver coins. The *Sir J. J. Z. Madresa Jubilee Volume* (pp. 435-38, Mr. Khodâyar's article) gives an interesting account of what is called, the "Vers" and "Verd" ceremonies in the nawar initiation there.

please you that this candidate may be initiated?" The Head-priest present, after the interval of a few seconds, takes the silence of the assembly for its assent and nods his head, or puts forward both his hands, to signify the acquiescence of the gathering.

The candidate must be free from leprosy¹ or any wound from which blood oozes, otherwise he would be rejected and the necessary permission refused. It is to give the assembly an opportunity to see or examine him well, that he is presented before it after the removal of the upper garments.² The candidate then returns to the *Yazashna-gah* to go through the ceremonies of his [195] initiation and to recite the Yasna with its ritual. The visitors disperse after flowers and rose-water have been presented to them. If the father or the guardian of the candidate is well off, he distributes money among the assembled priesthood. Relations and friends are, at times, feasted at noon and even at night, if parents can afford to do so.

On retiring to the *Yazashna-gah*, the candidate recites the Mino-Nawar Yasna (Yasna without the Visperad)³ with its ritual, he acting as the *joti* and the priest who initiates him acting as the *raspi*. In the afternoon, he performs the baj⁴ ceremony and takes his meals, after which he performs the Afrinagan ceremony. I give here an illustration which shows the nawar initiate performing the Yasna ceremony.

On the second and the third day, the candidate is permitted to have only one meal. The above three ceremonies are repeated in honour of Srosh on the second day, and the baj is performed in the morning instead of in the afternoon as on the first day. On the third day, the above three ceremonies are again repeated in honour of Siroza (the Yazatas presiding over the thirty (*si*) days (*rouz* [or *ruz*]) of the month). On the fourth day, the Yasna is recited with the Visperad, the baj and Afrinagan in honour of Ahura Mazda. Thus qualified, the priest now called herbad (*Avesta*, *aethrapaiti*, teacher) can perform the Afrinagan, Navjote, marriage, and such other ceremonies, but not the Yasna, the Vendidad or the baj ceremonies.

It appears, that the nawar has been from the first, a ceremony of

-
- 1 On the Iranian horror of leprosy, cf. Vendidad 2:29, 37; Aban Yasht, Yt. 5:92. Herodotus I, 138, "Whoever of the citizens has the leprosy or scrofula is not permitted to stay within a town, nor to have communication with other Persians." According to Ctesius, Megabyzus escaped from the hands of his captors, on pretending that he had leprosy.
 - 2 It is said that, in Persia the candidate is taken to an adjoining room and there made stark naked and examined (*vide* Mr. Khodayar's article in the *Sir J. J. Z. Madressa Jubilee Volume*, p. 437)
 - 3 *Vide* Darmesteter, *Le Zend Avesta*, Vol. I, p. LXVII.
 - 4 *Ibid*, Vol. II, pp. 152-53.

trial, of self-abnegation, self-denial, and self-renunciation. The following facts point to that inference:-

1. The candidate is expected to pass his days during the continuation of the whole ceremony which lasts about a month, in a kind of retreat, in order to be free from worldly thoughts and to be engaged in pious thoughts; he must sleep on the floor and not on a cot, and take his meals at stated hours after prayers. According to the present custom, if the candidate [196] has a *pollutis nocturna* during the two barashnoms, he is disqualified and has to go through the barashnom again, because the untoward occurrence is held to show that he was not passing his time in pure divine meditation, which he was expected to do, as a would-be priest, but that he thought of worldly matters.¹ 2. During the last four days, when he is regularly being initiated and performs the Yasna ceremony himself as *jôti*, he has to take only one meal on the second and third days, to prove that he has control over hunger and thirst and hence over other passions.

A good deal of the original lofty ideal seems to be losing its ground now. In order to avoid the risk of failure in the test of pious meditation, self-abnegation, or control of passions, candidates are made to go through the initiatory ceremony in their early boyhood before the age of fifteen or sixteen, when according to the course of nature, they are expected to be free from *pollutis nocturna*. Again now-a-days, it is not only those boys, who are really intended to be priests in the future, that go through the initiation, but many others who are intended by their parents for other walks of life. The latter are made to go through it with the idea, that it is a religious ceremony worthy to be gone through. There are many medical men, lawyers and merchants of the priestly class, who have been made to go through it by their parents in their boyhood. That being the case, the whole of the Yasna is not learnt and not recited but only a part. One would not object, and must not object, to this procedure, if even in these cases, the original lofty ideal were kept in mind. The salutary effect would not be lost, if a boy were to be made to go through the discipline of the initiation in an intelligible manner. A doctor, a lawyer, or a merchant, if trained in early boyhood to a little discipline, pious meditation, self-control, and self-abnegation, would be a better man in his profession by that kind of discipline, trial, and training. What is wanted is, that the original high ideal must always be kept in view. [197]

1 If this occurs during the last four days, the candidate is called *nâbûd* (Pers., نابود 'non-existent') and is absolutely rejected as unfit for the priesthood.

2. THE MARTAB.

The second degree for priesthood is known as *martab*.¹ The degree of *nawar* does not entitle a priest to perform, what may be called, the ceremonies of the inner circle of the Fire-temple. He cannot perform the *Yasna*, the *Vendidad* and the *Baj* ceremonies. He cannot officiate at the purification ceremonies of *nân* and *barashnom*. In order to qualify himself to do so, he must go through the *Martab* ceremony. Besides the *Yasna* and the *Visparad*, which he had to read for his *nawarhood*, he has now to read the *Vendidad*.

For this ceremony, the candidate has to go through one *barashnom* of 10 days. On the 11th day, he, in company with a qualified priest, performs the *khub* ceremony² and recites for it the *Mino Nawar Yasna* with its ritual. On the second day in the morning, he has to recite another *Yasna* in honour of *Srosh*, and at midnight he recites the *Vendidad*. This completes the *martab* ceremony and he is now entitled to perform and recite any of the Zoroastrian rituals and prayers.

The Zoroastrian *nawarhood*, in some of its features, reminds us of the Christian Knighthood of olden times, when Knighthood was a kind of religious order. The following passage presents many points of similarity between an Iranian *nawar* and an ancient Christian Knight: “The young man, the squire, aspiring to knighthood, was first of all stripped of his garment and put into a bath, the symbol of purification. On his coming out of the bath, they clad him in a white tunic, the symbol of purity, a red robe, emblematic of the blood he was to shed in the cause of the faith, and a black doublet, in token of the [198] dissolution which awaited him as well as all mankind. Thus purified and clothed, the novice kept a rigorous fast for twenty-four hours. When evening came, he entered the church and passed the night in prayer, sometimes alone, sometimes with a priest and with sponsors who prayed in company with him. . . . When the sermon was over, the novice advanced towards the altar with the sword of knighthood, suspended from his neck; the priest took it off, blessed it and attached it to his neck again. The novice then went and knelt before the lord, who was to knight him. ‘To what end,’ the lord then

1 The word is Arabic *murattab lit.* prepared, classified. It seems to be connected with the word *martaba* مرتبة a step, dignity. It may thus mean, one who has risen to a higher step or grade or dignity. Some speak of this initiation as مراتب *marâtib*. In that case, it is Arabic *marâtib*, i.e., grades and gradations of rank. The sense then would be “one who has passed through more than one grade or rank.”

2 The *khub* is of two grades; for the major, the recital of the whole of the *Yasna* with the full ritual is requisite; for the minor, the recital of a few *has* or sections (3 to 7) are requisite.

asked him, 'Do you desire to enter into this order'? If it is that you may be rich, repose yourself, and be honoured without doing honour to knighthood, then you are unworthy of it."

The points of similarity are the following:—(1) Both, the Iranian nawar and the Christian Knight, had to go through purificatory baths. (2) Both had a white dress as a symbol of purity. (3) The Knighthood had its fasts. The nawarhood had no fasts but a kind of abstention or temperance. (4) Both had some weapons to serve as symbols. The Knights had swords; the nawars had *gurzs* or maces. (5) Both the orders signified poverty and a desire to serve and work against evil. [199]

PART IV. THE CONSECRATION CEREMONIES.

CHAPTER IX. (I) CONSECRATION OF THE SACRED FIRES AND THE FIRE-TEMPLES.

Consecration.

Consecration is “the act or ceremony of separating from a common to a sacred use, or of devoting and dedicating a person or thing to the service and worship of God” by certain rites or solemnities. Consecration does not make a person or thing sacred but declares him or it to be sacred, that is devoted to God or to divine service; as the consecration of priests among the Israelites; the consecration of the vessels used in the temple; the consecration of a bishop.¹ The Parsees have no consecration of persons, in the sense in which the word is used among the Christians, e.g., the consecration of a bishop. If, by consecration is meant the conferring of a certain qualification upon a person to enable him or to entitle him to do a certain religious function or rite, they have such a consecration. But the principal idea is, that the person seeks consecration by his own willing acts rather than any other person conferring the consecration. So, in the case of a person, the more proper word, from a Parsee point of view, is “initiation” than “consecration.” I have already spoken of these initiation ceremonies under a separate head.² Among things, there is the consecration of the following:-

- I. The Sacred Fires and the Fire-Temples.
- II. The Towers of Silence.
- III. The Alat (implements, apparatus), i.e., religious requisites.

The three grades of the Sacred Fire.

1. There are three grades of the Sacred Fire—(A) The Sacred Fire of the Atash Bahram, (B) that of the Atash, Adaran and (C) that of the Atash Dadgah. These three have their different rituals of consecration and also different rituals for the daily [200] prayers at the five times (*gahs*) of the day, when they are fed with fresh fuel. We will, at first, speak of the process of consecrating these three grades of the sacred fire.

1 Webster.

2 *Vide* above, Chapters VII and VIII.

(A) Consecration of the Sacred Fire of the First Grade the Atash Bahram.

The 16 fires which make up one.

The ritual formulated for the consecration of the sacred fire seems to have been developed from certain passages of the eighth chapter of the Vendidad (8:73-96), where, it is enjoined, that the fires used for different purposes and by different tradesmen may be carried from their places of use and business and enshrined in a Dâd-gâh (Av. Dâityo-gâtu), i.e., in a proper place. The list of fires there enumerated is as follows:— Fires used (1) in burning a corpse, (2) in burning filth, (3) in burning dirt. (4) The fire used by a potter, (5) a glass-blower, (6) a coppersmith, (7) a goldsmith, (8) a silversmith, (9) an ironsmith, (10) a steelsmith, (11) a baker, (12) a furnace-worker, (13) a tinsmith, (14) a shepherd, (15) a military man or soldier, (16) a neighbour.

The process of collecting the different fires and of purifying and consecrating them is so long and intricate, that, naturally, authorities differ in the matter of the details, though they agree on broad general principles. While writing on the subject of this process, the late Dastur Minocheherji Jamaspji Jamaspasana¹ said, that in the case of all the six Atash Bahrams founded and consecrated in Bombay and elsewhere, there has not been any similarity in the matter of the process. The process has differed in details. In the following account, I principally follow the description given by the late Dastur Erachji Sohrabji Meherji Rana.² The Ithoter Revayet also refers to this subject.³

The list of the *Vendidad* given above has suggested to later ritualists the thought of collecting 16 kinds of different fires to [201] produce, out of them, one fire for consecration. The different fires now collected in practice are the following :— (1) The fire used in burning a corpse, (2) the fire used by a dyer, (3) the fire from the house of a king or a ruling authority, (4) that from a potter, (5) a brick-maker, (6) a *fakir* or an ascetic, (7) a goldsmith, (8) a mint, (9) an ironsmith, (10) an armourer, (11) a baker, (12) a brewer or distiller or an idol-worshipper, (13) a soldier or a traveller, (14) a shepherd, (15) fire produced by atmospheric lightning, (16) household fire or fire from the house of any Zoroastrian.

1 I was indebted to the late Dastur Kaikhosru Jamaspji for kindly giving me a perusal of his late grandfather's manuscript notes on the subject.

2 *Vide* his account in the *Tamâm Avestâ ni Ketâb*, published by Mr. Dadabhoy Cowasji, Vol. II, pp. 213-44.

3 Published in 1346.

Different stages of the consecration of the Sacred Fire of the Atash Bahram, the Fire-Temple of the First Degree.

Each of the above fires is at first collected, purified, and consecrated in a certain manner. All these fires, thus collected, purified, and consecrated, are united into one fire, which is then consecrated as one united fire. This consecrated fire is then enthroned in a Temple which itself is previously consecrated. I will describe these processes under the following heads:—

1. Collection of the 16 fires.
2. Purification of the 16 fires.
3. Consecration of the 16 fires.
4. Union of the 16 consecrated fires.
5. Consecration of the united Sacred Fire.
6. Consecration of the Temple itself.
7. Enthroning the united fire.

1. The process of the collection of the 16 fires.

The fires of the above-mentioned 16 tradesmen or functionaries are collected, purified, and consecrated according to a fixed procedure. We will here describe in detail the process of collecting or fetching the first kind of fire, *viz.*, that from a burning corpse:— A Zoroastrian is to go to a burning ground and ask for a portion of the fire that burns a corpse.¹ If the party gives it of his own accord, at the time when the [202] burning process takes place, well and good. If not, the Zoroastrian must wait there till the whole of the corpse has been burnt, and then, when the relations and friends of the deceased go away, he is to take a portion of the fire left. He must ask a non-Zoroastrian to take out for him a certain portion of the fire from the burning mass. If a non-Zoroastrian is not available, or if he refuses to do that work for him, then two Zoroastrian laymen may perform the *padyab kustî*, hold the *paiwand*, recite the Srosh Baj upto *Ashahê*,² and then hold over the fire, at the distance of about a foot, a perforated ladle containing a little powdered sandalwood and frankincense and such other substance as may easily ignite. They must not let the ladle touch the fire. The heat of the fire from the burning corpse easily ignites the fuel on the perforated ladle. The fire so ignited must be taken by the laymen to an open place. They must

1 Dastur Minocheherji's above-mentioned notes say, that it is preferable to have, if possible, the fire from a Brahman's corpse.

2 The Ithotar Revayet (i.e., the 78 Revayets, p. 9) is over-scrupulous and enjoins that when one goes before the fire of the corpse all those precautions for pollution, as are required in the case of the corpse itself, should be observed.

then finish the Baj and have a bath of the *riman* purification. As the fire is that which has burnt an impure corpse, it is believed to have a part of the corpse's defilement; so, the carriers of it are required to purify themselves.

The fire thus brought from a burning ground is then fed with fuel and is placed on a piece of ground open to wind. By its side and in a windward direction, they place a heap of powdered sandalwood, frankincense, and such other easily combustible substances. The heat and the blaze of the fire, carried by the wind towards the heap, ignites it. When thus ignited, this fresh fire is fed with fuel. Then, again, by its side another heap of powdered sandalwood, frankincense, and such other combustibles is placed in such a position, that the blaze and the heat of the fire produced as above may be carried by the wind towards it and that it may be easily ignited. This process is repeated 91 times. The distance between each burning fire and the next heap to be ignited must be about half a *gaz* or about a foot. Each preceding fire is allowed to extinguish [203] itself. The fire ignited for the 91st time is then considered to be fit for use and it is kept burning by being regularly fed. This is the process of collecting the first fire in the above list of 16 fires, *viz.*, the fire of a burning corpse.¹

All the other 15 fires are similarly collected, but the process differs in the following points:— (a) The number of times, for which the above process is to be repeated, varies. For example, in the case of the second fire in the above list, *viz.*, the fire of a dyer, the number of times for which the process is repeated is 80. I give below² a table which shows at one sight, the number of times through which the process of collection, the process of purification, and the process of consecration, passes. (b) In the case of the other fires, no defilement is supposed to be attached to them as that to the fire of the burning corpse; so, the laymen, who fetched them from their respective places, need not personally go through any kind of *riman* purification as that required in the case of the fire that burnt a corpse, (c) Again, a portion of any one of the next 15 fires can be bodily lifted up from the mass and carried to the place of its use. It need not be produced by the ignition of powdered fuel on a perforated ladle, as in the case of the fire that burnt a corpse. The rest of the process is the same.

In the case of the sixteenth fire, the household fire, it must be that

1 The Ithoter Revayet enjoins a more tedious process. It says, that the fire brought, as said above, from a corpse may be purified by passing through the process over nine pits. Over it, one Yasna of Srosh, one Visperad and one Vendidad of Srosh must be recited. In this way, the whole process is to be recited 91 times, i.e., 91 fires may be brought at different times from a burning corpse and purified and then collected together.

2 *Vide* below, pp. 222-23.

of the house of a Mazdayasnian or a Zoroastrian. But in this class are included several fires. A Zoroastrian may be a priest or a layman. So, the fire must be made up of the fires from the houses of a priest and a layman. Among the priests, there are the Dasturs or the head-priests and Mobads or ordinary priests. So, the fire from the house of the priests must be made up from two fires, fetched from the houses, both [204] of a Dastur and of a Mobad. Again, to this last class of fire, *viz.*, the household fire, must be added the fire produced by friction which was the earliest primitive way of producing fire for household purposes. There were two ways of producing fire by friction in early days, *viz.*, (a) the friction of two pieces of flint and the friction of two pieces of wood. So fires produced by both these two ways of friction must be added to the household fire fetched from the houses of priests and laymen.

At first, the household fire, made up from the fires of the houses of the priests and laymen, must be made to pass 40 times through the above process of ignition, wherein a fire is produced by some combustibles being placed in the windward direction of a burning fire. To the household fire, thus collected, may be added the fire produced by the above-said two methods of friction. The fire thus formed by ignition or combustion must again be passed 144 times through the above-described process.

2. The process of purification.

The fire thus collected is considered fit to be handed over to priests for purification and consecration. Two priests take charge of it. They perform the *padyab-kusti*, hold the *paiwand* and recite the Srosh Baj upto the word *Ashahê*. While reciting the Srosh Baj, they recite in it the Dasturi also as in the case of the barashnom purification.¹ They then proceed to purify the fire. In this process of purification, they follow the precepts of the *Vendidad* (8:73-78) which refers to the practice of purifying a fire that is burning a corpse. It enjoins as follows:— (a) At first, the burning matter may be removed and its further burning may be stopped. (b) Then a Zoroastrian may take a perforated ladle, place some easily ignitable fuel upon it and then hold it above the burning fire so as not to touch it. The heat of the original fire, which was burning the corpse, passes up through the holes of the ladle and ignites the fuel on it. The fire so produced must be put by the side of the fire that was burning the corpse at a distance of a *vitashiti*, i.e., about 10 inches from [205] it. The original fire may then be allowed to extinguish itself, (c) The fire thus prepared by the first stage of purification may then be fed with further fuel. Then a second

1 *Vide* above, Barashnom Purification, p. 128, *Vide* also p. 64.

fire may be prepared from it by the above process, i.e., by holding over it at some distance, a perforated ladle containing some easily ignitable fuel. On the fuel being ignited, this second fire thus prepared may be placed by the side of the first fire at a distance of about 10 inches. The second fire must be fed with further fuel and the first fire allowed to extinguish itself in its turn. This is the second stage of purification. This process is repeated nine times. Just as a man, that has come into contact with a dead body, has to be purified at nine different *magas* or pits, each at the distance of a fixed measure, so the fire that was defiled by coming into contact with a dead body had to be purified nine times. After the ninth process, the fire produced thereby is considered to be pure.

The modern practice in conformity with the Vendidad.

Now the modern practice of purifying the fire, fetched or collected as above, follows the above process enjoined by the Vendidad but with an increased number of times. Two priests take charge of the fire collected for them, as said above, by two laymen. They hold over the fire, at the height of about half a *gaz* or about 12 to 15 inches, a perforated ladle containing powdered sandalwood, frankincense and such other easily combustible substances. When ignited, they place it on a clean place and feed it with fuel.

The later Rivayats say, that the priests are to prepare 91 *magas* or pits, each with a little powdered fuel of the above kind. Then they are to place the fire kindled as above into the first of these pits. Then they are to hold a perforated ladle over the fire kindled as above and get the powdered fuel over it ignited. They are to place the fire so ignited in the second pit which is full of powdered fuel. This fuel further kindles the fire. They are to hold the perforated ladle over it and thus repeat the process over the 91 pits for 91 times. The fire thus produced at the 91st time is said to be purified and fit for consecration. Each of the pits is to be connected with the preceding adjoining pit by a *paiwand* formed of [206] apiece of string or apiece of sandalwood. As the process goes on, the preceding fire or the fire of the preceding pit is allowed to extinguish itself. Now, it being not practicable in towns to have a large open place, where 91 pits of the above kind can be provided, in present practice, the pits are replaced by fire-vases, and the process is repeated in vases. The number of censers need not be 91. A few as would allow the process to be repeated 91 times can do.

This is the process of the purification of fire named first in our above list, *viz.*, the fire of a burning corpse. Similar is the process for purifying the other 15 fires. But the number of times for which the process is repeated is different for the different kinds of fire. The

number of times for the purification process is in each case the same as the number of times for the collection process. The table which I give below (pp. 210-211) will show this at one glance.

3. The process of consecrating the 16 fires.

The fire, collected and purified as above, is placed in a censer and taken to the place where the religious ceremonies for the consecration are to be performed. Two priests, who have gone through the barashnom, take a portion of that fire, in a separate censer, and recite over it an Yasna and a Vendidad ceremony with the Khshnuman, or in honour of, Dadar Ahura Mazda. The fire, over which these recitals — one of the Yasna and one of the Vendidad — with their ritual are made, is kept separate in a separate censer and constantly fed. In the meantime the fire collected and purified as above, and out of which only a portion was removed on the first day for consecration, is fed and kept burning. On the second day, another portion out of it is taken and the Yasna and Vendidad ceremonies are performed over it in honour of Ahura Mazda. The fire (which is a portion of the same first kind of fire, *viz.*, the fire of a burning corpse) thus consecrated on the second day is mixed up with the fire consecrated on the first day and which, as said above, is kept burning in a separate censer. On the third day again, another portion of the above purified but unconsecrated fire of the first kind, is taken and consecrated as on the first two [207] days with a recital of the Yasna and the Vendidad in honour of Ahura Mazda. The fire (i.e., the third portion of the first kind of fire) thus consecrated on the third day, is mixed up with the fire which was consecrated on the first two days and which was united or mixed up on the second day.

Then, similarly, a portion of the purified but unconsecrated fire of the first kind may be taken each day from roz Ohrmazd (i.e., the first of the month) to roz Anagran (i.e., the 30th day of the month), i.e., for 30 days and consecrated each day by the recital of one Yasna in the morning and one Vendidad after midnight, both recited in honour of the Yazata or the angel presiding on the particular day on which the consecration takes place. For example, on roz (day) Ohrmazd, the recital of the Yasna and the Vendidad must be in honour of Ahura Mazda; on roz Vohuman, in honour of Vohuman, and so on. The fire consecrated each day is to be united with the united fire made up of the consecrated fires of all the preceding days including the first three days.

On the completion of the first round of the ceremonies for the 30 days of the month, commencing with Ohrmazd (the first day) and ending with Anagran (the 30th day), a second round of 30 days, in the

same way as above, must be gone through. Then a third round must be similarly gone through, but not for the whole of the month, i.e., for 30 days, but only upto the Zamyad [Zam] roz, i.e., the 28th day. Thus, as shown above, altogether 91 recitals of the Yasna and 91 of the Vendidad are to be repeated for consecrating the fire of the first kind. The following table explains this:—

	Recitals.
On the first three days in honour of Ahura Mazda	3
On 30 days from the 1 st day (roz Ohrmazd) to the 30 th day (roz Anagran) of the month	30
On 30 days as above for the second time	30
On 28 days from the 1 st day to the 28 th day (roz Zam) during the third month	28
91	

[208]

Now, in the recital of the Yasna and the Vendidad, two priests are required. So, if there be one pair of priests, they would take 91 days to complete the consecration of the first kind of fire, *viz.*, the fire of the burning corpse. One pair can perform and recite more than one Yasna during the Hawan gah or the morning hours, but they can perform only one Vendidad in the Ushahin gah or after midnight. So, one pair would take at least 91 days to complete the consecration of the first kind of fire. But more than one pair can take part — and they generally do so — in the consecration of fires. In that case, the time would be shortened. Then the recital in honour of the Yazatas from Ohrmazd to Anagran need not be from day to day, i.e., on the respective days on which they presided. What is considered as essentially wanted is 91 recitals of the Yasna and 91 of the Vendidad, of which the first three are in honour of Ahura Mazda, the next 30 in honour of the 30 Yazatas in their order, the second 30 also in honour of the 30 Yazatas, and the last 28 in honour of the 28 Yazatas from Ohrmazd to Zam. The fire of the first kind, thus united and consecrated after 91 recitals of the Yasna and the Vendidad, (the number of the recitals being the same as that of the processes of collection and of those of purification), is to be kept apart in a censer marked with its name. A similar process is to be gone through over the other 15 fires.

Consecration of the other 15 fires.

In the case of the other 15 fires the details of the process of consecration are well nigh the same. The points of difference are two: Firstly, the number of recitals of the Yasna and Vendidad over the

portions of fire, i.e., the number of the processes of consecration varies in each. For example, in the case of the fires Nos. 2, 3, 4, etc., viz., that of the dyer, the king, potter, brick-maker, etc., the number of recitals is 80, 70, 61, etc., which was also the number of its processes of collection and purification. Secondly, the order of the Yazatas with whose *Khshnuman*, i.e., in whose honour, the recital is made, differs. For example, in the case of the second kind of fire, viz., that of the dyer, the recitals of the Yasnas and [209] the Vendidads for the first three days are in honour of the second Yazata Vohuman. Then the remaining 77 recitals begin from Vohuman, the second Yazata, and taking two rounds of 30 days end in the third round at Rashu, the eleventh Yazata. In the case of the third kind of fire, the 1st three recitals must be in honour of the third Yazata Ardwahisht. Then the remaining 67 begin with the third Yazata and end with Adar in the third round. In the case of the fourth kind of fire, they are in honour of the fourth Yazata Shahrewar and so on, so that the recitals for the 16th kind of fire are in honour of the 16th Yazata Mihr.

I append here a table, giving the particulars, above referred to, about the different kinds of fires that are united to form the Sacred Fire of the Atash Bahram. (1) The first column gives a list of the names or the kinds of fires. (2) The second column gives the number of times the processes of (a) collection, (b) purification, and (c) consecration are repeated. The number for the repetition of each of all these three different kinds of processes is the same in the case of each of the fires.¹ (3) The third column gives the names of the Yazatas with whose *Khshnuman*, or in whose honour, the consecration recitals of the Yasnas and the Vendidads for the first three days and nights are to be made. (4) The fourth column gives the names of the Yazatas in whose honour the rest of the consecration recitals of the Yasna and the Vendidad are made and the number of the recitals. The number of recitals given in this column and the three recitals in honour of each of the Yazatas mentioned in the third column, make up the number of the second column. The second column of the above list shows that there must be in all, 1,128 consecration recitals of the Yasna during the morning hours of the day, and of the Vendidad after the midnight hours. One pair of priests can recite only one Vendidad. So, if only one pair of priests were to perform the ceremonies of consecrating the sixteen fires, they would take 1,128 days, i.e., about 37 to 38 months. But generally more than one *jôr* or pair is [212] employed in the consecration ceremonies. So, the whole ceremony is gone through in about a year or even less than a year. Again, several *Jashan* days, i.e., religious feast days and the *Gahambar* feast days occur during the

¹ E.g. in the case of the first fire, there are 91 repetitions for collection, 91 for purification, and 91 for consecration.

time that the whole process of consecration lasts. On such feast days, one Yasna and one Vendidad in honour of that particular *Jashan* must be recited. On the occasion of the Gahambar, i.e., the season festivals, the Visperad in honour of the Gahambar festival must be recited. The number of these additional recitals cannot be fixed as that depends upon the time of the year. [210]

A Table giving the particulars about the different kinds of Fires that are united to form the Sacred Fire of the Atash Bahram and showing the number of the processes of Collection, Purification, and Consecration.

	The Kind of Fire.	No. of times for (a) the Collection, (b) Purification, and (c) Consecration processes.	Names of the Yazatas in whose honour the three recitals of the Yasna and Vendidad are said for the first three days.
1	Fire of a burning corpse	91	Ahura Mazda
2	... Dyer	80	Vohuman
3	... King or ruling authority	70	Ardwahisht
4	... Potter	61	Shahrewar
5	... Brick-maker	75	Spandarmad
6	... Ascetic	50	Hordad
7	... Goldsmith (or Alchemist)	60	Amurdad
8	... Mint	55	Day-pa-Adar
9	... Ironsmith	61	Adar
10	... Armourer	61	Aban
11	... Baker	61	Khwarshed
12	... Brewer, Distiller, or Idol-worshipper	61	Mah
13	... Soldier or Traveller	35	Tir/Tishtar
14	... Shepherd	33	Gosh (Drvasp)
15	... Atmospheric Electricity	90	Day-pa-Mihr
16	... Zoroastrian, i.e., a Dastur (head-priest), a Mobad (priest), or a lay-man and of friction by flint and pieces of wood.	40+144=184	Mihr
	Total ..	1128	

[211]

Names of the Yazatas in whose honour the rest of the recitals of the Yasna and Vendidad are said and the number of the recitals. By

the word “first” Is meant the first, beginning with the Yazata mentioned in the third column.

- 1 3 recitals in honour of the first 28 Yazataa from Ohrmazd to Zamyad and 2 in honour of Mahraspand and Anagran. Thus $(28 \times 3 =) 84 + (2 \times 2 =) 4 = 88$.
- 2 3 in honour of the first 17 Yazatas from Vohuman to Rashnu (i.e. 51) and 2 in honour of the next 13 (i.e. 26). In all $51+26=77$.
- 3 3 in honour of the first 7 Yazatas from Ardwhisht (i.e. 21) and 2 in honour of the remaining 23 (i.e. 46). So in all $21+46= 67$.
- 4 in honour of the first 28 Yazatas from Shahrewar (i.e. 56) and 1 in honour of the remaining 2 (i.e. 2). So in all $56+2 = 58$.
- 5 3 in honour of the first 12 Yazatas from Spandarmad (i.e. 36) and 2 in honour of the remaining 18 (i.e. 36). So all $36+36= 72$.
- 6 2 in honour of the first 17 Yazatas from Hordad (i.e. 34) and 1 in honour of the remaining 13 (i.e. 13). So in all $34+13 = 47$.
- 7 2 in honour of the first 27 Yazatas from Amurdad (i.e. 54) and 1 in honour of the remaining 3. So in all $54+3 = 57$.
- 8 2 in honour of the first 22 Yazatas from Day-pa-Adar (i.e. 44) and 1 in honour of the remaining 8. So in all $44+8= 52$.
- 9 The same order as in the case of the fourth kind of fire, but beginning with Adar.
- 10 The same order as in the case of the fourth kind of fire, but beginning with Aban.
- 11 The same order as in the case of the fourth kind of fire, but beginning with Khwarshed.
- 12 The same order as in the case of the fourth kind of fire, but beginning with Mah.
- 13 2 for the first 2 Yazatas from Tir (i.e. 4) and 1 for the remaining 28. In all $4+28=32$.
- 14 1 for all the 30 Yazatas beginning from Gosh. So 30 in all.
- 15 3 for the first 27 Yazatas, from Day-pa-Mihr (i.e. 81) and 2 for the remaining 3 (i.e. 6). Thus in all $81+6 = 87$.
- 16 6 for each of the 30 Yazatas beginning from Mihr (i.e. 180) and 1 more in honour of Ahura Mazda. Thus 181 in all.

[212 continued]

What delays the process at times is the collection of the fire of atmospheric electricity, i.e., the fire produced by the burning of a tree, grass or wood due to the fall of lightning. Months before the proposed time of the ceremony, messages are sent to different stations, requesting the Parsees there to be on a look-out to see if a falling lightning has produced a fire, and to take up a portion of the fire if so produced. The ceremony of consecrating the other fires need not be delayed for this fire. It may go on. But, if, by the time all the fires are consecrated, the fire produced by lightning does not come forth, the final unition and consecration of all the fires cannot take place. It must be indefinitely postponed until this fire is produced and consecrated.

4. The final unition of all the 16 fires.

As said above, all the sixteen fires are, after the different consecrations of its portions for the number of times stated against their names in the second column of the above table, collected and fed in a separate censer. So, in all, there are 16 different censers containing the 16 different fires. The final unition or collection must take place on the first Gatha Gahambar Festival day, i.e., on the first of the five intercalary days at the end of the year. A large censer is prepared for this process. Two Yaozdathragar priests, i.e., priests with barashnom and Khub, form a *paiwand*, and, at first, remove, by means of a ladle, the consecrated fire prepared from the fire that burnt a corpse, from its censer to this large censer. Then, the other fires are [213] carried there and united with the first in the consecutive order of their consecration.

5. The final consecration of the United Fire.

The censer, containing the fire thus united and formed from the 16 consecrated fires, is then carried to the Yazashna-gah for final consecration. At first, for three consecutive days, two priests recite, with their ritual, three Yasnas and three Vendidads, each on one day, with the Khshnuman of Sraosha, i.e., in honour of the Yazata Sraosha. Then, from Ohrmazd, the 1st day of the next month to Anagran, the 30th of the month, 30 Yasnas and 30 Vendidads are recited, each on one day, in honour of the particular Yazata presiding on the particular day. Then, on the last day fixed for the final consecration and enthronement of the Sacred Fire, another Yasna in honour of Sraosha is recited with its ritual over it. This completes the ceremony of consecrating the Sacred Fire of Atash Bahram, the Fire of the first degree. What remains to be done is to place it, or, as the Parsee phraseology goes, to enthrone it, on its proper place (*dâityô-gâtu*).

6. The Consecration of the chamber of the Fire (the Sanctum Sanctorum).

The Sacred Fire being consecrated, the chamber in the Fire-Temple where it is to be enthroned must also be consecrated. That consecration ceremony lasts for three days. It must be performed before the final day of consecration and enthronement. It consists of the performance there, for three consecutive days, of the Yasna and Vendidad ceremonies in honour of Sraosha.

7. The final Enthronement.

On the day fixed, the final consecration-recital of the Yasna being said, the Sacred Fire is removed to the consecrated chamber with all dignity and solemnity. A procession is formed. The procession is

headed by the head-priest and other priests who have officiated at the various ceremonies of the consecration. Some bear swords and some *Gurz* or maces in their hands. The path, which leads from the Yazashna-gah where the final [214] consecration of the Sacred Fire took place to the consecrated chamber where it is to be enthroned, is separated from the adjoining place by *pavis* to keep it undefiled. Again, the path itself is divided into several *pavis*, so that the two priests who carry the censer containing the Sacred Fire can remain, at each advance, in a separate *pavi*. It must be remembered that, during the whole of the consecration processes also, the fire was kept within a separate *pavi* where it was fed by the consecrating priests. The fire, after being carried thus to its chamber, is placed on a large censer standing on a large slab of stone surrounded by a *pavi*. Then, it is fed with sandalwood and frankincense, and an *Atash Niyayesh* i.e., a prayer in praise of fire, is recited. Then, in the front hall of the Temple, a *Jashan* ceremony is performed, wherein three *Afrinagans* are generally recited. The first is with the *Khshnuman* of *Sraosha*, the second with that of *Dahman* and the third again with that of *Sraosha*. Similarly, the *Bajs* are recited. This finishes the ceremony of enthroning the Sacred Fire.

The spiritual rule of the Sacred Fire.

The above ceremony of placing the Sacred Fire in its chamber is spoken of as the ceremony of *takht-nashini* i.e., enthronement or coronation. The Sacred Fire is metaphorically spoken of as a King, having a spiritual jurisdiction over the district round about. The stone slab or stand, on which its censer stands, is considered and spoken of as its throne (*takht*). Its chamber is in the form of a dome, giving an idea of the dome of the heavens. It is just under the centre of the dome that the censer stands on the slab. From that centre hangs, high above over the fire, a metallic tray which is spoken of as the crown (*taj*) of the Sacred Fire, which is looked at as the symbolic representation or emblem of a spiritual ruler. One or two swords and one or two maces are hanging on the inner walls of its chamber. They serve as symbols of the Church militant, and signify, that the faithful should fight against moral evils and vices, just as they would fight against their enemies, and thus make it, in the end, triumphant. [215]

A national toast of the Parsees, connected with the Sacred Fire of the Atash Bahram, represented as a King.

The Parsees have some general toasts, which may be called their "national toasts," and which are now and then proposed at most of their dinners. The first is "*Yazdân ni Yâd*, i.e., "In Honour and to the Glory of the Creator." Another, at times, is "*Ashô Farohar ni Yâd*,"

i.e., “In honour of the dear departed holy ones.” One of the others is “*Atash Beherâm pâdshâh nâ pâe-takht ni salâmati*,” i.e., “For the safety of the foot of the Throne of the kingly Sacred Fire of the Atash Bahram.” In this toast, by the use of the word “throne,” the idea of the spiritual rule of the Fire is intended to be held. At times, even up to a few years ago, some laymen addressed the priests as pâdshâh, i.e., the king, because they attended to, and fed, the kingly fire. The visible fire of the Church is a symbol of the Invisible Church of God.

The State and the Church in ancient Iran.

In ancient Iran, the State and the Church were generally united. In bringing about by the Iranian Renaissance after the Dark Ages of the Parthian rule, brought about the fall of the Achaemenian Empire at the hands of Alexander the Great, one of the ways adopted for the purpose by Ardeshir Babegan was that of the Unity of the Church and the State. His Vazir and Dastur (minister and head-priest) Taosar [Tansar] alludes to this, at some length, in his letter¹ to Jasnafshâh, the King of Tabaristan.² In Zoroastrianism, the Unity of the Church is represented, as it were, by the Unity of the Fire. [216] Purity and Unity play the important part in the consecration of the great Sacred Fire. At present, though the Zoroastrian Church is separated from the State, it looks to the State — though now a non-Zoroastrian State — for its protection, for its sway. So, in their Afrinagan prayers, they pray, even now, as they did in ancient Iran, for the long life, prosperity and just and happy rule of the king. What Herodotus said of the ancient Iranians, that they, before praying for themselves, prayed for their sovereign and for their community, is true even now.³ Not only in the Afrinagans, but also in the Tan-dorosti prayer, recited at the end of all the formal prayers, a Parsee prays for his king. In their big dinners also, the “Health of the King” is one of their toasts.

1 *Journal Asiatique*, Tome III, March-April 1894.

2 During the last century, this question was discussed in another way and had even gone to the Court of Law. The Shahanshahi sect of the Parsees at Surat opposed the erection of an Atash Bahram by the Kadmi sect, on the ground that there cannot be two Atash Bahrams in one city. Both parties produced before the Court evidence from religious books, old and new, to support their case. The Court decided that there may be more than one Atash Bahram in one city. The same question was discussed in Bombay at the end of the last century. There existed Atash Bahram of the Shahanshahi sect. Its Dastur objected to the erection of another, saying, that, as there cannot be two kings in one and the same city, there cannot be two Atash Bahram padshahs (kings) in one and the same city. Both sides published treatises. In the end, the second Atash Bahram, known as the Anjuman Atash Bahram, was founded.

3 “He that sacrifices is not permitted to pray for himself alone; but he is obliged to offer prayers for the prosperity of all the Persians and the king, for he is himself included in the Persians.” (Herodotus, Bk. I., 132.)

Signification of the purifying and consecrating processes of the Sacred Fire.

Now, what does a Sacred Fire, purified and consecrated as above, signify to a Parsee? (a) A Parsee has to think for himself: "When this fire on this vase before me, though pure in itself, though the noblest of the creations of God, and though the best symbol of the Deity, had to undergo certain processes of purification, had to draw out, as it were its essence, — nay, its quintessence — of purity, to enable itself to be worthy of occupying the exalted position, how much more necessary, more essential, and more important is it for me — a poor mortal who is liable to commit sins and crimes and who is likely to come into contact with hundreds of evils both physical and moral — to undergo the process of purity and piety, by making my *manashni*, *gavashni*, and *kunashni* (thoughts, words, and deeds) pass, as it were, through a sieve of piety and purity, virtue and morality, and to separate by that means my *humata*, *hukhta*, and *hvarshata* (good thoughts, good words, and good deeds) from my *dushmata*, *duzukhta*, and *duzvarshata* (bad thoughts, bad words, and bad deeds), so that I may, in my turn, be enabled to acquire an exalted position in the next world? (b) Again, the fires put together as above [217] are collected from the houses and places of business of men of different grades of society. This reminds a Parsee that, as all these fires from the houses of men of different grades have by the process of purification, equally acquired the exalted place in the vase, so, before God, all men — no matter to what grades of society they belong — are equal, provided they pass through the process of purification, i.e., provided they preserve purity of thoughts, purity of words, and purity of deeds, (c) Again, when a Parsee goes before the Sacred Fire, which is kept all day and night burning in the Fire-temple, the officiating priest presents before him the ash of a part of the burning fire. The Parsee applies it to his forehead, just as a Christian applies the consecrated water in his Church, and thinks to himself: 'Dust to dust. The Fire, all brilliant, shining and resplendent, has spread the fragrance of the sweet-smelling sandalwood and frankincense round about, but is at last reduced to dust. So, it is destined for me. After all, I am to be reduced to dust and have to depart from this transient life. Let me do my best to spread, like this fire, before my death, the fragrance of charity and good deeds and lead the light of righteousness and knowledge before others.' In short, the Sacred Fire burning in a Fire-temple serves as a perpetual monitor to a Parsee standing before it, asking him to preserve piety, purity, humility, and brotherhood."¹

1 Vide my *Religious System of the Parsis*, second edition of 1903, pp. 27-28. Vide for this paper *The Report of the World's Parliament of Religions*, Vol. II, p. 908. Vide the chapter on "Religion," contributed by me, in Mr. Dosabhoj Framjeo'e *History*

The ceremony of removing the ash of the Sacred Fire for the ritual of Purification.

While speaking of the purificatory ceremonies, we have said that the sacred ash of the Sacred Fire of the Atash Bahram is required to be mixed with the consecrated urine. We will here describe the ceremony with which this ash is removed from the vase of the fire:— Two priests with barashnom, who have performed the Khub ceremony, go before the Sacred Fire in the Ushahin gah, i.e., after midnight. They, [218] at first, make *pav*¹ i.e., religiously pure, a metallic tray, two metallic ladles and a piece of linen. Holding a *paiwand* between them, they recite the *baj* with the Khshnuman of Ahura Mazda. Reciting it upto “*vidhvao mraotu*,” they utter the word “*ashem*” (i.e., purity) and repeat it in *baj*, i.e., in a suppressed tone. One of the priests then puts on gloves, and by means of the ladles, removes from the vase of the Sacred Fire as much of the ash as he requires, and places it in the metallic tray. Then, removing the gloves, both wash their hands and make them *pav* with pure water. They let the hands dry and then pass the ash through the linen as through a sieve. The ash so collected is then put in a vessel previously made *pav*. The vessel is then tied up with three turns of twisted yarn with two final knots and kept apart. Having done this, the priests go out of the chamber of the Sacred Fire and finish the *baj*. The ash is then supplied as required to the different Fire-temples of the lower grade under the jurisdiction of the great Temple for purificatory ceremonies.²

The Bui ceremony of feeding the Sacred Fire. Meaning of the word “bui.”

We will here describe the Bui ceremony, i.e., the ceremony of keeping the fire always burning, by feeding it with fragrant wood. The word “bui” is the Persian form of the Avestan word “baodha.” It is “bui” in Pahlavi. Ordinarily, the word means “odour” or “smell.” In the Parsee ceremonial phraseology, it means perfume, or good odour. Fire plays a prominent part in all Zoroastrian rituals. No ritual can be complete without the presence of fire. So sandalwood, frankincense, and such other articles of fuel that emit good odour on burning are necessary requisites in all ceremonies. In the temples, where the Sacred Fire is kept perpetually burning, the feeding of the fire is an important ceremony. It is called “*bûi dâdan*” in Persian, and “bui

of the Parsees, Vol. II, p. 214.

- 1 The process of making a thing *pâv*, or religiously pure, consists in reciting *Khshnaôthra Ahurahê Mazdâo* and one *Ashem Vohu* and then washing it with pure water. This process is repeated three times.
- 2 *Vide* above, pp. 96 and 114.

devi" (i.e. to give the perfume) in Gujarati. [219]

The ceremony varying for the three grades of the sacred fires.

The ceremony varies a little according to the different grades of the Fire-temples: As said above, there are three grades of Fire-temples:— (1) the Atash Bahram (in Pahlavi, *Verêhrâm* or *Vahrâm*; Avesta *Verethragna*), i.e., the fire of Victory (victory over evil influences or powers); (2) the Atash Adaran, i.e., the fire of fires; (3) the Atash Dadgah, i.e., the fire (ceremoniously established) in a proper place. Dadgah is the *Dâitya-gâtû* of the Vendidad (Chapter 8). In the first two grades of fire temples, it is the priest alone who can go before the fire and feed it. In the case of the third grade of temples, in the absence of a priest, even a layman can feed it. In the case of the Atash Bahram, the fire can be fed only by a priest who has become a martab and who is observing all the ceremonies required to be observed by one with a barashnom. In the case of the Atash Adaran, it can be fed by any priest, even when he is not observing the barashnom. In the case of the Atash Bahram, the officiating priest must also have performed the ceremony of Khub before going to the sacred fire to feed it. The Khub ceremony consists of the performance of the Yasna ceremony. Having once performed that ceremony, its qualifying influence lasts for four days. After the fourth day, it must be performed again. A bath during the interval, or a wet dream, which necessitates a bath among the Parsees, or the partaking of food without the regular recital of the baj, i.e., prayer for grace, or the coming into contact with a non-Zoroastrian, breaks the influence of the Khub, which, in such cases, must be performed again.

The five periods for the performance of the ceremony.

The Bui ceremony is performed five times every day. It is performed at the commencement of each of the five gahs or periods of the day which correspond, to a certain extent, with the canonical hours of the Christians.¹ These periods are the [220] following:— (1) Hawan. It begins from early morning when the stars begin to cease to appear, and lasts upto 12 o'clock when the sun comes overhead. Literally, it means the time when the ceremony of pounding the haoma is performed. (2) Rapithwin. It runs from 12 o'clock noon to 3 p. m. Literally, it means the pith (*pithwa*) or the middle part of the day (*ayarê*) (3) Uzerin. It runs from 3 p.m. to the time when the stars begin to appear. Literally, it means the time of the advancement of the

1 The five gahs seem to correspond to Matin, Prime, Sext, Nones, and Compline. In the Atash Bahram at Naosari certain priestly families had the right of the Bui ceremony for a certain number of days. This reminds us of a similar practice in the Assyrian and Babylonian temples.

sun. (4) Aiwisruthrem. It runs from nightfall to midnight. (5) Ushahin. It runs from midnight to dawn when the stars begin to cease to appear.

Difference in the way of feeding the fire, according to its grades.

The ceremony of Bui in the case of these three grades of Fire temples varies. (a) In the case of the second and third grades of Fire-temples, (the Atash Adaran and the Atash Dadgah), the fire can be fed with one piece of sandalwood, but in the case of the Atash Bahram, the fire must be fed with a mâchi¹ of sandalwood. In this case, six pieces of sandalwood are placed on the Sacred Fire. The Atash Bahram is spoken of, as said above, as Atash Bahram Padshah, i.e., the king.² Being the highest Grade of Sacred Fire, it is compared to a king. So the sandalwood, with which the Sacred Fire is fed, is placed on it in the form of a Machi or throne. The six pieces are arranged on the fire in pairs of two pieces, placed one over the other, (b) The next point, in which the ceremony of the Bui varies in the case of these different grades of Fire temples, is this: In the case of the second and third, the Atash Niyayesh (the prayer in honour of the angel presiding over fire) is recited only once, but in the case of the Atash Bahram it is recited several times. In the first period of the day (the Hawan), it is recited eleven times; in the second (the Rapithwin), nine times; in the third, seven; in the fourth, seven; in the fifth, six times, (c) Again, in the case of the [221] second and third grades of the Sacred Fire, the Bui ceremony is very simple. The priest performs the Kusti-padyab (i.e., performs ablutions and unties and puts on the Kusti again with the recital of a prayer), and then goes into the sacred chamber, places one or more pieces of sandalwood over the fire and recites the Atash Niyayesh, but in the case of Atash Bahram, the ritual is a little long in other respects. I will describe it here:—


The Bui ceremony in an Atash Bahram.

A priest who has performed the Khub ceremony, performs the Kusti-padyab at the commencement of each new Gah, i.e., the period of the day, as described above, and then recites his Farziyat, i.e., the necessary prayers, which are the Srosh-baj, the Gah according to the time of the day, and the Khwarshed and Mihr Niyayeshes during the day periods, i.e., the above-named first three gahs. During the night-periods which form the last two gahs, the Khwarshed and Mihr Niyayeshes are replaced by Srosh Yasht (Yasna 57) and Srosh Hadokht. He then goes into the sacred chamber, puts on white gloves, places some frankincense over the Sacred Fire, and then the Mâchi,

1 Mâchi comes from Sanskrit *manch*, meaning a throne, a seat of honour.

2 Vide my contribution in the *Zend Avesta* of Darmesteter I., Introduction LXI-II.

i.e., the six pieces of sandalwood as said above. If sandalwood is not obtainable, six pieces of any other kind of clean good wood will do. The six pieces are placed over the fire from three different positions, thus: –



[222]

At first, the priest, standing before the censer, faces the east and places two pieces (AA and BB in the above figure) of sandalwood over the fire at a short distance from each other. Then he turns to the south and places two more pieces (CC and DD) over the first two. Then he turns towards the west and places two more pieces EE and FF over the four.¹ He then washes with pure water² the stone-slab on which the censer of the Sacred Fire stands.³ This ceremony of washing the

1 In all the ceremonies of the Parsees, the north side is, as a rule, generally avoided. *Vide* above, p. 56.

2 For these purification ceremonies, the water itself is, as it were, purified. Two water-pots, full to the brim with well water, are taken into the chamber. The water from the one is poured into the other, which itself is full to the brim until the water overflows, and while thus overflowing cleans and purifies also the sides of the vessel. This is done three times with the recital of the words *Khshnaoθra Ahurahē Mazdao* and of the *Ashem Vohu* prayer. The water of the other pot is similarly purified. Then the water-pots with the water in them are said to be made *pav*, i.e., pure or clean with water (*pa-âv* = Persian, *ba-âb*).

3 The stone-slab is ordinarily spoken of by the priests as *Khuân* or *Khân*. Prof.

pedestal or the stone-slab (*Khân*) on which the Sacred Fire stands, is alluded to in the 9th chapter of the Yasna.¹ The priest then places on the fire a little sandalwood and frankincense three times, speaking the words Humata, Hukhta, Hvarshta, i.e., good thoughts, good words, and good deeds. Then he goes round the censer with a metallic ladle in his hand, and, standing in eight² different positions (*viz.*, the four sides and the four corners), and then going back to his original position on the west of the censer and facing the east, recites, in these nine positions, different words of a short formula of prayer. This [223] ceremonial of going round the censer is spoken of as ‘*chak farvun*,’ i.e., going round the circle (Pers. *chak*, i.e., “one side of four; an eighth part of a thing”).


A chart of the different positions.

The following chart points out the different positions in which the priest stands whilst reciting the various parts of the prayer-formula. The numbers point out the consecutive order in which he stands at the different positions before the censer on the altar:

Darmesteter, by some mistake (*Le Zend Avesta* I. Introduction LXX) calls the metallic tray, standing on a metallic stool on the left side of the censer, the Khân, but in the ordinary parlance of the priesthood, that tray is called *Khânchê* while the stone-slab is called *Khân*.

1 Y. 9:1.

2 In the performance of the Afrinagan ceremony also, the *Âtravakhshi*, i.e., the person sitting before the fire, at the recital of the Ahunwar or Yatha Ahu Vairyo and Ashem Vohu, points with his ladle in the tray, the eight different directions. From an anthropological point of view, the custom has some similarity, with the sides and corners pointed by the Hindu Svastika and the pre-Christian Cross.



I give here an illustration of the performance of the Bui-ritual in the sanctum sanctorum of the Fire-temple.¹ [224]

The following table gives the different words of the text, recited in the different positions before the censer, the references to the Avesta text for the words, and their meanings

Table of the formula recited.

Directions.	Words of the Avesta Text recited.	Reference to the Texts.	Translation of the words.
1. West	Âthwâ âthro gârayêmi.	The first two words from Y51:9.	I praise (Thee, O God) through thy fire.
2. North-East	Vanghéush mananghô zaôthrâbyô yazamaîdê.	Y68:3.	We praise through the offerings of good thoughts.
3. South-East	Âthwâ âthro gârayêmi.	Same as No. 1.	Same as No. 1.
4. East	Vanghéush ukhdhahâ zaôthrâbyô yazamaîdê.	Y68:3.	We praise through the offerings of good words.

¹ The priests of the Shahanshahi sect put on white turbans, those of the Kadmi sect put on the *fentâ*, which is a hat of an Irani type. In this illustration it is a Kadmi priest who officiates.

5. South-West	Âthwâ âthro gârayêmi.	Same as No. 1.	Same as No. 1.
6. North-West	Vanghéush shyaôthnahê zaôthrábyô yazamaidê.	Y68:3.	We praise through the offerings of good actions.
7. North	Sukâi manangha.	Y68:4.	For the enlightenment of (our) thoughts.
8. South	Sukâi vachangha.	Ibid.	For the enlightenment of (our) words.
9. Coming back to the original place on the West of the censer and facing East...	Sukâi shyaôthna.	Ibid.	For the enlightenment of (our) deeds.

[225]

The meaning of the above formula on the whole is as follows:— “O God! We praise Thee, through Thy fire. We praise Thee, by the offerings of good thoughts. We praise Thee through Thy fire. We praise Thee by the offerings of good words. We praise Thee through Thy fire. We praise Thee by the offerings of good deeds. (We do all this) for the enlightenment of our thoughts, for the enlightenment of our words, and for the enlightenment of our deeds.” That is to say, the worshipper standing before the sacred fire, taking it as the symbol of God’s refulgence and purity, and placing over the fire sandalwood and frankincense as visible offerings, offers the real, though invisible offerings of good thoughts, good words, and good deeds, and thereby hopes and prays for the further enlightenment of his thoughts, words, and deeds.

Having recited the above short but pithy formula of prayer the priest places again over the fire a little sandalwood and frankincense, and then recites, as said above, the *Atash Niyayesh*¹ several times, according to the *Gah* or period of the day. While reciting the first *Niyayesh* for the first time, the priest goes on placing bits of sandalwood and frankincense (*aêsma bûi*) at the intervals of a few words.

The ringing of the bell.

During the recital of the first *Niyayesh*, and during the recital of the first *Pazand* portion of it, whilst uttering the words “*dushmata*,” “*duzhukhta*,” “*duzvarshta*,” i.e., evil thoughts, evil words, and evil deeds, he rings a bell thrice; some ring the bell thrice, whilst uttering each word, i.e., in all give nine strokes of the bell. This is, as it were, to

1 S. B. E. XXIII., p. 357. *Le Zend Avesta*, par Darmesteter, II., p. 705.

emphasise that portion of the prayer, wherein the worshipper expresses a desire to shun bad thoughts, bad words, and bad deeds. At the end of the first recital of the principal portion of the Atash Niyayesh, the priest draws by means of two ladles two circles in the ash in the censer at its ridge, and at the similar end of the second recital he obliterates the circles again. While reciting the Niyayesh during the first and the fifth Gah or period of the day (the [226] Hawan and the Ushahin), the priest stands on the West of the censer with his face towards the East, and during the other periods vice versa.

(B) Consecration of the Sacred Fire of the second grade, the Atash Adaran.

The later Persian books say, that in a town or village where ten Zoroastrian families reside, the presence of a Fire-temple of the second grade, the Atash Adaran, is necessary. The process of collecting, purifying and consecrating the fires for this sacred Fire of the second grade is not very long. Four principal kinds of fire are required to constitute this fire. They are: Fire from the houses of (a) the Athornans, i.e., the priestly class, (b) the Rathaêshtârân, i.e., the military class, (c) the Vâstryosân, i.e., the agricultural class, (d) the *Hutokhshân*, i.e., the artizans, tradesmen, and manufacturers. We will speak of the consecration of the Sacred Fire of the second degree under the following heads: 1. Collection of the fires. 2. Purifying the fires. 3. Consecrating the fires. 4. The final consecration of the united fire. 5. The final enthronement.

1. Collection of the fires from the houses of different classes.

(a) The first requisite fire is that from the houses of the Athornans, i.e., of the men of the priestly class. For this purpose, fires from the houses of the following persons are generally collected and united:— (1) The Dastur, or the head-priest of the town. (2) An ordinary priest. (3) The leading or the head layman of the town. (4) The donor. In case the Fire-temple is founded by a private individual with a charitable or religious motive, the fire of his house is generally taken, if convenient. If he lives in a town different from that where he founds the Fire-temple, the fire of his house need not necessarily be had. The fires from the houses of these different persons are collected together.

(b) For the preparation of the fire of the Rathaeshtars, i.e., the military or the governing class, fires from the houses of the following grades of persons are collected:— 1. Fire of the house of the Governor, or the ruling authority of the place. For [227] example, if a Fire-temple is sought to be founded in Bombay, the fire from the cook-room of the Governor's house may be had. If it is to be founded in a mofussil

town, that from the house of the Collector or the Assistant Collector or the Deputy Collector, or any other officer who is the head ruling authority of the place may be had. 2. Fire of the house of a military officer or person residing in the town or in the neighbourhood may be had. If there are no houses of military officers or soldiers near at hand, the fire from the house of a Police Officer may be had. 3. Fire from the house of the leading judicial authority. For example, if it is in Bombay that a Fire-temple is being founded, the fire from the house of the Chief Justice or of any one of the Judges of the High Court may be had. In the mofussil, it may be had from the house of any judge or magistrate or other judicial officer. All these fires, are then mingled together to form a fire of the military or the ruling class.

(c) The fire of the house of an agriculturist may be had from the house of any tiller of the soil in the locality. If there is a Parsee cultivator at hand, the fire from his house may be had, and then from that of a Hindu cultivator. A fire from the house of an ordinary gardener may be had. Then all these fires are mingled together to form one fire of the agricultural class. The fire of the artizan class is prepared out of the fires of different tradesmen and workmen. They are generally fetched from the places of business of artizans and others, such as the goldsmiths, silversmiths, ironsmiths, tinsmiths, copper smiths, dyers, distillers, bakers, potters, tillers, brick-makers, chunam-makers, shepherds, caravanbashis, sentinels, etc The fires from their houses or places of business are all united to form one fire of the artizan class.

2. Purification of the fires.

The process of purification is well nigh the same as that described above in the case of the different fires that were united to form the Sacred Fire of the first Grade. A ladle with holes containing powdered fuel, etc., is held over the fire at some [228] distance from the flame. The process differs in only one respect, viz., that in this case the process is repeated thrice only, while in the case of the Sacred Fire of the first Degree the number of repetitions varied from 33 to 91 times.

3. Consecration of the four fires.

Each of the above-said four united fires, after being purified as above, is consecrated separately. Each of the four fires is placed in a separate vase and two priests take charge of each fire, i.e., in all, eight priests are required to consecrate them. A lesser number can do, but in that case it would take a larger number of days. On the first day, each of the four pairs of priests performs over the fires, in the morning, the Yasna ceremony and, after midnight, the Vendidad with the *khshnuman* of Srosh. On the second day, the same ceremonies are

performed again, but with the *khshnuman* of Ahura Mazda. During these recitals the four fires are placed before the officiating priests.

4. The final consecration of the Sacred Fire.

Then, on the third day, the four fires are all united into one. The vase or censer containing the first, i.e., the fire of the Athornan or priestly class, receives in itself the fire of the next three classes. All the priests who officiate at the consecration unite themselves by a *paiwand* and then, reciting the *Yatha Ahu Vairyo* [Ahunwar] formula, combine the fires together in the first censer. Having done so, they recite the *nemashkâr* [Namaskar]¹ of Atash or homage to the Sacred Fire three times, finishing it with the Ahmai-raeshcha prayer, etc. It runs as follows: "Homage to thee, O Fire of wise Ahura Mazda, the benefit-giving great Yazata."

Having thus combined the fires and having thus paid an homage to the united Fire, two priests — generally the two priests who had at first consecrated separately the fires of the priestly class — perform over it the Yasna ceremony in the morning and the Vendidad at midnight with the Khshnuman of Srosh. Then, on the morning of the fourth day, a Yasna with the Khshnuman of Dadar Ahura Mazda is recited over [229] the united Fire. This finishes the preparation and the consecration of the Sacred Fire of Atash Adaran.

5. The enthronement of the Sacred Fire.

The Sacred Fire being thus prepared and consecrated, there now remains the final ceremony of enthroning it. It is well-nigh the same as that for the Sacred Fire of the First Grade. The assembled priests and others form a procession and formally carry the Sacred Fire to the chamber which itself has been cleaned, purified, and consecrated, as in the case of the Atash Bahram. There, it is enthroned on a large metallic censer which stands upon a raised stone-platform or slab. A priest then feeds this Sacred Fire reciting the Atash Niyayesh. All others also recite this Niyayesh. Then, they assemble in the outer hall of the Temple and perform the Jashan ceremony. In this, either the three Afrinagans referred to in the case of the Jashan of the Atash Bahram or the following Afrinagans are recited:— 1. Ardwhisht Ameshaspand. 2. Ahura Mazda. 3. Spandarmad. 4. Arda Fravash. 5. Dahman, 6. Srosh. Similarly, the Baj ceremony is performed at the same time.

1 Vide Spiegel, translated by Bleeck, *Khordeh Avesta*, pp. 3-14.

(c) Consecration of the Sacred Fire of the Third Grade: The Atash Dadgah.

The ritual of the consecration of this fire is very simple. It is the ordinary fire of the household that is consecrated. So there is no special process of collection for it. Again, there is no special purification. The principal function is the consecration of the Temple where it is to be deposited. The fire, that is used in the consecration of the Temple itself while performing the Yasna and the Vendidad ceremony, forms the Sacred Fire of the Atash Dadgah. The following is the process of consecrating the Temple building:— The building intended or built for the temple is cleaned and washed. Some later writings say, that all Temple buildings may, at first, be washed and purified thrice with gomez or cow's urine, but the practice is not generally resorted to now. It may then be purified by being washed thrice with water. After this purification and cleaning, commences the consecration ceremony. It lasts for [230] four days. During the first three days, in the morning, a Yasna ceremony with the Khshnuman of Srosh, and after midnight, a Vendidad with the same Khshnuman are recited. On the morning of the fourth day, a Yasna with the Khshnuman of Arda Frawash is recited. Then finally, the Jashan ceremony is performed. In this Jashan ceremony, five Afrinagans are recited with the Khshnuman of:— 1. Ardwhisht. 2. Ahura Mazda. 3. Spandarmad (Spanta Armaiti). 4. Ardafrwash. 5. Dahman. 6. Srosh. Similarly, six Bajs are recited.¹ [231]

1 At times, the numbers of Afrinagans and Bajs vary. For a list of the Fire-temples of all grades *vide* Khân Bahâdur Bomanji Byramji Patel's contribution in the *Bombay Gazetteer*, Vol. IX, Part II. *Vide* Zoroastrian Calendar of 1476 Yazdazardi (1906-07), by Mr. Manoharji Jagosh.

CHAPTER X. (II) CONSECRATION OF THE TOWERS OF SILENCE.

There are three ceremonies in connection with the consecration of a Tower. They are the following:— I. *Kodâri mârvi* (*lit.*, to strike the first spade),¹ i.e., the ceremony for digging the ground to lay the foundation. II. The *Tânâ* ceremony, or the ceremony of laying the foundation. III. The Consecration ceremony proper.

1. The preliminary ceremony of digging the ground.

The first ceremony is that of digging the ground. It is performed a few days before the formal laying of the foundation. In the centre of the spot chosen for a Tower, a barashnomwala priest encloses a certain place with a “pavi”² and thereon performs, at first, the *Khub* ceremony with the five springs of the Barsom (*pânc̄h tâi ni khûb*). Then he recites the “baj” in honour (1) of Sraosha, the guardian angel guiding the souls of the deceased, (2) of Ahura Mazda, (3) of Spenta Armaiti, the Archangel presiding over ground, a portion of which is now being enclosed for the construction of the Tower, (4) of “Ardafrawash,” i.e., all the departed souls, and (5) of “Haft Ameshaspands,” i.e., the seven Archangels. Having recited these prayers, the priest holds a spade in his hand and recites the *Srosh Baj* upto *Ashahe*. He then digs with his own hand a part of the ground required for the Tower. While digging, he recites the *Yatha Ahu Vairyo* [Ahunwar] prayer 21 times.

II. The *Tânâ* or the ceremony for laying the foundation.

A few days after, when the whole of the required plot of ground is excavated by the labourers, two priests perform in the morning the “*Tânâ*” ceremony for laying the foundation of the Tower. The ceremony is so-called from the fact of “*tânâ*” or [232] a very fine thread being used to mark out the circumference of the Tower and its different parts for the laying of the foundation. One hundred and one³

1 The old Egyptian ritual for laying the foundation-stone of a temple, referred to below, also speaks of the use of the spade.


2 “Pâvi” [pavi] (from “pâv,” i.e., sacred) is a kind of trench a few inches deep in the ground. It is intended to separate a portion of a place from the adjoining ground in order to perform a sacred ceremony therein. No outsider is allowed to enter within this enclosed place while the ceremony is being performed. The *Yasna*, *Baj*, and *Vendidad* ceremonies are performed only within such enclosed spaces. In Fire-Temples, the sacred fire burns on a censer within such an enclosed space.

3 One hundred and one is a sacred number, because, according to the Parsee books, the Almighty God has one hundred and one names which signify all his virtues. These one hundred and one names are recited in several ceremonies, e.g., in preparing the sacred “*Zaotra*” or consecrated water for the *Haoma* ceremony.

fine threads are woven into one strong thread or string. The thread so prepared should be as long as would suffice to go round the circumference and the inner parts three times.¹ Some time before its use, this thread is made "*pâv*," i.e., washed, purified, and dried. To hold this thread, the priests have to fix in the ground 301 nails of different sizes and weights. The following are the various numbers and weights:— (a) One central nail (shown in the plan by the letter A) of one maund without any holes. (b) Four side nails² (i.e., for South-East, South-West, North-West, and North-East sides) (B, E, D and C,) each of half a maund. Each of these four nails is to have three holes, one being straight and the other two crosswise, (c) Thirty-six nails (16 in the outer circle, each shown in the plan by the letter F, and twenty in the inner circle, each shown in the plan by the letter G,) weighing altogether about one maund. (d) Two hundred and fifty-six nails, altogether weighing one maund, 32 on each of the eight rows marked HH in the plan, (e) Four nails of the same size as the above 256 to be fixed at the places marked J J. These five sets of nails give the total of 301.

1 The number three is a sacred number, being symbolic of Humata, Hukhta, and Hvarshta, i.e., good thoughts, good words, and good deeds, the three precepts on which the moral structure of the Zoroastrian religion rests.

2 These nails correspond to the pegs in the Egyptian ritual. For the four nails, cf. "the four supports of heaven" (vide below, pp. 236-37).



On the day of the Tānâ ceremony, in the morning, two barashnumwala priests get down into the excavation that has been dug for the foundation. Having performed the *padyab*, they perform the *Khub* ceremony with the five-twigs of the barsom. They then put on their full sacerdotal dress (*Jâmâ pichhori*) and hold the *paiwand* between them. They then recite the [233] Srosh Baj upto the word *Ashahê*, and begin to fix the nails in the ground. They recite one Ahunwar or Yathâ-ahû-vaîryô, while striking each nail. The central large nail A is struck first. The greater part of it is left above the ground. Then the nails on the South-East, South-West, North-West and North-East are struck. Then the above 36 nails are struck in the order marked in the plan beginning at G on the S.-E. which is marked as G 1. The order is G 1, F 2, G 3, F 4, G 5, F 6, and so on in the first quarter. Then G 10, F 11, and so on in the next quarter. Thus, the last or the 36th nail is at G 36 in the fourth quarter. Then the 256 nails are struck in eight different lines shown in the plan. The first 32 must be struck in the line between H and G 1. The next 32 on the similar row

on the opposite side H-G 36. The third 32 on the third similar row H-G 10 and then the fourth 32 on the opposite row, and so on, till all the 256 are struck in the 8 rows at 32 per row. Then the last four are struck at the 4 points marked J. During the whole of the process of nailing, the priests recite Yathâ-ahû-vaîryôs.

After finishing the nailing, the priests commence passing the tânâ or the thread through the nails. They begin with the nail on the South-East quarter, B, one of the four large nails with three holes. The thread is passed through the lowest hole, and the end is fastened with it with a double knot which is put over. it with the recital of two Ahunwars. The long thread is then carried from nail to nail in a metallic tray. One of the two priests carries the tray and the other passes the thread from nail to nail, always moving to the right, i.e., from Southeast to the South, then to the Southwest, then to the West, and so on. Beginning with the nail at B, he takes the thread to G 1, then to F 2, then to G 3, then to F 4; and so on. Finishing the first quarter of the outer circle, i.e., passing the thread round the first 9 nails of the outer circle, he passes the thread through the lowest hole of E, the second of the four large nails with three holes. It is then passed round the 9 nails of the second quarter of the circle, then through the lowest hole of D; then round the 9 nails of the third quarter of the circle; then through C; then round the 9 nails of last quarter of [234] the circle. The nails in each quarter are fixed alternately, one at the side towards the inner well of the proposed Tower and the other at the furthest outer circle which is to form the foundation of the well of the round tower.

The above process finishes one round. The thread must be taken round for the second time in the same manner as in the first round, but with this difference, that in the case of the large-holed nails B, E, D, and C, it is to be now passed through the second or the middle hole. Then the thread is to be taken round for the third time. The process is the same, but differs in two points. Firstly, the thread is now to be pierced through the topmost hole of the four big-holed nails; and secondly, in the third round, the thread is also to be taken round each of the 32 nails which make each of the 8 rows. Going in one direction in the line of the 32 nails, in the first quarter of the circle, the thread is passed round one of the nails J. It is then passed round each of the 32 nails of the opposite row. Thus, in the process of the third round, all the double rows, each of 32 nails, are passed through in each of the four quarters of the circle. The thread is then passed round the biggest central nail which was struck in the centre of the plot and which pointed the position of the central well, known as the *bhandâr*. The whole of the remaining part of the thread is put

round this central big nail. The two priests now finish the Srosh Baj, with the recital of the first part of which they had commenced the ceremony. This finishes the whole of the Tâna ceremony.

The place marked A in the plan forms the centre of the inner well of the circle where the bones gather after flesh is devoured. The outer circle next to, or out of, A marks the place of the first set of *pâvis*, on which, when the tower is finished, bodies of children are placed. The next outer circle marks the middle circle of the tower when completed, on the *pâvis* of which the bodies of females are placed. The third or the outermost circle marks the circle of the *pâvis* on which bodies of males are placed.

The Assembly.

Thousand of Parsee visitors, men, women, and children, gather to witness the ceremony. On the occasion of the Tâna ceremony of the [235] Tower at Deolâli, about 100 miles from Bombay, which took place a few years ago, six special trains from Bombay took devout Parsees there. It is said that about more than 5,000 people collected there to witness the ceremony. The visitors were seated in a covered *mandap* round the excavations dug for the foundation of the Tower. Of course, all are not expected to witness the ceremony. Hardly a thousand can see it actually performed. But the other thousands go there with the devout object of participating in the work. On the close of the ceremony, the remainder, who have not been able to see the whole ceremony, go to the place and see the nails and the thread as spread there. All the visitors throw into the excavation, gold, silver and copper coins and even currency notes as they can afford. Some more devout even throw their rings. That is considered to be their contribution to the pious work of building a Tower. It is announced, that at the above-said Tower ceremony at Deolâli, they collected in this excavated ground a sum of a little more than Rs. 2,000. The head-priest of the district, in whose ecclesiastical jurisdiction the town lies, is believed to have the privilege of having the sum thus collected at these Towers of Silence ceremonies, but he generally gives it away to the subscription fund for the maintenance of the Tower, etc. It is believed, by many people, that it is meritorious to see the ceremonies of the consecration of at least seven Towers during one's life-time. Hence such large gatherings.

For two or three weeks after the ceremony, the excavations with the nails or pegs and threads are left as they are, so that people, who had no opportunity to go and see it on the day of the ceremony, may go and see it at their convenience. Hundreds generally go there and throw their humble mite in the excavated foundations. The place

assumes a festive look for several days. Booths are put up by tradesmen for the sake of refreshments, etc. When the influx of people diminishes, the foundation work proceeds over the whole thing as it is. The nails and the thread remain underground and the foundation work proceeds over it. [236]

The signification of the Tânâ ceremony.

Now what is the signification of this Tânâ ceremony? The Avesta and old Pahlavi books say nothing of it. The signification seems to be this: As it is enjoined in the Vendidad that the ground must not be polluted with the corpses of dead bodies but must be exposed, this Tânâ ceremony seems to signify that the proposed Tower is expected to pollute the ground, only to the extent of its excavations. The thread all along limits, as it were, the extent of pollution. The pollution, if any, is 'Within the four corners of the walls of the Tower. It does not extend even underneath. The position of the nails and the threads points out, as said above, the position of the different parts of the Tower when completed. We see from the description of the Tower, that it has four underground drains, through which the rain-water, etc., falling over the bodies in the Tower passes into the ground. The area of those underground drains which are likely to carry a little polluted water are also, as it were, limited by the four double rows, each of 32 nails, and their thread. Again, the whole process of nailing begins with the central big nail and the whole process of the spreading of the thread ends at that central big nail. This seems to point to the idea of unity in the Beginning and unity in the End. We all come from One, from the One. We all go to that One. The whole creation is, as it were, united in its birth. It is united in its end. There is One in All. There is All in One.

A somewhat similar foundation ceremony of the Egyptians.

The Tânâ ceremony of the Parsees reminds one of a somewhat similar foundation-ceremony of the ancient Egyptian temples; The well-known astronomer Norman Lockyer says:- "We learn from the works of Chabas, Brugsch, Dümichen, and others, that the foundation of an Egyptian temple was associated with a series of ceremonies which are repeatedly described with a minuteness, which, as Nissen has pointed out, is painfully wanting in the case of Greece and Rome. Amongst these ceremonies, one especially refers to the fixing of the temple-axis; it is called, technically, 'the stretching [237] of the cord.' Another part of the ceremony consisted in the king proceeding to the site where the temple was to be built, accompanied mythically by the goddess Sesheta, who is styled 'the mistress of the laying of the foundation-stone.' Each was armed with a stake. The two

stakes were connected by a cord. Next the cord was aligned towards the sun or star as the case might be; when the alignment was perfect, the two stakes were driven into the ground by means of a wooden mallet One boundary wall was built along the line marked out by this stretched cord.”¹

The old Egyptian word for laying the foundation-stone was *Put-ser*, wherein *put* means ‘to stretch,’ *ser* means, ‘cord,’ “ so that part of the ceremonial which consisted in stretching a cord in the direction of a star was considered of so great an importance, that it gave its name to the whole ceremonial.”² Similarly in the Parsee ceremony, the *tânâ* or the thread used in the ceremony has given its name to the whole ceremony. One Egyptian inscription says: “The Kherheb read the sacred text during the stretching of the measuring-cord and the laying of the foundation-stone On the piece of ground selected for the temple On account of the stretching of the measuring-cord, the Egyptian engineers were called by the Greeks, whose art Democritus boasts of having acquired.”³ Another inscription says: “The hammer in my hand was of gold, as I struck the peg with it Thy hand held the spade during the fixing of its (the temple’s) four corners with accuracy by the four supports of heaven” In one picture, the king and the goddess are represented with clubs in their hands, to hammer the pegs.

3. The consecration proper of the Tower.

On the Tower being completed, a particular day is fixed for its consecration. It is generally consecrated in the dry season, so that the ceremony, which is mostly to be performed in the open air with a temporary covering, may not be interrupted by the rains. It lasts for four days. The Tower is surrounded by a *pâvi*. In [238] the central well of the Tower, called the “Bhandâr,” two priests perform for three consecutive days the Yasna ceremonies during the day in the “Hawan Gah,” and Vendidad ceremonies at night in the “Ushahin Gah.” These ceremonies are in honour of the angel Sraosha, who is protecting the souls of the dead for three days and nights after death. On the morning of the fourth day, the opening day of the Tower, a Yasna ceremony is performed in honour of Ahura Mazda. Then the Baj and Afrinagan ceremonies are performed in honour of Ahura Mazda, of Ardafarosh, i.e., the departed souls, of Spandarmad, i.e., the Yazata presiding over mother-earth, a portion of which is now occupied for laying the dead upon, and of Sraosha. In the Afrinagan ceremony,

1 *The Dawn of Astronomy* by Norman Lockyer, (1894), p. 173.


2 *Ibid*, p. 175.

3 *Ibid*.

known as the Jashan¹ ceremony, which is performed in the presence of a large number of the community assembled to witness it, the name of the donor at whose expense the Tower is built is mentioned and the blessings of God invoked upon him. If the Tower is constructed by the donor in honour, or to commemorate the memory, of a deceased relative, the name of that relative is publicly mentioned. When the ceremony is over, the persons assembled go into the Tower to see it and throw into the central well, gold, silver, or copper coins as their mite in the expenses of the construction of the Tower. Some throw even their rings and ornaments. These go to make up the sum necessary for building the Tower, if it is built at the expense of the Anjuman or the whole community. If it is built at the expense of a generous donor, the amount thus collected goes to the head priest of the district in whose ecclesiastical jurisdiction the Tower lies. At times, he gives it for the use of some charitable funds of the town.² I give here a plan of the Tower itself.

1 "Jashan" is the contraction of "Yazashna."

2 For a list of the Parsee Towers of Silence, *vide Bombay Gazetteer* Vol. IX, Part II: Khan Bahadur Bomanji Byramji Patel's contribution. *Vide Zoroastrian Calendar of the Yazdazardi Year 1276 (1906-7)*, by Mr. Muncherji Jagosh.



[239]

CHAPTER XI. (III) CONSECRATION OF THE ÂLÂT OR RELIGIOUS REQUISITES.

Consecration of *gomez*. Signification of the word.

A minor form of consecration is that for the Âlât or the requisites used in some religious services. One of such thing is *gomez* or cow's urine. Among the ancient Iranians, water, urine, and sand or a particular kind of earth or clay were considered to be the best means of purification. Water was the best purifier, but before washing the body with it, the application of cow's urine was considered necessary. *Gaomaêza* is the Avesta word for it. It comes from *gao*, a cow and *miz*. Sanskrit *mih*, Latin *ming-ere*, to sprinkle. When the urine is consecrated by religious ceremonies, it is, in religious parlance, spoken of as *nirang* or *nirang-din* (i.e., the *nirang* prepared by religious ceremonies). It is so called, because a *nirang*, i.e., a religious incantation is recited on its application.

Urine has been used by several nations from very old times as a purificative. Its original use as a purificative has led to the notion of its being considered as a charm against evil spirits. Prof. Eugen Wilhelm says on the subject of its use:- "That the practice of using cow's urine as a preservative against the influences of evil spirits is very old indeed, and likely to date from the most ancient times, we may conclude from the fact, that traces of this same custom. existing with our Aryan brethren in the East in India and Erân may be found sometimes even today in the West, in the Bretagne, that province of France which holds its name from the Celtic Britons who sought refuge there."¹ Dr. Wilhelm gives references from Roman and Hindu books for its use and then shows that "the urine was employed in medicine from the most ancient times."² It was so used in Egypt, Greece, Rome, and Scandinavia. Pliny the Elder refers to its use as medicine in the 18th chapter of [240] the 28th book of his *Natural History*.³ Galenus, "the most prominent physician of antiquity"⁴ next to Hippocrates, refers to this fact. It was an Indo-Germanic conception. Prof. Darmesteter, on the authority of Luzel (*Le Nirang des Parsis en Basse-Bretagne, Mélusine*, 493), says, that "the use of *gaomez* has been lately found to be known in Basse-Bretagne." (S. B. E., Vol. IV, 1st ed., Introd. p. 88, n. 3).

1 "On the use of Beef's Urine according to the precepts of the *Avesta* and on similar customs with other Nations," by Dr. Eugen Wilhelm, p. 31.

2 *Ibid.*, p. 29.

3 *Ibid.*, p. 35.

4 *Ibid.*, p. 38.

The urine used for ordinary purifications is the urine of a domesticated animal like the cow, the bull, or even the goat. But the urine used for higher purificatory services is that of an uncastrated bull and it is consecrated with certain ceremonies. The Vendidad enjoins its use for purification in several passages; but the principal passage is the 21st section of the 19th chapter. Therein, there is a question to this effect: How can one purify a person who has become a *hamrit* (i.e., one who has come into direct contact with a dead body) or a *patrit* (i.e., one who has come into indirect contact with a dead body by coming into contact with a *hamrit*)? The reply is, that he can be purified by the urine of a bull that is (a) uncastrated (*bikhedrem*) and (b) that is properly prepared (*dâityô-keretem*, i.e., properly consecrated). This passage requires, that the urine must be that of an uncastrated bull, and that the bull must be one properly selected and qualified.

Rapp on Nirang.

In considering, what place goes or cow's urine or, what is ceremoniously known as "nirang" occupies in Zoroastrian ritual, we must look to the times in which its use was enjoined and also to the idea with which it was enjoined. Prof. Rapp says on this point:- "It would presume little acquaintance with the peculiarities of the ancient world, if we wished to bring to bear our present notions of decency and loathsomeness on the customs of old Can we judge now of the ideas and customs in this fashion from the point of view of European modern notions? And before we determine to bring in accord all the customs of the ancient world that were employed for purifications to our modern rational notions, we might like to know [241] to be sure what advantage has that blood of an animal which Moses used, in respect of the purpose in view, over the urine of an ox! It will not be possible for us altogether to comprehend the conceptions of the ancient notions of what is pure and what is not pure and of their ceremonies in religious purifications, if we do not ascend up to the very origin of all these notions, namely, to the ancient doctrine of the double creation, that of the pure and of the impure world. That in the purifications so much value is set on the ox and all that issues out of it, the sacred legends of the Zend people make it quite comprehensible. We have seen that the entire ceremonial law of Zoroaster rests upon the conception of a pure and impure creation, and therefrom it follows that the corporeal impurity was just as punishable and just as abhorrent in the eyes of Ahuramazda, the pure, as the moral impurity of the soul, and that men should purify themselves from the first as from the last pollution by just the same means.

“Now, we believe ourselves to be able to prove that the entire ceremonial law of Moses reposes upon these very ideas and that no one can correctly comprehend nor understand the Mosaic law generally, if he does not start from these ideas when attempting his interpretations.”¹

An account of the Nirangdin ceremony.

We will now describe the Nirangdin ceremony, i.e. the ceremony for consecrating the urine. At first, two priests go through the barashnom ceremony of ten days. There is one difference in the barashnom gone through by the priests on this occasion and that gone through by the priests on other ordinary occasions. In the latter case, it is the nocturnal pollution during the first three nights that vitiates the barashnom and necessitates a repetition. But, in the case of the priests who are to perform the Nirangdin ceremonies, they are to pass all the nine nights of the barashnom in vigil, watch and prayer. If they have the nocturnal pollution during any of the ten nights, they are to repeat the barashnom. [242]

As described in the account of the barashnom ceremony, the complete barashnom takes ten days. On the eleventh day, one of the two priests takes an early bath and puts on a new set of clothes. Then, performing his padyab-kusti, says his morning prayers. Then he performs the Khub² ceremony. On the second day, i.e., on the twelfth day from the beginning, the second priest performs the Khub ceremony. His colleague, who has performed the Khub ceremony on the first day, gets him through that ceremony. Then, both the priests perform the Gewrâ,³ ceremony. During the six days of the Gewrâ, the priest whose turn it is to keep the Gewrâ has to pass the night in vigil, as said above. Again, he is to take his meals after reciting the great baj and not the ordinary baj, or prayer of grace. On the completion of the sixth Gewrâ, both the priests perform the baj ceremony and each partakes of the *dron* consecrated by his colleague. This inter communion, or partaking of the sacred bread consecrated by one another, is spoken of as “being hamkalam,” i.e., “being one or united (ham) in their words (kalâm) of prayer.” Then they purify the utensils to collect the urine of the bulls for consecration. They make pav, i.e., ceremonially pure, two large water-pots—one larger than the other—two small water-pots, and a cup that would cover the large water-pot. All these pots are metallic.

1 K. R. Cama's Translation of the Article on the Vendidad from the German of Rapp, pp. 15-16, 19.

2 Vide above, p. 202. The Nawar ceremony.

3 Vide above, p. 202. The Nawar ceremony.

The Varasyô, or Sacred Bull.

By this time, a white bull known as the Varasyô is brought into the Temple where the ceremony is to be performed. We saw above that the Vendidad refers to an uncastrated bull for the use of the urine, but does not speak of its being a white one. Later books have enjoined that it must be a white one. A single black hair on the body disqualifies it for being used as a sacred bull. The word 'varasyo' comes from the Avesta word 'varesa' meaning 'hair,' because the hair of this white bull is used symbolically in the Yasna ceremony. A metallic ring used in the ritual is known as "varaç ni viti," i.e., 'the ring with the hair.' The hair of this sacred bull is put round the ring. [243]

The two priests after being "ham-kalâm" as said above, and after making the utensils pāv or religiously pure, go with one of the small metallic pots before the sacred bull and collect his urine in the pot. Even a few drops of his urine are necessary to begin the collection. Having collected his urine, they collect the urine from a number of other ordinary uncastrated bulls. The work of collecting the urine must be finished some time before sunset. When it is so finished, one of the priests performs the paragnâ ceremony in the Uzerin Gah, i.e., in the afternoon-period of the day. Then the Vendidad ceremony is performed at midnight, commencing at a little after 12 o'clock. The vessel containing the urine of the sacred white bull and of other uncastrated bulls is placed between the Alat-gah, i.e., the slab of stone on which the sacred utensils for the performance of the ceremony are placed, and the censer of fire. Another vessel containing pure well-water is placed by the side of this vessel. The priests then recite the Vendidad, the recital of which together with the accompanying ritual lasts for about 7 hours. This final ceremony consecrates the urine which is then known as nirangdin, i.e., the consecrated urine. The water consecrated with it is known as âv, i.e., the consecrated water.

Consecration of the Sacred Bull and his hair.

In many eastern nations, the bull was held to be an emblem of Life, of Vital Energy. The Egyptians had their Apis. The Hindus have their Nandi. In Christian art, St. Luke is symbolized by an ox, and it is said that this symbolization has some connection with the reference to the ox in Ezekiel (I. 10) and Revelation (IV, 6). The white bull used by the Parsees under the name Varçyô (i.e., the possessor of Varas, or hair which is used in the ritual) reminds us a little of the Apis of the Egyptians. Apis represented the moon. "He was supposed to have been born of a virgin cow rendered pregnant by a moon-beam or a flash of lightning." When he died he "received a splendid burial As universal joy pervaded on his discovery, so his death threw all Egypt into general mourning, and everyone shaved off his beard."

[244]

The Parsees have such white bulls in their principal towns. They are held useful for two purposes. One is, as described above, for their urine, which, together with that of other ordinary bulls, was consecrated. The second purpose is the use of their *varêsa*, i.e., hair which is used in the Yasna liturgy to serve as a kind of hair-sieve. This use is referred to in the Visparad (Karda 10:2: varasâi Haomô angharezânâi, i.e., the hair to pass, as through a sieve, the Haoma-juice). This bull is not used for any domestic purpose. On its death, all the liturgical services, wherein his varêsa or hair is used, are stopped in the town or towns. Another white bull is immediately sought out and consecrated. Until it is consecrated, all the necessary Vendidad, Yasna, and Visparad ceremonies in which its hair is used cease to be performed in the town, and are directed to be performed in other towns, which have their separate white bulls. This is something like the above. mentioned” general mourning” on the death of Apis in Egypt.

The Ritual of the consecration of a White Bull.

The consecration of the Sacred White Bull consists in having its hair carefully cut with religious ritual and then performing the Yasna ceremony with it. All big Parsee centres generally keep such a bull in reserve. On the death of the one in use, the second spare one is brought to an adjoining Fire-temple and washed and cleaned. He is kept within a ‘pâvi.’ Two barashnomwala priests who have bathed previously and put on new suits of clothes, perform the pâdyâb, say their morning prayers, perform the Khub ceremony of *pânc̄h tâi* (i.e., of the five twigs of the Barsom). They then take seven metallic cups, a golden or silver ring, a pair of scissors, and a pair of long metallic tongs, and carefully wash and purify them with pure, clean water. The two priests then go before the bull. One of them holds his tail aloft with the help of the tongs and the other cleans and purifies it with pure water from a pot in his hand. He recites *Khshnaothra Ahurahe-Mazdao* and one Ashem Vohu, while doing this. He repeats this process three times. Then, facing the south, he cuts off with the scissors, referred to above, two hairs from the tail of the bull and ties them on the [245] metallic ring. He does this while reciting the Baj ceremony with three Ashem Vohus and Fravarane up to Vidhvaô Mraotu; with the Khshnuman of Ahura Mazda. It is while uttering the word Ashem and two Ahunwars, that he ties the two hairs on the ring. Then he finishes the Baj. The priests then go to the place where the Yasna ceremony is performed, and with the recital of various short prayers and with some ritual, consecrate the above ring with the hair, holding it before the fire, rubbing it with the bhasam or the

consecrated ash of the Sacred Fire of the Atash Bahram, and then washing it by dipping it, several times, is the above-referred to metallic cups which are full of pure, clean water. Then, with this newly obtained varesa, or hair, they perform the *Gevrâ*⁷¹ ceremony for six days. On finishing the ceremony on the sixth day, the two priests go before the bull again and washing and purifying his tail as before, take a fresh and a larger quantity of hair. This is distributed among the different temples within the jurisdiction of their temple for being used with the rings in their Yasna and Vendidad ceremonies. This completes the ceremony of the consecration of the bull and of his hair. The liturgical ceremonies, the performance of which was suspended, are now resumed with the symbolic use of the hair of the new bull. [246]

1 *Vide* above, p. 202, the Nawar ceremony.

PART V. THE LITURGICAL CEREMONIES.

CHAPTER XII. THE INNER LITURGICAL CEREMONIES. (I) THE YASNA: ITS LITURGICAL APPARATUS.

The liturgical ceremonies may be divided under two heads :-

I.-The Inner Liturgical Services.

II.-The Outer Liturgical Services.

The “Inner and Outer Liturgical Services.”

By the inner liturgical services,¹ I mean those religious services which can only be performed in a separate place specially allotted for the purpose. Such a place is known as the Dar-i-Mihr² and is generally connected with a fire-temple. Again, such ceremonies can only be performed by the priests who observe the barashnom.³ These ceremonies are generally spoken of as the *pâv mahal* (پاو مهيل) ceremonies, i.e., the ceremonies of the holy or consecrated house. The priests capable of performing these ceremonies are spoken of as Yaozdâthragar Mobads, i.e., priests who are purifiers.

By the outer liturgical services, I mean those religious services which may be, but need not necessarily be, performed in a Dar-i-Mihr or a place specially allotted for the purpose. They can also be performed in any ordinary or private house or place. Again, they may be performed by any priest, even by one who does not observe the barashnom or by one who has only gone through the Nawar and not the Martab initiation.⁴

Under the heading of the inner or *pâv mahal* liturgical services, fall the following ceremonies:

I.- Yasna or Yazashna.

II.- The Visparad. [247]

III.- The Vendidad.

1 In my account of the details of these ceremonies, besides my knowledge of what I have practised and observed, I have drawn information and particulars from other sources and especially from the Tamâm Khordeh Avesta of Mr. Dadabhoy Akhbari-Saudagarwala and the Yasna bâ Nirang of the late Ervad Tehmuras Dinshaw Anklesaria.

2 Vide below, p. 261.

3 Vide above, barashnom Chap, V.

4 Vide above Initiation, Chap. VIII, p. 207.

IV.- The Baj.

The Dar-i Mihr, or the place for performing the inner liturgical service

I will first describe here what a Dar-i-Mihr, where only the inner liturgical ceremonies can be performed, or the, place for is. A fire-temple is, as the word signifies, a temple or a sacred place for the preservation of the sacred fire. These temples have generally a place or a set of apartments attached to them where the above-said inner liturgical ceremonies are performed. These places are known as the Dar-i-Mihr. Though, strictly speaking, these places or portions attached to the temples for the performance of these ceremonies form the Dar-i-Mihr proper, generally the whole religious building, including the chamber of the sacred fire, is called the Dar-i-Mihr. All the fire-temples need not necessarily have these Dar-i-Mihrs or the apartments for the performance of the inner liturgical services attached to them. For example, the Atash Behram, or the Great Fire-temple at Naosari, has not the Dar-i-Mihr attached to it. There, the Dar-i-Mihr is in a separate building. But generally, almost always, the fire-temple and the Dar-e Mihr are in one and the same building and so, they are spoken of by both names. The building is spoken of generally as the Atash Bahram or the Atash Adaran, according as it contains the fire of the first or the second grade. If it is a building containing the fire of the second grade, it is spoken of both as Atash Adaran or Dar-e Mihr. A Dar-e Mihr always contains the sacred fire of the third grade, *viz.*, Atash Dadgah, burning in it. A fire-temple or a Dar-e Mihr is, at times, also spoken of as an Agiary, *i.e.*, the place of *Āg*, Agni or fire.

The name Dar-e Mihr is made up of *Dar* (Avesta *dvāra*, Sans. *dvāra*, German *Thür* or *Thor*, English door) and *Mihr* which is the later form of Avesta Mithra. So it means “the door¹ or the porch of Mithra.” Mithra or Mihr (or Meher) occupies a [248] prominent place in Zoroastrian angelology.² He is the Yazata [Yazad] or the angel

1 The word “dar” or “door” is used here in more than its ordinary physical sense. It is rather used in the allegorical sense in which it is used in John 10:9, where we read: “I am the door: by me if any man enter in, he shall be saved, and shall go in and out, and find pasture.” The word “dar” is used in later Persian, also for “Chapter.” For example, the religious book *Sad-dar* derives its name from its having 100 (*sad*) chapters. Another equivalent of the word “dar” is also “bâb” (meaning both door and chapter). Hence, the word “bâb” has also received an allegorical religious signification. Hence it is, that Bâb, the founder of the Bâbi religion in Persia, has derived his name. The word “Chapter” which, as said above, is another signification of the word “dar” has received a religious signification among the Christians also.

2 For an account of the attributes of Mithra and for a comparison of some of his attributes with those of St. Michael, *Vide* my papers on “Mithra of the Parsees and St. Michael of the Christians” in the Journal of the Anthropological Society of

presiding over light and justice, and as light is the symbol of truth and justice, and, as such, the symbol of divinity, the place where all the higher religious liturgical services in honour of God are performed, has come to be specially called Dar-e Mihr, i.e., the house of Divine light and justice.

Just as a church, an abbey or a cathedral, at times, contains several chapels where different priests conduct their services, so a Dar-e Mihr has several divisions, where different sets of priests conduct their services. In the Yazashna, Vendidad, and Visparad ceremonies, it is always necessary to have two priests to officiate. These different parts or divisions of the Dar-e Mihr, where different pairs of priests perform their ceremonies, are known as (a) Yazashna-gah, or (b) Urviç gah, or (c) Hindholâ.

(a) By Yazashna-gah is meant the place (Pers. *gâh*) where the Yazashna ceremony is performed.

(b) Urviçgâh (the place of Urviç) is another synonym of Yazashna-gâh. The *Dadestan-i Denig* (48:13)¹ speaks of the Yazashna-gâ as the Aûvés. The meaning of the word *urviç* is not certain. Darmesteter says: "Uryaêsa signifie proprement 'tour'² (urvaêsa vardashna: Dastur Hoshangji and Haug's *Old Zand-Pahlavi Glossary*, p. 23, 1. 9)." According to Darmesteter, the word means a place where they turn (le lieu où l'on tourne). The word can be derived from "vars" hair, [249] i.e., the place where the "vars" or the hair of the *varasya* or sacred bull is used in the ceremonial. We know that in Persian, the word *urviç* (ارويش or ارويس) means a hair-rope. West thinks that the word "is probably to be traced to the Avesta 'urvaesa' (𐬰𐬀𐬭𐬀𐬎𐬎𐬀) goal."³ The word occurs in the Frawardin Yasht (Yt13.58) in the sense of 'limit.' Darmesteter translates the word *dura-urvaesa* there, as "far-evolving circle." In the Vishtasp Yasht (Yt24.29), the word is used in connection with the running of a horse in a circle ("as an excellent horse turns back from the wrong way (*hacha urvaesat*) and goes along the right way (*fratarem urvaesem*) (smiting the many Drujs." Darmesteter. S. B. E. XXIII p. 335). So, West seems to be right. Urviç is the circle or the limits within which the celebrants have to remain. At times, the stone slab on which the ceremonial utensils are arranged is also called *Aurves* (Dadistan-i-Dini, 48:14).

Bombay, Vol. VI, pp. 237-1S3. Vide my Anthropological Papers (Part I), pp. 173-190.

1 S. B. E., XVIII, p. 163.

2 *Le Zend-Avesta* I, p. LXII, n. 2.

3 S. B. E., Vol. XVIII, p. 163, n. 4.

(c) The word Hindhorâ or Hindholâ is another name of the Yazashna-gah. It seems to be a form of the Sanskrit *Hindhola*, i.e., a swing. The priests while reciting their prayers generally assume a swinging posture. So, perhaps it has received its name from the swinging posture of the celebrants. The stone platform on which all the ceremonial utensils and requisites are placed is also known as a *hindholâ*. Perhaps the word *hindholâ* may be a corruption of the Avesta word *arâthru* which is used in the Nirangestan¹ for the seat of the zoti. The Pahlavi rendering of that word there is *udgâh*. The word *arâthru* when written in Pahlavi may be read *hanatrâ* from which the word may have been corrupted to *hindhorâ*.

The different Yazashna-gahs are separated from each other by a *pavi*,² which serves both as the limit of each and also as the passage for the water used in the ceremonial. If somebody enters within the limit marked by the *pavi* while the service is [250] going on, he vitiates the ceremony. If there are two Yazashna-gahs side by side, they are separated by a narrow strip of space enclosed between two *pavis*. The Yazashna-gahs are so constructed as to permit the Zaoti or the principal officiating priest to face the south.

Characteristics of a priest qualified to perform the liturgical ceremonies.

A priest, who performs the inner liturgical ceremonies of the Yasna, the Visperad, and the Vendidad, is spoken of, at times, as *Yaôz dâthragar*, i.e. "one qualified to give or spread purity. According to the later Pahlavi and Persian writings, he must possess the following 15 characteristics (Vide *Darab Hormmazdyar's Revayet. Yasna ba Nirang* by Tehmuras D. Anklesaria, Introduction, p. 25):—

- (1) Aiwîza hîm, i.e., of pure nature or unblemished.
- (2) Âsnideh Kherad, i.e., possessed of innate wisdom.
- (3) Din-aspanârgân, i.e., firm in his belief in religion.
- (4) Yazdân-mînîdâr, i.e., One who often thinks of God.
- (5) Minô-vînashna, i.e., One who looks into spiritual things.
- (6) Pâk-minashna, i.e., one of pure thoughts.
- (7) Râst-gavashna, i.e., one who speaks the truth.
- (8) Kheradi-kunashna, i.e., one who acts with wisdom.
- (9) Yaozdâthra tan, i.e., one with a clean body.
- (10) Shîvâ-hizvân, i.e., sweet-tongued.

1 The photo-zinco text, folio 156-b, l. 11. Darmesteter's *Zend Avesta*, III, p. 130.

2 Vide Chapter on Purification Ceremonies, p. 115.

- (11) Narm-nask, i.e., a slow or careful reader of the sacred books.
 (12) Râst-avestâ, i.e., one who recites the Avesta properly.
 (13) Pâdyav sâzashna, i.e., one who does all work with padyab, i.e., after observing the forms of purification.
 (14) Khub-nirang, i.e., one who knows well the religious formulas.
 (15) Nâbar-ziwan, i.e., one who leads his life like a Nawar, i.e., observes during his life all the forms [251] required to be observed during initiation into priesthood.

I will now proceed to describe the liturgical service of the Yasna.

Yasna or Yazashna

The word Yasna, of which Yazashna is another and a later form, comes from the Avesta root *yaz*, Sanskrit *yaj*, meaning "to invoke, to worship, to praise." The word is the same as Sanskrit *yajna* or *yagna* meaning "a sacrifice." Thus, it is a prayer which includes the praise of God and his spiritual Intelligences which invokes their aid. It is a long prayer which is accompanied with certain ritual and in which certain things are presented as symbols. Its celebration requires the recital of the 72 chapters, known as the *Hâs'* of the Yasna. Two priests are required for its celebration. They are, for the time being, spoken of as the Zaoti and the Raspi or Atravakhshi. They must, at first, have a bath and put on a clean suit of clothes. They must clean their nails, so that there may be no impurities in them. They must have a clean mouth, so that there lurk no particles of any food between their teeth.

The Yasna is celebrated in two parts:—

- I.—The Paragnâ.
 II.—The Yasna proper.

I. THE PARAGNA.

The word *paragnâ* comes from *para* (Avesta *para*) before or and Sanskrit *yagna* (Avesta *Yasna*), and mean, "the recital or the ritual that comes before or precedes the Yasna proper." Some think, that the word is a corruption of *paragra*, which is the corrupted form of *prakriyâ*, i.e., (the *kriyâ* or ceremony) preceding (*pra*) the ceremony proper. [252]

This Paragna ceremony consists of the following ceremonies:—

- (1) The Barsom ceremony.

1 The word *Hâ* is the Avesta word *hâiti*, meaning chapter or section, and comes from the root *hâ*, to cut. The 72 fine threads which go to make up the *Kusti* or the sacred thread are said to symbolise the 72 *hâs* or chapters of the Yasna.

- (2) The Aiwyaonghan ceremony.
- (3) The Urvaram ceremony.
- (4) The Jivam ceremony.
- (5) The Zaothra or Jor ceremony.
- (6) The Haoma ceremony.

We will describe these different rituals of the Paragna of the Yasna ceremony under the different heads of the religious requisites of the Yasna ceremony which bear their names. For the performance of the Yasna, the Visparad and the Vendidad ceremonies, certain requisites, both organic and inorganic, are necessary. We find a part of the list of these in the third chapter of the Yasna itself. Some of these requisites are mentioned in the recital of the paragna prayer which contains portions of the 24th and the 4th chapters of the Yasna. We give below a complete list of the apparatus required. We will describe these things, and, while doing so, describe the ceremonies bearing the names of, and connected with, these things.

The liturgical apparatus or the requisites in the Yasashna-gah.

The following are required in a Yazashna-gah for the performance of the Yasna, the Visperad, and the Vendidad ceremonies. Some of these are required for the Baj ceremony also:—

(A) Khwân [Khwān] or Stone slabs.

(B) Metallic requisites, known as Astama (Astâmâ) or Alat (Âlâ) i.e., metallic utensils or instruments. They are generally of brass, and, at times, of silver. Among these are:—

(a) and (b) Havanim and Lala (Hâvanim and Lâla), i.e., mortar and pestle.

(c) Tashta, i.e., chalice or plates and cups.

(d) Mahrui (Mârui), i.e., crescent-shaped stands.

(e) Barsom, vegetable twigs or metallic wires [253]

(f) Varas ni viti, i.e., a ring entwined with hair (of the sacred bull).

(g) Kaplo (Kâplo), i.e., a knife.

(h) The Kundi and other vessels for water.

(C) Organic requisites. Among these are:—

(a) Aiwyaonghana (Aiwyaônghana), the leaf of a date-palm.

(b) Urvaram (Urvârâm). the twig of a pomegranate tree.

- (c) Jivam (Jivâm), the fresh milk of a goat.
- (d) Dron (Darun, Darûn), the sacred bread.
- (e) Goshudo (Goshûdô), the clarified butter.
- (f) Haoma, the twigs of the Haoma plant.

(D) Zaotra or Zor (Zôr), the consecrated water.

(E) Fire and its requisites. Under this head come:—

(a) Fire.

(b) Afrinagan (Afarganiun, Afargâniun), a vase to hold the fire, with its accompaniments, the laddle and the tongs.

(c) Aesma-boy (Aêsma-bûi), i.e., the fragrant fuel.

Of all these requisites the principal that are often referred to as appertaining to a *Zaotar*¹ or sacrificer are the Aesma, Barsom, the Jivam, and the Havanim (Aesmo-zasto, Baresmo-zasto, Gao-zasto, Havano-zast. Vendidad, III, 1; Yasna Yasht X Meher 91). A priest in the midst of the ritual is spoken of as one holding these in his hands (*Zasta*).

The ritual of making the requisites *pav* (*pâv*) or pure.

[Consecration of the ritual implements.]

In all inner liturgical services, it is enjoined, that the utensils before being used, must be made *pav*, i.e., ceremoniously purified. The following is the process adopted for this purification:—

Pure clean water is fetched from a well in utensils previously cleaned and washed. Well-water only is used; water drawn from pipes is not permitted. For this purpose, all temples are provided with a well. A priest observing the *khub* goes to a well with the utensils previously cleaned and washed and draws [254] the water himself. Water drawn for the first and second time is rejected. It is the water that is drawn for the third time that is considered to be sufficiently pure for the ceremony. He carries this water to the chamber or place where the liturgical ceremonies are performed, and, with it, makes *pav*, the utensils to be used in the liturgical service. The utensils are filled up to the brim with water and then the priest utters the following formula and pours additional water so as to let it overflow the brim. He first says "*Khshnaothra Ahurahe Mazdao*, i.e. (I do this) for the pleasure of God," and then recites one *Ashem Vohu*. He recites

1 For the function of the Zaotar and eight other functionaries of his class, *vide* the *Nirangistan* Bk. II, Ch. XXVII. For the Holy Ministers of the Church, their powers, qualifications, instruction, initiation, their triple quinary and octonary orders, &c., *vide Nirangistan* by Mr. S. J. Bulsara. Introduction, pp. 29, *et. seq.*


this formula three times, and, at each recital, pours further water so as to let it flow over the brim. In the interval of each formula, he recites in Baj, or mutters with a suppressed tone, the following words: — *Yaozdâthra Zareh Frâkand*, *Yaozdâthra Zareh Varkash*, *Yaozdâthra Zareh Pûiti*, i.e., with the purity of the seas, Frakand, Vouru Kasha and Puiti. The first two are the two names, Pahlavi and Avesta, of the Caspian Sea. The third is supposed to be the sea of Aral. With these three, the holy waters of the heavenly prototype of the river Ardisura, supposed to be the Oxus, is also remembered (*harvasp mînô Ardisura âw-i pâk Yaozdâthra*). What is meant by this recital and purification seems to be this: The celebrant names the principal sources of water in ancient Iran and symbolizes by the ceremony the fact of the purifying process of water in the whole nature. All things required to be ceremoniously purified for ritualistic purposes are made pure in this way. A priest makes his hands also clean or pure in this way. Now, I will proceed to describe all the above requisites.

(A) Khwan (Khwân) or stone slabs.

The Khwan is a stone slab used in the Yazashna-gah. Over it are spread all the utensils required in the liturgical services of the Yazashna, the Visperad, and the Vendidad. The word is the same as the modern Persian *khwân* (خوان), meaning a table. It is so called because it is a slab standing on four feet in the form of a table. It is cut out of ordinary stone or marble. Altogether six stone slabs are used in the Yazashna-gah. Of [255] these four are large and two small ones. Of the four large ones, three are square and one round. They are—

- (a) Alât no khwân, i.e., the table or slab for the instruments.
- (b) Atash no khwân, i.e., the slab for the fire.
- (c) Kundi no khwân, i.e., the slab for the water vessel.
- (d) Zoti no zaota's khwân, i.e., the slab for the Zaota priest to sit upon.
- (e) and (f) Âesam boy no khwân, i.e., the slab for the fuel.

The positions of the slabs in the Yazashna-gah are shown below:—



(a) Alât-no Khwân or the âlât-gah.

The Alât Khwân is the Khwân proper, because it serves as a table (Khwân) on which the priest spreads all the sacrificial plates, cups and other instruments, the Dron (Darun) or sacred bread, the Jivam (Jivâm) or the fresh milk, the *urvarâm* or the pomegranate twig, Haoma, etc. It is called Alât-gah, i.e., the place over which all the necessary sacred instruments (alat) are placed. It is also called *Âlât no takhtô*. The word *takhtê* in Persian has the same meaning as Khwân, i.e., a board or table. Hence, the word means “the table for the (religious) instruments.” It is also known as Urviç.¹ [256]

All the liturgical instruments and other requisites are arranged on the slab as shown below:

¹ Vide, [above, p. 263](#).

South

The cup to hold spare Haoma juice with a saucer over it.

The *tashta* for dron, i.e. the saucer to hold the sacred bread and *goshudo*.

Hâvanim lâla, i.e. the mortar and pestle for pounding the Haoma twigs.

Cup to hold Haoma twigs for a time.

The Haoma and *urvarâm tashta*, i.e., the plate containing the haoma and pomegranate twigs.

East

The two mah-ruis, i.e. the crescent-shaped stands with the barsom standing upon them.

Jivâm nô tashtô, i.e. the saucer for the fresh milk.

The kaplo or the knife.

The cup containing the *varas ni viti*, i.e. the ring with the hair.

West

The cup containing the holy zaothra or *zor* water.

The Haoma cup.

North

[257]

Before all the above plates, cups and other requisites are placed over it, the *Khwân* requires to be made *pâv*, i.e., cleaned and purified. The officiating priest takes his seat upon his stone-slab and then, making a water-pot and the *Kundi*, *pâv*, makes his two hands *pâv*, and then taking some *pâv* water from the vessel (*Kundi*), recites the *Khshnaothra* formula six times and pours from a saucer the *pâv* water over the *Khwân* before him six times. During the first three recitals, he pours the water, so as to let it fall from north to south, and then, during the second three recitals, from west to east. These six pourings of water over the *Khwân* makes it *pâv*.

Starêta or carpet, the Alat-gah of ancient times.

It seems that the use of stone-slabs as the *alât-gâh* or the place for religious utensils, though old, is comparatively recent, because it does not seem to have been referred to in the Avesta. In the Avesta (Visperad XI, 2), we find the word *starêta* referred to, as one of the requisites for the performance of the liturgical ceremonies. This word *starêta* (from *star*, Sanskrit *star*, Lat., *stru-ere*, to strew, spread) means a thing spread, i.e., a kind of matting. So, it seems, that in very old times, all the sacrificial requisites were spread on a matting or carpet. Herodotus (Bk. I, 132) seems to support this view, when he says about the sacrificial offering that the priest "strew under it a bed of tender grass, generally trefoil."

(b) The Adosht or the Khwan of Fire.

The stone-slab for fire is placed opposite the first *Khvân* or the Alat-gah at a distance of about five feet. It is the slab upon which the Aferganiun [=Afrinagan]¹ or the censer containing the ceremonial fire stands. It is about 20 to 24 inches square and about 12 to 16 inches high. It is generally known as *Atash no Khwan* (*Âtash no Khvân*), i.e., the slab for the fire. In the Dâdestan-i Denig (Chap. XLVIII, 15),² it is called *Âtashto*, i.e., the place for the fire to stand upon [*Âtash*, fire, and *stâ*, to stand]. This word *Âtashto* has latterly [258] become *Âdusht*. It is also spoken of as *Atash-gah* (*Âtash-gâh*), i.e., the place of fire. When the Haoma Yasht (Yasna IX, 1) speaks of purifying the fire all round (*âtarem pairi-yaozdathentem*), it refers to the washing or purifying of this stone slab as is done in the modern ritual. The Pahlavi of this chapter makes it clear (*amatash âtâsh gâs kâmîstâ khalêlunastan*. *J. R. A. S.* July 1900, p. 517. "The first preparers of the Haoma" by Dr. Mills.)

(c) The Khwan for the Kundi.

The third stone-slab is a small and round one. It is about 18 inches high and 15 inches in diameter. It stands on the right of the first *Khwan* or the Alat-gah. It is called *Kundi no Khwan*, i.e., the slab for the Kundi, because the *Kundi*, or the vessel containing pure water and all the utensils when they are not used, stands over it.

(d) Zoti's Khân

This is a stone-slab, sufficiently large for the Zaota or the officiating priest who recites the whole of the Yasna, to sit upon. It is spread over with a carpet. It simply serves as a seat and has no sanctity attached to it. The Raspi, or the Atarvakhshi, i.e., the priest who looks after the fire opposite, has a carpet or a stool to sit upon. It is also spoken of as *Zôd-gâh*, i.e., the place or seat of the Zoti (Zaotar).

(e) and (f). The two Khwans for the Aesam boy.


The fire in the Yazashna-gah, besides being fed ordinarily, is fed with pieces of sandalwood and frankincense at particular parts of the ritual, with the recital of particular words in the prayers. For this purpose, a few pieces of the fuel are set apart on two small slabs of stone during particular parts of the recital.


(B) The Metallic requisites, the Alât or Astâma.

I will now describe the metallic utensils, which are known as the

1 The censer is so called, because *Afrins* or benedictions, etc., are generally recited before it when fire is burning on it.

2 S. B. E. Vol, XVIII, p, 164.

Âlât (plural of the Persian word *Âlat*, meaning utensil, instrument, or apparatus). The technical word used by the priests for these utensils or apparatus is *Astama* (Astâmâ). The word seems to be the corruption of *staômya*, and means the apparatus used in singing the praise (*staômi*) of God [259] and His Divine Intelligences. Perhaps it is the Pahlavi  *astâmeḥ* (Pahl. Vend. XIV, 7), which is the Pahl.

rendering of Av. *garêmo skarana* and is taken by some to represent the fire-vase (*afergânyun*. Dastur Jamaspji's Pahl. Vend. Translation, p. 133). According to Dastur Hoshangji (Pahl. Vend. p. 400, n. 7) a Pers. gloss gives for it . So, perhaps the *astâmeḥ* or fire-censer, being the principal alat or instrument required in the ceremonial, all others are mentioned under that name. Just as the first word of prayers gave their names to the whole prayers (*e.g.* *Yatha ahu vairyo* or *Pater Noster*), so the most important and essential instrument or requisite gave its name to the whole set.

(a) and (b) The Hâvanîm and the Lâlâ (mortar and pestle).

As the principal ceremony in the Yasna liturgy is the preparation and celebration of the Haoma, Hâvanîm, the mortar in which the twigs of the plant are pounded, and the pestle, with which they are pounded, form an important part of the liturgical apparatus. Hâvanîm is a kind of metallic mortar. It is the Hâvana of the 14th chapter of the Vendidad (XIV, 8) which gives a list of the religious instruments of a priest. The word comes from the Avesta root *hu* (Sanskrit *su*) to pound. Thus, it means an instrument in which the Haoma plant is pounded. It is spoken of as *dâityô-kêrêta* (Vend. XIV, 8) i.e. properly prepared. This refers to its proper preparation, so that it may give a proper metallic ringing sound when struck by the lâlâ or dasta, i.e., pestle. It appears from the Avesta, that it was made either of stone (*asmana hâvana*, Vend. XIV, 10) or of iron (Yasna., XXII, 2: Visparad, X,2). It is the metallic Hâvanîm that is now used in the ritual.

The Lâlô or the pestle is the instrument with which the Haoma twigs are pounded in the Hâvanîm. It is also the instrument with which the Hâvanâna, i.e. the priest performing the Haoma ceremony, strikes the Hâvanîm and produces a ringing metallic sound. The word seems to be the Persian (لاله) *lâla*, i.e., a tulip. It is so called from its resemblance to the stem of the tulip flower. It is also called *dasta*, i.e., a handle, from [260] the fact of its being held in the hand to pound the Haoma in the Hâvanîm.

(c) Tashta.

The word *tashta* is the Avesta (Vend., XIX, 8,) *tashta* (Fr. tasse,

Germ. tasse, Eng. dish). It is a chalice, plate, or cup used in the ceremonial. The fourteenth *fargard* of the *Vendidad* and its Pahlavi commentary refer to some of these *tashtas*. There are two kinds of *tashta*: One is that known as *rakâbi* which is a Persian word (رکابی) for a plate. The other is that known as *fuliun* and is probably so called from Sanskrit *fûl*, i.e., flower, because it is hollower than the *rakâbi* or plate and looks like a full-blown flower.

The *tashta* or plates used in the ritual are five in number. One is known as *Hom nô tashtô* (*tashta* Haomya: *Vendidad*, XIV, 8), i.e., the plate for holding the Haoma. The second is known as *Jivâm nô tashtô*, i.e., the plate for holding the *Jivâm*, i.e., the fresh milk. It is the *gaoidhya* of the *Vendidad* (Chap. XIV, 8). It is spoken of in Pahlavi books as *Gosh-dân*, i.e., the utensil containing kine-products. The third is known as *surâkhdâr tashto*, i.e., the plate with holes (Pers. *surâkh*, a hole). It is the plate through which the Haoma juice is made to pass down into a cup as through a sieve. It is the *Raêthwishbajina* (i.e., purifier of the drujs) of the *Avesta* (*Vend.*, XIX, 8). The fourth is the plate that holds the *dron* (*Draôna*) or the sacred bread. The fifth is one for covering the cup holding some extra Haoma juice prepared by pounding the Haoma.

The *fuliâns* or the second kind of cups are also five in number. One of these is for holding the Haoma juice after pounding the Haoma plant with the *urvarâm*. It is the Haomya of the *Avesta* (*Visparad*, XI, 2). The second is that for holding the *zaothra* or *zor* water. It is the *Zashta zaotrô-barana* (i.e., the chalice which carries or holds the *zaothra*) of the *Avesta* (*Visparad*, X, 2).

The third is for holding the *varas* ring. The fourth is for holding some extra quantity of the Haoma juice. The fifth is an extra one placed near the *Mahrui* for extra purposes.

(d) *Mâh-ruî* [=mah-ruî].

The *Mah-ruî* (*lit.* moon-faced) are two metallic stands about nine inches in height. They are so called because they have a moon-faced or crescent-shaped [261] top. They are always used in pair, one placed in front of the other. They are also called *Barsom-dân*, because the *Barsom* twigs are placed upon them. They are the ceremonial instruments referred to as *Mâh-ruyô* in the *Dadistan-i Denig* (Chap. XLVII, 14).¹ There, the *Aurvis*, or the stone slab of the *Yazashna-gah* is spoken of as the proper place for the *mah-ruî*. They must always be metallic (*shatvarin*).²

1 S. B. E., Vol. XVIII, p. 163.

2 *Ibid.*, p. 165. *Dadestan*, Chap. XLVIII, 17.

*mah-rui***(e) The Barsom.**

The barsom (or barsam) forms an important part of the liturgical apparatus. In the modern ritual, the old vegetable barsom has been replaced by metallic barsom. As it is referred to by a classical writer like Strabo, and in the Old Testament, and as its ceremony has been referred to by Firdousi and others, I will speak of it at some length. The word barsom is the Avesta word baresman. It comes from the Avesta root *barez*, Sanskrit *barh*, to grow. The twigs of a particular tree used in liturgical ceremonies are spoken of as the barsom. Later books say that the twigs may be of the pomegranate tree or of the tree known as the *chini*. But the Avesta itself does not specialize any particular tree. It speaks generally, that the barsom must be of a tree (Yasna 25:3; urvarâm baresmanim). The *Shayest Ne-Shayest* (14:2),¹ though it does not particularize the tree, says that only twigs of the proper tree must be used. But, now-a-days, instead of the twigs of any tree, metallic wires are used. They are generally of brass, but at times of silver. They are about nine inches long and one-eighth of an inch in diameter. Each of such wires is called a *tâê* (Pers. *tâi*, i.e., a thin thread). The practice of using metallic wires seems to have come into force within these last 1,000 years, because the *Dadestan* refers to

¹ S. B. E., Vol. V, p. 370.

vegetable twigs.¹

The number of twigs required differ in different services. The *Shayest Ne-Shayest* (14:2)² enjoins, that neither more [262] nor less than the requisite number should be used. The celebration of the Yasna requires 23 twigs of which 21 form a bundle. One twig is placed on the foot of the mah-rui, i.e., the moon-faced or the crescent-like stand which is otherwise known as the *Barsamdân*. This twig is called *zor-nô tâe*, i.e., the twig of the saucer containing the *zor* or *zaothra* water. The other, i.e., the twenty-third twig is placed on the saucer containing the *živâm*, i.e., the mixture of water and milk. The celebration of the Vendidad requires 35 twigs, of which 33 form a bundle and the other two are used as above. The celebration of the Visperad requires 35 twigs, that of the Yazeshna of Rapithwin 15, and that of the Baj 5. In the case of the ceremony of Nawar, i.e., the initiation into priesthood, the recital of the *Mino-Navar baj* requires seven twigs. The Sraosh Yasht (Yasna 57:5) speaks of the use of three, five, seven, and nine twigs by Sraosha. The greatest length of each of the twigs is spoken of here as that of the height of a knee, i.e., about two feet. According to the *Nirangistan*, the minimum number be used in the ritual is three, the minimum thickness of each twig to be equal to that of a hair, the maximum length to be one *aesha* and the maximum breadth one *yava*. The Vendidad (19:19) also gives the length of one *aesha* and the breadth of one *yava*. Darmesteter³ takes “aêsha” to be the length of a ploughshare and the “yava” to be the breadth of a barley-corn. According to English measures, three barley-corns make one inch.

In the ritual, the barsom twigs or wires are placed on the above-mentioned two crescent-shaped metallic stands made generally of brass or at times of silver, of which the *Shayest Ne-Shayest* (3:32; 10:35)⁴ speaks as *Barsamdân*, i.e., the holder of the barsom. We will see later on, that the barsom is the symbol of God’s vegetable creation. As said above, the very etymology of the word suggests growth. The moon and its crescent (Lat. *crescere*, to grow, increase) give an idea of growth. [263] Again, the moon is believed to have some influence on the growth of vegetation.⁵ So, barsom, the symbol of the vegetable

1 Dadistan-e Denig, XLVIII, 17. Vide S. B. E., Vol XVIII, p. 165, n.3.

2 S. B. E., Vol. V, p. 370. For some varying numbers, vide the Nirangestan Bk. III, Ch. VII. Appendix A. (Mr. Bulsara’s Translation, pp. 434. *et seq.*)

3 *Le Zend Avesta* II, p. 265.

4 S. B. E., Vol. V, pp. 284, 333.

5 Vide my paper on “The Ancient Iranian Belief and Folklore about the moon, etc”. (Journal of the Anthropological Society of Bombay, Vol. XI. pp. 14-39. Vide my Anthropological Papers, Part II, p. 302, *et seq.*)

world of God has, for its stand, moon-shaped metallic stands.

The second chapter of the Yasna shows that the barsom was considered to be an essential requisite in the liturgical service of the Yasna. This chapter is called the Barsom Yasht. The Vendidad (14:8) speaks of it as one of the requisites of an Athornan, i.e., a Fire-priest performing liturgical services. Being such an essential requisite, the very tree whose twigs serve as barsom is an object of praise (Yasna 25:3). All the religious rites of the inner liturgical service of the Zoroastrians are celebrated with barsom (Zand-i Vohuman Yasht 2:57-58).¹

According to the *Nirangistan*, the barsom ceremony existed in the time of Zoroaster, whose contemporary, Jamasp, is said to have celebrated it in a particular way (Fragments, 6. *Nirangistan*, Fargard III, 89).² In many passages of the Avesta, Niyayeshes, and Yashts, it is always associated with the Haoma and Jivam ceremonies (Haomayo gava baresma). So, as the Haoma ceremony³ is very ancient, it follows that the barsom ceremony also is as ancient as that. The Zand-i Vohuman Yasht (3:29, 37)⁴ speaks of it as celebrated by Peshotan, a contemporary of Zoroaster.⁵ [264]

1 S. B. E., Vol. V, pp. 212.

2 Darmesteter, *Le Zend Avesta*, III, p. 136. *Vide* the *Nirangistan* (B. II, Chap. V, Appendix A) by Mr. S. J. Bulsara. His Introduction may be read with advantage to have a brief view of what is said in the *Nirangistan* about the barsom and about other articles of the *alat* (*Airpatastân and Nirangistan* by Sohrab Jamshedji Bulsara. Introd. p. XLIII-VII.)

3 *Vide* below, p. 300.

4 S.B.E., Vol. V, pp. 227, 229.

5 It is this ceremony that Ezekiel refers to when he says: Then he said unto me, Hast thou seen this, O son of man? Is it a light thing the house of Judah that they commit the abominations which they commit here? for they have filled the land with violence, and have returned to provoke me to anger and lo they put the branch to their nose. Ezekiel 8:16-17). The Parsee priests even now hold the twigs up to their face. Hence it is that Ezekiel speaks of the branch as being held to the nose.

Strabo also refers to this ceremony. He says: They (the Persians) then lay the flesh in order upon myrtle or laurel branches; the Magi touch it with slender twigs and make incantations, pouring oil mixed with milk and honey, not into the fire, nor into the water, but upon the earth. They continue their incantations for a long time, holding in the hand a bundle of slender myrtle rods. (Strabo, Bk. XV, chap. III, 14. Hamilton and Falconers Translation (1857), III, pp. 136-137.)

The Flamines or the Fire-priests of the ancient Romans also carried bunches of such twigs in their hands in their ritual. Dino, a contemporary of Philip, is said to have referred to the barsom, though not as a sacrificial instrument but as an instrument of divination (Darmesteter *Le Zend Avesta*, III, p. LXIX). The *Denkard* (Bk. 8, chap. 19:83, chap. 20:12) seems to refer to this use of the barsom when it speaks of its being used as an ordeal (Baresmok-varih) in judicial matters (S. B. E., Vol. XXXVII, pp. 48, 55).

The barsom used in the recital of grace before meals.

The Parsees have three forms of prayers to be recited as grace before meals. One of these, which is the longest and in which certain chapters of the Yasna are recited, is used by priests on certain occasions when they officiate in continued inner liturgical services. In the recital of this form of grace barsom is a necessary requisite. But, it seems, that in ancient times, barsom was a requisite in even the simple forms of grace recited before meals. The reciter held barsom in his hand during these recitals. It was so in Sasanian times. We learn from Firdausi, that Yazdegird, the last Sasanian king, when he concealed himself during his flight in the house of a miller, asked for the barsom to say his grace before the meals. This led to the discovery of the place of his hiding and he was treacherously killed by his general Mahui Suri. Again, we find, that in the reign of Khosro Parviz (Chosroes II), this custom of using the barsom in the recital of grace before meals was on the point of leading to a war between Persia and Rome.¹ [265]

Its similarity to a Hindu ceremony.

The barsom is "identified with the *Barhis* or sacred grass (Kusha grass) of the Brahmans, which they spread at their sacrifices as a seat for the gods who are expected to come."² Dr. Haug differs from this identification, and says that it resembles "a peculiar rite at the great Soma sacrifices. At the time of the Soma libation (called *Savana*) which is to be performed three times on the same day, from 8 to 12 a.m. (morning libation), 1 to 5 p.m. (mid-day libation) and 6 to 11 p.m. (evening libation), the three Sâmaveda priests, the Udgâtâ, the Prastotâ, and the Pratihartâ, require a certain number of wooden sticks to be placed in a certain order when chanting the sacred *sâmas* (verses of the Sâmaveda.) They use for this purpose the wood of the Udumbara tree, and call them *Kusha*, which name is generally given to the sacred grass. the Agnishtama, 15 such sticks are required at the morning libation, 17 at noon, and 21 in the evening; in other

1 Rehatzek thus describes the incident: "On another occasion, the Persian monarch gave a banquet and had tables arranged for that purpose, in a rose garden. He had put on the royal diadem, and Nyâtus (the Roman ambassador) with the philosophers sat around the table Bandvy, one of his (Khosru's) favourite magnates with the Barsom (or little twigs held by Mobeds when praying) in his hand arrived and stood near his sovereign, who muttered the Baj (i.e., the prayer of grace) When Nyâtus beheld this scene, he laid aside his bread, and was so annoyed that he left the table, saying that the Baj and the Cross together were an insult to the Messiah." (Journal of the B. B. R. A. Society, Vol. XIII, p. 88, note.) Firdausi refers to this subject at some length (vide *Le Livre des Rois* par M. Motl, Vol. VII, p. 183).

2 Haug's Essays, second edition, p. 283. Vide Journal B. B. R. A. Society, Vol. XIV. pp. 5-15.

sacrifices, such as the Aptoryâma, even a much larger number of such sticks is required.”¹ The very fact, that the barsom is not spread on the ground but is enjoined to be held up in the hand — left hand according to the Vendidad. (XIX, 19) — as referred to in Ezekiel and by Strabo, and as practised at present, seems to show that its identification with the *barhis* of the Hindus is not correct and that Haug’s identification seems to be more probable. Again, as we have seen above, as a symbol of vegetable creation, it is connected with the moon which helps growth of vegetation. So, its identification with a rite of the Saoma sacrifice seems to be correct, because Saoma has some connection with the moon. [266]

The object of the barsom ceremony.

It appears from the Vendidad (19:18, 19), that the object of performing the barsom ceremony seems to be the payment of homage to the vegetable creation of God. There, in reply to the question of Zoroaster, as to with what kind of praise or ritual (Yasna) he should worship or laud the creation of God, Ahura Mazda replies, that he should go before a flourishing growing tree, utter the words, “Praise be to thee, the good pure tree created by Ahura Mazda (*nemô urvairê vanghuhi*, etc.)”! and then cut the barsom out of the tree. This passage not only shows, that the barsom represents the vegetable creation of God, but also that the barsom ritual is intended as a means of celebrating the praise of God for the creation of the world, especially the vegetable world. The Vishtasp Yasht (Yasht 24:21-23) also gives a similar interpretation.

In the ritual, the holy water (the *zaothra* or *jôr* water) is poured over the Barsom. Now, this *zaothra* or purified water represents, or is the symbol of, rain through which the world receives the gift of water from God. Thus, the ritual of pouring this sacred water, which is the symbol of the drops of rain, upon barsom, which is the symbol of vegetable creation, signifies the celebration, or the worshipful commemoration of the process of the whole vegetable world being fertilized by rain. Prof. Darmesteter expresses this point very pithily and briefly in the following words:

“Le symbolisme de ces opérations est transparent: Le Baresman représente la nature végétale, le *zohr* (i.e. the sacred water) représente les eaux: on met le *zohr* en contact idéal avec le Baresman pour pénétrer toute la flore des vertus de l’eau et féconder la terre.”²

The celebrant is enjoined to look continuously to the barsom

1 Haug, *ibid.*, p. 283.

2 *Le Zend Avesta*, I, p. 397.

during the ceremony and to concentrate his mind upon it (Vend. 19:19), because, by looking upon what represents, or is the symbol of, the vegetable creation, he conceives in his mind the whole of the creation. The object aimed at by the ritual is not gained if the celebrant or worshipper is immoral and vicious [267] (Mihr Yasht, Yt. 10:138). In the case of a righteous person (*ashavan*), even one single sincere performance of the barsom ceremony is sufficient to exalt him and to put down the evil influences of the wicked (Fragments Tehmuras, XXIV, 40-41).¹ According to the *Menog-i Khrad* (57:28),² the celebration of this ceremony which symbolized the act of praising God for his creation, broke the power of the demons or of the evil influences. The *Denkard* (Bk. VIII, Chap. 26:24)³ says, that the celebration of the praise of God with this ceremonial on a day of battle, helps the soldiers a good deal; it is something like throwing a well-aimed arrow. Firdausi refers to its use in the ritual in the Fire-temples in the time of Behrangour (Behram V).⁴

Preparation of the Barsom (a) gathering it and (b) tying it.

The *Denkard* (Bk. VIII, Chap. 29:16),⁵ referring to the Husparum Nask, says, that one of the sections of the Nirangistan refers to the "gathering and tying the sacred twigs (barsom)." In modern practice, the ceremony of the preparation of the barsom for liturgical purposes consists of only one part. But, at one time, it consisted of two parts:— (a) The first part, *viz.*, the gathering or the collection of the twigs now-a-days is different from the old method, because, instead of vegetable twigs, metallic twigs are used now. (b) The second part, *viz.*, that of tying the twigs or wires is performed even now. I will describe both the old ritual of gathering the twigs and the modern ritual of tying them.

(a) According to the old practice, a priest who had performed the Khub ceremony — either the small or the large Khub — performed the ceremony of preparing the barsom. He fetched pure water from a well and with it made a water-pot *pâv*, i.e., pure. With this pure water, collected in a ceremoniously [268] purified utensil, he went before the tree whose twigs were to be used in the ritual as the symbol of the vegetable creation, and washed, with his right hand, the twig which he wanted to cut. Then, holding a knife (*kaplo*) in the right hand and the

1 Darmesteter, *Le Zend Avesta*, III, p. 61.

2 S. B. E., Vol. XXIV, p. 103.

3 S. B. E., Vol. XXXVII, p. 89.

4 M. Mohl, *Le Livre des Rois*, Vol. VI, p. 65.

5 S. B. E., Vol. XXXVII, p. 96. *Vide* also Chapters. XIII-XVI, pp. 469-77 of the *Nirangistan* translated by Mr. S. J. Bulsara.

utensil of *pâv* water in the left, he took the Baj with the *Khshnuman* for *urvara* or trees, recited a formula of prayer, wherein the bountiful vegetable creation of God was praised (*frasastayaecha urvarao vanghuyao mazdadhatayao ashaonyao*) and cut off the twig he required for the ritual. He cut off the twig with the recital of an Ashem Vohu. With the word "Ashem," he cut off and rejected the partly dried tip or the end. With the word Vohu, he touched the stem and with the word Vahisstem, he cut it off. At the end of the recital, he thus paid his homage to the good vegetable creation of God, as enjoined in the *Vendidad* (Chapter 19:18): "Homage to thee, O good holy tree, created by God! (*Nemo urvaire vanguhi Mazdadhate ashaone*). With the cutting of each twig the above ritual is repeated. He then retires to the Yazashna-gah. In the modern practice, a priest with the Khub makes the metallic wire *pâv*, i.e., pure, together with all the metallic utensils required for the Yazashne ceremony. The *Shayest Ne-Shayest* (14:2)¹ enjoins that they all must be made *pâv*. He then holds the requisite number of wires, all but one, in his left hand. Then, holding the remaining one in his right hand, with the usual recital of three Ashem Vohus and Fravarane, takes the Baj with the *Khshnuman* of Khshathra-vairyra or Shahrewar Ameshaspand who presides over metal. In the old practice, the *Khshnuman* was that for trees because the twigs used were those of a tree. Then, during the recital of the Ashem Vohu of the Baj, touching both the ends of the bundle of wires in his left hand with the *zaothra* or *zor* wire (so called because it is to be placed on the *zaothra* water cup) in his right hand, he finishes the Baj. While finishing the Baj during the recital of the *Yasnemcha* formula, with the mention of the name of Khshathra-vairyra who presides over metals, he touches again both the ends of the bundle of the barsom wires in his left hand with the *zor* wire in his right hand. [269]

(b) Having prepared the barsom the next process is that of tying the wires into a bundle. A strip of the leaf of a date-palm known as *aiwyaonghana*² is used for the purpose. The priest takes the Baj with the *Khshnuman* of *Ahurahe Mazdao*. During the recital of this Baj, while uttering the words *Ahurahe Mazdao* (i.e. God), *raevato* (i.e., the Brilliant) and *Kharenanghato* (i.e., the Glorious), the priest, holding the barsom on the *aiwyaonghana* which lies over the crescent of the Mah-rui, ties the barsom with the strip of the leaf of the date-palm. He then dips four times the bundle of wires and the strip of the leaf in the water of the Kundi or the vessel on his right hand side. While doing this, he recites four Ashem Vohus. He then recites two Ahunwars. During the recital of the first, he puts on two

1 S. B. E, Vol. V., p. 370.

2 *Vide* below, the ceremony of preparing the strip of leaf for the Aiwyaonbana, p. 291.

knots over the bundle of the wire. During the recital of the second, cuts off and polishes with a knife the ends of the strip of the leaf of the date-palm. The knife used in the recital for the purpose (the *ashtra* of Vendidad 14:8), known at present as the Kaplo, is spoken of at times as the Barsom-chin. The tying process being completed, the priest finishes the Baj.

(f) Varas ni viti i.e., the ring with the hair of the sacred bull.

The hair (vars, varç)¹ of a sacred white bull, entwined round a ring, is a necessary requisite. The number of hairs used is three, five, or seven. The vars or the hair of a sacred white bull particularly kept for the purpose is used only as long as that bull is living. On the death of that bull, his vars or hair are rejected and that of a new bull, which in its turn is consecrated, are used. The ring with the hair is purified before being used in the ritual. This purification of the hair-ring takes place every time that it is used, i.e., at each performance of the Haoma ceremony. The ring with the vars or hair lies on the stone-slab before the priest in a small metallic cup. Before preparing the *Zaothra* water, the officiating priest makes the ring *pav* or purifies it. He takes one wire of the barsom in his right hand and places his left hand with the wire on two small metallic *Zaothra* cups which are placed in an inverted position on [270] the stone-slab. Then holding the vars ring in his right hand he dips it in the *Kundi* on his right. He then utters in Baj or in a suppressed tone, the 101 names of God. This recital of the 101² names is repeated ten times. This dipping of the ring with the recital of God's names purifies the ring for ritualistic purpose.

When used in the Haoma ritual after the above purification, the ring is used with a Baj prayer, known as *Varaç ni Bâj*, i.e., the Baj for the use of Varas. The priest, who has to prepare the Haoma juice, holds in his left hand the barsom wire, known as the *Zor* wire (*Zôr nô tâi*) and in his right hand the hair-ring. Then holding both the hands together before his face, he takes the Baj with the Khshnuman of the Fravashi or Farohar of Zarathushtra Spitama, and then finally reciting an Ashem Vohu prayer dips it in the cup containing the *Zor* water. The ring thus consecrated is then used in the subsequent ceremony of straining the Haoma juice.

In the ritual of preparing all the other requisites, the Baj with the Khshnuman referring to the particular requisite is recited. For example, (a) In the case of having the vegetable barsom twigs, the Khshnuman referring to trees (*urvarayao vanghuya*

1 *Vide* above p. 256 *Varaçyô* in the Consecration Ceremonies.

2 For these 101 names of God, *vide Darab Hormzdyar's Revayet*; by Ervad M. R. Unvala. *Yasna bâ Nirang* by Ervad Tehmuras D. Anklesaria, pp. 24-26.

mazdadhatayao ashaonyao, i.e., the good holy trees created by Mazda) is enjoined to be recited. (b) In the case of tying the metallic twigs of the barsom, the Khshnuman relating to metal (*Khshathrahe vairyehe ayokhshustahe*, i.e., the Ameshaspand Shahrewar presiding over the metals) is recited. (c) In the case of Jivam or the milk of the bovine creation, the Khshnuman referring to the cow (*geush tashne geush urune*, i.e., the bovine creation, the soul of the bovine creation) is recited. (d) In the case of the preparation of the *Zaothra* or *Zor* water, the Khshnuman relating to water (*aiwyo vaughubyo vispanamcha apam mazdadhatanam*, i.e., good waters, all the good waters created by Mazda.) is recited. (e) In the case of the ritual of purifying the Haoma twigs, the Khshnuman referring to Haoma (*Haomahe ashavazangho*, i.e., Haoma giving the strength of piety) is recited. But in the case of the *varas*, i.e., the hair, [271] the Khshnuman recited refers to the holy spirit of Zoroaster (*Zarathushtrahe Spitamahe ashaono Fravashēe*, i.e., the holy Fravashi of Spitama Zarathushtra). The reason does not seem to be clear, but it is traditionally said, that in the early days of the foundation of the ritual in Zoroaster's times, the hair of the horse of Zoroaster were used as the *varas* (*vide* the Rivayats).

The haired ring, when placed in the perforated chalice (*surâkhdâr tashta*) and used in the Haoma service, seems to serve, as it were, as a strainer for the Haoma juice. This *varas* or hair is spoken of in the Avesta (Visperad 10:2) as Varesa Haoma *angharezân*, i.e., the Varas or hair for straining the Haoma juice.

Ashtra or Kaplo, i.e. a knife.

A knife with a metallic handle is another requisite. It is the 'ashtra' of the Vendidad (14:8). It is now called *kaplo* [kâplô], because it is used for the purpose of cutting (*kapvûn*) the *aiwyaonghana* or the leaf of the date-tree, and the *urvaram* or the root or twigs of the pomegranate tree. It is also used in cutting and smoothening the ends of the *aiwyaonghana* which fastens the twigs of the barsom. It is also spoken of as the barsom-chin, i.e., the instrument for picking and collecting the barsom twigs.

(h)The *kundi* and other water vessels.

As all the utensils and other requisites require purification, a quantity of water is always required in the Yazashna-gah. The first important vessel water for containing this is known as the *kundi* (Sanskrit *kund*, a basin or bowl), i.e., the water basin. It is a large metallic basin about 15 inches in diameter and 12 inches in depth. All the sacred utensils are, before being spread on the *khwan* or stone-slab, collected in this *kundi*. Instead of making each and every one of

the utensils severally *pâv* or purified, they are all placed at first in the *kundi*, which is then made *pâv*. The process of making the *kundi pâv* makes all the utensils contained in it also *pâv*.

The other utensils used in the Yazashna-gah are two or three water-pots known as *karasyâ* or *kâhrnâ*. They do not form part of the *alat* or the sacred utensils properly so called, but they form a part of the necessary requisites. The *karasyâ* is a [272] small water-pot. The word seems to have come from Persian *karsân* (کرسان), an earthen or wooden vessel. Two of these are generally used in the Yazashna-gah. They hold the water used for making the several requisites *pâv*. The other water-pot is known as *kâhârnoo*. It is a large water-pot. It seems to have been so called from the word *kâhrvun*, i.e., to draw (water), because it is generally used for drawing water from the well.

As a quantity of water is used in the Yazashna-gah for purification purposes, an outlet for the water is provided by the *pavis*.¹ The *pavis* serve, both, as limits or marks within which certain ceremonies must be performed and which must not be encroached upon by others, and as conduits for the waste-water to get out.

(c) The Organic Requisites.

We will now speak of the organic requisites. Though Haoma is the most important of these requisites and though the ceremony of pounding and preparing its juice forms an important part of the Yasna liturgy, we will first describe the other organic requisites, because they are required for the Haoma ceremony and their preparation and purification precede that of the Haoma.

(a) The *aiwyaonghana*, a leaf of the date-palm.

Aiwyaonghana is the strip of a leaf of the date-palm. The word comes from the Avesta *aiwi* (Sans. *abhi*, Gr. *epi*, round about) and *yaôngha*, (Sans. *yâç*) to put on, and means putting round about. The word literally means a bond or tie. The strip of a leaf of the date-palm used in the Yasna liturgy is called *aiwyaonghana* because it is put round the barsom to tie it.

The date-tree (the *aiwyaonghana*), a symbol among the ancient Iranians.

According to Pliny,² the ancient Iranian kings had a special date-palm growing in their gardens. It was known as the "royal" date-palm. It was a native of Babylonia. Syagri was a species of that date-palm.

1 *Vide* the word *pâvi* in the Purificatory Ceremonies, p. 115.

2 Bk. XIII, chap. 9. Bostock and Reiley's Translation, Vol. III, p. 174.

Pliny¹ says of this species, that no sooner did a tree die another [273] grew out of the old root. The story of the bird phoenix rising again from the ashes of its former self seems to have been taken from the story of this tree. The date-tree was for this reason held to be an emblem of immortality and of royalty among the ancient Iranians as among some other nations.² [274]

The ceremony of preparing the *Aiwoyaonghana*: Its signification.

As the date-palm is essential in the liturgical services, every Fire-

1 *Ibid.*

2 Among the ancient Chaldaians, the date-tree signified the tree of life. Its roots go far down below into the earth, and its top with its branches points high above towards the sky. So, it was considered as a proper symbol of the tree of life, signifying, that man has come from long unknown past and is advancing towards some unknown future. Its green branches symbolize the active element in our life and its trunk and root, the passive element. Among the ancient Assyrians, it was a symbol of fertility. Old Assyrian cylinders present pictures wherein a priest is represented as pointing to a date-tree. ("The Sacred Tree," by Mrs. Philpot, p. 88.)

The ancient Egyptians knew the date-palm by the name "Bai," and as it was an emblem of the immortality of the soul, the soul also was known as "Bai" or "Ba." Again, as the leafy part at the top pointed to the heavens, the date-palm symbolized the science of astronomy among the ancient Egyptians. The Egyptian Thoth, who was "the Deity who superintended the life of man," held in his hands a palm, each branch of which represented a year. ("Manners and Customs of the Ancient Egyptians," by Sir Gardiner Wilkinson, Vol. I, p. 256.) "Mercury, the Hermes of Egypt, was represented with a palm branch in his hand: and his priests at Hermopolis used to have them stuck in their sandals on the outside. The Goddess Isis was thus represented." (Bryant's *New System, or Analysis of Ancient Mythology*, (1807) Vol. II, pp. 3-4.)

Owing to its straight and majestic appearance, it was held among the ancients as an emblem of honour. So, it was presented to triumphant persons as a symbol of a prize. "The ancients always speak of it as a stately and noble tree. It was esteemed an emblem of honour; and made use of as a reward for victory. *Plurimarum palmarum homo* (i.e. a man like many palms) was a proverbial expression among the Romans for a soldier of merit. Pliny speaks of the various species of palms; and of the great repute in which they were held by the Babylonians. He says, that the noblest of them were styled the royal palms, and supposes that they were so called from their being set apart for the king's use. But they were very early an emblem of royalty" (*Ibid.* p. 3).

The ancient Hebrews also held the palm as a symbol of triumph and victory. They carried boughs of the palm in their hands in some of their festivals. At the celebration of the nuptial ceremonies, it was used as a symbol of joy and good luck. "It was thought to have an influence at the birth" (*Ibid.* p. 4.) According to Leviticus (Ch. 23:40), among the ancient Hebrews, in the Feast of the Tabernacle, the Israelites were enjoined "to take the boughs of goodly trees, branches of palm-trees . . . and rejoice before the Lord." According to Ezekiel (41:18-20), the palm played a prominent part in the places of angels and holy men. In the Temple, "a palm-tree was between a cherub and a cherub From the ground unto above the door were cherubims and palm-trees made, and on the wall of the temple." In later Hebrew coins it is found as a symbol of Judaea. The Blessed are represented

temple or Dar-i-Mihr has one or more date-trees growing in its compound. The officiating priest who has observed the Khub goes before the tree with a potful of water, made ceremoniously *pâ* or pure. He washes three times with that water the particular leaf which he wants, reciting the usual formula of *Khshnaothra*. Then, with a knife which is also previously washed clean, he cuts off, at first, the top or the end of the twig, and rejects it, lest it may be a little dried and damaged, and then, he cuts off the leaf. He then once more washes it with the *pav* water and then placing it in the water-pot, carries it to the Yazashna-gah. There, he divides the leaf into six thin strips, which being divided at first into two groups of three each, are then twisted into one string and knotted [275] at both the ends. It is then placed in a clean *pav* metallic cup and afterwards used for tying the barsom.

We said above, that the barsom represents the creation of God. The separate twigs or wires of the barsom represent that the creation

as standing before the throne of God "clothed with white robes and palms in their hands" (Revelation, 7:9). Being an emblem of royalty, when Christ entered Jerusalem, the people welcomed him with branches of palm-trees in their hands. They "took branches of palm trees, and went forth to meet him, and cried Hosanna; Blessed is the King of Israel that cometh in the name of the Lord" (John 12:13). On account of its straight growth, the Psalmist considered the palm to be a symbol of righteousness. He said: "The righteous shall flourish like the palm tree" (Psalm 92:12.) It rises and grows in spite of the great weight of its branches on its top or the head. Instead of being depressed by the weight of the branches, it thrives the more, the greater the number of branches. That fact symbolized the moral, that man must not be depressed under difficulties but try to rise to the occasion. (Bryant's Ancient Mythology, Vol. II, pp. 4-5.)

The palm was a classical symbol of Victory and Triumph. The Christians then assumed it as the universal symbol of martyrdom. In many a picture of the martyrs, an angel is represented as descending with the palm. "Hence it is figured in the tombs of the early martyrs and placed in the hands of those who suffered in the cause of truth, as expressing their final victory over the powers of sin and death." (*Sacred and Legendary Art*, by Mrs. Jameson, p. 31.) In the Greek Church it is held as the emblem of the Victory of Faith.

The date being their and their cattle's staple food and being a tree of which all the parts are utilized by them in one way or another, it is held by the Arabs in estimation and loved dearly, and they cultivate it and fructify it with religious fervour. Where Nature is not strong enough for the fructification of the palm, they at particular seasons cut off the male spathes and transfer the pollen to the female spathes. Bent thus describes the process: "It was just then the season at which the female spathe has to be fructified by the male pollen and we were interested in watching a man going round with an apron full of male spathes. With these he climbed the stem of the female palm and with a knife cut open the bark which encircles the female spathe. and as he shook the male pollen over it, he chanted in a low voice, "May God make you grow and be fruitful." (*Southern Arabia*, by Mr. and Mrs. Theodore Bent, London, 1900, p. 117). In the sandy part of Arabia, it is held as dear as a mother. There they say on the authority of their prophet Mahomed: "Honour the date tree, for she is your mother." ("Ibid p. 19). In the holy month of Ramzan, the day's fast is first broken by eating a date. So, the idea of one's duty is bound up with the date in their proverb, "At the same time a date and a duty." (Ibid, p. 20).

consists of various parts. The *aiwyaonghana* which binds or ties together the barsom signifies union or unity among these parts. It seems to signify that the whole Nature is one. We are one with it. We learn from the Pahlavi commentary of the Yasna¹ (Chap. 9:26) where *aiwyaonghana* is referred to, that the idea or the main object seems to be that of *ayokardgih*, i.e., of unification. The word *aiwyaonghana* is also used in the *Avesta* for the Kusti or the sacred thread. One of the interpretations about the Kusti is, that it unites into a circle of harmony all those who put it on. Similarly the *aiwyaonghana* or the strips of the leaf of the date-palm, when put round the separate twigs or wires of the barsom for the purpose of uniting them all into one bundle, signify the fact of the unity of the creation, the unity of Nature. On finishing the Yasna, while reciting the 72nd chapter, the *Zaota* puts on further knots over the barsom with the strips of the *aiwyaonghana* [276] signifying that the liturgical ceremony has led to or signified further unification.²

(b) The Urvaram. Its symbolism and the Ceremony of preparing it.

The word comes from Avesta *urvara*, (Sanskrit *urvarâ*, Latin *arbor*, Fr. *Arbre*) tree. Originally, it means a tree. Then it has been applied specially to a twig of the pomegranate tree used in the liturgical service. The *Dadestan-i Denig* (Ch. 48:16) specializes the pomegranate as the *urvaram* or as “the tree.” There, it is called *hadanapag* (Avesta *hadhânaêpata*), i.e., evergreen, from *hadhâ* = Sanskrit *sadâ*, i.e., “ever” and from *nip* or *nap*, to be green. “On a review of the whole evidence, botanical, literary and linguistic, Alphonse de Candolle (*Origine des Plantes Cultivées*) decides in favour of its source in Persia and the neighbouring countries.”³ . . . The fruit is frequently represented on ancient Assyrian and Egyptian sculptures, and had a religious significance in connexion with several oriental cults.”⁴ *Dâram*, the Parsee name of the pomegranate fruit, comes from the Sanskrit name of the fruit *dalim*, (दालिम) or *dadim* (दाडिम). It is the rimmon of the Bible.⁵ The plant known as *hadhanaepata* (or, as the word signifies, the evergreen) in the Avesta

1 Spiegel's *Pahlavi Yasna*, p. 76, sec. 81. Vide Mills' Pahlavi Text of Yasna 9:49-103 (Journal of the American Oriental Society, Vol. XXIII (1902), p. 11.

2 Prof. Darmesteter, while translating this chapter has committed the mistake to say that the priest here unties the knots (dénoue deux nœuds). On the contrary, he goes on putting on five more knots. (*Le Zend Avesta*, I, p. 438).

3 *Encyclopædia Britannica*, Vol. XIX, p. 442.

4 *Ibid.*

5 “Rimmon” is the Hebrewized form of Rammân, the Babylonian air, weather, and storm god assimilated by popular etymology to the word for pomegranate. (Dr. Hasting's *Dictionary of the Bible*).

and, at one time, considered to be a fragrant plant (Vend. 8:2), is considered to be the pomegranate tree. The pomegranate being an evergreen plant is considered to be an emblem of the immortality of the soul.¹ It is also held as a symbol of plenty and prosperity, from the fact that it contains [277] a number of grains within itself. For this purpose, when benedictions are recited upon a child during its investiture with the sacred shirt and thread, grains of pomegranate mixed with grains of rice and raisins, etc., are besprinkled over it. In the Afrinagan ceremony, where fruits and flowers are used as offerings, the pomegranate is often used. If other kinds of fruits are not available, a few grains of the pomegranate are supposed to serve the purpose. It is, as it were, taken as the representative of all kinds of fruit.² From all these considerations, we see that the pomegranate served variously as symbol: (1) It represented the vegetable creation and especially the fruit-growing trees. (2) It symbolized the immortality of the soul. (3) It symbolized the fecundity of nature. (4) It served as an emblem of plenty and prosperity.

The ceremony of preparing the *urvaram* twig is similar to that of preparing the *aiwyaonghana*. The priest who has observed the Khub goes with a pot of water made *pav* and with a knife before the pomegranate tree, washes and purifies with the *pav* water the particule twig which he wishes to have; and then, reciting three times the *Khshnaothra* formula, cuts it off. [278] He then washes the twig 80 cut and returning to the Yazashna-gah places it in a metallic cup. It is then used with the Haoma and Jivam in preparing the Haoma juice.

1 It took the same place among the ancient Iranians as the Acacia plant in the mythology of some other nations. Again, the pomegranate symbolized the "Ark" which was known as Damater or Demater (the mother) among the ancients and was looked as the "Mother of Mankind" or "The Womb of Nature." The Ark contained many seeds or rudiment. of men and other living creatures. The pomegranate also abounds with many seeds. So, "it was thought no improper emblem of the Ark, which contained the rudiments of the future world. From hence the Deity of the Ark was named Rhoia, which signified a pomegranate and was the Rhea of the Greeks. The ancient Persians used to have a pomegranate carved upon their walking-sticks and sceptres; undoubtedly on account of its being a sacred emblem." (Bryant, *Analysis of Ancient Mythology*, III, pp. 237-8). Here, Bryant attributes to the ancient Persians a desire to have a device on their sticks, just as Herodotus (Bk. I, Chap. 195) attributes a similar desire to the ancient Babylonians.

The pomegranate was held sacred in Syria and Egypt. In an ancient temple at Pelusium, the statue of a goddess carried this "mysterious fruit, in her hand" (Bryant III, p. 239). Pomegranates were "the universally accepted symbol of the female" (*Pagan and Christian creeds. Their Origin and Meaning*, by Edward Carpenter. p. 183). So, as such, they crowned the two pillars set up by Solomon in the front of his Temple—Jachin and Boaz—which pillars symbolized the male (*Ibid.*)

2 It is said that Hera was the goddess presiding over fruit among the Greeks. In her pictures at Argos, she is represented as holding the pomegranate in her hand, because that fruit was held to typify all kinds of fruit.

(c) The *jivam*. It preparation.

Just as every Dar-e Mihr must have a date-tree and a pomegranate tree, it must have a she-goat for the use of its milk in the liturgical service *Jivam* [jivâm] is the abbreviated form of *gâm jivyâm*¹ (lit. the living product of the cow), i.e., the fresh milk of the cow. Though the word *gâo* or *gao* (Sanskrit *gô*, German *kuh*, English *cow*) suggests that the milk must be that of the cow, the word includes the flock of goats and sheep, and the milk used in the ceremony is always that of the goat and not that of the cow. A milk-giving goat is fetched into the Yazashna-gah and generally made to stand with its face turned towards the east. A priest with the Khub goes before it with a pot of *pav* water and, reciting the *Khshnaothra* formula thrice, at first washes his own right hand and then the udder of the goat. He faces the south. He then takes the Baj with the Khshnuman of “*geush tashne, geush urune,*” i.e., of the 14th Yazata Gosh or Dravasp who presides over the bovine creation. Then, while reciting the *Ashem Vohu*, he begins to milk the goat. The first stream of milk is allowed to be dropped on the ground. Then reciting the word “*asha sara manangha,*” i.e., “with the mind uppermost in purity,” lets a stream of milk pass into a pot. Then while reciting another Ashem, lets a second stream drop on the earth. Then reciting the words “*asha sara vachangha,*” i.e., “with words uppermost in purity,” takes in a second stream in his pot. With the third Ashem, another stream is allowed to drop on the ground, and then, with the words “*asha sara shkyothna,*” i.e., “with deeds uppermost in purity,” takes in a third stream into the pot again. He then finishes the Baj. By the recital of the above words, he means to say, that the liturgical service he is going to perform is intended to be performed with a view to secure great purity of thought, word, and deed. Then, patting the goat on its back, he recites twice the words “*hazangrem baeshazanam, baezare baeshazanam,*” i.e., [279] “thousand-fold health, ten thousand-fold health.” These words are meant to signify that the milk of the bovine creation, drawn with all possible sanitary care when drunk by a person with purity of thought, word, and action gives a thousand-fold health to him. It is said, that formerly, at times, the milk of more than one she-goat or cow was drawn. The second person form of the recital, in which the she-goat or the cow was addressed varied, as *tava, yavâkem, and yûshmâkem* (اگر گار و گوسپند یک بید اگر دو بید اگر سه بید ایا گاه بید) i.e., according as the cow or goat was one or two or three or flock, i.e., more than three). *Vide* Westergaard’s text, fragment VI, p. 333).

1 Yasna 3:3.

(d) Dron [Darun]

Dron is the later form of the Avesta word *Draonangha* (*lit.* that which makes us strong, from *dru* to be strong). It is a flat unleavened round bread made of wheat flour and ghee or clarified butter. It is a necessary requisite for the celebration of the Yasna, the Visperad, the Vendidad, and the Baj ceremonies. For the Yasna, Visperad, and the Vendidad ceremonies one bread is required. For the Baj the number varies. For the Baj in honour of all the Yazatas, four breads are required. For the Baj of Sraosha six are required. Out of these four and six, half the number are what is technically named *nâm-pâdelâ*, i.e., named and the other half are *vagar-nâmnâ*, i.e., unnamed.

The naming and the unaming of the sacred breads is as follows: The sacred breads are required to be prepared by members — whether male or female — of the priestly class. While preparing them, the person mutters the words *humata*, *hukhta*, and *hvarshta* (i.e., good thoughts, good words, and good deeds) three times and while muttering them makes three marks at each recital. So during the three recitals he makes nine marks in the order as shown here:



The sacred breads thus prepared with the marks are said to be “named.” The others are said to be “without names.” [280] Those named or marked with the symbolic signs of “good thoughts, good words, and good deeds” are known as the *dron* proper. The others that are without name or are unmarked, are spoken of as the “*frasast*,” from the fact, that during the recital of one of the chapters of the Yasna in the Baj ceremony (Ha 8:1), while uttering the word “*Frasasty*,” i.e., praise, he lifts up the unnamed *dron*. In the third chapter of the Yasna, where most of the sacred requisites are named the sacred bread is not named specially as *Draôna*, but is referred to under the name of “*Kharathem myazdem*,” i.e., the offered eatable food.¹ The *Nirangestan* gives some detailed directions as to how the *dron* should be prepared (Bk. I, Chapter VIII, Appendix A, B. C. Mr. S. J. Bulsara’s Translation, pp. 86-104.) It is forbidden that the consecrated *drons* may be eaten by non-Zoroastrians.

1 The *dron* corresponds to the sacred bread of the Christians. When consecrated (technically said to be *injelo*, i.e., sanctified or consecrated), it corresponds to the consecrated bread of the Christians. (a) Like the “Host” of the Christians, it is required to be “round.” (b) Like the sacred bread of the Christians it must be prepared by one of the priestly class. (c) The “naming” of the *drons* corresponds to the mystic signs of the Cross over the “sacred bread” of the Christians. (d) Like the sacred bread, it must not be eaten by people of other religions.

The *chashni*, i.e., the partaking of the dron and the haoma by the priest.

Of all the requisites placed on the stone slab or table, two are what we may call edibles. They are the dron and the haoma. The eating and the drinking of these two is technically spoken of as *chashni*. The word comes from the root *chash*. (Persian *châshidan*) to taste, to eat, and literally means eating or tasting. The word is confined or limited to ceremonial eating or drinking. Again, it includes in itself the meaning not only of physical eating or tasting but also mental or spiritual eating. For example, we have the word *din-chashidar*, i.e., the taster of religion, which is applied to one versed in religious learning. The *Nirangistan* refers to at some length to the subject of this *chashni*.¹ (Bk. I. Chapter VIII, Appendix C. Mr. Balsara's Trans., p. 96.)

Of the above two, the dron and the haoma, the *chashni* or the ceremonial tasting of the dron or sacred bread takes [281] place first. As said above, the dron is prepared beforehand by a person of the priestly class, and is placed on the sacrificial table of the stone-slab. It is after the recital of the first eight chapters of the Yasna that the priest eats the sacred bread. In the first two chapters of the Yasna, the priest invokes God and the Divine Intelligences. The next six chapters are the chapters whose recital consecrates the sacred bread. They are known by the name of "Srosh dron," i.e., the chapters for the consecration of dron or the sacred bread in honour of Srosh. The 8th chapter is specially known by that name, because, it is while reciting this that the priest ceremoniously partakes of it. In the very commencement of the chapter the priest says: "I present with piety this appropriate food, water, vegetable, the product of the cow, haoma, para-haoma and the fruits." The food referred to here (*kharethem myazdem*) is the sacred bread. The other priest, the Raspi, then says to the assembled congregation: "Ye persons! who have been qualified by your righteousness and piety, partake of this consecrated food." By these words he means to say, that only the righteous have a right to partake in the religious feasts. The Zaota or the officiating priest then considering himself worthy of the privilege breaks a portion of the consecrated bread and partakes of it. Then the other celebrants may also partake of it if they like.

These chapters of the Yasna known as the chapters of the 'Srosh Dron' are also recited in the Baj ceremony. It is at the end of this ceremony that the assembled congregation makes the *chashni*, i.e., partakes of the consecrated bread. Prof. Darmesteter aptly calls this

1 *Le Zend Avesta*, Vol. I, p. 75.

8th chapter the “Communion.”¹

(e) Goshudo.

The word *goshudo* [gushûdo] is the Avesta *geush hudhâo* which literally means a product of the well-created cow. So, it may mean flesh as well as milk. But in the liturgical service of the Yasna, while *jivam* is the fresh milk, *goshudo* is the ghee or clarified butter which is a product of the milk of the cow. In the ritual, it always accompanies the dron or sacred bread. A small [282] quantity of it is placed over the dron and is eaten as *chashni* with the dron.

The Yasna of the Parsis and the Jyotishtoma of the Brahmins.

Before proceeding to consider the other requisites of the Yasna ceremony, I will quote here what Dr. Haug says about some similarity between the Yasna of the Parsis and the Jyotishtoma of the Brahmins, so that, what is said above about some of the requisites and what will be said now about Haoma and the other requisites, may be properly understood. Dr. Haug says:—

“The Yajishn or Ijashne ceremony, as performed by the Parsi priests now-a-days, contains all the elements which constitute the different parts (four or seven) of the *Jyotishtoma* cycle of sacrifices, the prototype of all the Soma sacrifices. The *Agnishtoma*, (i.e., praise of Agni, the fire), which is the opening sacrifice of this cycle and indispensable for every Agnihotri to gain the object wished for, viz., heaven, bears a particular resemblance to the performance of Ijashne. Of course, the whole ceremony is much shortened, and the rites changed in accordance with the more enlightened and humane spirit of the Zoroastrian religion. In the *Agnishtoma* four goats must be killed and their flesh is partly offered to the gods by throwing it into Agni, the fire, who is the mediator between gods and men, and partly eaten by the sacrificer and the priests. During the Ijashne ceremony no animal is killed; only some hair of an ox is placed in a small vessel and shown, together with other things, to the fire. This is now-a-days the only remnant of animal sacrifice on this occasion, but formerly they used a piece of meat besides. The *Purodâsha*. of the Brahmins, or the sacrificial cakes, which must be offered to different deities in a certain order, during the recital of two mantras for each deity, is changed into a flat kind of

1 *Le Zend Avesta*, Vol. I p. 75.

bread (similar to a very small pancake), called *dron*. The fresh milk required at the time of performing the Upasad ceremony, is to be recognised in the *geûsh jîvya*. Ghi, butter, etc., required for less important ceremonies at the time of the Agnishtoma (when making the so-called Prayajas for the six seasons) are represented by the [283] *geûsh hudâo*. The Zaothra or consecrated water is required at the commencement of the Brahmanical sacrifices also, where it is called *udaka shânta*.¹

(8) Haoma.

The last but not the least organic requisite of the liturgical apparatus of the Yasna ceremony is the haoma. The ceremony of preparing, pounding, and squeezing the haoma juice, which, when so prepared is spoken of as para-haoma, is an important function in the ritual. So we will speak of it at some length. The word haoma (Skr. *soma*, Pahl. and Pers. *hom*) comes from an old Aryan root *hu* — Skr. *su*, 'to pound' 'to squeeze.' *Hâvana*, the utensil in which the twigs of the Haoma plant are pounded, *hâvan*, the *gâh*, or the part of the day when this plant is pounded, and *hdvandna*, the priest who pounds it, — all these words come from the same root.

In the Avesta we meet with four Haomas:- (1) Haoma, whom for convenience sake we may call Haoma the prophet. Chapters 9, 10, and 11 of the Yasna speak of him as well as of the plant haoma discovered by him. Further allusions are found in Yasna 57 (19 and 20) and Yashts 10, (Mihr) 88-90 and 17, (Ashi) 5. (2) Haoma, the plant. Chapters 9, 10, and 11 of the Yasna especially speak of this Haoma, (3) Haoma, who may be called Haoma the hero (Y11:7; Yt. 9:17; Yt. 17:37, 38). (4) Haoma Khvarenangha (Yt. 13:116). In the Frawardin Yasht we have a long list of the departed worthies of ancient Iran who had rendered some service to the community. The group in which Haoma Khvarenangha is mentioned seems to be a list of the names of some of the immediate successors of Zoroaster. It appears, therefore, that this Haoma Khvarenangha, whose fravashi is invoked, was a great man of Iran, who had done some good deeds that commemorated his name.

These four different Haomas have one or more special names In the Avesta. Haoma the prophet is called Haoma Duraosha. The plant haoma is spoken of as *haoma zairi* (e.g. Ys. 9:17, 30 32). Haoma the hero is known as *Haoma Frâshmi* in the [284] Yashts. The fourth Haoma, as we have said above, is named Haoma Khvarenangha.

Haoma the prophet is called *frâshmi* as well as *duraosha* The

1 Haug, Martin, E. W. West, and E. P. Evans. *Essays on the Sacred Language, Writings and Religion of the Parsees*, second ed.: London, 1884, p. 281.

Haoma *Frâshmi* of the Gosh and Ashi Yashts is quite different from the Haoma *Frâshmi* of the Yasna and of Yashts 10 and 11. The reason, why these two Haomas, who lived at different times — one in the time of the Peshdgdian dynasty, and the other in that of the Kayanian — are called *Frâshmi*, seems to be that they both belonged to the same family stock.

Just as Haoma the prophet had, besides his special designation of Duraosha, that of *Frashmi*, so Haoma, the plant, had, besides the special appellation of *zairi*, also that of *dûraosha* and *frâshmi* (Y10:21; Y42:5). It was called *zairi*, on account of its yellow or gold-like colour. The other appellations were due to the fact of its being discovered by Haoma Duraosha, who was also known as Haoma Frashmi.

Haoma the prophet

It appears from the Avesta, that there lived in ancient Iran a pious man named Haoma. He belonged to the early times of the Peshadadian dynasty, before the time of Vivanghant (Vivasvat of the Vedas), the father of Yima (Yama of the Vedas). He was a very learned man (*vaêdhyâ-paiti*)¹ versed in the old religious literature. He had passed a good deal of his time in divine meditation on the Hukairya peak of the lonely mountains of the Alburz.² Before Zoroaster, he was the first man or prophet to proclaim to the world the Mazdayasnian religion.³ As Zoroaster had his own religious compositions, so had Haoma.⁴ He had his Gathas⁵ (*imâosê tê haoma gâthâo*), and had as an opponent one Keresani.⁶ It was this Haoma who gave his name to the plant, which he seems to have discovered, and to the Haoma ceremony, which he is said to have introduced. According to Yasht 10,⁷ he was the first man who produced the juice in the mortar (*hâvana*) on the Alburz mountain. It appears, that, while absorbed in deep [285] divine meditation in his retreat in the mountains, he discovered this plant growing on the heights, and found it to be nutritious. health-giving, and invigorating. He introduced it to the world as such; but, in order to make it doubly efficacious, he instituted a form of ritual, designed to absorb the mind of the people

1 Yasna 9:27.

2 Yasna 9:26. Yt. 10:88; Y57:19

3 Y9:26.

4 Yt. 17:5.

5 Y10:18.

6 Ibid, 9:24.

7 Yt. 10.90.

in holy and religious thoughts. A plant, in itself health-giving and vigorous, when partaken of under a partial inspiration of divine thoughts, was likely to be beneficial to the mind as well as to the body.

The haoma plant.

Haoma is a medicinal plant which grows in Persia and Afghanistan. It is a species of Ephedra (Nat. Ord. *Gnetaceæ*¹). Mountains and mountain-valleys are mentioned as places where the plant grows luxuriantly. In some passages, Mount Alburz (called in the Avesta. Hara Berezaiti) is specially mentioned as its habitat. But it must be borne in mind that the name Alburz not only denoted the present Mount Elburs, a peak of the Caucasus, but was applied to the whole range of mountains extending from the Hindu Kush in the East to the Caucasus [286] in the West. The haoma is described as a plant with branches and sprigs,² as possessing medicinal properties, and as golden-coloured.³

-
- 1 Dr. Aitchinson, who accompanied the English Afghan Boundary Commission of 1885 as a Naturalist, and to whom I had sent for identification and inquiry in Afghanistan a few twigs of the Haoma plant used by the Indian Parsis in their ritual, with an account of the plant as given in the Avesta, said in his reply:— “The specimens you sent me are the twigs of a species Ephedra (Nat. order *Gnetaceæ*). A species grows all over this country — Beluchistan, Afghanistan, Kashmir, and Western Thibet — which seems to be identical with the species received. This species is here, in all this country, called *hum* (pronounced as the English word *whom*, also *huma*). In Beluchistan, it as well as a totally distinct plant, *Periploca aphylla* is called *hum*. It grows equally on exposed hills and valleys consisting of ‘branches and sprigs,’ one mass of upright twigs, each twig, if you notice, being made up of joints like the joints of the fingers. When covered with male flowers, the bush (from 1 to 2 feet) is golden coloured, and the twigs are more or less so.... This plant has no leaves. It is all twigs and jointed. Amongst the Pathans of the Khyber Pass and all over that country the twigs are with water made into a decoction and employed very largely as a household remedy in sickness, and are considered as possessing health-giving and healing properties. Owing to a general likeness between the stiff rod-like growth, upright and erect of the two plants, in Beluchisten, the natives equally give both the same name. No one would mistake the jointed and true *hum* for the non-jointed *falae hûm*, *Periploca*. The latter does not exist here at all. The Ephedra here is only employed to mix with snuff, being first of all burnt. The ashes cause the snuff to be more irritating, whether applied as a sternutatory or to the upper gum under the front part of the lip as is the habit here Before your letter and specimens came, I had made up my mind that the Ephedra was the nearest to the ‘Soma’ plant that I had got to, but as it was stated that the Parsis employed the twigs of *Periploca* it rather put me out. Your specimens are all on my side.”
- 2 The Avesta word for this is *frasperega*, in which *fra* is a prefix, and *sperega* is the same as English ‘sprig.’
- 3 The Avesta word is *zairi-gaona*, which some Orientalists take to mean “green-coloured.” But as green is the usual colour of vegetation, there was no apparent necessity to say so. The writer seems to mean ‘yellow’ or ‘gold-coloured,’ in which sense the word is also used elsewhere.

The religious or spiritual properties attributed to the haoma plant are described in a rich poetical style, and in a tone overflowing with heartfelt admiration and praise. Haoma, prepared and drunk in a state of pious, spiritual inspiration, is believed to give wisdom, courage, success, health, increase, and greatness.¹ In such a state, the devotee becomes as powerful as an independent monarch, and is able to withstand many dangers coming from ill-disposed persons.² Heaven, health, long life, power to contend against evils, victory against enemies, and fore-warnings against coming dangers from thieves, murderers, and plunderers, are the six gifts bestowed by haoma when adequately praised and prepared.³ Haoma is specially sought for by young maidens in search of good husbands, by married women desirous of being mothers, and by students striving after knowledge.⁴ It affords special protection against the jealous, the evil-minded, and the spiteful.⁵ It is a check upon the influence of women of loose character, who change their affections as frequently as the wind changes the direction of the clouds.⁶ For all these reasons, haoma is called *nmâna-paiti*, *vis-paiti*, *zantu-paiti*, *danghu-paiti*, i.e., 'Lord of the house, the village, the district, and the country.'⁷ [287]

The qualifications which are required of the man who would drink haoma with advantage are good thoughts, good words, good deeds, obedience to God, and righteousness.⁸ On the other hand, Haoma curses thus those who are sinful and evil-disposed: "I, Haoma, who, am holy and keeper away of death, am not a protector of the sinful."⁹ "May thou be childless, and may evil be spoken of thee."¹⁰

Antiquity of the Haoma ceremony.

It appears from the Avesta that the Haoma ceremony was in existence as early as the time of the Peshdadian dynasty. It is as old as the time when the ancestors of the Parsis and the Hindus, and even of the ancient Romans, dwelt together. It seems to have been always accompanied by the Barsom ceremony, as it is even at the present

1 Y. 10:17.

2 *Ibid.* 18.

3 *Ibid.* 19, 21.

4 *Ibid.* 22, 23.

5 *Ibid.* 28.

6 *Ibid.* 32.

7 *Ibid.* 27.

8 Y. 10:16.

9 Y. 11:3.

10 Y. 11:1.

day. Now, it appears that the ancient *flamines*, who were Roman fire-priests, and many of whose practices resembled those of the *athravans*, or Iranian fire-priests, used twigs of a particular tree, whenever they went before the sacred fire. This practice resembles that of the Parsi priests, who also, as said above, used twigs of a particular tree when performing the Yasna ceremony before the fire. The twigs are now replaced by metallic wires.

The plant used after purification.

We said above that the twigs of the plant are brought from Persia. They are not used directly in the ceremony. On being taken to a temple, or Dar-i Mihr, they are washed and purified, and then laid aside for a period of at least thirteen months. A qualified priest takes a quantity of these twigs, and washes and purifies them with water, reciting the formula *Khshnaothra Ahurahe Mazdao, Ashem Vohu*, etc., which means "Pleased be Ahura Mazda. Piety is the best good and happiness. Happiness to him who is pious for the best piety." After being thus purified with water, the twigs are kept in a metallic box, similarly washed and purified, for at least thirteen months and thirteen days before being used in the [288] ceremony. When so prepared and purified, they can be used several years afterwards.

The Vendidad (6:42, 43) enjoins the purification of those haoma twigs which have come into actual contact with filth and impurities; but the present custom, which is designed to make assurance doubly sure, demands the purification of all haoma twigs intended for use in religious ceremonies. Again, the Vendidad requires the twigs to be laid aside for one year; but the present custom prescribes a period of thirteen months and thirteen days.

Description of the Haoma ceremony.

This falls under four heads:— (1) the preliminary preparations; (2) the ceremony of purifying or consecrating the haoma twigs; (3) the ceremony of preparing and straining the haoma juice; (4) the ceremony of drinking the haoma juice.

(1) Preliminary preparations.

Two priests take part at this stage, as in the whole of the Yasna ceremony. One of them with the *khub* (i.e., ritual for qualification); either small or great, duly observed, first prepares the *aiwyaonghana* (strips of date palm), the *urvaram* (twigs of pomegranate tree), and the *jivam* (fresh goat's milk). All the *alat* (the necessary sacred utensils) are emptied, washed, and put into the *kundi* (the large water vessel on the stone slab). The fire is kindled in the censer or vase, and the *aêsma* (fragrant wood) and *boy* [*buî*] (frankincense) are placed on

the two adjoining small stones. Two water-pots — one small and the other large — are placed on the *khwan* or stone slab for the *alat*. The cup containing the *aiwyaonghana* and the *urvaram* is placed on a small stone by the side of the stone slab on which the priest sits. The haoma twigs are also ready by his side in a cup. The officiating priest (*zaota*) now takes his seat on the stone slab, which is covered with a carpet. He makes *pav* (ceremonially pure) the smaller of the two waterpots, and with the water of that pot makes the *kundi* containing all the utensils *pav*. He then prepares the *zaothra* water and ties the barsom wires. Having done all this, he next proceeds to make the haoma twigs *pav*. [289]

(2) The ritual of purifying the Haoma twigs.

The priest takes a few pieces of twigs of the haoma plant out of a cup, and, holding them between the fingers of his right hand, washes them thrice with the *pav* water. While doing so, he recites the *Khshnaothra* formula three times. He then commences the *baj* and the *khshnuman* of *Haoma ashavazangha*, wherein he says, that he does this for the homage, glory, pleasure, and praise of Haoma, the giver of the strength of purity. Then, reciting the *Ashem* four times, he dips both his hands, together with the twigs, in the *kundi* on his right hand. He dips them four times into the water — thrice in the direction pointing from his position to the opposite side (i.e., from north to south), and once in the opposite direction. Having thus made the twigs *pav*, he finishes the *baj*, and dips the purified twigs in the *zaothra* water. Then, drawing the *havana* before him, he inverts it and places on it three pieces of the consecrated haoma twig; the rest are placed over the foot of the *mah-rui* (the two crescent-like stands). He next places a piece of the *urvaram* by the side of the haoma twigs.

(3) The ceremony of (a) preparing and (b) straining the haoma juice.

(a) The priest begins by saying: “I invoke all the belongings (i.e., the requisites for the performance of the ceremony) of the haoma, for the sake of Ahura Mazda.” Then he enumerates some of the important requisites which lie before him on the stone slab. While reciting their names, he looks at them. The requisites which he enumerates are: haoma, *myazda*, (i.e., the *dron*, or sacred bread, which is spoken of as *kharethem myazdem*, ‘appropriate or sacred food’), the consecrated water (*zaothra*), the twigs (*barsom*), some product of the cow such as fresh milk (*goshudo* or *geush hudhao*), a twig of the pomegranate tree (*urvarâm hadhânâpatâm*), pure good water (*aiwyô vanguhibyô*), mortar for pounding the haoma (*havana*), fragrant wood (*aesma*) and frankincense (*baoidhi* or *boy* [*bui*]), and fire (*âthra*). The prayer, in

which he invokes or enumerates the requisites, and in which, while reciting their names, he looks at each of them as they lie before him on the stone slab, forms a part of the 24th chapter [290] of the Yasna. He recites the chapter from section 1 to section 12, omitting therefrom, in sections 1 and 6, the words, *imâmchâ-gâm jivyâm ashaya uzdâtâm* ('this *jivam*, or fresh milk, held up with righteousness'), because, at the time when he recites this prayer, the *jivam* is not yet placed on the stone slab. Sections 9 to 12 of this 24th chapter are the same as sections 4 to 7 of the fourth chapter.

The Haoma ceremony may be performed either in the *hawan gah* or in the *ushahin gah*, i.e., during the morning or the midnight hours. So, after reciting the first twelve sections of the 24th chapter, the priest recites the 13th section, if he prepares the haoma juice in the *hawan gah*, or the 17th section, if he prepares it in the *ushahin gah*. Having thus recited the *khshnuman* of the particular *gah*, during which the ceremony is performed, he recites the *khshnuman* formula of the particular day of the month and the particular month of the year on which he performs the ceremony. Then, he proceeds to recite the prayers contained in the fourth chapter of the Yasna from sections 17 to 25 up to the word *vahishtât*, omitting the portions which refer to *rathwô berezato* and *sraoshahê ashvehê* (in sections 22 and 23). Next, he recites the prayers contained in the 25th chapter of the Yasna, from sections 1 to 3, omitting the reference to *gâm jivyâm* (fresh milk) in section 1. On reciting the words, *Ameshâ spentâ* (chapter XXV, section 1 of Spiegel), the priest holds between the thumb and the forefinger of his left hand the twigs of the haoma and pomegranate plants which were on the foot of the inverted *havana* and, lifting the latter with his right hand, knocks it thrice in its inverted position on the stone slab, and places it in its proper position. Then, reciting the words *imem haomem*, etc., (*ibid.*, sec. 2, Spiegel), and taking the haoma twigs into the right hand from his left hand, he places them in the *havana*, or mortar. Next, reciting the words *imâmchâ ûrvarâm*, etc., (*ibid.* sec. 4), he similarly places the *urvaram*, or pomegranate twigs, in the mortar. Reciting the words *aiwyovanguhibyo*, etc., (*ibid.*, sec. 5 to 11, Spiegel), he pours into the mortar, with his right hand, a few drops of the *zaothra* water which [291] lies before him. He now invokes the Fravashi, or Guardian Spirit, of Zoroaster by reciting Yasna 26:11 (Spiegel). Then, reciting the words *iristanam urvâno* (*ibid.*, 35) and the *yenghe hatam* prayers, he takes out of the *kundi*, the *surâkhdâr tashta* (i.e., the plate with holes which serves as a strainer), and places it on the haoma cup at the foot of the *mah-rui*. Reciting *athâ ratush ashâtchît hachâ*, etc., he removes the *lâlâ*, or pestle, from the *kundi*, passing it round in a circle within the vessel, and touching its rim from within, The circle begins

from the north and passes in the direction of west, south, and east. Then, reciting the words *aêtat dim*, etc. (Y27:1, Spiegel), he lets the lower end of the pestle, and while reciting the words *ratûmcha yim*, etc., (*ibid.*, sec. 1), the upper end of the pestle, touch the stone slab. As he recites the words *snathâi*, etc., (*ibid.*, sec. 2, Spiegel), which signify that the Daevas, or evil influences, may be beaten or struck, he strikes the metallic mortar with the pestle, which produces sonorous sounds. At first, he strikes from without, i.e., strikes the pestle on the outer rim of the mortar. The sonorous strokes are given in the order of east, south, west, and north. When striking on the north side, he gives three more strokes. Then both the priests say, *Shekastê Ganâminô*, etc., in *baj*, i.e., “May the Evil Spirit be broken! May 100,000 curses be on Ahriman!” The priest then recites *Fradathâi Ahurahê Mazdâo* (Y27:3-7, Spiegel). Next he recites four *Yatha ahu vairyos*. While reciting the first three, he pounds the haoma and the *urvaram* twigs in the mortar; and while reciting the fourth, he strikes the *havana* on the outside with the pestle. In like manner, he recites *Mazdâ at môi* (*ibid.*, 8, Spiegel; or Y35:15) four times, to the accompaniment of a similar pounding during the first three recitals and a striking of the *havanim* during the fourth. This is followed by a recital of *Airyema ishyo* (Y27:9, Spiegel; or Y54:1) with like poundings and strokes.

Next comes the recitals of three *Ashem Vohus*, during which the priest pours a little of the *zaothra* water into the mortar three times. Then, while reciting the words *haoma pain-hare-shyantê* (Y27:10, [292] Spiegel), he gives a little push to the pestle which is within the mortar, and causes it to turn a circle in the direction of north, west, south, east.¹ While reciting the words *athâ, zinê, humâyô-tara*, which form the last part of the passage, he takes up the twigs of the haoma and the *urvaram* from the mortar between his thumb and fingers, and, holding the pestle also, he touches, or brings these in contact with the barsom, the plate of *jivam*, the haoma cup at the foot of the *mah-rui*, and the stone slab. At the last word *anghen*, he places the twigs and the pestle in the mortar again. He then recites four *Yatha aha vairyos*, during the recital of the first three of which he pounds the twigs. He strikes the *havana* during the recital of the fourth. During each of the first three recitals and poundings, he pours a little of the *zaothra* water into the mortar with his left hand at the recitals of the words *athâ, ashât, and hachâ*. At the end of each *Yatha ahu vairyo*, he pours the haoma juice so pounded over the pestle, which is held with the left hand over the strainer. From the strainer the juice passes into the haoma cup below. The recital of the fourth *Yatha ahu vairyo*

1 This part of the ritual is a relic of the old practice, when, after being pounded, the haoma twigs were regularly rubbed in the mortar with the pestle to extract the juice further — a process now known as *gûntvû*.

is accompanied by the striking of the mortar. At the end of this, the whole of the haoma juice is passed into the cup, as described above. If any particles of the twigs still remain unpounded, they are removed from the mortar and placed in the strainer, where they are rubbed with the hand to make all the extract pass into the cup below. During this process of rubbing, the priest recites thrice *yê sevish tô*, etc. (Y27:11, Spiegel, or Y38:11). The strainer is then washed and placed over the mortar. The particles of the twigs still left unpounded or undissolved are removed and placed in an adjoining clean corner. The pestle is washed and placed in the *kundi*.

(b) The next ceremonial process is that of straining the haoma juice with the help of the *varas ni viti*, i.e., the ring entwined with the hair of the sacred bull. The *varas* is put over the strainer (*surâkhdâr tashta*, ‘perforated plate’). The [293] priest holds the cup containing the zaothra water in his left hand, and places his right hand over the knotty part of the *varas* in the strainer. He recites *us môi uzâreshvâ, Ahurâ*, i.e., O God purify me, etc. (Y33:12-14), at the same time pouring the zaothra water over the *varas*, and rubbing the knots of the *varas*. He recites two *Ashem vohus*, the second of which is recited in *baj*. He then holds the strainer with the *varas* in his right hand, and the cup containing the haoma juice in his left hand; and repeating *humata, hukhta hvarshata* thrice, pours the haoma juice into the strainer, which is held in different positions over the *khwan*, or stone slab, as the different words of the triad are repeated. While reciting the word *humata* each time, he holds the strainer over the right hand of the stone slab, so that the haoma juice falls over it through the strainer. On each recital of the word *hukhta*, the haoma juice is similarly dropped into the cup of the *zaothra* water, which has just been emptied into the mortar through the strainer, and the *varas* with it. At each recital of the word *hvarshata*, the haoma water is allowed to drop into the mortar. The haoma juice cup is now put back in its proper place on the stone slab, and the strainer with the *varas* is placed over it. Then all the juice in the mortar — a mixture of the zaothra water and the haoma juice, or, more properly speaking, the juice of the haoma and the *urvardm* twigs — is poured into the strainer, through which it passes into the haoma cup below. After its contents have been emptied, the mortar is once more put in its proper place. The milk-plate (*jivâm no tashtô*) is placed at the foot of the *mah-rui*. The priest also puts the other cups and saucers in their proper places. He deposits in their proper plate some of the spare twigs of the haoma and the *urvaram* which are at the foot of the *mah-rui*. He places some of these in a spare cup and lets fall over them a few drops of the haoma juice prepared and collected in the cup, as described above. It is at this stage that the other priest who is to join

him in the recital of the Yasna, and who is now to act as the Zaota, enters the *yazashna gah*. Reciting an *Ashem vohu* and a certain number of *Yatha ahu vairyos*, the number of which depends on the particular kind of [294] Yasna to be performed, he goes before the *khwan* of fire and purifies or consecrates the fire (Y9:1). The priest who has performed the ceremony of straining the haoma now takes the zaotira wire of the barsom in his left hand, and the *varas* ring in his right hand, and finishes the *baj* of the *varas* which he had commenced some time before. To do this, he recites two *Yatha ahu vairyos* and the *Yasnemcha* with the *khshnuman* of the Fravashi of Zoroaster. He next dips the *varas* ring in the zaotira water cup and places it in its own cup. He then rises from his seat, and, taking the haoma cup which contains the juice prepared and strained, as above, places it in a niche of the adjoining wall. He brings the *jivam* and pours it into its saucer (*jivam no tashto*). In a plate on the stone slab he now places the *dron*, or sacred bread, which was up till now in another vessel in the *yazashna-gah*. He then recites an *Ashem vohu* and *Ahmai raeshcha*, etc., finishes the *baj*, and performs the *kusti*.

This closes the ceremony of preparing the haoma juice, more properly spoken of as the ceremony of straining the haoma (*Hom gâlvô*). With its completion terminates the *paragna*, i.e., the first of the preliminary preparatory ceremony of the Yasna. The second priest, who has now entered the *yazashna-gah* and who is to recite the whole of the Yasna, mounts the stone slab or platform which serves as a seat. As he does so, he recites two *Yatha ahu vairyos*. While uttering the word *shyaothananam* of one *Yatha* he places the right foot over it, and, while reciting the same word of the second, his left foot.

Symbolism of the ceremony.

The *Dadestan-i Denig* (48:30-33) tries to explain part of the symbolism of the above ceremony of preparing and straining the haoma juice. For example, the four poundings of the haoma twigs during the recital of four *Ahunwars* symbolize the coming of Zoroaster and his three future apostles. "The pure Hom, which is squeezed out by four applications of holy water (*zorih*) with religious formulas, is noted even as a similitude of the understanding and birth of the four apostles bringing the good [295] religion, who are he who was the blessed Zaratusht and they who are to be Ushedar, Ushedarmah and Soshyant."¹ The striking of the metallic *havana* while pounding and straining the haoma reminds one of the triad of thought, word, and deed on which the ethics of Zoroastrianism rests. The *Dadestan* says on this point: "The metal mortar (*havan*) which is

1 S. B. E. Vol. XVII, p. 170.

struck during the squeezing of the Hom, and its sound is evoked along with the words of the Avesta, which becomes a reminder of the thoughts, words, and deeds on the coming of those true apostles to the world.¹ The three ceremonial processes of pouring the zaothra water into the haoma mortar for the preparation of the juice are symbolical of the three processes of the formation of rain in Nature, viz., (1) evaporation, (2) formation of clouds, and (3) condensation as rain.²

The juice, prepared as above, by pounding the haoma twigs together with the urvaram in the zaothra water, is called para-haoma.

(4) The Ceremony of drinking the Haoma.

The last ceremony in connexion with haoma is that of drinking it. We saw above that its preparation and straining formed a part of the *paragnâ*, i.e., the ceremony preparatory to the performance of the Yasna. The ceremony of drinking it forms a part of the Yasna itself. It begins with the recital of the ninth chapter, and finishes with the recital of the 11th. In these three chapters, the priest sings the praises of Haoma. The *Zaota* describes in a highly poetical strain the good qualities of the haoma juice which lies before him. On his finishing the description and the praises of haoma, at the eighth section of the 11th chapter, his colleague, the *raspi* or *atravakhshi*, makes his hand *pav*, and, coming to the *zaota*, lifts the cup containing the haoma juice from the stone slab, and carries it round the sacred fire burning on the censer on the slab opposite, at the same time taking the *aesma boy* (sandalwood and frankincense) from their stone slabs and placing them on the fire. He then comes back to the *Zaota*, and, holding the cup over the *barsom-dân*, says to [296] the *Zaota*: "May the haoma juice be of twofold, threefold, ninefold efficacy to you." Next, he hands the juice-cup to the *Zaota*, who, holding it in his hand, looks into it, again addresses a few words of praise, and prays, that the drinking of it may bring spiritual happiness to him. Finally, he holds up his *padân*, or cloth veil, away from his mouth and drinks the haoma. He does not drink the whole quantity at once, but in three draughts. In the interval between each of the three draughts the *rathwi* recites an *Ashem vohu*.

During the recital of the Yasna, the haoma juice is prepared and strained twice. As described above, at first it is prepared and strained by one priest in the preparatory *pargana* ceremony. It is drunk by another priest during the recital of the 11th chapter of the Yasna. Then the priest who drank it prepares it a second time during the recital of

1 *Ibid.*

2 *Ibid.*, 170-171.

the three chapters of the Yasna from the 25th to the 27th. The process of pounding the haoma twigs and striking the mortar continues during the recital of the 32nd, 33rd, and 34th chapters, with which the second preparation terminates. Though the ceremony proper commences for the second time during the recital of the 25th chapter, it may be said to begin with the 22nd chapter, because all the requisites of the ceremony are enumerated and invoked at its commencement. These two preparations and poundings are spoken of in the Avesta (Yasna 10:2) as *fratarem hâvanem* and *uparem hâvanem*, i.e., the first and the second squeezing of the haoma.¹

Dr. Haug on the preparation of the haoma juice among the Parsees and the soma juice among the Brahmans.

Dr. Haug thus compares the Iranian haoma and the Brahmanic soma ceremonies. "The most important part of the offerings in both the Jyotishtoma sacrifices and the Ijashne ceremony, is the juice of the *Soma* plant. In both, the twig of the plant itself (the Brahmans use the stalks of the *Pûtika*, which is a substitute for the original *Soma*, [297] and the Parsis use the branches of a particular shrub which grows in Persia) in their natural state are brought to the sacred spot, where the ceremony is to take place, and the juice is there extracted during the recital of prayers. The contrivances used for obtaining the juice, as well as the vessels employed, are somewhat different, but on closer inquiry, an original identity maybe recognised. The Brahmans beat the stalks of the plant, which are placed on a large flat stone, with another smaller stone till they form a single mass; this is then put into a vessel and water is poured over it. After some time this water, which has extracted the greenish juice, is poured through a cloth, which serves as a strainer, into another vessel. The Parsi priests use, instead of stones, a metal mortar with a pestle, whereby the twigs of the Haoma plant, together with one of the pomegranate tree, are bruised, and they then pour water over them to obtain the juice, which is strained through a metal saucer with nine holes. This juice (para-haoma) has a yellow colour and only very little of it is drunk by one of the two priests (the zaota) who must be present. whereas all the Brahmanical priests (sixteen in number), whose services are required at the Jyotishtoma, must drink the Soma juice, and some of the chief priests (such as the Adhvaryu and Hotâ) must even take a very large quantity. The Parsi priests never throw any of the juice into the fire, but the Brahmans must first offer a certain quantity of the intoxicating juice to different deities, by throwing it from variously

1 For an analysis of the three chapters of the Yasna on Haoma (Chapters 9 to 11), etc., vide my paper on Haoma in the Journal of the Bombay Anthropological Society, Vol. vii., No.3 (1904), p. 203. Vide my *Anthropological Papers* Part I, pp. 225-43.

shaped wooden vessels into the fire, before they are allowed to taste 'the sweet liquor.' The Parsi priests only show it to the fire and then drink it. Afterwards the juice is prepared a second time by the chief priest *Zaota* and then thrown into a well. These two preparations of the Hama juice correspond to the morning libation (*prâtaḥ savana*) and mid-day libation (*maidhyandina savana*) of the Brahmans; for the third, or evening libation, there was no opportunity in the Parsi ritual, because no sacrificial rites are allowed to be performed in the evening or night time."¹ [298]

With reference to what is said above by Dr. Haug, we must note, that it appears from the Avesta, that at one time, even the Parsis had stone mortars. Again, as to the last part of Dr. Haug's statement, we must note, that the Parsis also have an evening libation, and that in the rare exceptional case of the performance of the Nirangdin ceremony. In this case the Haoma juice is prepared late in the afternoon preceding the night when the Vendidad is recited at midnight.

D) Zaothra Water: its purification or consecration. Object of the ceremony.

Zaothra or *zor* is the water that is consecrated for the purpose of being used in the liturgical services of the Yasna, the Visperad, and the Vendidad. The word comes from Avesta *zu*, Sanskrit *hu*, meaning "to perform religious ceremonies." Literally, it means any sacrificial offering over which a religious ceremony is performed. Then it is restricted to the water which is consecrated for the ritual.

The priest has before him the two cups or chalices that are to hold the *zaothra* water. He then recites the Baj with the *Khshnuman* of "*aiwyô vanghubyô vispanâm apâm Mazdadhâtanâm*," i.e. of all the good waters created by Mazda." Then, uttering the word "*ashem*," i.e., righteousness, he holds the empty *zaothra* cups over the surface of the water in the *kundi* or water-vessel, and then, reciting the formula of "*Frâ-tê-staomaidê*," etc., and at the recital of the different parts of the prayer step by step, he gradually fills the cups with water from the *kundi*. The water thus consecrated is the *zaothra* water fit to be used in the haoma ceremony and in the Yasna. The priest then finishes the Baj.

Symbolism of the ritual.

The *Bundahishn* indicates what the symbolic signification of this ceremony was. We know from the Avesta and Pahlavi books and from the classical writers like Herodotus (I., 138) and Strabo (Bk. XV, 3),

1 Haug's *Essays on the Parsis*, second ed., pp. 281-3.

that the ancient Persians were very careful to preserve the purity of water. This ceremony seems to have been intended to inculcate that idea. This appears from the following passage of the *Bundahishn* (21:3) which refers to [299] the *zaothra* or *zor* ceremony.¹

“This, too, they say, that of these three rivers, that is the Arag river, the Marv river and the Veh river, the spirits were dissatisfied, so that they would not flow into the world owing to the defilement of stagnant water (*armesht*) which they beheld, so that they were in tribulation through it until Zaratusht was exhibited to them, whom I (Ohrmazd) will create, who will pour sixfold holy water (*zor*) into it and make it again wholesome; he will preach carefulness.”

Thus, it seems that this ritual was intended to inculcate the lesson that man must try to keep the sources of drinking water pure. There must be no stagnation of water anywhere. The *Bundahishn* in connection with this matter refers to the process of evaporation and says that in the case of perfectly pure water, the water that evaporates from it returns to its source in three years. In the case of water which has pollution, or impurity and purity in equal proportions, it takes six years, and in the case of that wherein impurities predominate over purity, it takes nine years. Then, in order to give a moral advice, it adds: “So, likewise, the blessings (*afrin*) which the righteous utter, come back in this proportion to themselves.” What it means is this, that the purer a man is in his thoughts, the earlier he gets the return of these thoughts. The result of his thoughts and also the result of his words and actions re-act upon him. So, the greater the necessity of preserving purity in life. If a man prays even for some one else, that prayer re-acts upon him and does him good. The purer his thoughts, the purer his mind and head, the greater the return, the greater the re-action.

Zor-melavvi, i.e., the ritual of mixing the zor (zaothra).

At the completion of the Yasna ceremony, both the officiating priests go to the well whence they had brought the water for the liturgical consecration and carry with them in the *hâvanim* the consecrated water. There, standing before the well and saying short formulae of prayers, the Zaota pours that water back into the well in three parts. He gives back to the well, a part of the water which he had taken from it, and that in a much more [300] purified form. This ceremony is called *zor-melavvi*, i.e. to unite the *zaothra* or *zor* water with the original source of the water whence it was taken. The *zor*

¹ S. B. E., Vol. V, p. 84. Vide also the *Nirangistan* on this subject.

ceremony, then, is intended to impress, that it is one's duty to keep the sources of water pure, and to learn from its ritual the lesson, that it is his duty to keep his mind, which is the source of all his actions, also pure.

(E) Fire and its requisites.

Under the heading of Fire and its requisites fall (a) fire (*âtar*), (b) the metallic censer (*afrinagan* or *afarganiun*) on which it burns, with its accompaniments, the ladle (*chamach*) and the tongs (*chipyâ*) with which the fuel is arranged over the fire and (c) the fuel (*aêsma bûi*).

(a) No Zoroastrian ritual or religious ceremony can be complete without the presence of fire. For the celebration of the Yasna, Visperad, and the Vendidad, any household fire may be used, but all temples or Dar-e Mihrs generally keep a fire for the purpose burning day and night in the Yazashna-gah. Like all the *alats* or instruments used in the ritual, the fire used in the ritual is also purified for the time being.

This ceremony of purification consists in cleaning and washing with water the square stone slab (*âtash no khwân*) on which the *afrinagan* or the fire-vase stands. It is in the midst of the Haoma ceremony that it is made *pâv* or religiously pure. The ceremony of making this slab *pâv* is referred to in the Haoma Yasht (Yasna 9:1, *âtarem pairi yaozdathentem*) and is performed as follows: The zaota or the chief officiating priest holding a water-pot containing the *pâv* water in his right hand, makes his left hand *pâv*, reciting the *Khshnaothra* formula. Then putting the hand thus made *pâv* or purified into the pot so as to hold and lift it, makes his right hand *pâv*. Then, he goes near the *khwân* on which the fire-vase stands and faces the east and looks towards the fire. He then recites the *nemâz*, i.e., praise or homage to fire (*nemase te Atarsh Mazdao*, i.e., Homage, to thee, O Fire of God). He then takes the Baj with the *Khshnuman* of Fire. Then, reciting at the end three Ashems, he washes with the pure water of the water-pot in his hand the *khwân* or the slab on which the fire-vase stands. [301] He turns round the slab proceeding at first to the south, then to the west, then to the north and then back to the east and washes it from all sides. In the Pahlavi *Dadestan* (Chap. 48:15),¹ this stone slab for the fire-vase is called *âtashto*, (*âdashto* or *âdosht*) i.e., the place for the fire to stand upon. The Pahlavi Yasna speaks of it as *âtashgâs*, i.e., seat of fire.²

(b) The *afrinagan* is a metallic censer or vase over which the fire is made to burn on ceremonial occasions. It is so called, because its

1 S. B. E., Vol. XVIII, p. 164.

2 *Amatash âtashgâs kamist shustan* (Spiegel's Pahl. Yasna IX 2).

presence is necessary in the recital of Afrins, i.e., religious benedictions or prayers. Its size varies. In the case of Izashna-gah, the size varies from about 15 inches to 18 inches in diameter and 18 to 30 inches in height. In the Fire-temples, its size is about three to four feet in diameter and about three to four feet in height.

The fire censer or vase has always as its accompaniment a *chamach* (Persian *chamcheh* چمچه , a spoon or a ladle) i.e., a ladle and a *chipiô* (from Persian *chapânidan* چپانیدن , to squeeze, to compress) i.e., tongs.

(c) The ceremonial fire requires to be fed during the liturgical services at stated parts of the recital of the Yasna, the Visperad, and the Vendidad. The fuel required for the purpose is known as *aêsma-bui*. The pieces of sandalwood and frankincense that are arranged on small stone slabs set apart for the purpose are especially known by that name.

The word *aêsma* is the Avesta word *aEsma* (Sanskrit, ईष्म *idhma*, Persian, هیزم *hizam*) meaning fuel. In the Vendidad (8:2), four kinds of fuel are generally spoken of. They are *Urvâsna*, *Vohûgaona*, *Vohû-Kereti*, and *Hadhânaêpata*. The first, viz., *Urvâsna*, is generally taken to mean sandalwood; the second, *Vohûgaona*, to mean olibanum, the third, *Vohû-Kereti*, to mean *agar*,¹ a kind of fragrant shrub; the fourth *Hadhânaêpata*, to mean the wood of the pomegranate tree. [302]

The word *boy* [*bui*] is the Avesta word *baodha*, Persian *bui* to smell.

In modern practice, *sukhad*, i.e., sandalwood serves for *aêsma* and *loban* (Arab. *lobân*, *lebonah*, *olibanum*) i.e., frankincense for *boy*. Olibanum is a special product of Arabia, and we learn from Herodotus (Bk. III, 93) that the Arabs used to give to the Persian king Darius, as tribute, frankincense worth about 1,000 talents, i.e. about £2,43,000. It was the trade of incense that brought the ancient Arabs of Yemen into contact with the then civilized world. Frankincense was one of the three things which the three Magi from Persia are said to have presented to infant Jesus (Matt. 2:11). It was taken to be the symbol of Divine power.²

1 Perhaps Arab. اقر *aqar* white bright, noble, i.e., the brightest or noblest of fuel.

2 As in the Avesta, so in the Old Testament, four kinds of fragrant fuel are spoken of Stacte (nataph), onycha (sheheleth), galbanum (heelbenoh), and pure frankincense (lebonah zaccah). Frankincense is referred to in Exodus (30:7 and 8) as being burnt in the Sanctum Sanctorum. Leviticus (16:12) refers to it when it speaks of "sweet incense beaten small." The Parsis also use it after pounding it to a state of powder.

II. THE YASNA PROPER.

We have described, at some length, the requisites necessary in the performance of the Yasna ceremony, and, while describing these requisites, described also at some length the preliminary paragna ceremony. We will now speak of the celebration of the Yasna proper. Most of the ritual is performed during the performance of the paragna ceremony. The Yasna proper mostly consists in the recital of the 72 chapters of the Yasna with some ritual here and there. We will describe the main outlines of the ritual while describing the several component parts that make up the Yasna.

The *Paragnâ* prepares and the Yasna consummates.

In the paragna ceremony, we find, what we may call the laying out or preparation of certain principal or essential requisites, such as the *dron*, the haoma, the zaothra. In the Yasna proper, we find, what we call the consummation. In the *paragnâ*, we described the following six ceremonies:— (1) the [303] Barsom, (2) the Aiwyaonghan, (3) the Urvaram, (4) the Jivam, (5) the Zaothra, and (6) the Haoma. All these ceremonies, though separate, may be said to be accessories to the Haoma ceremony. The Aiwyaonghan, after its preparation and consecration, was associated with the barsom. The *urvaram* or the pomegranate plant twig, after its preparation and consecration, was pounded with Haoma twigs. The Jivam or the milk, after its preparation and consecration, was added to the juice of haoma and urvaram. The zaothra water, after its preparation and consecration, was used in preparing the haoma juice. All these four, (1) the haoma, (2) the urvaram, (3) the jivam, and (4) the zaothra water went to form the para-haoma. So, the main function of the *paragnâ* may be said to be to prepare and consecrate the haoma juice or the para-haoma.¹ Then, it is in the Yasna proper that it is consummated. So, what the Paragnâ prepares, the Yasna proper consummates.

The Yasna (a) prepares, (b) consecrates and (c) consummates.

But it is not the consummation of the Haoma alone that we find in the Yasna proper, but we also find therein the consummation of the *dron*. But the *dron* (*draona*) or the sacred bread ought to be consecrated before being consummated. This consecration takes place in the Yasna itself, in its early part. So, taking into consideration these questions of preparation, consecration, and consummation, the Yasna proper can be divided into several parts. We will describe these divisions, and while doing so, refer to the ritual observed therein.

¹ "The whole of the grander ritual of the Mazdayasnas centres round that holy idea" of "the Everlasting Life" represented in Mazdean Theology by Haoma." (Vide S. J. Bulsara's *Nirangistan*. Introduction p. XL.)

Chapters 1-2 invoke and offer.

On the Zoti taking his stand on his stone-slab, as referred to in the Paragna ceremony, both the priests recite in *baj* the Pazend Dibache دیباجه (preface, exordium), reciting the name of the particular *Yazata* with whose *Khshnuman* the Yasna is to be celebrated, and the name of the person (living or dead *zinda-rawan* or *anosha-rawan*) for whom the ceremony is to be performed. [304] On finishing the recital of the Dibache, each of the two priests joins together his two feet. This they do by placing the thumb of their right foot on that of their left foot. The idea is, that the first chapter, which is the chapter of invocation and which begins with the invocation of God, must be recited by them standing on one foot. The belief is that the prayer said standing on one foot or straight foot (۲۵ ۲۰ or ۲۰ ۲۰) is a good form of prayer recited in all humility. So the two feet are in the above process united, as it were, into one. Again, another form for prayer often referred to in the Avesta is that of raising up the two hands (*ustana-zasto* उस्तान हस्त). So, both the priests join their two hands together and raise them up towards their face. In this position, they recite the prayer of *Ferastuyê* (Yasna 11:17-18), known as the Patet (i.e. penitence) of the Avesta and the prayer of the particular *gah* with the proper *Khshnuman*. Then they commence the Yasna proper.

In the very first chapter of the Yasna, the celebrant invokes in the very beginning “Ahura Mazda, the Creator, the radiant and glorious, the greatest and the best, the most beautiful (to our conceptions), the most firm, the wisest, and the one of all whose (spiritual) body is the most perfect, who attains His ends the most infallibly, because of His Righteous Order, He, who disposes our minds aright, who sends His joy-creating grace afar, who made us, and has fashioned us, and who has nourished and protected us, who is the most bounteous Spirit.”¹ (Yasna 1:1). Then, he invokes the Amesha-spentas. He invokes them and submits his offerings to them. He tenders his homage to the grand divisions of time and space, which all go to make up the grand Nature, and even to the different grades of society.

Then, in the second chapter, he specially refers to the *zaothra* and the barsom, and repeats his former invocation and offerings. In the early part of this chapter, he makes several passes with the barsom held in his hands through the crescent curves of the *mah-ruī*, i.e. the crescent-shaped stands of the barsom, The Zoti then takes his seat on his *khwan*. [305]

Most of the chapters of the Yasna are recited by the Zoti, the Rathwi or the second priest joining him in the recital occasionally.

1 S. B. E., XXXI, pp 195-96.

The latter's principal business is to feed the fire by placing on it the *aêsma boy* (the sandalwood and frankincense) at the recital of particular portions of the Yasna. He is therefore also spoken of as the Ataravakhshi, Atravakhshi, or Athravakhshi, i.e., one who increases the brilliance of the fire by feeding it (*atar* and *vahsh* — to wax). Thus, the first two chapters are the preliminary chapters for Invocation and offerings.

Chapters 3-8. The Srosh-Dron chapters.

With the recital of the third chapter begins the portion which is intended for the consecration of the *dron*, i.e., the sacred bread. Chapters 3-8 are known as the chapters of Srosh-Dron, i.e., (the consecration of) the sacred bread in honour of Srosh. At particular portions of the recital of these chapters and of other chapters, the Zoti occasionally takes a handful of water from the *kundi*, or the water-vessel on his right hand, and drops it on the barsom and on the *aiwydonghan* which ties the barsom wires. This is a relic of the old times, when, instead of metallic wires used now, twigs of trees were used as barsom. It was to keep these vegetable twigs fresh and green that the water was sprinkled over them formerly. Latterly, though the custom of using vegetable twigs ceased, the ritual of keeping them green and wet continued.

The consecration of the *dron* finishes at the seventh chapter. Then, in the eighth chapter,¹ each of the two celebrants says, "I offer these things, this *dron*, water, haoma, etc., through righteousness" (*ashaya dadhemi* Yasna 8:1). The Atravakhshi places sandalwood and frankincense over the fire and says; "O ye men! Ye who have deserved it by your righteousness and piety! eat of this Myazda, the meat offering." Thereupon, the Zoti, who thinks himself to have been qualified to eat it, recites the formula of Baj or the prayer of grace and eats a bit of the sacred bread (*dron*) and then finishes the Baj. The *dron* then can [306] be passed out of the Yazashna-gah and may be eaten by other members of the congregation if present. This is said to be the Dron-chashni or the ceremonial eating of the sacred bread.

The Haoma chapters. 9-11.

The ceremonial eating of the consecrated bread being finished, the drinking of the haoma juice begins. The juice has been already prepared and consecrated in the *paragnâ* ceremony. So, it requires no consecration in the Yasna proper. The priest continues his recital of the Yasna. The Haoma juice is there before him on the *Alat-gah*. So, looking to it, he recites the Haoma chapters (chaps. 9-11) which form

1 *Vide* above p. 298.

the Haoma yasht (the chapters in praise of Haoma) and then drinks it. We have described this process above, under the head of Haoma.

Chapters 12-18. The Declaration of Faith, Invocation, and Dedication.

After the ceremony of eating the consecrated bread and drinking the consecrated haoma juice, the Zoti recites the 12th chapter which contains the articles of the Zoroastrian faith. Then follows the recital of Chapters 13-18 which contain prayers of invocation and dedication of the sacred things still standing on the *Alat-gah*.

Chapters 19-21. Praise of the three best prayers.

The next three chapters contain praises of, and form a sort of commentary on, the three most important and old prayers of the Avesta, (1) the *Ahunwar* or the *Yatha Ahu Vairyo*, (2) the *Ashem Vohu*, and (3) the *Yenghe Hatam*.

Chapters 22-27. Second preparation of haoma.

From chapter 22 may be said to begin the recital for the second preparation of haoma juice. The celebrant refers to the haoma, the *jivam*, the *urvaram*, the *zaothra* (the Holy Water), the *havanim*, the barsom, etc., before him (*imem haomem ... gâm jivyâm*, etc., Yasna 22:20-22), and says, that he desires to have them with the recital of their praise. They are again referred to in the 24th chapter. Then the recital of Chapters 25-27 is accompanied by the preparation itself, i.e., the haoma is pounded, squeezed, and strained. The juice thus prepared for the second time is not drunk by the priest but set apart for the requirements [307] of the congregation.¹ The 26th chapter of the above group is that which forms the *kardeh* (section) of *Satum* and it recited with the Dibache in the Satum ceremony.

Chapters 25-34 and 43-51 and 53. The Gatha chapters.

With the 28th chapter begin the Gathas, believed to be the oldest writings in the Avesta and to be the compositions of the Prophet himself. The following chapters make up each of the five chapters. Gathas: Gatha Ahunawad – Chapters 28-34; Gatha Ushtawad – Chapters 43-46; Gatha Spentomad – Chapters 47-50; Gatha Wohukhshathra – Chapter 51; and Gatha Wahishtoist – Chapter 53.

1 As said in my papers on the Birth and Funeral Ceremonies, there is a custom, though not generally observed now, to give a few drops of the haoma juice to a newly born child and to a dying man. These drops were given from the juice of the second preparation.

Chapters 35-42. The Yasna Haptanghaiti, and Chapter 52. The Hoshbam.

The intervening eight chapters 35-43 are known as the Yasna Haptanghaiti. These chapters though they do not form the Gathas proper, are written mostly in an older Gathic dialect. Of these, the first seven chapters, 35-41, form, as the name *haptan* (Greek *hepta*, Lat. *septem*, Fr. *sept*, German *seiben*) implies, the Yasna Haptanghaiti proper. The remaining eighth chapter, the 42nd, forms a supplement or appendix to the seven chapters. These chapters are also known as Haptan Yasht and are recited by the laity also as one of the Yashts. The 52nd chapter forms the Hoshbam or the prayer of Dawn.

Chapter 54 and 55. Praises of certain prayers.

The 54th chapter contains the prayer of Airyema-ishyo which forms a part of the recital in the Ashirwad or the nuptial ceremony. The 55th chapter is in praise of the Gathas and the Staota Yasna prayers. As to what chapters form the 33 Chapters of the Staota Yasna, which literally means the Yasna of praise, there is a difference of opinion.¹ [308]

Chapters 56-57, the Srosh Chapters.

The 56th and the 57th chapters are in praise of Sraosha, Of these the 56th chapter is called Srosh Hadokht, because it is believed to have come down from Hadokht Nask, the 20th book of the original 21 books of the Avesta. The 57th chapter forms the Srosh Yasht proper and is known as Srosh Yasht *vadi* i.e., the larger Srosh Yasht. It forms the principal night-prayer of the Parsees.

Chapters 58-59. Praise and invocation.

The 58th chapter contains the prayer known as *Fshusha manthra*, which is often referred to in other parts of the Yasna. A large part of the 59th chapter (1-27) is a repetition of two former chapters (22:1-17 and 26:1-10) and consists of invocation and praise. That part which is new consists of some blessings.

Chapter 60. Chapter for blessing a house.

The 60th chapter contains the well-known prayer known as the *Kardeh* or section of the *Tâo ahmi nmâne*, which is recited in the performance of the Afrinagan ceremony. It invokes beautiful blessings upon the house of the celebrant. It is an excellent prayer to be recited at the *moorat* or the house-warming ceremony of a new house. It is a

1 Vide Dr. West (S. B. E. Vol. XXXVII. Denkard Bk. VIII. Chap. XLVI, n. 1. Darmesteter (*Le Zend Avesta*, Vol. I Introduction Chap. IV, s. IV, pp. 87-88) Bulsala (*Aerpatastân and Nirangastan*, p. 47, n. 10.)

kind of *tan-dorosti* and *man-dorosti* prayer in the Avesta language.

Chapters 61-69. Prayers against the evil-minded and in praise of fire and water.

The 61st chapter is a prayer desiring ability to stand against evil-minded persons and evil influences with the help of the tenets preached by the above referred-to three celebrated prayers, *viz*, the Ahunwar, the Ashem, and the *Yenghe hatam*. The 62nd chapter forms the Atash Niyayesh in praise of fire. The Zoti stands upon his *khwan*, holds the barsom in his hand, and looking to the fire opposite, recites this prayer with the *Atravakhshi*. The seven chapters from 63 to 69 refer to water and its consecration. The 63rd praises the waters. The 64th is, to a large extent, a repetition of the 50th chapter (The Spentomad Gatha) which praises Ahura Mazda who has created the health-giving waters, The 65th forms the Avan Ardivisura [309] Niyayesh and refers to the waters of the river Ardivisura, supposed to be the modern Oxus.¹ The Zoti holds the cup of the Zaothra water in his right hand, gets down from his seat or his *khwan*, and looking to the water in the *kundi* by his side, recites this chapter. Chapters 66-69 continue the ceremony of further consecrating the *zaothra* water.

Chapters 70-72. The finishing chapters.

The last three chapters finish the Yasna ceremony by invoking the Amesha Spentas and praising the good creation of Ahura Mazda. The recital of the 72nd chapter finishes the Yasna proper. The Zoti gets down from his seat and exchanges a *Hamazor*, a kind of Zoroastrian kiss of peace,² with the Raspi or Atravakhshi. Both then finish the Baj. They had begun the ceremony by taking up or holding the Baj and finish it by laying down or completing the Baj. They then perform the *kusti*.

The concluding ceremony – *Zor-melavi*.

Both then go before a well which is indispensably necessary in a Fire-temple, the Zoti holding the *Havanim* containing the zaothra water in his hand. They face the sun and perform, as said above, what is called *Zor-melavi*, i.e., to mix the zaothra consecrated water with the water of the well whence the water was first drawn. This they do by pouring the water from the *Havanim* into the well.

1 *Vide* my Paper in Gujarati on the Geography of the Avesta.

2 *Vide* my Paper on "The Kiss of Peace among the Bene-Israelis of Bombay and the Hamazor among the Parsees." *Journal of the Anthropological Society of Bombay* Vol. VIII, pp. 84-95. *Vide* my *Anthropological Papers* Part I, pp. 283-94.

The antiquity of the Yasna ceremony.

While speaking of the Barsom and the Haoma ceremonies which form the component parts of the Yasna ceremony, I have referred to their antiquity. The antiquity of these ceremonies which form the component parts leads us to infer that the whole of the Yasna ceremony may be very ancient. The materials of some of the requisites required in the ceremony also suggest its antiquity. For example, (1) the *Havanim* or the mortar in [310] which haoma is pounded in the *paragna* of the Yasna ceremony is said to be either that of stone or iron (*asmana ayanghaena*: Yasna. 22:2; Visperad 10:2). Now-a-days, the metal generally used is bell-metal. Iron is never used. So, the words stone and iron suggest that possibly the ceremony must have first been introduced when the use of stone and iron was greatly prevalent and when other metals were rarely used. (2) Again, the use of the twigs of a tree for *barsom*, instead of metallic wires also suggest a remote antiquity. (3) The use of the *varas* or the hair of the bull in the plate (*tashta*), which serves as a sieve for the haoma juice to be passed through for purification, leads us to infer that the times of the introduction of the ceremony were very old when other materials to serve as a sieve were less known. Now-a-days though a metallic plate with holes (*surâkhdâr tashta*) serves as a sieve, the Varas ring is still used with it as a relic of the old usage. [311]

CHAPTER XIII. (II) THE VISPERAD CEREMONY.

Derivation and the different renderings of the word.

The word Visperad is formed from the Avesta words *vispa ratavo* which have two significations, viz. (1) all seasons and (2) all lords or chiefs. So, Visperad is a form of prayer intended to celebrate the season festivals, and, it is also a form of prayer, wherein all the ‘rads’ or chiefs or the best of the creations are invoked. The word *ratu* or *rad* is too technical to be properly translated. Dr. Mills¹ says:

“The word Visperad means ‘all the chiefs,’ referring to the ‘lords of the ritual’ Lords, because ruling as chief objects of attention during their mention in the course of the sacrifice, also, as in this case, genii guarding over all of their class.”

Anquetil² translates the words in the text as ‘Destours’ or chief priests, and in a note, as ‘Chefs,’ i.e., chiefs. He uses the word ‘chef’ in the sense of ‘premier.’ So every species of creation has its *ratu* or *rad*, i.e., its best type or prototype. Burnouf³ translates the word as ‘grand’ and ‘maitre’ or master. Dr. Haug⁴ translates it as ‘chief or head.’ He says:

“The name Visperad (Avesta *vîspê ratavô*) means “all chiefs or heads’ The primary type of each class is its respective *ratu* or chief.”

Darmesteter follows Burnouf and translates it as ‘maître’ or master. He says:⁵

“Ce mot de *ratu* ... est un des termes les plus importants de la langue religieuse. Il signifie proprement maître, au sens de maître spirituel Il désigne le chef qui est supposé placé à la tête de chaque classed’êtres.”

Harlez⁶ translates the word as ‘chef’ or chief. He says:

“L’esprit de systématisation des mages avait fait diviser l’univers entier en catégories d’êtres, et assigner à chaque catégorie un chef président, [312] à l’action

1 S. B. E., Vol. XXXI, p. 335, ns. 1 and 3.

2 *Zend Avesta*, Vol. I, partie II, p. 87.

3 *Commentaire sur le Yaçna*, pp. 4 and 17.

4 *Essays on the Parsees*, second edition, pp. 191-192.

5 *Le Zend Avesta*, I, pp. 6-7.

6 *La Zend Avesta*, p. 225, n. 5.

générale des êtres de cette classe.”

Spiegel¹ translates it as ‘All lords.’ Geiger² and Kanga³ translate it as ‘master’ and as ‘leader’ or ‘chief.’

The word ‘rad’ is a form of the Avesta word ‘ratu,’ which comes from Avesta *areta* = Sanskrit *rita*, which means, ‘to be straight, to say the truth.’ This word *areta* is the same as English ‘right.’ Now, in a species, that which is straight or perfect, that which is true, correct or well-formed, enjoys superiority over others. So the word *ratu* or *rad* has come to mean ‘a chief’.

From the fact of the division of beings into two classes, the spiritual and physical, and from the fact of their having their own *ratus* or chiefs, and from an insight into the different writings on the subject, we find, that, like the words *fravashi* [*farohar*] and *khwarenah* [*khwarrah*], the word *ratu* has a broad special signification. Every member of the animal creation has its own *fravashi*. Creatures of both, the physical and spiritual, worlds, have their *fravashis* or guiding spirits. Again all bodies have their *khwarenah* or glory or splendour. All bodies, both of the spiritual and the physical world, have their *khwarenah*. Similarly, all bodies both of the spiritual and the physical world have their *ratus*. Even substances of inanimate creation have their *ratus*. But, there is this difference, that while individual bodies have their *fravashis* and *khwarenahs* special to themselves, it is not the individual bodies that have each a *ratu* for itself, but it is each class or species that has a *ratu* of its own. The priestly class has its own *ratu*. The military class has its own *ratu*, and so on. So, each member of these classes also has a *ratu* but that is not a separate *ratu* for himself. Every member has a common *ratu*, to whom he or it can look as his or its chief, as his or its best type, as a high ideal worth imitating. For example, the Athornans or the priestly class [313] must have a *ratu* or chief — both physically and mentally pure — to whom they can look for guidance, whom they may hold before themselves as a ‘High Ideal’ for imitation and guidance.

The texts which treat of the *ratus* or *rads* and the classes of the *ratus*.

Of the different parts of the Avesta that treat of the *ratus*, the principal are the following:—(1). The Gahs; (2) Yasna, Has 1 to 4, 6, 7, and 12, 13; (3) Visperad, Kardeh 1 to 3; (4) the Ahunwar or *Yatha ahu*

1 Bleeck’s Translation, II, p. 2, Introduction.

2 *Civilization of the Eastern Iranians*, translated by Dastur Darab P. Sanjana, Vol. I, Introduction, p. XXXIX, l. 10.

3 *Avesta Dictionary*, p. 439.

vairyo. The 24th chapter of the *Bundahishn* specially refers to the subject of *rads*. We can classify the beings — both spiritual and physical — of which the *ratus* or primary types are referred to in the Parsee books, as follows:—

1. The spiritual beings. Ahuramazda and his Amesha Spentas and Yazatas. Ahuramazda stands at the head as *ratum berezantem*, i.e. the Exalted Chief.

2. Mankind. The different grades and professions of men have their own *rads* or chiefs. Zoroaster (*Zarathushtrém ashavanem ashahe ratum*) stands at the head of mankind as the best type of mankind. Then, the different professional grades of the priests, the warriors, the husbandmen, the artificers (*Athornan rathaêshhtarân*, etc.), have their own *rads* or chiefs. Then, the different constitutional divisions of the country—the house, the street, the village, the country (*nmâna, visa, zantu, danghu*)— have their own *rads* or chiefs. Then, the priests performing the different functions of the priesthood—the *Havanan, Atarvaksh, Fraberetar, Aberetar*, etc.—have *rads* of their own.

3. Animal creation other than men. (a) Animals living in water, (b) living on land, and (c) living in air have their *rads* or chiefs.

4. Inanimate creation. Even objects of inanimate creation have their *rads* or chiefs. For example, *Arus-i-Razur* is the *rad* or principal type of all forests. The Hukairya mountain is the best principal type of all the mountains.

5. Religious abstractions. Even religious abstractions have their *ratus*. For example, the prayers of Ahunwar and Yenghe Hatam [314] are the *ratus* or the best primary types of the prayers of Ahura Mazda (*Ahuirim tkaêshem*).

Connection between *asha* and *ratu*.

There is one thing which must be remembered in the consideration of the meaning of the word *ratu*. It is this: Wherever the word *ratu* is used, it is used with the word *asha*, i.e., righteousness, piety, purity. The *ratu* is always spoken of as “*ashahê ratûm*,” i.e., the chief of righteousness. As the word Fravashi is always connected with the word “*ashaunam*,” i.e., of the righteous, so the word “*ratu*” is always connected with “*ashahê*,” i.e., of righteousness. Again, the very roots of the words “*ratu*” and “*asha*” are the same. Both the words come from “*aret*” (right) to be straight, to be righteous. Thus, the word *ratu* carries with it the idea of straightness, perfection, excellence, righteousness. Among men, one who is straight-forward, righteous, perfect, becomes the *ratu* or *rad* or chief

of his class, to whom others look as a leader, worthy to be followed. Among things, that thing which is perfect, complete, pure, unblemished, beautiful, etc., is the *ratu* or *rad* or chief of the whole class, and is looked to as the best type.

The signification of the word and the object of the ceremony.

Thus, the meaning of the word *rad* or *ratu* enables us to understand, what the prayer known as the Visperad is. In the word Visperad, “vispa” means “all.” So, the Visperad is a prayer or collection of prayers or religious writings which treat of, and praise, all the *ratus*, *rads* or chiefs of the different creations of God. It signifies, that every person must have before him a high ideal (*ratu*) which he must do his best to reach. An agriculturist must have before him the ideal of a *ratu* of his class, i.e., of the best type of agriculturist. He must try to imitate and follow him. Not only that, but in the matter of his business materials, he must use the ideal or the best type of materials. In the matter of the seeds that he uses, he must use the *ratu* or the chief or the best of the seeds. In the matter of his implements, he must use the best available.

The 24th chapter of the *Bundahishn* speaks of the different *ratus* of the different classes of creation. Therein, at the end, [315] we read the following sentence, which sums up, as it were, the object of the celebration of the Visperad; It says: “Hangard denman, âigh kolâ mân kâr-i-mas vâdûnêt, adinash kasich veh,”¹ i.e.; “The conclusion is this: that he, who does a great work, has the best individuality or personality,” or, as Dr. West puts it “The conclusion is this, that every one who performs a great duty has then much value.”² In other words, the celebration of the Visperad should suggest to the celebrant the idea of “Excelsior.” How is that state of “excelsior” to be attained? We find the reply in the 15th chapter (s. 1) of the Visperad which says:

“O Zoroastrian Mazdayasnians! Keep your feet, hands, and understanding, steady for the purpose of doing proper, timely, charitable works and for the purpose of avoiding improper, untimely, uncharitable works. Practice good industry here. Help the needy and relieve them from their needs.”

Recital of the Visperad.

The Visperad is divided into 23 Kardas (Av. *karêta*) or sections. It is never recited alone but is always recited with the Yasna. The

1 *Vide* my *Bundehesh*, p. 112. [Modi, Jivanji Jamshedji. *Bundehesh*. Bombay: Education Society's Steam Press, 1901.]

2 S. B. E. V., p. 91, Ch. XXIV 30.

Visperad is preceded by the *paragnâ* which is the same as that of the Yasna. In fact, the celebration of the Visperad is the celebration of the Yasna, with the additional recital of the 23 chapters of the Visperad. Ordinarily, the Visperad is recited whenever the Vendidad is recited. But there are special periods of the year when the Visperad is specially recited. These periods are known as the Gahambars (season festivals), and the Visperad then recited is known as *Gâhambâr ni Visperad*, i.e., the Visperad of the Gahambars. It is specially celebrated on the occasion of the Gahambars, because the Gahambars are the “*ratus*” of time. The furtherance, progress, development, and improvement of everything in the world depends upon time, upon the due succession of seasons at their proper times. It is the due observation of time (*gah*), that enables a man to do his best in all his different walks of life, whether he be an agriculturist, trader or a professional [316] man. Nature holds forth, before men, the Gahambars or the seasons as the best type, as the best ideal, for all work to be done at the proper time. Such being the case, the Gahambars are specially considered to be the proper times for the celebration of the Visperad ceremony.

The eight priests referred to in the Visperad. A plan showing their positions and functions.

It appears from the Visperad (3:1), that, at one time, more than two priests were required for the celebration of the Yasna ritual. The Uzerin gah (Gah 3:5) and the Vendidad (5:57) also refer to them. The priests enumerated in the Visperad, besides the Zaotar himself, are the following:—(1) Hâvanân, (2) Âtare-vakhsh, (3) Fraberetâr, (4) Âberetâr, (5) Âsnatâr, (6) Rathwîshkara, (7) Sraosha-varez. In the modern ritual, the Zaotar or the senior officiating priest calls for their presence (*âstâya*). He is, as it were, calling out a roll-call. Instead of the above different priests answering to their names, it is only the Âtravakhshi or Rathwî who replies and says “I am here” (*azem vîsâi*). He shifts his position as the names are called out one after another and he takes his stand in the different corners and sides of the *Yazashna gah* before giving replies to the calls. The different positions occupied by him now in the ritual show the positions occupied at one time by the different priests when they all took a part in the ceremony. The positions are the following, the Zaotar himself sitting on his *khwan* in the north:—

The designation of the priests


Their positions in the Yazasha-gah.

- | | |
|---------------|--|
| 1. Zaotar ... | North, facing the fire-vase before him in the south. |
|---------------|--|

- 2. Havanan ... On the right side of the Zotar or Zoti, in the north-west corner of the Yazashna-gah.
- 3. Atravakhsha ... On the right side of the Zoti and facing the fire, i.e., on the south-west corner. [317]
- 4. Fraberetar ... On the left side of the Zoti, on the north-east corner.
- 5. Aberetar ... On the left side of the Zoti and facing the fire, i.e., on the south-east corner.
- 6. Asnatar ... On the right side of the Zoti and between the Zôdgâh (i.e., the seat of the Zoti) and the Atash-gah or the slab on which the fire-vase stands, i.e.; on the west in the middle of the Yazashna-gah.
- 7. Rathwishkara ... On the left side of the Zoti and between the Zôd-gah and the Atash-gah, i.e., on the east.
- 8. Sraoshavareza ... Opposite to the Zoti and in front of the fire-vase, i.e., on the south of the Yazashna-gah.

A diagram of the positions as observed now.

I give below a diagram to show the positions of the eight priests in the Yazashna-gah as pointed out now, by the different positions occupied by the Atravakhshi in the Visperad ceremony, when responding to the call of the Zaoatar for the presence of the different priests.



The positions as determined by the Nirangistan.

The *Nirangistan*¹ seems to be the authority on which the positions for the different priests are determined. The modern practice tallies

1 The Photo-zinco text, folio 155a to 157b; Darmesteter, *Le Zend Avesta*, III, pp. 130-31.

with the description of the *Nirangistan* except in the [318] case of the positions of the Âsnatar and the Rathwishkara. The Âsnatar's position in the modern ritual is on the right hand side of the Hâvanân who is represented as facing the barsom. But the *Nirangistan* gives it on the left. The same is the case with the position of the Rathwishkara whose position now is on the left of the Fraberetâr and not on the right as said by the *Nirangistan*. I think the words *haoyât* and *dashinât* (left and right) may have been interchanged by mistake by the original copyist. The Pahlavi *Nirangistan*¹ also briefly refers to the functions (*kairya* (𐬵𐬀𐬎𐬎)) of these eight priests. Their functions are as follows:—

1. *The Zaota*. The word zaotar means one who performs the ceremony from *zu*, Sanskrit *hu*, to perform the ceremony. He corresponds to the *Haotar* of the Brahmins. He is the principal officiator. He stands first in the list, and in the *Bundahishn* (30:30). Ahura Mazda himself is allegorically spoken of as officiating as zaotar in the Yasna ceremony with the Yazata Sraosha as the Raspi. The *Dadestan-i-Denig* (XLVIII, 13), which describes some parts of the ritual of the Yasna, refers to the Urvis-gah as his proper place. According to the *Nirangistan*, his principle function is to sing the Gathas (*gâthâoscha frasarvayâiti*).² This is a reference to the fact that it is the Zaotar who has to recite all the chapters of the Gathas in the performance of the Yasna ceremony.

2. *The Hâvanân*. It appears that in ancient times, there was a priest whose special function was to pound the Haoma (*haomemcha a-hunavat*) in the Havanim (mortar) in the Hawan gah (the morning hours), to drink its juice ceremonially, and to do all the needful for the Haoma ceremony.³

3. *The Âtravakhsha*. As the word itself shows, his function was to feed (*vakhsh*, English *wax*, to grow, to increase) the fire (*âtra*). The *Nirangistan* further says that one of his [319] functions was to purify the fire (*âthrascha yaozdathat*).⁴ This refers to the ritual in the Yasna ceremony, wherein, before the commencement of the Yasna proper, the stone-slab (*khwan*) on which the fire-vase stands is washed by the priests. Dr. Haug⁵ compares his functions with those of the Agnidhra (who holds the fire) of the Brahmins.

4. *The Fraberetâr*. The function of this priest was to carry (*bar*,

1 *Le Zend Avesta* par Darmesteter III, pp. 128-30. Mr. Sohrab Bulsara's *Aerpatestan and Nirangstan*, Chap XXVII.

2 Darmesteter, *Le Zend Avesta*, III, p. 129. Bulsara, p. 392 n. 1a. *Ibid*.

3 *Ibid*.

4 *Ibid*.

5 *Essays on the Parsees*, second edition, p. 281.

English *bear*) forward (*fra*, English *forth*) all the requisites of the ceremony. Out of these requisites, the *Nirangistan* specializes the barsom and the Fire (*barêsmâncha frâkem athraêcha*).¹

5. *The Âberetâr*. The function of this priest is to carry (*bar*) water (*ap*). for the ceremony (*apem abarat*). The *Nirangistan* points out this as his only function.

6. *The Âsnatâr*. His function was to wash or clean (*snâ*, Fr. *nâger*) the ceremonial utensils and requisites. The *Nirangistan* specially refers to the process of purifying the haoma twigs and of straining the haoma juice (*haomemcha â-snayât, haomemcha paiti-harezât*).²

7. *The Rathwishkara*. He was the priest whose proper function was to do (*kar*) the work of arranging all the requisites in their proper (*rathwya*) order. The *Nirangistan* specializes his work as that of properly mixing the *jivâm* (*gava*, the milk) with haoma juice, and then of dividing the mixture (*bakshayâtcha*). This seems to refer to the present practice of the Zaotar dividing the haoma juice and dropping it in different places.³

(8). *Sraosha Vareza*. Sraosha Vareza was a priest, who, to a certain extent, corresponded to a ‘confessor.’ He made the people act (*varez*) in obedience (*sraosha*) to certain rules of penances, etc. If a person did a wrongful act, and if he wanted to do something to atone for that wrongful act, he (the *sraosha vareza*) [320] asked him to do certain good deeds, which could, to a certain extent, go to wipe off the effects of the previous wrongful deeds. Dr. Haug⁴ thinks that the Zoroastrian *Sraosha vareza* corresponds to the Brahmanical Pratiprasthâtâ. Sraosha, whose functions, the Sraosha-vareza represents to a certain extent in the superintendence of the ritual, holds an uplifted weapon (*êrêdhwa snaithisha*, Srosh Yasht; Yasna 57:16) in his hand. The Pratiprasthâtâ holds “a wooden sword” in his hand. The *Nirangistan*⁵ specializes his work at the Yasna ceremony as that of a general supervisor (*aiwyâkhshayât: aiwi*, about, and *akhsh*, to watch).

The Visperad’s list of the best typical (*rad*) prayers.

The Visperad (1:3-9) gives us a list of the prayers which were held in great veneration at the time when it was written. It enumerates the following prayers:— (1) Staota Yasna, (2) Ahunwar, (3) Ashem Vohu,

1 Darmesteter, *Le Zend Avesta*, III, p. 129; Bulsara, *op. cit.*, p. 393, l. 8.

2 Darmesteter, *Le Zend Avesta*, III, p. 130; Bulsara p. 393.

3 *Ibid.*

4 *Essays on the Parsees*, second edition, p. 280.

5 Darmesteter, *Le Zend Avesta*, III, p. 130. Bulsara, *op. cit.*, p. 394.

(4) Yenghe Hatam, (5) Gatha Ahunawad, (6) Yasna Haptanghaiti, (7) Gatha Ustawad, (8) Gatha Spentomad, (9) Gatha Wohukhshathra, (10) Gatha Wahishtoyisht, (11) Dahm Afriti, (12) Airyema-ishyo, (13) Fshusho Mathra, (14) Hadhaokhta, (15) Ahuiri Frashna. I will here briefly refer to the first four which are held to be very important among the best (*rad*) prayers.

1. The Staota Yasna.

Among the list of prayers enumerated by the Visperad, the Staota Yasna stands first; but scholars differ as to which chapters of the Yasna form the Staota Yasna referred to by the Visperad. I think by this prayer the whole of the Yasna is referred to. I give below a list, showing which chapters are referred to by various scholars as forming this prayer.¹

Scholars.

Chapters of the Yasna.

Harlez (Le Zend Avesta, p. 226, .. The last chapters of the n) Yasna.

Mills (S. B. E., XXXI, p. 294) "That .. Chapter 57, et seq. [321]
part of the Yasna which begins with the Sraosh Yasht."

Darmesteter (*Zend Avesta*, I, .. Chapters 14 to 59.
Introduction, LXXXIII)

K. R. Cama (*Zarthosht Nameh*, 2nd .. Chapters 55 to 59 or 57 to
edition, p. 232) 71.

Sheriarji D. Bharuoha (*Zarthoshti* .. Chapters 58 to 60.
Abhyâs, No. VIII, p. 457)

Khurshedji E. Pavri (*Zarthoshti*, I, Chapters 58 and 59.
No. 4, p. 318)

Among the prayers enumerated by the Visperad, three require a special mention. They are the Ahunwar, the Ashem, and the Yenghe Hatam. I will describe them at some length.

2. The Ahunwar.

The prayer is called Ahunwar (Ahuna vairya, Yasna, 19:3) from its second and third words, and because it speaks of the Lord (*ahu*)

1 Staota Yesnya (Phl. Stud-Yasht, Stot Yasn) is the name of the 21st Nask of the ancient canon of the Avesta, and constituted the earliest fixed liturgy. Malandra (*Encyclopaedia Iranica*, "yasna" entry) gives it as Yasna chapters 19-58. See also Boyce, *History of Zoroastrianism* vol. 1., p. 265, Bartholomae, *Air. Wb.* 1589; Geldner *GIP* II, 25-6. -JHP

whose desire (*vairya*) is supreme, and who is independent. From its three first words; the prayer is more properly known as “Yatha Ahu Vairyo.” This prayer corresponds somewhat to the “Word” of the Christians. It is spoken of as being uttered by God before the very creation (Yasna 19:1-3, 8). The Yasna further says that if this prayer is recited by one perfectly and right sincerely, its meritoriousness is worth the recital of 100 Gathas. If one recites it, understands it, and praises it, i.e., right sincerely acts up to its dictates, he goes to heaven (*Ibid.*, 5 and 6). Of all the prayers of Ahura Mazda, it is the best (*Ibid.*, 10; Srosh Hadokht, Yasht 11:3). He who recites it and properly understands it, acknowledges Ahura Mazda as his Lord and sets an example to others to so acknowledge Him. Its recital helps a man in all difficulties and calamities (Yasht 11:4). Hence, it is a custom, even now, for an orthodox Parsee to recite one or more Ahunwars or Yatha Ahu Vairyos, when starting on a journey, or going out for business, or on leaving his house for ordinary daily business.¹ According to the Vendidad (19:9), when Ahriman, the Evil Spirit, tried to tempt Zoroaster, it was with the recital of the Ahunwar that the [322] Prophet, emboldened himself, rejected his (Ahriman’s) proposals, opposed him, and withstood the Temptation. There, Zoroaster speaks of this prayer as one taught by God himself (Mazda-fraokhta) and calls it an excellent weapon to defend himself.

The Ahunwar is the very first prayer which a Zoroastrian child is taught to recite. There is hardly a prayer, small or great, which does not include in itself the recital of the Ahunwar once or more than once. On account of the importance and efficacy and sanctity attached to it, the *Shayest Ne-Shayest* (Chap. 19:15) says, that religion is as much connected with it as the hair is connected with, and gives glory or beauty to, one’s face.² The Ahunwar and the Ashem are, to a certain extent, to a Zoroastrian, what the Pater Noster is to a Christian. If a person does not know his other daily prayers, or if he does not know to read them from the prayer book, he is required to recite a certain number of Ahunwars in the place of each of these prayers. He holds a chaplet or string of beads [rosary] in his hand and turns a bead at the recital of each Ahunwar.³

List of (a) the recital of the Ahunwars in place of certain prayers and (b) on particular occasions.

The following list gives the number of Ahunwars which one can

1 *Vide* Mr. M. R. Unwala’s *Rivayat* with my Introduction, Vol. I, pp. 13-15.

2 S. B. E., V, p. 393.

3 *Vide* my paper on Rosaries (*Journal of the Anthropological Society of Bombay*, Vol. of 1913).

recite instead of different prayers.¹

Prayers.	Number of Ahunwars.
Khwarshed Niyayesh, i.e., the prayer in praise of the Sun	103
Mihr Niyayesh, i.e., the prayer in praise of Mithra	65
Mah Niyayesh, i.e. the prayer in praise of the Moon	65
[323] Ardvisura Niyayesh, i.e., the prayer in praise of Water	65
Atash Niyayesh i.e., the prayer in praise of Fire	65
The five Gahs, i.e., the prayers for the five periods of the day	65
The Patet, i.e., the repentance prayer (with twelve Ashem vohu prayers)	121
Ahura Mazda Yasht (with 12 Ashem Vohus)	103
Ardwahišt Yasht	65
Srosh Hadokht	75
Srosh Yasht vadi (Yasna 57)	103
The Afrinagan (with 12 Ashem vohus)	121
Each of the five Gathas to be recited on each of the five intercalary days at the end of the year	1200

The Ahunwars for these Gathas are recited with a particular Baj, i.e., a small introductory prayer, and a prayer recited at the end.

The *Shayest ne-Shayest* (Chap. 19)² gives the following list of the Ahunwars to be recited by a Zoroastrian on particular occasions to withstand difficulties, to have courage and help, and to win success:—

Occasion of business.	No. of Ahunwars.
1. When “one goes forth to an assembly or before grandees and chieftains, or on any business; or when he goes to ask for what he wants, also when he quits any business”	1
2. On the recital of some blessings upon somebody (It is for this reason that the recital of the Tandorosti prayer invoking blessings upon [324] somebody and the recital of the Ashirwad blessings upon a marrying couple begin with two Ahunwars)	2
3. On the recital of thanksgiving prayers at season-festivals. So, the	4

1 *Vide Darab Hormuzdyar's Rivayat* by M. R. Unwala with my Introduction Vol. I, pp. 13-15. *Vide* રીવાયત દસ્તુર દર્શિય ઉપજયાર, Rustamji Jamasji Dastur (1896). pp. 14-15. *Vide* K. E. Kanga's *Khordeh Avesta*. 8th ed. p. 149.

2 S. B. E., V. pp. 390-92.

Afrinagan of the Gahambaras or the season-festivals begin with four Ahunwars)	
4. On the occasion of atonement or repentance for sins. (Thus, the Patet or the Repentance prayer begins with the recital of five Ahunwars)	5
5. When one “goes to seek power” or to win a battle	6
6. When one recites the praises of the Yazatas. (The recital of the Afrinagans with the Khshnumans of the Yazatas or angels begin with seven Ahunwars)	7
7. On the occasions of remembering and invoking the Fravashis of the dead. (It is for this reason that the Afrinagan of Ardafarosh, recited in honour of the dead, begins with eight Ahunwars)	8
8. When one goes to sow corn in his field (The corn was believed to take, in all, nine months from the time of its being sown, to be fit for use)	9
9. When one goes to seek a wife	10
10. When one begins the work of breeding cattle	10
11. When one climbs up a mountain	11
12. When one goes to low districts or valleys	12
13. When one loses his way and wants to find his way back. (The Srosh Hadokht specially refers to the recital of Ahunwar on such occasions (<i>Pathâm vâ paiti vîcharanâo</i> : Yasht 11:4)	13
14. On crossing a bridge or a river. (The Srosh Hadokht also refers to the recital of Ahunwars on crossing rivers and bridges (<i>apâm vâ nâvayanâm paiti peretush</i>) implying that the process [325] involves some danger and difficulty on dark foggy nights (<i>Khshapo vâ tânthryâo aipi-dvânarayâo</i>)	13

The list according to the Rivayats.

The later Rivayats give a list, slightly different from that of the Pahlavi *Shayest Ne-Shayest*.¹ We give the list below:—

1	(a) When leaving the house for business.... (b) When entering the house on return from business.... (c) When beginning a new work.... (d) On finishing a work.... (e) When beginning an important conversation with somebody.... (f) On going before a ruler, or governor, or a great man.... (g) On entering a river, lake, or any such great reservoir of water.... (h) On lending money to somebody.... (i) On borrowing money from somebody....	1
2	On blessing somebody....	2
3	On removing nails from one’s fingers....	3
4	On the recital of the Gahambar Afrinagan....	4

1 *The Gujarati Rivayet of Darab Hormuzdyar* by Ervad Rustomji Jamasji Dastur, pp. 11-12. Vide M. R. Unwala’s Text with my Introduction, pp. 13-15.

5	On the recital of the Patet or Sraosh Baj or Afrinagan....	5
6	When attending a marriage....	6
7	When going on a battle or to fight a cause....	7
8	On the recital of the Afrinagans of (a) Ardafarosh and (b) Gatha....	8
9	(a) On sowing seeds, (b) on planting fruit trees, etc.....	9
10	(a) On purchasing cattle, (b) on bringing cattle home....	10 [326]
11	On fixing a nail or peg into the ground to tie the cattle, (b) on cohabitation, (c) on carrying messages for betrothal, etc.....	11
12	On going over a mountain, a fortress, a bridge, or on climbing any lofty place and on going into a subterranean room, into a cave, or into a stepped reservoir or well of water....	12
13	(a) On missing the road, (b) on entering a new village or city....	13
14	On entering into the heart of a great city....	14

The 21 words of the Ahunwar and the 21 books (nasks) of the Zoroastrians.

This sacred prayer is made up of three metrical lines each containing seven words. So, the whole prayer contains 21 words. The names of the 21 books (*nasks*) which formed the ancient Avesta literature are said to have corresponded to the 21 words of this sacred formula. The following is the list of the words that make up this passage and of the names of the books that correspond to them:¹—

Words of the Ahunwar.	Names of books which correspond to these words.
(1) Yatha	Studkar [sudgar]
(2) Ahu	Varshthah-manthrah [wahashta-mansr, warsht-mansr]
(3) Vairyo	Bagh [bag, bago]
(4) Atha	Damdad (or Duazdeh Hamast)
(5) Ratush	Nadur [nadar]
(6) Ashat	Pazun [pazag, Pajako Pajeh, Pajam]
(7) Chit	Ratushtayid [ratushtaiti]
(8) Hacha	Barish [327]

1 The names of the books and even the order vary a little according to different authorities. The two great compilations of the Rivayets by Darab Hormazdyar and Barzo Kamdin give the names and contents. The *Denkard* (Bks. VII and IX) and the *Dini Vajarkard* give fuller contents (*vide* S. B. E. Vol. XXXVII). For a brief account of the contents prepared by me, *vide* Mr. Dosabhoy Framji's *History of the Parsees*, Vol. II, pp. 157-64. *Vide* M. R. Unwala's Riv. with my Introduction pp. 3-4.

(9) Vangheus	Kashsrob [kishsrub, kishkisrub, kashkisrob, kashasrob]
(10) Dazda	Vishtaspad [gushtaspad, wishtasp-sast, Vishtasp Yasht]
(11) Manangho	Dad [washtag, Dadok]
(12) Shyaothananam	Chidrasht [chihrdad, Chithradad, Chidrast]
(13) Angheus	Spentah [spenta, spand, Spend]
(14) Mazdai	Bayan-yasht [bagan yasn]
(15) Khshathremcha	Niyadam [nigadum, Nikadum]
(16) Ahurai	Duvasarajit [dusrujid, duwasrud, Dubasrujd]
(17) A	Husparam [husparum]
(18) Yim	Sakadam [sagadum, Sakadum]
(19) Drigubyo	Jud-dev-dad [jud-dew-dad, vendidad, Videvdad]
(20) Dadat	Hadokht of the Dvazdah-hamaspah [hadokht]
(21) Vastarem	Yasht [stud-yasn]

The substance of the Ahunwar prayer.

Though it is a small prayer, scholars differ in their translation of it. The substance of it runs thus:-

As Ahu (Ahura Mazda or the spiritual Lord) is an independent ruler (because He rules) according to Order (*ashât*, i.e., according to fixed laws), so, should a Ratu, (i.e., the temporal Lord) (rule according to fixed laws). The gift of good mind is for the work of the world for (the sake of) Mazda. He who gives (himself up) as the nourisher of the poor (or he who gives nourishment to the poor) gives kingdom to Mazda (i.e., acknowledges him as king).

The Ashem.

The prayer of Ashem Vohu is next to Ahunwar in importance and sanctity. It is the prayer in praise of Asha which can be said to be the watchword of the Zoroastrian religion. According to the Hadokht Nask (Yasht Fragment 21), if there is any one prayer which can be said to be the prayer of praise of all the good creation, — of all the good creation that has for its main principle, Asha or Order, — it is the prayer of Ashem Vohu, because it is the prayer which praises Asha, (i.e., Order, Harmony, System, Righteousness, [328] Law). He who praises Asha from the inmost of his heart praises God himself. Not only that, but he praises some of the best things of his creation, *e.g.*, water, earth, vegetation, animal creation, etc., in the evolution and growth of which we see Order and Law. The prayers of Ashem and Ahunwar give courage and victory to those who recite them and follow

their teachings (Yasht 21:4). Such being the efficacy of this prayer which praises Order and Righteousness, its recital on certain particular occasions or periods of one's daily work or life, have greater advantages than its recital at ordinary times. One Ashem Vohu recited at such particular occasions is worth several recited at other ordinary times. For example, it is said that one Ashem Vohu recited at meals is worth ten Ashem Vohus recited on other occasions. An Ashem recited while going to bed is worth 1,000 Ashems recited at other times. An Ashem recited on getting up from bed is worth 10,000 recited at other times. An Ashem recited by a person at the time of his death is worth the price of the whole continent of Xwaniratha (Khanirath). What is intended to be conveyed is this: If a man has led his whole life in a pious and righteous way, following the path of Asha, i.e., Order, Harmony, Righteousness, Law, and if he can conscientiously recite at the end of his life one Ashem Vohu, i.e., if he can conscientiously say "I have led a righteous (*ashô*) life," then the spiritual wealth of that righteousness is worth the material wealth of Xwaniratha, which, of all the seven karswars or regions spoken of in the Avesta, was the best and the richest. On account of this reference to the Ashem Vohu in connection with the end of the life of a man, it is a custom among the Parsees, that when one hears the news of the death of a friend or relation, he recites or mutters in a low voice the Ashem Voha prayer.

Such being the importance attached to this prayer, it is the second prayer taught to a Zoroastrian child after the Ahunwar. The Ashem Vohu prayer, small though it is, is differently translated by different translators. But the substance seems to be the same. It can be thus translated:

Piety is the best good and happiness. Happiness to him
who is pious for the best piety. [329]

The prayer of Yenghe Hatam.

This is the third of the three short but most important prayers or formulae of the Zoroastrians. There is hardly a prayer which does not contain this formula. The Gahs, the Niyayeshes, the Yashts, the Yasna, the Visparad, the Vendidad all include its recital which in some cases is repeated more than once. Like the two prayers of Ahunwar and Ashem, it is variously translated. It can be translated thus:

Ahura Mazda knows (*lit.*, is the knower of), who among the living is the best in prayer through righteousness, (i.e., says his prayer in the best way possible by observing *asha*, i.e., righteousness). We praise them (those recognized as above by Ahura Mazda) whether male or female. [330]

CHAPTER XIV. (III) THE VENDIDAD CEREMONY.

Meaning of the word Vendidad. Its divisions. Its place in the Avesta literature.

The word Vendidad comes from the Avesta word *Vî-daêva-dâta*, i.e., the Law given against the Daevas or the evil spirits. The word is *Javid-shedâ-dâd* in the Pahlavi, It is *Jud-div-dâd* in Persian. It is so called, because a large part of it contains rules, regulations, and instructions as to how to withstand best, the evil influences of the Daevas, i.e., of all evil spirits or forces that lead to the impurity and decay both of body and mind. A part of it may be called the sanitary code, and a part, the criminal code of the ancient Iranians. The divisions or chapters of the different parts of the Avesta are known by different names. The chapters of the Yashts are known as *Kardâs* (Av. *Kareta*) or sections. Those of the Yasna are known as *Hâs* (Av. *hâiti*). But the chapters of the Vendidad are known as *pargards* or *fargards*, (*para-karêta*, a greater section), a word which corresponds exactly, as Dr. Haug points out, to ‘*pericope*,’ i.e., sections. The Vendidad has 22 chapters in all. The first chapter seems to be very old.

According to the *Denkard* (Book VIII),² the Vendidad formed the 19th book of the 21 books (nasks) which contained the whole of the Avesta literature of ancient times. It corresponded with the word “Dregubyo” in the Ahunwar prayer, the 21 words of which are, as said above, believed to have corresponded with the 21 books. Some of the Rivayats take it to be the 20th book in the list corresponding with the word ‘*dadat*.’ Of the three groups in which the nasks are divided, — the *gâsânic*, the *dâtik*, and the *Hadha-manthrik*, — the Vendidad belongs to the second group, viz., the *dâtik* or the groups of books containing Zoroastrian laws, rules, and regulations on religious, sanitary, social, and other matters. [331]

The Vendidad ceremony. Preliminary preparations for the performance of the Vendidad ceremony.

Two priests participate in the performance of the Vendidad ceremony. They must be those who have observed the great *Khub*. Again, the Vendidad proper is preceded, as in the case of the Yasna, with the *paragnâ*. The ceremony is performed in the Ushahin Gah, i.e., at midnight after 12 o’clock. In the case of the Vendidad performed for the Nirangdin ceremony, a part of the *paragnâ* ceremony is performed in the preceding afternoon in the Uzerin gah. It is the Zaothra ceremony, i.e., the ceremony for preparing the

1 *Essays*, second ed., p. 225.

2 S. B. E. Vol. xxxvii., p. 7 n, 3, Chap. i; 1 11-12.

consecrated Zaothra or Zor water that is so performed in the preceding afternoon.

The celebration of the ceremony. The order of recital.

The celebration of the ceremony consists of the ritual of its 22 chapters, not successively but with additions of the different chapters of the Yasna. and the Visperad. The Vendidad thus formed is known as the "Vendidad Sadah." As far as the ceremony or the recital itself goes, most of it is performed during the recital of the Yasna and the Visperad chapters. The following list describes how the different chapters of the Vendidad are recited with those of the Yasna with some sections here and there omitted and the Visperad during the ritual.¹

- | | |
|---------------------------------------|-------------------------------|
| 1. Yasna 1:1 to 8. | 26. Visperad 14. |
| 2. Visperad, 1, complete. | 27. Vendidad 7 to 8. |
| 3. Yasna 1:10 to 2:8. | 28. Visperad 15. |
| 4. Visperad, 2, complete. | 29. Yasna 35 to 42. |
| 5. Yasna 2:10 to 11:8. | 30. Visperad 16 to 17. |
| 6. Visperad 3:2-5. | 31. Vendidad 9 to 10. |
| 7. Yasna 11:9 to 15. | 32. Yasna 43 to 46. |
| 8. Visperad 3:6 to Kardeh 4. | 33. Visperad 18. |
| 9. Yasna 11:16 to Ha. 14. | 34. Vendidad 11 to 12. |
| 10. Visperad 5. | 35. Yasna 47 to 50. |
| 11. Yasna 15. | 36. Visperad 19. |
| 12. Visperad 6. [332] | 37. Vendidad 13 to 14. |
| 13. Yasna 16 to 17. | 38. Yasna 51. |
| 14. Visperad 7 to 8. | 39. Visperad 20. |
| 15. Yasna 18 to 21. | 40. Vendidad 15 to 16. |
| 16. Visperad 9. | 41. Visperad 21 to 22. |
| 17. Yasna 22. | 42. Vendidad 17 to 18. |
| 18. Visperad, 10 to 11. | 43. Yasna 52 to 53. |
| 19. Yasna 23 to 27. | 44. Visperad 23. |
| 20. Visperad 12. | 45. Vendidad 19 to 20. |
| 21. Vendidad, Pargards 1 to 4. | 46. Yasna 54. |
| 22. Yasna 28 to 30. | 47. Visperad 24. |
| 23. Visperad 13. | 48. Vendidad 21 to 22. |
| 24. Vendidad 5 to 6. | 49. Yasna 55 to 72. |
| 25. Yasna 31 to 34. | |

[333]

¹ Vide K. R. Cama's *Zarthusht Nameh*, first Edition, p, 194. Vide Ervad Tehmuras's *Yazashna bâ Nirang*. Therein, in the Visperad portion, the portions of the Yasna as interspersed are given in brief.

CHAPTER XV. (IV) The Baj Ceremony

The derivation, literal meaning, and different significations of the word Baj.

The derivation of the word is doubtful. (a) Some derive it from the Avesta word *vach* (Sans. *vâch*, Lat. *vox*) meaning word or speech. So, the word Baj means, certain words or prayers religiously recited in honor of particular beings, such as the *yazatas* or angels and the *Fravashis* (*Farohars*) or the guarding spirits of the living or the dead. (b) Perhaps, it is the Persian باز or باژ *bâz* or *bâzh* which means a tribute. In the Baj ceremony and prayer, certain things which serve as representations or symbols of the different kinds of creation, such as animal creation, or vegetable creation, are submitted as offerings. So these offerings are, as it were, a tribute to the glory of the particular Yazata or heavenly being, or to the memory of a particular dear departed one. Ordinarily, the word Baj has several significations in the religious phraseology of the Parsis. They are the following:—

I. The anniversary of the death of a person, when the Baj ceremony is generally performed.

II. The offerings of sacred bread, fruits, etc., submitted during the recital and celebration of the Baj.

III. A peculiar suppressed muttering tone in which some prayers are recited, or in which conversation is held on certain religious or solemn occasions when a kind of Baj is recited.

IV. A certain class of prayers recited on particular occasions with certain formalities.

I. Baj, the anniversary of one's death.

We will now speak of these different significations. Baj is the name of one of the liturgical services which form the funeral services after one's death. The first three days after death are the principal days when these ceremonies are performed. After this period of the first three days, the principal occasions during the first year after death are, as referred to in the Pazand [334] Dibache of the Afrinagans, the following: 1. Chehârum, or the Fourth day. 2. Dehûm, or the Tenth day. 3. Sirouz, or the Thirtieth day. 4. Sâlrouz, or the Anniversary.

During the first year, the Baj ceremony is performed every month on the ruz or the day of the month of the death of the deceased and the day is known as *pehlâ mahinâni Bâj*, *bijâ mihinâni Bâj*, i.e., the first month's Baj, the second month's Baj, and so on. After the first year, the Baj ceremony is generally performed on every succeeding

anniversary, which anniversary is known as the Baj of the deceased. Just as an Englishman would say, "Today is the fifth or sixth anniversary of the death of A or B," a Parsi would say, "Today is the fifth or sixth Baj of A or B." At times, he would speak a little more definitely and say, "Today is the Baj of the fifth or sixth year of A or B." It is considered to be the duty of the son or the nearest heir to perform the Baj ceremony in honor of the deceased person. The name of the deceased person is recited in the Baj prayers.¹ The name of the person who gets the ceremony performed is also recited as *Farmâyashnî*, *i.e.*, as that of the person giving the *Farmân* or the order to get it performed. At times, persons in their lifetime, or by their wills, set apart certain sums, out of the interest of which such ceremonies known as the *Baj-rozgâr* ceremonies are performed. There are cases known of deceased persons whose Baj's have continued to be performed, *i.e.*, whose death anniversaries have been religiously celebrated every year, for more than hundred years. In the case of some great worthies who have done yeoman's service to their towns, their Baj's or death anniversaries are celebrated by public subscriptions. For example, the anniversaries of the deaths of Dastur Meherji Rana and of Desai Khorshedji of Naosari are observed with religious Baj ceremonies by their townspeople even now, about 300 years after the death of one and 150 years after the death of the other person. After the ceremonies, solemn dinners are held in which the subscribers participate. [335]

II. Baj, the offerings made for the celebration and recital of the Baj.

In the celebration of the Baj, certain offerings are necessary. These offerings, when placed in an utensil or vessel, are also called a Baj. The utensil containing the offerings is called the Baj of the particular deceased whose funeral ceremonies are performed. For example, suppose that a certain day is the anniversary of the death of more than one person. Then for each such person, such vessels with offerings are prepared. Then each of the vessels containing these offerings is said to be the Baj — or, to speak more correctly, the vessel containing the Baj — of A, B, or C as the case may be.

The requisites of a Baj.

The most essential requisites of the Baj, *i.e.*, of the offerings are (a) the dron, or the sacred bread, (b) some kind of fruit, (c) some kind of animal production.

(a) Of the Dron or the sacred bread, we have spoken at some

1 *Vide* above p. 81. 'Funeral Ceremonies' for the form of the recital.

length in the description of the Yasna ceremonies.¹ The Rivayats say that each of the named Drons, *i.e.*, the sacred breads with the sacred marks, must be about 31 *tânks*² in weight, and each of the unnamed drons or Farshasts, *i.e.*, the sacred breads without the sacred marks, must be about 33 *tânks*.

(b) As to fruit, it is generally the practice to place in the Baj some fruits of the season. In India, where plantains or bananas are plentiful and are obtainable throughout the whole of the year, they form an essential requisite. One plantain or banana is placed in each Baj. Ordinarily, it is believed that for the poor or for those who cannot afford much, one or two dates or a few grains of the pomegranate are sufficient as representative of the offering of the vegetable creation of God.

(c) As to some products of the animal creation, in India, an egg is considered to be an essential as easily obtainable. But for those who cannot afford, a very small quantity of ghee or clarified butter as representing an offering of the animal creation of God is sufficient. [336]

III. The recital or utterance in a suppressed tone known as Baj.

In the Parsi prayers there are several portions which are recited not in the ordinary tone but in a suppressed tone. The mouth is shut and the utterance is given expression to in a suppressed tone. The tone under these circumstances is generally nasal. This kind of expression is often referred to by Firdausi as 'Zamzamê.'

(a) The Parsi prayers are mostly in the ancient Avesta language, but latterly some portions in the later Pazand language are added. These Pazand portions when they occur in the beginning or at the end of an Avesta prayer are recited in the ordinary way, but when they occur in the midst of long Avesta prayers, they are recited in a suppressed tone and are then said to be recited in Baj. In the case of such Pazand portions, the prayer-books say in brackets "*Bâj ma bhanvun,*" *i.e.*, to recite in Baj, *i.e.*, in a suppressed tone.

(b) Again when a person is reciting a long prayer and if he has unavoidably to say something for business, he speaks in Baj or in a suppressed muttering tone. For example, the celebration and recital of the Vendidad lasts from midnight to about 6 or 7 in the morning. If, in the midst of this ceremony, the priest has to ask for something or say something, he has to do so in Baj.

(c) Not only during prayers but on other occasions when one has

1 *Vide* dron in the Yasna ceremony. *Vide* above, p. 296.

2 72 *tânks* make one *seer*.

recited a Baj (*Vide* below, the fourth signification of the word) if he has to say something, he must say that in Baj. For example, if one has recited a Baj for meals, *i.e.*, said grace before meals, he is not to speak anything unless it be in Baj, *i.e.*, in a suppressed tone. After taking his meals, he finishes the Baj. It is after this finishing prayer that he can speak in the ordinary way.

IV. The Baj, or Baj prayers recited on particular occasions with certain formalities.

The principal signification of the word Baj is a certain class of prayers known as Bajis and which are recited on different occasions with certain formalities, great or small. Some of these Bajis are recited only by the priests observing [337] the Barashnom and the Khub. The others are those that can be recited even by the laymen. So we will divide these Bajis into two classes.

(A) Bajis recited by the priests with offerings as a part of their liturgical service.

(B) Bajis recited on smaller occasions without any offerings.

(A) Bajis recited by priests observing the Barashnom, etc.

The Bajis of this class are the principal Bajis.

The principal occasions — though not the only occasions — on which they are recited are the Baj days, *i.e.*, the anniversaries of the deaths of persons. The necessary formalities or conditions required for this class of Bajis are the following:

(a) They must be recited by priests, holding the Barashnom and qualified with a Khub.

(b) They must be recited over a Baj or a collection of certain offerings such as Drons or sacred breads, fruit, water, milk-product such as ghee or clarified butter.

(c) Fire burning in a vase with sandalwood and frankincense is essentially necessary during their recital.

(d) They must be recited in a specially enclosed place; for example, in the Yazashna-gah of the temples or when in a private residence, in a place specially cleaned, washed, and enclosed in 'pavis.'

Requisites of this class of Bajis.

The following are the requisites which the priest must have before him within the pavis or an enclosed space.

1. Atash or fire burning in a vase, with *aesma* and *bui*, *i.e.*, sandalwood and frankincense.

2. Âp or water made *pâv*, or ceremoniously pure.

3. Drons or sacred breads. The number of these Drons are four in the case of all Bajis but six in the case of the Baj of Srosh. Half of this number are *nâm pâdelâ*, *i.e.*, named or marked with nine marks in their preparation, and half *vagar nâmnâ*, *i.e.*, unnamed or unmarked. [338]

4. Urvarâm, or a few grains of the pomegranate.

5. Goshudo, (gâush hudhâo), *i.e.*, ghee or clarified butter.

6. An egg.

The following figure shows the respective places where the requisites are placed within the enclosed *pâvi*: The requisites numbered 1 to 5 are placed in a tray or vessel.

	Fire vase	Small stone-slabs for
		<i>Aesma bui</i> , <i>i.e.</i> , sandalwood and frankincense
No. 3 Dron (named)	5 egg.	No. 4. Frashast (<i>i.e.</i> , unnamed Dron with <i>urvarâm</i> over it).
No. 2 Frashast (<i>i.e.</i> , unnamed Dron).	No. 1 Dron (named) with <i>goshudô</i> over it.	A small vessel containing âp or water
	Place of the priest who recites the Baj either standing or sitting	

Chapters recited in the great Baj.

Chapters three to eight of the Yasna are known as Srosh-Dron. They are so called because certain selected portions of these are recited in the celebration of the Baj for the consecration of the Dron. At first, an introductory prayer in Pazand which is known as the Dibache is recited. Therein, the name of the person – either living or dead – for whose *naiyat*, *i.e.*, for whose intention or purpose the ceremony is performed, is mentioned. The name of the particular Yazata or angel in whose honor the Baj is recited is also mentioned in the Dibache. After the recital of the Dibache, the chapters of the Srosh Dron are recited. During the recital of the eighth chapter, the priest makes the *Dron-châshni*, *i.e.*, partakes of the sacred bread consecrated by him. He partakes of it five times in small bits.

Different kinds of the liturgical Baj.

There are different kinds of the Baj, recited by the priest as a part of the liturgical service. The chapters of the Yasna recited are mostly

the same, but the difference arises from the difference in the Beings in whose honor the ceremony is performed. The [339] following is the list of the different Bajis as given in Parsi books of ritual:

1. Baj of *pânc̄h tâi* or five wires of Barsom.
2. Baj of Srosh.
3. Baj of the Fireshti or Firashtâ.
4. Baj of Pantha Yazata.
5. Baj of Neryosang Yazata.
6. Baj of Haptoiringa.
7. Baj of Agrêras.
8. Baj of Vanant.
9. Baj of ruz Aspandad and mah Frawardin.
10. Baj of ruz Hordad and mah Frawardin, or Khordad Sal.
11. Baj of Jashan-i Tiragan. Ruz Tir mah Tir.
12. Baj of Jashan-i Mihragan. Ruz Mihr mah Mihr.
13. Baj of Jashan-i Abangan. Ruz Aban mah Aban.
14. Baj of Jashan-i Adargan. Ruz Adar mah Adar.
15. Baj of Frawardigan. Ruz Frawardin mah Adar.
16. Baj of the Disa, (*i.e.*, the anniversary of the death) of Zoroaster. Ruz Khwarshed mah Deh.
17. Baj of Jashan-i Vohumanyan. Ruz Vohuman mah Vohuman.
18. Baj of Avardad Sal-gah. Ruz Hordad mah Aspandad.
19. Baj of Din Beh Mahraspand. Ruz Mahraspand mah Aspandad.
20. Baj of Ardafrawash, *i.e.*, of all the Fravashis or Farohars.
21. Baj for the performance of the Khub in the Gatha days.
22. Baj of Gatha, (or the intercalary) days.
23. Baj of Chehârûm ni Bâmdâd, *i.e.*, the Baj to be recited at dawn on the fourth day after death.
24. Baj of Mino Râm for the *zindeh ravân* of the survivor of a married couple to be recited on the dawn of the fourth day after the death of any one of the two.
25. Baj of the Gahambar. [340]
26. Baj of the Haft Ameshaspand or the seven Archangels.
27. Baj of Siroza.
28. Baj of Nao Nawar, *i.e.*, the Baj recited by the Nawar or the new initiate into priesthood.
29. Baj of Rapithwin.
30. Baj Shehan.

We will shortly describe these different Bajis and their occasions.¹

¹ *Vide* my paper on "The Ketâb-i-Darun Yashten" in the Journal of the K. R. Cama Oriental Institute No. 1, for some other Bajis.

(1) Baj of Pâñch tâi

This Baj is so called, because, in its recital, five *tâis* or wires of Baj of Barsom (*Vide* Barsom ceremony) are used. It is recited by the priests for the performance of the small *Khub*, the celebration of which is required for the ceremony and recital of all the Bajis and of the Yasna, etc. The Barsom tied for the performance of this Baj is not used for the performance of any other Baj for which the Barsom must be freshly tied. The Barsom tied by a priest, who has performed the small *Khub* with this Baj of five wires, can be used for the recital of three more Bajis. The Barsom tied by a priest with the great *Khub* of Mino-Nawar can be used for the recital of nine Bajis. For the recital of more Bajis than nine, the Barsom must be freshly tied with its ceremonial.

During the recital of this Baj, the Pazand Dibache of Humata, Hukhta, Hvarshta, wherein, the name of the person -- living or dead -- for whom it is recited is mentioned, is repeated thrice. At the end, after the recital of Ha 8.4, the priest makes the '*châshni*' of the Dron or the sacred bread, *i.e.*, eats a small part of it. The *châshni* (*i.e.*, the tasting of the bread by the priest) forms an important part of the Baj. In the case of this Baj, the *châshni* is made five times. 1. At first, a small bit of Dron No.1 (*Vide* figure above) with a little *goshudô* or ghee, is eaten. 2. Secondly, a bit of the Farshast No.2 with a little *goshudô* (from No.1) is eaten. 3. Thirdly, a bit of the Dron No.3 with a little *goshudô* and with a little âp, *i.e.*, water, (*i.e.*, being dipped a little into the vessel of water) is [341] eaten. 4. Fourthly, a bit of the Farshast No. 4 is similarly eaten. 5. Fifthly, a little of the *goshtudô*, *urvar* and âp is eaten.

Other members of the congregation, if any, afterwards partake of the *châshni*. The sacred bread and other things are passed round for all to take a bit for *châshni*.

(2) Baj of Srosh.

While in the recital of all other Bajis four Drons or sacred breads are used, in the recital of this, six are used, half of which are 'named,' *i.e.*, marked with nine marks made with the recital of the words Humata, Hukhta, Hvarshta, (*i.e.*, good thoughts, good words, and good deeds), and half 'unnamed.' The three 'named' ones are arranged on the left-hand side in a tray and the three Farshast or unnamed on the right-hand side. The first one, *i.e.*, the one nearest to the priest in the left-hand row carries over it the *goshudô* or the ghee, *i.e.*, the clarified butter. The last one, *i.e.*, the one furthest from the priest in the right-hand row carries over it the *urvarâm*, (*i.e.*, some product of the vegetable world) represented generally by a few grains of the

pomegranate or a date. The recital of the Baj of Srosh generally concludes the recital of all Bajs. It is generally recited in all the Gahs or the five periods of the day during the first three days after death in the name of the deceased. In its recital, the Pazand Dibache is recited twice. In the case of the Srosh Baj, as there are six sacred breads instead of four as in the *Pânch tâi* and other Bajs, the officiating priest makes the *châshni*, (i.e., partakes of the offered sacred bread, etc.,) seven times instead of five as in the other Bajs. The two additional *châshnis* are of the two additional Drons, one of which is 'named' and the other 'unnamed' (Farshast). This Baj of Srosh is also recited for the consecration of *gehâns* or the iron-biers. At times, on the death of a person, his relations wish that a new bier may be provided. They get this bier consecrated before being used. That consecration is effected with this Baj.

According to an old custom still prevalent, the contents of the Srosh Baj, i.e., the offerings of sacred bread, fruit, etc., offered in this Baj, are taken by the priest as a part payment in kind of his fees. [342]

(3) Baj of the Fireshtes.

This Baj is recited in honor of the 33 *Fireshtes*, (فرشته i.e., Yazatas or angels). The recital of the Baj for each of these 33 Yazatas is the same (a large part of the Yasna, Ha 3 to 8) except in the following points:

(a) The Pazand Dibache of Humata, Hukhta, Hvarshta is recited twice (once in the very beginning and for the second time, after Ha 7.25) in the case of the Bajs of all the Yazatas, but in the case of the Bajs of those Yazatas, (e.g., Day-pa-Adar, Day-pa-Mihr, Day-pa-Din) in whose *Khshnuman* the formula of *Vispaesham Yazatanâm* occurs, it, as in the Bajs of *Pânch tâi* and Ardafrawash, is to be recited thrice (the third being recited with the Kardah of *staomi zbayemi* just before the recital of Ha 7).

(b) The *Khshnuman* for the Baj of each Yazata varies. The small *Khshnumans* recited in Ha 3, 4, 6, and 7 are taken from their respective *Khshnumans* in the smaller *Siroza*. The larger *Khshnumans* recited once in Ha 6 are taken from their respective *Khshnumans* in the larger *Siroza*.

(4) Baj of Pantha Yazata.

The word 'pantha' is Av. 'Pathan' (Sanskrit *panthan*, German *pfad*, English *path*). In the Khwarshed Niyayesh (verse 8) a straightforward road or path is considered as an object of praise (*pathâm khâstâtîm yazamaidê*). The word is figuratively used for a course of life and for prescribed rules for that course of life as in the case of the English

word 'path.'¹

Now a good spirit or a heavenly being was supposed to guide this path. From this idea, there was one step more, and it was supposed that some heavenly spirit or guide, guided all our movements even in our ordinary roads of travels, if one moved on straight and straightforwardly.²

So, this Baj of Pantha Yazata or the angel presiding over paths and roads was recited on an occasion when one went on [343] a long journey, so that God may guide his movements. It is rarely recited now.

(5) Baj of Neryosang Yazata.

Neryosang is the name of a Yazata. He is the messenger of God. He presides over a particular fire or a kind of vitality supposed to live in the navel of kings. He seems to resemble the Narâshâns of the Vedas who also is a messenger of God and is also the name of a fire. As he presides over a kind of fire, he has some connection with the phenomenon of Light, and as such he is the *collabateur* of Mithra, the angel of light. The Baj under consideration is recited in honour of this Yazata. It is not recited now, but seems to have been recited in old times on rare occasions.

(6) Baj of Haptoiringa.

Haptoiringa is the Avesta Haptôiring of the Yashts (Yt8.12; Yt12.28; Yt13.60). It is the name of a heavenly body. Dr. West thinks it to be Ursa Major. It is associated with Tishtrya (Sirius), Vanant (Vega), and Satvas (Canopus³). It has great influence on the waters of the northern seas (Bundahishn, Chap. 8.12). It is the Saptârashayahi of Pânini. The Yazata presiding over it guards, with 99,999 Farohars or good guiding spirits, the gates of hell and prevents the 99,999 demons residing there from escaping into the world to do harm to the good creation. This Baj is not recited now. It seems to have been recited in former times when people had greater faith in astrology.

(7) Baj of Agrêras.

Agrêras is the Agraêratha of the Avesta (Yasht 13.131; Yt9.22; Yt19.77). He is the Agraêrâd of the Bundahishn and Agriras of

1 Cf. "He marketh all my paths," Job 33.11; "Hold up my goings in thy paths." Psalm 17.5.

2 Cf. "All the paths of the Lord are mercy and truth unto such as keep his covenant and his testimonies," Psalm 25.10.

3 Vide Mr. M. P. Khareghat's paper on "The Identity of some Heavenly bodies" in the *Sir J. J. Z. Madrassa Jubilee Volume* (pp. 116-58.)

Firdausi. He was the brother of the Turanian King Afrasiyab [Franrasyan] and of Karsevaj, the Machiavelli of ancient Iran. It appears from the *Shah-Nameh* and from the *Bundahishn*, that when Afrasiyab shut up Minocheher, the king of the Persians, in the mountains of Pâdashkhvârgar and reduced them to straitened circumstances, Agrêras, though a brother of Afrasiyab, the enemy, like a kind, honest and straightforward man, prayed for the release of the Iranian [344] king, and his army. He helped them to free themselves from their confined position in the mountains. Afrasiyab is said to have killed his brother Agrêras for thus helping his enemy. Firdausi places this event in the reign of Naodar. (*Vide* the word Agraêratha in my Dictionary of Avesta Proper Names, pp. 7-10). For this exceptional service, Agrêras was considered to be one of the saintly worthies of ancient times, and, though a non-Iranian, was canonized in the saints' calendar of the Frawardin Yasht. Now, though the Parsi books of the Zoroastrian rubric give in the list of the Bajs, a Baj in the name of this Turanian saint, it cannot strictly be called a Baj, because there is no separate *Khshnuman* in his name. The Baj enjoined to be recited as the Baj of Agrêras is simply the ordinary Baj of Ardafrawash, with the instruction that the name of Agrêras may be recited in the place where the names of the departed ones are recited.

The reason for a Baj connected with his name as given in the list of the book of rubrics seems to be, that in former times, on exceptional occasions, perhaps people celebrated the anniversary of his death or celebrated the Baj of Ardafrawash in his honor in the fulfillment of a vow for a particular object. We have a recent instance of this kind. About 139 years ago, (in 1783), a Parsi of Broach named Homâjee Jamshedji was hanged by the British Government for the murder of a Parsi lady. The cause of the dispute which ended in the death of the lady arose from the controversy of the *Kabiseh* or the intercalary month which had produced a great schism among Broach, Surat, and Bombay Parsis. Many a people considered Homâjee to be innocent and to be a saintly person. So, even now, there are several persons who, on the anniversary of his death, celebrate his Baj, *i.e.*, get the Baj of Ardafrawash recited in his honor with his name. Some take a vow, that if they would succeed in such and such an object of their life, they would get his Baj celebrated.

(8) Baj of Vanant.

Vanant, according to the Avesta, is the name of a star (Yasht 20.1). It is supposed to be the star Vega. According to the *Bundahishn*, (2.7) at the end of summer, it was a southern star. It is an associate of [345] Tishtrya (Sirius). It has an Yazata of the same name presiding over it. This Yazata observed a watch over the Alburz mountains. It enabled

the Sun, Moon, and other heavenly bodies to move undisturbed in their movements. With Tishtrya who presided over rain, it had some influence over rain. It was supposed to have a special influence in withstanding the evil influences of the Devs or the evil spirits. To emphasize this belief, the priest, while reciting its *Khshnuman* (vanantô stâro mazdadhâtahê aôkhtô nâmanô yazatahê) in this Baj, strikes a stick over a stone, thereby showing that the evil influences may be struck and annihilated. In the recital of this Baj, the priest makes five chashnis as in the case of the Baj of the five wires (*Panch tâi*) of Barsom and of other Bajs (except that of Srosh), but with this difference, that four of the *chashnis*, instead of being made from the four sacred breads, are made from only two of the breads — one named and the other unnamed (*frashast*). This Baj is recited only on ruz Ohrmazd mah Frawardin, *i.e.*, on the New Year's Day [Nawruz]. In the recital, the *frashast* is required to be lifted up and then lowered and then turned round in all directions (Dasabhoy Kawasji's Avesta Bk. II. p. 184).¹

The ceremony of *Vanôt Kâpvi*, connected with this Vanant.

There is a ceremony known as *Vanôt Kâpvi*, *i.e.*, to cut the Vanôt, which is connected with the name of this Vanant Yazata, whose Baj is under consideration. The word Vanôt is the modern corrupted form of Vanant. By the name Vanôt is meant a Dron or sacred bread prepared and consecrated in the name of the Yazata. A priest takes, *i.e.*, recites the particular Baj known as *Vanôt ni Baj*. It consists in the recital of the ordinary Pazand prayer of "Pa nãm-i-Yazdân" with the *Khshnuman* of Vanant. After reciting the larger *Khshnuman*, the priest recites a *Yatha Ahu Vairyô* and divides the bread with a knife into four parts. For each bread that he has cut, he recites a *Yatha Ahu Vairyô*. Having done so he finishes the Baj. This ceremony is also performed on the New Year's Day. The Dron of Vanôt differs from [346] other Drons in this that it is sweetened a little. That the prayers and ceremony connected with the Vanant Yazata were believed to have a charm-like effect in withstanding the influence of evil spirits or mischief-making bodies, is shown by the fact that a part of the recital of the Vanant Yasht, which can be recited even by a layman, is accompanied by a clapping of hands, Once, twice, and thrice, to emphasize thereby that the evil influences are struck, beaten and annihilated.

Bajs of other Jashan days. Bajs from No. 9 to No. 22.

The other Bajs, from Baj No.9 to Baj No.22 require no particular

1 Cf. The Christian ritual, wherein also the sacred bread is lifted, lowered, and turned.

mention, except this, that they have their own particular Khshnumans. The Baj of the day known as *Zartosht no diso*, i.e., the anniversary of the death of Zoroaster (Ruz 11th Khwarshed of the 10th month Deh), though named as a separate Baj (No.16) in the list of Bajs given in the Parsi books of ritual and rubric, is not strictly speaking a separate Baj. The Baj recited on that day is the Baj of Ardafrawash recited in honor of the dead. The name of the Prophet is mentioned therein as that of the person in whose honor it is recited.

(20) The Baj of Ardafrawash.

The Baj of Ardafrawash in the above list requires a little explanation. The word Arda in Ardafrawash is the later form of *asha* (cf. *Asha Vahishta* and *Ardi-behest*) and Frawash is the later form of *Fravashî*. So Ardafrawash is the later form of "*ashaonām Fravashinām*," i.e., the Farohars or the guiding spirits of the holy. Hence the Baj of Ardafrawash is the Baj in honor of the Fravashis or the Farohars, i.e., the spirits of the departed ones. The liturgical services in honor of the dead, whether the *Yasna*, the *Vendidad*, the *Afrinagan*, or the Baj, are celebrated with the *Khshnuman* of Ardafrawash which is the *Khshnuman* of Frawardin, the 19th Yazata. The chapters of the *Yasna* recited in this Baj are the same as in other Bajs, but the Pazand Dibache of *Humata*, *Hukhta*, *Hvarshta*, wherein the name of the deceased person is mentioned is, instead of being recited twice as in the case of all the Bajs, is repeated thrice [347] as in the case of the Baj of *Pânc̄h tâi* and of the Baj in whose *Khshnuman* the formula of *Vispaeshām* occurs. The third Dibache is repeated with the additional recitals of the prayer of *staomi zbayemi* (*Yasna*, Ha 26), which is a special prayer in honor of the dead and which is known as *Satum no kardô*, i.e., the section or chapter of *Satum* or the prayer for praising the dead. (*Vide* below for the *Satum*).

(23) Baj of Chehâram ni Bâmdâd.

The dawn (*Bâmdâd*) of the fourth day (*chehâram*) after one's death is held to be the most important occasion in connection with the funeral ceremonies of the dead. The soul of the deceased is believed to hover for the first three days in the precincts of the world. It is at the dawn of the fourth day, that it passes away, out of the precincts of this world, to the other world. While so passing away, the soul is judged by *Mihr Dâver*, i.e. *Mihr* the Judge. So, this is considered to be the most important occasion for the recital of the Baj. Four Bajs are recited on this occasion, i.e., in the *Ushahin Gah* or after midnight of the third day. They are the following:

1. The Baj of *Rashnê Astâd*, i.e., with the joint *Khshnuman* of the *Yazatas* *Rashn* and *Ashtad*, who help *Mihr* in his work of justice.

Rashn presides over Truth and Justice. According to the Menog-i Khrad, he holds the balance of justice in his hand. Ashtad presides over Truth.

2. The Baj of Ram. The Yazata Ram presides over air and over ethereal substance. The soul now passes to the other world through the ethereal sphere of space. The Yazata Ram also presides over *Ramashni* or joy. So, the occasion being that of the transition for the soul, and therefore mournful for the survivors, the words *Râmnô Khâstrahê* which refer to his function of spreading joy is omitted when the Baj of Ram Yazata in honor of the dead is recited on this occasion. They are recited on other occasions after the third day.

3. The Baj of Srosh or the angel who protects and guards the souls of all persons whether living or dead. [348]

4. The Baj of Ardafravash.

These four Bajs are generally, though not always, repeated with the name of the partner of the deceased, *i.e.*, with the name of the husband, if the deceased is a woman, or of the wife, if the deceased is a man. The ceremonies of the first four days are generally performed for both members of the married couple, whether the other partner is living or dead. It is then spoken of as "*Jodâ ni Kriya*," *i.e.*, the ceremonies of the (married) pair.

(25) Baj of Gahambar.

This Baj is recited only on the occasions of the six Gahambars - or seasonal festivals.

(27) Baj of Siroza.

Siroza means thirty days. It is so called because therein all the thirty (*si*) Yazatas which preside over each of the thirty days (*ruz*) of the month are invoked in the words of their respective *Khshnumans*. This Baj is recited on the thirtieth day after one's death, and on the days preceding the day which finishes the periods of six months and a year after one's death. It is also recited by the new initiate into the priesthood, the Nawar, on the third of the last four days when he officiates at the completing ceremony.

(28) Baj of Nawar.

This is recited by the Nawar or the initiate into priesthood in the afternoon of the first of the last four days when he officiates at the ceremony of the concluding days.

(29) Baj of Rapithwin.

This is so called, because it is recited on the Rapithwin day, *i.e.*, the

third day, Ardwhisht, of the first month of the year.

(30) Baj of Shehan.

The word *Shehan* comes from *Shêh* or *Shâh*, i.e., king. It means royal. It is rarely recited now. It was recited formerly on very rare occasions when any great calamity or difficulty was believed to have overtaken the king, the community, or the country. Its recital is longer than all other Bajs because it is recited with two repetitions of the Khshnuman of Siroza, two of that of Srosh, and two of that of Ardafrawash. [349]

(B) Bajs recited are recited on smaller occasions.

Now we come to the second class of the Bajs – the Bajs that are recited on smaller occasions. They are recited without any offerings and some of them are recited even by the laity. While the recital of the Bajs of the first class (A) takes from about a quarter of an hour to half an hour, the recital of the Bajs of this second class (B) takes from half a minute to five minutes.

The following is a list of some of the smaller Bajs recited on different occasions:

- (1) Baj or prayer of grace to be said before meals.
- (2) Baj to be recited when answering calls of nature.
- (3) Bajs for consecrating certain things used for ceremonial purposes.
- (4) Baj for bathing.

We will speak of some of these smaller Bajs.

(1) Baj or prayer of grace recited at meals.

There are three kinds of *Jamvâni Baj* or prayers of grace recited before meals.

- (a) The great Baj with the Barsom.
- (b) The great Baj without the Barsom.
- (c) The small Baj recited at ordinary meals.

(a) The great Baj with the Barsom.

This Baj rather belongs to the Bajs of the first order A, but we speak of it under this head for the sake of conformity with the other Bajs of meals.

The priests who observe the *Khub* for the performance of some great liturgical services, as the *Yasna* or the *Vendidad*, have to say this

great liturgical Baj referred to above before taking their meals. It consists of the recital of a large part of chapters 3 to 8 of the Yasna with the Dibache. The recital is the same as that of the first kind of Baj which is recited as a part of the liturgical service. It is recited with the Barsom. The priests who observe the *Khub* cannot even drink water without reciting this great Baj. When there are several priests who observe the *Khub*, each and all of them need not recite the whole of this Baj. One of them recites the whole and [350] the others join him at the end at the recital of the eighth chapter of the Yasna wherein the officiating priest makes the *châshni*. They participate in the *châshni* and then take their meals. This Baj is recited in a separate place enclosed in *pâvis*.

(b) The great Baj without the Barsom.

This Baj is recited by the priests with their meals before them. It is a short recital lasting for a few minutes. It is recited at solemn feasts, e.g. at feasts on the anniversaries of deceased persons, at the celebration of Gahambaras, Jashans, etc. The diners first perform the *padyab kusti* and then wash their hands, and then, having their meals before them, recite 3 Ashem Vohus and Fravarânê, mentioning the particular Gah or period of the day at which they take their meals. They then recite Yasna, Ha 8.3-4, Ha 37.1. Then they recite in Baj the Pazand Dibache of Humata, Hukhta, etc., therein mentioning the name of the person in whose memory the solemn dinner is given. Having recited this they take their dinner silently.

In such solemn dinners, it is generally the custom to set apart a morsel of bread for the dogs of the street. The morsel is called *Kutrâ nô book*, i.e., the morsel for the dog (*Vide* below Satum). After finishing their meals they wash their hands and then finish the Baj. To finish this Baj (*Baj mukvi*), they at first say in Baj the Pazand prayer of Tan-Dorosti, naming the person who gave the dinner and invoking benedictions upon him. They then recite Yasna 8.5-8 and the Yasnemcha, etc.

(c) The small Baj recited at ordinary meals.

This Baj is to be recited at all ordinary meals, even by laymen. It takes about half a minute to recite it. It consists in the recital of a part of the first passage of the 37th chapter of the Yasna with a few introductory words in Pazand. It appears from Firdausi that even in the recital of Baj or prayers of grace at the table, it was a religious custom in Sasanian times to use the Barsom. It was a custom that led to a dispute between Bendui, a courtier of King Chosroes II (Khosro Parviz) and Nyâtush, a courtier of the Emperor of Rome. (*Vide my Glimpse into the work of the B. R. R. A. Society*, p. 89). [351]

Silence observed during the meals.

It is enjoined that after the recital of the Baj or grace before the meals, one must hold silence and take his meals in silence and not to talk or speak during the meals. If one has to speak for urgent purposes, he may do so, not with his mouth open and in the open ordinary tone, but in a suppressed tone, and that as little as possible. This utterance with a suppressed tone is technically said to be “speaking in Baj” (*bâjmâ bolvun*).

Reasons assigned for holding silence during meals after the recital of Baj.

Xenophon refers to this custom of holding silence during meals, and says that it was enjoined with a view that there might be no excitement while partaking of meals. This explanation of the custom corresponds with what is said to be given by medical men at present that a meal when disturbed with some exciting conversation is not easily digested and that therefore there must be a perfect peace of mind during the meals. Maçoucdi (Vol. II, p. 108) says that it was Kayomars who enjoined silence from a health point of view (*Vide my Asiatic Papers* Vol. II, p. 283). The Indian Purâns also refer to this Iranian custom.

Albiruni, a Mahomedan author, says that this custom of holding silence during meals was introduced in ancient Persia in the time of its Peshdadian king Faridoon. When this monarch freed Persia from the tyrannous yoke of Zohak, the people resolved to observe this custom as an expression of gratitude to God for the boon of freeing them from the thralldom of Zohak (Albiruni's *Chronology*, p. 209). Ammian is said to refer to this custom. He says that the ancient Persians were prohibited from speaking while dining. The reason which he is said to have given, *viz.*, “nothing might get polluted by the spittle”¹ does not seem to be correct.

Completion of the Baj. Baj dharvi and Baj mukvi.

The recital of the Baj or grace before meals is technically spoken of as *Baj dharvi*, *i.e.*, to hold the Baj. After the meals, a small prayer is again recited. That is technically spoken [352] of as *Baj melvi* or *Baj mukvi*, *i.e.*, to give up the Baj. It is only after reciting this that the eaters are to break their silence. After this recital they generally perform the *kusti*, *i.e.*, untie and retie the *kusti* with the recital of its *nirang* or prayer.

1 *The Religion and Customs of the Parsees*, by Dr. Adolph Rapp, translated by K. R. Cama, p. 302.

(2) Baj recited at natural functions.

A person when going to answer the calls of nature has to take a Baj and after performing the function, to finish it. It is generally known as “*pishâb ni Baj*,” i.e., the Baj recited while passing water. When at about three steps from the appointed place for the purpose, he recites “*Guneh shekastê sad hazâr bâd*” (i.e. May wrong actions be done away with hundred thousand times) and an *Ahunwar*. Then after performing the natural function, and after retiring for about three steps, he finishes the Baj. To do this he has to recite *Ashem Vohu* thrice, *Yasna Ha 35.2*, twice, *Ha 35.5*, thrice and then *Ha 18.9*, once.

(3) Baj for the consecration of certain religious requisites.

There are several Bajs or prayers which are recited for the preparation and consecration of certain things required in the ritual. For example, the sacred thread [*kusti*], after being prepared by the women of the priestly class, is cut and consecrated by the priest with the recital of the smaller *Srosh Baj* and a particular *nirang*. (*Vide* above p.184).

(4) Baj for bathing.

Before bathing, one recites the *Srosh Baj* up to the word *Ashahê* in the “*kem nâ Mazdâ*” prayer and then unclothes himself and bathes. Then having put on the clothes, he finishes the Baj commencing with the words “*nemaschâ yâ Armaitish izhâchâ*” and then puts on the *kusti*.

Technical phraseology about the Baj.

In the recital of all the Bajs there are three stages:—(1) The commencement of the recital of the Baj. It is technically spoken of as “*Baj dharvi*” or “*Baj levi*,” i.e., “to hold the Baj” or “to take the Baj.” (2) Then follows the function itself, whether [353] it be that of taking the meals, bathing, consecrating a thing or anything else. (3) Then follows the recital of the concluding portion of the Baj which is spoken of as “*Baj mukvi*.” i.e., to lay down or finish the Baj.

The object aimed at in the recital of the Bajs and Nirangs.

Some of these Bajs and Nirangs, which are lesser forms of prayer formulae, recited on small petty occasions, are rarely recited now, and most of them are recited by the priestly class. The object which led to their composition and compilation at first was to indicate that a man must take a serious view of life, and see that even in the enjoyment of God’s blessings and in all kinds of work, there is always, what can be called a religious side of the question. When a thing has to be done, let it be done with the ultimate view of doing good to all around us, It

meant to indicate that as Ruskin said “There is religion in everything around us.”

A religious bent was thought to be given to every action, so that, in the end, it may lead to ennoble the mind. As a writer¹ says: “Every act and function of the body should be consecrated to the soul and mind; the traveler on this way should pray unceasingly, by devoting his every act unto his God, thinking when eating: “As this food nourishes the body, so may the food of wisdom nourish the mind;” and when bathing: “As this water purifies the body, so may the water of life vivify the mind;” or when freeing the body of impurities: “As these impurities pass from the body, so may the refuse of opinion pass from the mind.” [354]

1 G. R. Mead, *The Gnosis of the Mind*, London, 1906, p. 13.

CHAPTER XVI. THE OUTER LITURGICAL SERVICES. (I) THE AFRINAGAN CEREMONY.

As said above, by the Outer Liturgical Services, I mean, “those religious services which may be, but need not necessarily be, performed in a Dar-e Mihr or a place specially allotted for the purpose. They can also be performed in any ordinary or private house or place. Again, they may be performed by any priest, even by one who does not observe the Bareshnum, or by one who has only gone through the Na.var and not the Martab initiation.” These Outer Liturgical Services are:— I. The Afrinagan. II. The Farokhshi, and III. The Satum.

I—The Afrinagan of the Parsees and the *Âpri* of the Brahmins.

The word Afrinagan comes from the root *fri*, Sanskrit *pri*, to love to praise. So an Afrinagan is a prayer expressive of love or praise. Perhaps, it has received this name from the fact, that that part of it which is common to all Afrinagans begins with the word *âfrinâmi*. (*Âfrinâmi Khshathrayân danghu paiti*, etc.) i.e., I pray for, etc. According to Dr. Haug, “in the Afrinagan ceremony of the Parsees there may be discovered a trace of the Brahmanical *Âpri* ceremony The name is the same: *â-pri* in Sanskrit, *â-fri* in the Avesta, which literally means ‘to invite;’ with which invitation the name of the being or beings, in whose honour the ceremony is being performed must always be mentioned.”¹

The Participants. The *Zoti* and the *Râthwi*.

The Afrinagan prayers may be recited by all priests, even by those not observing the Barashnum and even by those who have not gone through the second degree of Martab. They are performed generally by two or more priests. At times—and that very rarely when a second priest is not available — they are recited even by one priest. The senior, who [355] begins the ceremony with the recital of the Dibache, is called *Zoti* or *Joti* which is the later form of Avesta *Zaotar*, lit., one who performs the ceremony. He is so called, because he is the principal performer of ceremonies. The other is called *Âtra-vakhshi*, i.e., one who keeps up or feeds (*vakhsh*) the fire (*Âtar*). He is so called, because he sits near the fire vase and feeds the fire. He is also called *Raspi*, i.e., assistant, from Avesta root *râs* to help. He is also spoken of as *Râthwi*, i.e., an offerer from *râ* or *râd*, to give. The two priests who officiate at the Yasna, the Visperad, and the Vendidad ceremonies are also similarly called the *Zaoti* and the *Atravakhshi* or *Raspi* or *Râthwi*. Any number of priests can take part in these

¹ Haug's *Essays*, second edition, p. 284.

ceremonies. Only one can act as Zoti, the rest who join the Atravakhshi act as Raspi. Even laymen can participate in the prayer as Raspis. Again, the Afrinagans can be recited anywhere, even in private residences and need not have any special or enclosed space. Their recital must begin, as in the case of all prayers, with Padyab-Kusti. Though any number of priests can take part in an Afrinagan ceremony, it is only two who perform the actual ceremony.

Parts of an Afrinagan.

Each Afrinagan is divided into three parts. I. The Pazand Dibache, II. The Afrinagan proper in the Avesta language and III. The Pazand Afrin.

Of these three parts, the Zoti recites all the three and the Atravakhshi, Râthwi or Raspi recites with him only the second part. We will describe these three parts:—

1. The Dibache.

In the matter of all liturgical services, the Dibache is the principal part. One must clearly understand what the Dibache is, so that he may have a clear grasp of the object of the Liturgical services.¹ The word Dibache (دیباجه) is Persian and means “preface.” It is made up of *dibâ* (دبیا) brocade and the diminutive particle [356] *chēh* (چه). So, literally, it means “the lesser brocade.” As brocade, which is a kind of silk stuff, is superior to other stuffs, so, the preface (dibache) which precedes a book is superior to other parts of the book, inasmuch as it is often written in a good ornamental style and prepares the reader for what he expects to read in the book. In the Afrinagan prayer also, the Dibache is the principal part, wherein the reciter announces the subject or the name of the particular Afrinagan which is to be recited, the name of the person, living or dead, in whose honour the prayer is recited, the name of the person who directs (*farmâyashné* فرمایشنه) the performance of the ceremony, etc. The more proper rendering of the word in the case of the Dibache of the Liturgical services of the Parsees would be, I think, “Exordium,” meaning the introductory part of the service which prepares the audience or the congregation for the main rmbject of the service. The Dibache plays a prominent part in all liturgical services — in the Yasna, Vendidad, Visparad, Baj, Afrinagan, Farokhshi, Satum, Pâvi, etc. All these services have a Dibache which is almost common. It is written in the Pazand language and, as its name implies, is to be recited in the beginning of prayers. It is so recited, for example in the beginning of the Afrinagans. But in the case of long

1 *Vide* for translation, Spiegel, translated by Bleek, *Khordeh Avesta*, 172. Spiegel is wrong in speaking of it as “Prayers after the Afergâns.” It is a “Prayer before the Afrinagans.”

services which have long recitals of more than one prayer or of an aggregation of prayers, it has to be recited in the midst of these services. For example, though in the case of the Afrinagan it precedes, as its name implies, every Afrinagan, yet the Afrinagan ceremony as a whole being an aggregate of several Afrinagans, the Dibache, besides being repeated in the very beginning, has to be repeated in the midst of the whole ceremony or recital before each separate *kardeh* or section of the Afrinagan.

Now the general rule of the Zoroastrian rubric is this: All prayers written in the Pazend language or even in the later Persian language, when they precede or occur in the beginning of the Avesta prayers, or when they occur at the end, are recited in the ordinary open loud tone in which we ordinarily speak. But, when they occur in the midst of Avesta prayers or of an aggregate of prayers, they are recited in a suppressed low [357] muttering tone which is then said to be uttered in *Baj*.¹ So the Pazand Dibache, when recited in the beginning of a prayer, is recited in the ordinary open loud tone, but when recited in the midst of a prayer, a ceremony or an aggregate of prayers, it is recited in *Baj*.

The Dibache of the Afrinagan is like the Dibache of all liturgical services, but it has one additional thing, *viz.*, that in the very beginning it announces (a) the number of Ahunwar prayers that are to be recited with the Afrinagans proper, and (b) the gah or period of the day in which the ceremony is performed. An Afrinagan can, like the *baj*, be recited in any part of the day.

We said above that the Dibache or the exordium announces to the audience or the congregation the main subjects of the service. Those main subjects are two:

(A) It announces the name of the Yazata or the Heavenly being in whose honour, or for whose glorification or invocation, the service is celebrated or the ceremony performed. (B) It announces the name of the person — living or dead — in whose honour or memory the service is held and the name of the person at whose instruction or direction it is held. The technical phrases for these two kinds of announcements are—

1 Pers. *baj* باج “a silence observed by the Magi at meals and while performing their ablutions” (Steingass, *Persian Dictionary*). The prayer muttered in a low tone is also said to be uttered in *bâj*. The (زمزمه) *Zamzama* referred to by Firdousi and other Mahomedan writers, is this recital in *baj*. As Maçoudi, says, the illiterate speak of the Avesta as *Zamzama*. “Il. (Zeradect, fils d’Espiman) fut le prophète des Madjou (Guèbres) at leur apporta le livre que le vulgaire appelle Zemzemeh, mais dont le vrai nom, chez les Madjous, est Bestah (Avesta).” (Maçoudi traduit par Barbier de Meynard, Vol. II, p. 124).

(A) *Khshnûman*, and

(B) *Yâd*.

We will speak of these two here at some length, so that these words which occur often may be clearly understood. [358]

(A) *Khshnûman*.

The word “*Khshnûman*” comes from the Avesta root *khshnu* (Sanskrit *khshnu* ≍ १३▼) to please, to rejoice, to gladden, to satisfy. So the word *Khshnûman* means “joy, satisfaction, pleasure.” Now all the Parsee liturgical ceremonies are performed and the accompanying recitals are made for the *Khshnuman* of God, his Amesha Spentas or the Archangels, his Yazatas or angels, — in short, for the *Khshnuman* of God and His Heavenly Beings. They are celebrated in their Glory, to glorify them, to rejoice them, to satisfy them. All Parsee prayers, whether great or small, whether liturgical or non-liturgical, begin with the words “*Khshnaoθra Ahurahê Mazdâo, Ashem Vohu*” i.e. “I say this or I do this) to please or glorify the Great Omniscient Lord.” So, the Dibache announces the *Khshnuman* of the particular Heavenly Being or Power in whose honour or for whose glorification the ceremony is performed and the recital made. For example, if the service is for the *Khshnuman* or glorification of Ahura Mazda, the Dibache announces it in the words “*in Khshnûman i-Hormuzd Khudâi be-resâd*,” i.e., “may this (service) be (lit. arrive) for the pleasure, joy or glorification of Ahura Mazda.” If it be for the Yazata Vohuman, then the words used are “*in Khshnûman-i-Bahman Ameshâspend be-resâd*,” and so on, according as the Yazata or the Heavenly Being or the angel be one or another. If it be in the celebration of a Gahambar, i.e., a season festival, then the particular Gahambar which is being celebrated or commemorated is mentioned. The general formula for the announcement of the *Khshnûman* is “*in Khshnûman-i-N. N. ...¹ be-resâd*.”

When the *Khshnûman* is thus announced in the Dibache, then, in the Afrinagan proper, the recital of which follows that of the Dibache, after the recital of the particular Gah or time of the day in which the service is held, the appropriate respective formula praising that particular Yazata and describing his attributes is recited. These formulas are said to be the particular [359] respective *Khshnumans* of those particular Yazatas. These *Khshnûmans* are two: one is said to be *nâni* नानी or the small *Khshnûman*, and the other *vadi* वदी or greater *Khshnûman*. They are taken from the Siroza prayer or the Siroza Yasht, which also is said to contain the *nânâ* or the small Sirozas and

1 Here the name of the Yazata or the Gahambar, etc., is mentioned.

the *vadâ* or greater Sirozas. The small *Khshnûman* is recited after the word *frasastayaêcha* in the recital of the Gah and the greater after “*Vidhvâô mraotû*.” In the recital of the *Khshnûman* of the Yazatas, the *Khshnûman* of Ahura Mazda and the Amesha Spentas always precedes, *i.e.*, the worshipper first declares, that the service is held for the *Khshnûman* or glorification of Ahura Mazda, or God himself, and of His Amesha Spentas or the Archangels, and then for that of the particular Yazata named. The small *Khshnûman* is repeated in the *Yasnemcha* prayer which generally ends all prayers.

The following words in the recital of the Dibache draw our special attention: *Pa ganj-i Dâdâr Ahura Mazda rayômand khorehmand Ameshaspand be-resâd*, *i.e.* “May these (celebrations) arrive to the treasury of the Brilliant and Glorious Ahura Mazda and the Amesha Spentas.” What is meant is this: The worshipper has to pray with a view to ask for God’s blessings over all. His prayers are to go to the treasury (*ganj*) of God, from which there may be a general distribution to all. The influence of even one individual worshipper is far-reaching. His prayers spread their influence round about, in his household, in his city, in his country. He is to pray, not for himself but for many round about him. The words of the Afrinagan point to what Herodotus (Bk. I, 132) says of the ancient Persians, that they prayed not only for themselves but for the whole community, at the head of which stood the King.

(B) The Yâd in the Dibache. The Zindeh ravân and the Anousheh-ravân.

The word *yâd* is Persian and means “remembrance.” All the liturgical services, besides being performed in honour of a particular Heavenly being or beings, are celebrated in the name or in the memory of somebody who is named in the [360] recital. The words used are “*aidar yâd bâd*,” ايدر ياد باد *i.e.*, “may be remembered here.” The services may be performed in the name or in the memory of the living or the dead. If it is performed for the living, it is said to be performed for the *Zindeh-ravân*, *i.e.*, for the living soul. If for the dead, for the *Anoushêh-ravân*, *i.e.*, the immortal soul (of the dead). The word *Anoushêh-ravân* is *Anaoshâ-urvan* of the Avesta, *i.e.*, immortal-souled. It is an epithet applied to the dead in religious phraseology.¹

The following are the different forms of the nomenclature used for the *Yâd* in the Dibache. Suppose that the ceremony or service is for

1 It is this word *Anousheh-ravân*, which gave to Chosroes I, his Persian name Noshirvân. The modern Parsee name Noshervanjee or Nusserwanjee comes from it.

one Jamshed who is the son of Rustam. 1. If Jamshed is living his name is recited thus: “*Nam chishti¹ Zindeh-ravân Behedin Jamshed Behedin Rustam aidar yâd bâd,*” i.e., “May the person with a living soul and bearing the name Behedin Jamshed (son of) Behedin Rustom be remembered here.” 2. If the person is dead, his name is recited thus: “*Nam chishti Anousheh-ravân Behedin Jamshed Behedin Rustam aidar yâd bâd Anousheh-ravân ravâni,*” i.e., May the immortal-souled person bearing the name Behedin Jamshed (son of) Behedin Rustam be remembered here. In the first case, viz., of the *Zindeh-ravân*, if the father of the person be living, for the last words “*aidar yâd bâd*” the word “*be-resâd*” i.e., may good or help reach him, is used.

The word Behedin in the above formula means a layman, lit. one of the good religion. If the person belongs to a priestly class [361] and has gone through the first degree of priesthood, the epithet ‘Ervad’ (Pahl. *herbad* from Av. *aethra-paiti*, i.e., a master of learning, a teacher) is used instead of ‘Behedin.’ If he belongs to the priestly class but has not gone through the degree of priesthood, he is spoken of as “*ostâ*” (Av. *hâvishta* a disciple, a learner). If the person is a lady of the priestly class, she is spoken of as “*Osti*.” If the person is a high priest, he is spoken of as “*Dastur*.” Similar appellations are added to the name of the father according as he is a priest or otherwise.

Farmâyashna, or the name of the person directing the performance of the ceremony.

The recital of the name of the person, whether dead or alive, for whom the ceremony is performed, is followed by a mention of the name of the person who directs that the ceremony may be performed. The formula adopted for this announcement is “*Farmâyashna Behedin N.² Mazdayasni be-resâd,* i.e., “This ceremony is performed at the direction of the Mazdayasnian Behedin N. N. May help or good come to him.” The name of the elder or the head of the family is generally mentioned as the person directing the performance of the ceremony.

1 *Nam-chishti*, from Av. *nâman*, name, and *chishta* from *chish* or *chîsh* to give, bestow, attribute, means “the person to whom such or such a name has been given or attributed.” The word may also mean famous, celebrated. Later translators translate the word by *nâm-ba-nâm* (K. E. Kanga’s *Khordah Avesta*, eighth ed. Afrin-i Ardafarosh s. 13) when it occurs in the Afrinagan and Afrin. But that meaning does not seem to suit there. It may suit in the Pahlavi Vendidad (1:21; 3:41; V, 34, etc.), where it occurs in the sense of details. (*Nam-chishtik lâ goft ikvimunet*, i.e., the details are not given).

2 Here the name of the person directing the performance is mentioned.

II. The Afrinagan proper. Its (a) variable and (b) invariable parts.

The Afrinagan proper consists of two parts: (a) The Variable part and (b) The Invariable part.

(a) On the completion of the Dibache, which is recited by only one of the priests, the other priest joins him in the recital of the Afrinagan proper. At first, the number of the Ahunwars, which varies according to the nature of the Afrinagan as referred to above, are recited; then follow the recital of the formula of the *gah* or the period of the day, and that of the *Khshnûman* of the Heavenly Being in whose honour it is recited. Then follows the particular *Kardeh* of the Afrinagan. The following table gives the names of the Afrinagans and the particular *Kardeh* or section of the Avesta that is recited in it and the number of Ahunwars with which each Afrinagan begins (vide [362] *Darab Hormuzdyar's Rivayet* by Ervad M. R. Unwala, Vol. I, p. 15):—

	Names of the Afrinagans.	No. of Ahunwars.	Names of the Kardeh or sections recited.	When to be recited
1	Afrinagan of Dadar Ohrmazd	10	Tâo ahmi nmânê (Y60:2-7)	On any day.
2	Afrinagan of the Fireshtes or the Yazatas	7	Ditto (Some recite "Yâo Visâd" Kardeh.)	On any day.
3	Afrinagan of the Sirozas	7	Ditto.	On any day. Especially the 30th day after death and on the day preceding the first anniversary after death.
4	Afrinagan of Ardafrawash	8	Yâo Visâd.* Yt. 13.49-52, 156, 157. * (Some recite "Tâo ahmi nmânê," restricting "Yâo Visâd" to the last ten days of the year.)	On any day. It is the special Afrinagan for the dead. [363]
5	Afrinagan Dahman	2	Tâo ahmi nmânê	On any day. These Afrinagan Kardehs are recited after all kinds of Afrinagan.
6	Afrinagan of Sraosha	5	First three sections of Srosh Yasht (Y57:1-8.)	On any day. These Afrinagan Kardehs are recited after all kinds of Afrinagan.
7	Afrinagan of Rapithwin	12	Athâzi mraôt. (It	Only on the

			has a special Kardeh of its own.)	Rapithwin Jashan day, i.e. the 3rd day (Ardwahišt) of the 1st month (Frawardin). [*] (That is the present practice, but some books of ritual give ruz 6, mah 1, and ruz 29, mah 7 also.)
8	Afrinagan of Gahambar	4	Dâtâcha aêtê Mazdayasna. (It has a special Kardeh of its own.)	On the five days of each of the six Gahambers.
9	Afrinagan of Gatha	8	Yâo Visâd	During the five Gatha days, i.e., the five intercalary days at the end of the year.
10	Afrinagan of Dahm Yazata	7	Tâo ahmi nmânê	On any day, but especially on the dawn of the 4th day after death.
11	Afrinagan of Mino Nawar	7	Ahurem Mazdâm. (It has a special Kardeh of its own.)	To be recited by the Nawar or initiate on the first of the four last days of his initiation.

[364]

(b) After the recital of the particular *Kardeh* which forms the particular Afrinagan, the second priest, the *Atravakhshi* gets up from his place and standing before the fire and holding a flower, now given him by the first priest, the Joti, recites with him the *Kardeh* of “*Afrinâmi Khshathrayân Danghu paiti*.”¹ This *Kardeh* is invariable and is repeated after the variable part of all Afrinagans. It contains an excellent prayer, invoking blessings upon the ruler of the land, on whose stable, just and kind rule depends the prosperity of the country and of the people. It is as it were an Avestan “God save the King.”

III. The Afrin. Its different significations.

The word *Afrin* [Âfrin] literally means “benedictions.” This part of the Afrinagan prayers, which is, like the first part, written in the Pazand language, is so called, because it is full of benedictions. These Afrins are generally recited, but they do not form a necessary part of the Afrinagan ceremony. One can, if he likes, finish the Afrinagan ceremony after the recital of the Afrinagan proper, by reciting the

1 Westergaard, p. 321 Afrigan-i Gahambar 14-19.

finishing-Baj. For example, in the Afrinagan of Sraosha, recited for the first three nights at the house where a man dies, no Afrin is recited. There are several kinds of Afrins. Some of these are such as must be recited on particular occasions and after particular Afrinagans. The recital of others is optional. They are the following:—

1. Afrin of Gahambar.
2. Afrin of Rapithwin,
3. Afrin of Ardafrawash.
4. Afrin of the names of Buzorgs, or the departed worthies.
5. Afrin of Myasht.
6. Afrin of Spitaman Zarthosht.
7. Afrin of the Hamkaras, or the Afrin of Dahman.
8. Afrin-i Gahambar pâvi.

I will describe these Afrins in brief.

1. Afrin of Gahambar.

It is an Afrin which can only be recited after the Afrinagan of the Gahambars on each of the five days of the Gahambars or the six season festivals. This Afrin consists of three parts, the first [365] and the last of which are Afrins proper.¹ 1. In the first part the worshipper prays that the spiritual strength of the ceremony and the ritual may reach all. 2. It is the second part which renders this Afrin the Afrin of Gahambar, because, in it particular references are made to the six Gahambars of the year, to the periods of the year when they occur and to the different grand objects² of God's creation connected with those periods. 3. The third part again contains some benedictions.

2. Afrin of Rapithwin.

It is so called because it is the Afrin which is specially recited after the Afrinagan of Rapithwin, which is recited on the third day, (Ardwahišt) of Frawardin, the first month of the year. It may be recited after other Afrinagans on other occasions. This Afrin can be divided into two parts:—1. The first part contains the general form of benedictions found in other Afrins. 2. The second part contains a list of the names of the departed worthies of ancient Iran. Their Farohars or guarding spirits are remembered and commemorated. It contains, as it were, two lists of canonization; one, of the worthies of the time of

1 *Vide* Spiegel, translated by Bleek, *Khordah Avesta*, p. 179.

2 The order in which the grand objects were created is well nigh the same as that in the Genesis, *viz.*, the Heavens, Water, Land, Trees, Cattle, and Man. The Genesis speaks of the Creation on six consecutive days but this Afrin gives intervals of days between each of the six creations as follows; 45, 60, 75, 30, 80, 75, thus completing the 365 days of the year, the first creation, *viz.*, the Heavens being created on the 45th day of the year.

the cycle of Zoroaster, and another that of the cycle of the Sassanian times.

3. Afrin of Ardafarosh.

It is so called because it is generally recited after the Afrinagan of Ardafrawash or Ardafarohar or Ardafarosh,¹ which is the Afrinagan generally recited in honour of the dead. The worshipper prays in this Afrin that the spiritual strength of the ceremony performed, or of the recital made, may be a source of pleasure and help to the Farohars or the spirits of all who have departed and all [366] who may depart, from the time of Gayomard down to that of the coming Soshyos.

4. Afrin of the names of the Buzorgs.

It is an Afrin in the strict sense of the word. It is so called, because it contains a list of the names of some of the departed worthies (buzorgs) of ancient Iran, such as, Zarir, Siavakhsh, Bejan, Gushtasp, Sam Nariman, Rustam, Asfandyar, and Jamasp. The particular traits of character in which they excelled are mentioned, and it is prayed that the living person, in whose honour or for whose benefit the ceremony is performed or the person at whose direction (*Farmâyashnê*) the ceremony is performed, may possess those traits of character. In this Afrin, the name of the director is specially mentioned and good wishes expressed for him. This Afrin is generally recited after the Afrin of Ardafrawash as an additional Afrin. Being a prayer of benedictions in the ordinary sense of the word it forms a part of the marriage service also. When so recited, the names of the marrying couples are mentioned therein and blessings invoked upon them.

5. Afrin of Myazd.

This Afrin has fallen rather into disuse. It is recited rarely. It seems to have been so called because it was recited with the *Myazd* (the offerings of fruit, flowers, water, milk, etc.) before it.

6. Afrin-i Spitaman Zarthosht.

While all the Afrins above referred to are in the Pazand language, this is the only Afrin in the old Avesta language. Strictly speaking, it cannot be put into the class of Afrins, by which term is generally understood prayers recited after the Afrinagans as benedictions, because it is never recited during the Afrinagan ceremony. But in the strict and literal sense of the word Afrin, it is a real Afrin or a benediction. It is addressed in the second person. It is so called

¹ *Ardâ* is Av. *arêta*, i.e., *asha* holy and *farosh* is Av. *Fravashi*. The word thus means "the holy spirits."

because it is said to have been composed by Zarthosht or Zoroaster and addressed to his royal patron king Gushtasp. Such being the case, its phraseology is to a great extent adopted, [367] even now, by the Dasturs and other priests when they present laudatory addresses to personages of the Royal family.¹

7. Afrin of Hamkârâ.

This Afrin is generally recited after the Afrins of Ardafrawash and of the Buzorgs. It can be recited alone after any Afrinagan. It is known by several following names: (a) Afrin of Hamkara. It is so called because the Hamkars (colaborateurs) of the Amesha Spentas are mentioned therein.²

(b) Afrin of Haft Ameshaspand. It is so called because the seven (haft) Ameshaspands or archangels are one by one mentioned therein; and the demons or Evil spirits whom they combat are referred to.³

(c) Afrin-i-Dahman. It is so called because the Dahmân, *i.e.*, the pious, the good, who had long since departed — from Gayomard, the Peshdadian King, to Asfandyar of the Kayanian dynasty — are remembered therein.

8. Afrin-i Gahambar Châshni or Afrin-i Gahambar Pâvi.

This Afrin is not strictly an Afrin, but it is spoken of as such. Only its first two sections form an Afrin, the rest being the Dibache referred to above. It is recited over wine and milk on the occasions of the Gahambars or season festivals. It is [368] so called because at one time, the celebrants sat within a place enclosed by a *pavi*.

Ritual of the Afrinagan.

Having described at length the different parts and kinds of the Afrinagan, I will now describe the ritual:— Two or more priests

1 For its translation vide Spiegel, translated by Bleeck, *Khordeh Avesta* XL, p. 140.

2 The colaborateurs of the seven Amesha Spentas are the following:—

1 Ahura Mazda—Dae-pa-Adar, Dae-pa-Mihr, Dae-pa-Din.

2 Vohuman (Vohumana)—Mah, Goshorun (Dravasp), Ram.

3 Ardwhisht (Asha Vahishta)—Adar, Srosh, Warharan.

4 Shahrewar (Khshathra Vairya)—Khwarshed, Mihr, Asman, Aneran.

5 Spandarmad (Spenta Armaiti)—Aban, Din, Ard (Ashishwangh), Mahraspand.


6 Hordad (Haurvatat)—Tir/Tishtar (Tishtrya), Ardafrawash (Frawardin), Wad/Gowad.

7 Amurdad (Ameretat)—Rashnu, Ashtad, Zam (Jamyad).

[See also below, p. 483.]

3 Spiegel translates it under this head. *Vide Khordeh Avesta*, translated by Bleeck, p. 176.

perform the Padyab-Kusti, as is usually the case, before commencing the prayers. They seat themselves on a carpet. On a sheet of white cloth, the Zoti has before him in his front a tray which contains myazd, *i.e.*, fruits and flowers of the season. At times, when there is a large quantity of the mycwl, there are more than one tray. Besides fruit and flowers, there are milk, wine, water and sherbet (or syrup) in the tray in small vessels or glasses. Then, next to the tray containing fruit, flowers, and the above things, there is a fire vase opposite to the Zoti. Near the vase, there is a tray containing sandalwood and frankincense. The following diagram shows the position of the priests and the arrangement of the trays, etc.



A The seat of the Zoti.

B The seat of the Raspi or Atravakhshi.

C Vase of the Fire with a ladle and tongs.

D Tray containing sandalwood and frankincense.

E Tray containing the myazd, *i.e.*, fruit, flowers, milk, wine, water, sherbet, etc.

Myazda and its *châshni* or communion.

The word *myazda* comes from the Avesta root “*mid*” Sanskrit *mid* to bestow. So, it means things religiously offered in ceremonies.¹ The dron or the sacred bread, fruit, flowers, [369] wine, milk, etc., which are offered, and over which prayers are recited are all jointly known as *myazda*. The Fravashis or the guarding spirits of the departed ones take delight in coming to the place where such myazd is offered. We read in the Frawardin Yasht (Yasht 13:64): “We worship the good, strong, beneficent Fravashis of the faithful ... who run by tens of thousands into the midst of the Myazdas.”²

1 S. B. E. XXIII p. 196.

2 *Gathas*, by Dr. Mills, p. 134.

In the Gathas, *myazd* is offered to Ahura Mazda. "O Ahura! We offer Myazda to thee and to Asha with humility (or, with prayers *nemanghâ*. Ha, 34:3). "Among the different things offered, such as water, milk, wine, fruits, flowers, etc., fruits are specially spoken of as the myazda. For example, in the above passage of the Gatha, the Pahlavi translator renders the word *myazda* by fruit (*bar*). He says: "I place the fruit within thy possession (*bar pavan khvesh-i-lak yakhsenunam*).¹ Neryosang also translates the word by "*phala*," i.e., fruit. So, nowadays, the Parsees generally understand by the word myazd, which is corrupted into *mej*, "fruit used in religious ceremonies."

Haug derives the word otherwise. He says: "Originally it meant "flesh," as may be clearly seen from the cognate Armenian *mis*, "meat" (comp. Sans. *mânsa*) being identical with "meat." Some derive the word "mass" of the Christian ritual from the same source. Others derive the word "mass" from *missa* in the Latin phrase "Ite missa est," i.e. "Go, it is dismissed," but this derivation is supposed to be wrong and the initial conception is said to be of "flesh" and of a flesh-offering offering in sacrifice.² In old High German, the word is *maz*, in Gothic *matz*. In this sense, the word "massacre" is taken to be *masskhar* i.e., flesh-eater. Lat. *mensa*, which is a table [370] or the food spread thereon, has a similar connection. Similarly in Persian *miz* ميز is "table" as well as a guest. *Mizbân* means a "host." The word *myazd* in Persian also means a "banquet." In Latin "seconda mensa" similarly means "a second course."

Originally the *dron*, i.e., the sacred bread was included in the word "*myazda*." For example, in the Yasna, in one of the chapters known as those of Srosh *Dron* (Ha 3), the word *myazda* includes the *dron*. But, latterly, the word *dron* has often been mentioned separately; for example, in the Afrin (*Darun yashtahom, myazd hamirâyenim*). In a town like Naosari, in the ordinary parlance of priests, the word *myazd* has come to mean the ceremony of Afrinagan.

All the things offered as *myazda* are eatables (*Kharethem myazdem*, Ha 3:1) and the worshippers partake of them in a ceremonious way. This partaking of the eatables presented as *myazda* is spoken of as "*châshni*" (lit., tasting). It is only those who are deserving, who have deserved it by their righteousness (*asha*) and good conduct (*frêretî*) that are asked to participate in the *châshni* (Yasna, Ha 8:2). As Prof. Darmesteter says, the public gatherings for

1 *Essays on the Parsis*, second ed., p. 139.

2 *Vide* Sir E. Cox's articles in 'The Nineteenth century of March 1905' wherein the Christian ritual is said to have existed long before Christianity, in the Eleusian and Mithraic Mysteries.

offering the *myazda* and for eating them (*châshni*) were, as it were, gatherings for religious trials. He says: "Cette communion est une sorte d' épreuve religieuse. Il faut que le fidèle se sente en état de grâce pour y toucher et il semble, d'après l'adjuration solennelle faite par le Zaotar, que les effets du Myazda trahissent celui qui le consomme en état de péché." (*Le Zend Avesta*, Vol. I, p. 75). The ultimate object of these offerings is, that they may suggest to the worshippers, that the best offering is that of righteous actions. Prayer, praise and righteousness are the best offerings acceptable to God.

Wine in the Afrinagan ceremony.

Wine is generally used in the Afrinagan and other religious ceremonies. There are some Parsees now, who, being total abstainers abstain from using wine in the ceremonies at their place. [371] If we look to the time of the Avesta, we find no prohibition. But, we find that the wine then used was the juice of the grapes. That it was a sweet, nourishing and health-giving drink appears from several facts:

1. Firstly, the very Avestaic word for wine shows, that it was a drink as sweet as honey. This Avestaic word is *madhō* which corresponds to the Sanskrit *madhû*, Lat. *mel*, and French *miel*, i.e., honey.

2. Secondly, the root of the word shows its medicinal virtue, It comes from an old Aryan root *mad* or *madh* Sans. मद् *madh* Latin *mad-êri*, meaning to make a remedy, from which comes our English word medicine. "*Dâru*," (دارو) the later Persian word for wine which is now commonly used in Gujarati, also has the etymological meaning of medicine. *Davâ-dâru* is a colloquial phrase for medical treatment. It comes from an old Aryan root *dru*, Sanskrit *dhrû*, meaning to be strong, to be healthy.

3. Thirdly, it was prescribed as nourishment to ladies in their accouchement (Vendidad 5:52).

4. Fourthly, being a nourishing drink, its use was permitted even among the priesthood (Vendidad 14:17).

5. Fifthly, in one of the later writings, the Afrin-i-Gahambar, where they speak about the six Gahambars, it is said that the merit of celebrating the last season festival of the year, the Hamaspathmaedyem Gahambar, in honour of the creation of man, is just the same as that of feeding the poor and the pious. In the food referred to here, wine is spoken of as a part of the diet. At one time, it was generally thought, and even now it is thought by some, to be very meritorious to waste a little of the wine used in the religious

ceremonies of the Gahambar festival.

6. Sixthly, an allusion to wine in the recital of the blessings of the marriage ceremony of the Ashirvad, shows that the wine [372] used in the old Parsee books was not the wine that intoxicated. The officiating priests, in the recital of a long list of blessings that are invoked upon the marrying couple, wish the bride and bridegroom to be as sparkling and cheerful as wine.

Coming to the time of the Pahlavi literature of the Parsees, which flourished during the period of the Sassanian dynasty, we find Pahlavi writers permitting the use of wine and preaching moderation. Adarbad Marespand, in his *Pand-nâme*, or *Book of Advice*, thus admonishes his son: "Make a moderate use of wine, because he who makes an immoderate use, committeth various sinful acts." The *Dadistan-e Denig* (ch. 50, 51) allows the use of wine and admonishes every man to exert moral control over himself. To the robust and intelligent who can do without wine, it recommends abstinence. To others it recommends moderation. Only that man is justified to take wine, who can thereby do some good to himself, or at least can do no harm to himself, If his *humata*, *hukhta*, and *hvarshta*, i.e., his good thoughts, good words, and good deeds are in the least perverted by drink, he must abstain from it. The book advises a man to determine for himself once for all what moderate quantity he can take without doing any harm. Having once determined that quantity, he is never to exceed it. The most that a man should take is three glasses of diluted wine. If he exceeds that quantity there is a likelihood of his good thoughts, words, and deeds being perverted.¹ The *Denkard* (Vol. I, p. 4) considers excessive drinking to be a sin as it keeps away a person from prayers. [373]

Flowers in the Afrinagan Ceremony. The Language of Flowers.

Flowers play a prominent part in the Afrinagan Ceremony. If flowers are not available, leaves of any fragrant plant like the *sabza* (basil) are used. It appears, that in former times special flowers were used for the Afrinagans of particular Yazatas or angels in whose honour or with whose *Khshnûman* the separate Afrinagans were recited. It appears that the ancient Persians had, as it were, a

1 On the subject of the trade of wine-sellers, the *Dadestan-e Denig* says, that not only is a man who makes an improper and immoderate use of wine guilty, but also a wine-seller who knowingly sells wine to those who make an improper use of it. It was deemed improper and unlawful for a wine-seller to continue to sell wine, for the sake of his pocket, to a customer who was the worse for liquor. He is to make it a point to sell wine to those only who can do some good to themselves by that drink, or, at least, no harm either to themselves or to others. For the use of wine among the Persians, as referred to by the Classical writers, etc. *Vide* my paper "Wine among the ancient Persians" (1888).

language of flowers of their Own. The *Bundahishn* (Chap. 27:24) gives a list of the different flowers which were said to be the special flowers of the different Yazatas. The association of the different flowers with the different angels depended upon the moral qualities or characteristics believed to have been associated with those angels. For example, the Amesha Spenta Shahrewar (whose Avesta name is Khshathra Vairya) represents the Sovereign Will of God. Then he presides over the sovereign power of kings. He typified sovereignty, both physical and mental. The sovereignty of a king implies Order, Equity, or Justice. So Plutarch represents Shehrewar as the god of Order, Equity, or Justice. Now, according to the *Bundahishn*, the flower known as “Shâh-Asparêm” or the Royal Asparem is the special flower of this Amesha Spenta. This specialisation is very appropriate. The Shah-asparem of the *Bundahishn* is the flower “basil.” The word “Basil” comes from Basilicus. This flower is the “Königskraut” of the Germans. It is the “plant royale” of the French. We thus see, that the flower Shah-asparem or the Basil is very appropriately specialized as the flower of Shahrewar who presides Over sovereignty – sovereignty of body and sovereignty of mind. It appears then, that, in former times, when one recited the Afrinagan with the *Khshnûman* of Shahrewar, he used eight Shah-asparem or Basil flowers which symbolized sovereign will. In the same manner, in the recital of the Afrinagans of different Yazatas, different flowers, which were special to them and which symbolized the special characteristics or qualities over which the Yazatas presided, were used. [374]


The following list shows the connection of different flowers with different Yazatas.

	Name of the Yazata.	Pahlavi name of the flower	Probable equivalent names in English.
1	Ahura Mazda	Mûrd Yâsmin	Jasmine with leaves like the myrtle.
2	Vohuman	Saman-i-safid	Trefoil.
3	Ardwahasht	Merezan gosh	Sweet Marjoram.
4	Shahrewar	Shah-sparem	Basil-royal.
5	Spandarmad	Faranj-mashk	A sweet Basil, lit., the musk of the Firangis or Franks.
6	Hordad	Susan	Lily
7	Amurdad	Chambê	It is the Sanskrit Champak.
8	Dae-pa Adar	Vâdruz (vâdrang) bui.	Orange flower.
9	Adar	Âzergun	The Anemone or the Marigold.
10	Aban	Nilo-par	Water-lily.
11	Khwarshed	Marv-i-sped	Cat-thyme (Ger. katzen-kraut. Fr. Le Marum).
12	Mah	Ruges	Rush or Leek.

13	Tir/Tishtar	Vanaôsh	Flower of the Wan tree.
14	Goshorun	Meren	Vine-flower (Fr. Fleur de vigne. Ger. Weinblüthe).
15	Dae-pa-Mihr	Kârad	A flower of the species Pandanus odoratissimus.
16	Mihr	Vanush	Violet.
17	Srosh	Kheri Sorkh	Pepper grass.
18	Rashnu	Nistarun	Narcissus.
19	Frawardin	Aoroz	Cock's comb.
20	Warharan	Sisenbar	Water mint.
21	Ram	Kheri zerd	Yellow Pepper grass.
22	Wad, Gowad	Vâdrang-bui	Mountain-balm. [375]
23	Dae-pa-Den	Shambalit.	Fenugreek.
24	Den	Gul-i-sad varg	Rosa centi-folia.
25	Ard	Hamâk hamâk Vahâr	Buphthalmus.
26	Ashtad	Hamâk Hom-i-Safid	White Haoma.
27	Asman	Nanâ nânu sparam	Bread-vegetable.
28	Zam	Kalkam	Saffron, Crocus.
29	Mahraspand	Artashirân	A bitter plant.
30	Anagran	Haoma datô ai Hom	Haoma.

The arrangement and the Exchange of the Flowers. The Expression of Approval.

The flowers are at first generally kept in a small tray on the left, and, on the commencement of the recital of each *Kardeh* or section of the Afrinagan, eight flowers are taken into the principal tray containing the *myazd*, i.e., milk, water, wine, sherbet, fruit, etc. The eight flowers are arranged in two rows. The first flowers lower down in both these rows point toward the fire vase opposite. The three next are arranged face to face. The following diagram shows the arrangement of the flowers:



The flowers are arranged as above before the commencement of each *Kardeh* of the Afrinagans. At the end of the recital of the first or the variable part of the Afrinagan, the Raspi or the *Atravakhshi* gets

up from his seat on the carpet and the Zoti gives him the lowest flower on the right hand side and himself [376] holds the lowest on the left hand side. The former, while receiving the flower, utters the words “*Ahurahê Mazdâo raêvato Kharenanghatô*,” i.e., “of the Glorious and Brilliant God.” Then both recite together the second or the invariable part of the Afrinagans, the *Kardeh* of *Afrinami*. As said before, this part of the Afrinagan invokes the blessings of God upon the ruler of the land. Both recite this portion holding the flowers in their hands.

In Persia, the Zoroastrian priests hold up their finger instead of a flower. It seems that in ancient times, there was the practice for people to hold up their fingers to show approval and consent. In Tibet, even now, when a person with whom you converse, wants to show his approval or agreement with what you say, he raises up his finger. Just as you nod your head a little to show, that you follow what another person with whom you converse says, the Tibetan, now and then raises his finger. We learn from Firdausi that that is a very old custom. When Pirân entrusted young Kaikhosru to some shepherds to be brought up under their care, in order to save him from the grasp of his maternal grandfather Afrasiyab, who, as the result of a dream, thought of killing the boy-prince, the shepherds now and then raised up their fingers to show their approval and consent:¹

This part of the ritual seems to indicate, that, as there is one God above to rule over the world, there must be one King here as his representative to rule over the country. He must be powerful enough to over-rule all impiety, injustice, misrule, oppression, and immorality.

On finishing this second part, both the priests exchange their flowers. This exchange symbolizes the exchange of lives [377] between this world and the next. Souls are born and souls pass away. How do they do so? That is indicated and symbolized by the next process in connection with the flowers. The priests recite twice the prayer of *Humatanam*, etc. (*Yasna Haptanghaiti*, *Yasna* 35:2), wherein the reciters say that they praise those who practise good thoughts, good words, and good deeds. Now the Parsee books say that a pious righteous soul passes away to the other world, to the paradise, with three steps reciting, at each stage, the words *Humata*, *Hukhta*, and

1 نهاند انگشت بر چشم و سر (Johann August Vullers' *Firdusii. Liber Regum*, Tomus secundus p. 673, l. 2648. Macan's Calcutta ed. Vol. II p. 482 l. 3. Jules Mohl's *Le Livre des Rois*, Paris ed. Vol. II: 1876, p. 420.) *Vide* my paper on “A Tibetan form of Salutation, suggesting an explanation of a Parsee ritual,” in the *Sir J. J. Z. Madressa Jubilee Volume*, pp. 408-14. *Vide* also my paper on “Tibetan Salutations and a few thoughts suggested by them.” (*Journal of the Anthropological Society of Bombay* of 1914. *Vide* my *Anthropological Papers*. Part II, pp. 120-21.)

Hvarshta, *i.e.*, good thoughts, good words, and good deeds.¹ So, at this juncture, the Zoti, while reciting the above words *Humatanam*, etc., lifts up the three flowers on the right hand side, one by one, beginning from above. Then, reciting the same prayer of *Humatanam* for the second time, similarly lifts up the three flowers on the left hand side, but commencing from below. This process and this recital symbolize the above view, that a pious righteous soul has to come down to and move about in this world and then to pass away from this world to the other with the triad of good thoughts, good words, and good deeds. Having thus lifted up the two sets of three flowers with the above prayer praising goodness of thoughts, words and deeds, he gives them into the hands of the Raspi, who in the end, returns them to him. He finally places them on one side in the tray. At the first recital of the *Humatanam* prayer and at the first lifting up of the flowers, the Raspi stands on one side of the Fire-vase, *i.e.*, on the right hand side of the Zoti, and, at the second recital, on the other side. He, thus, changes his situation, to symbolize the change of situation on the part of the soul, after death.

The pointing of the directions with the ladle.

After the above recitals and after the abovesaid two processes of lifting the flowers from their two rows, the Raspi, who was all along standing before the fire-vase holding in his hand the ladle with which he placed sandalwood on the fire-vase, presents the ladle to the Zoti. The Zoti holds it from the side of the broad blade and the Raspi, from the side of the end of the handle. Both [378] recite an Ahunwar and an Ashem Vohu. While reciting the *Yathâ*, the Zoti moves the ladle in the tray before him pointing out the four sides or directions. While reciting the *Ashem*, he points to the four corners. In short, he points, as it were, to the different directions of the movements of the sun. In pointing out the first four directions he draws, as it were, a ☩. We know, that anthropologists say, that the Cross existed before Christ. that it symbolized to some extent the ancient sun-worship and pointed out the different directions in connection with the sun. In that respect, it resembled, to a certain extent, the savastika [swastika] of the Hindus which similarly symbolized the movement of the sun. Thus, the pointing of the different sides and corners with the ladle was something like describing a *savastika*.

After reciting the Ahunwar, and the Ashem, two more Ahunwars and an “*Yasnemcha*” are recited. Then the two priests pass their hands into each other’s hands in a particular way. This process of passing hands is known as *Hamazor*. Then a short recital of the

1 *Vide* also the Vispa humata prayer: “All good thoughts, good words, and good deeds lead us to Heaven.”

Humatanam, etc., finishes the Afrinagan prayer. The Zoti then recites one or more Afrins. The priests are, at this last stage, paid their fees spoken of as *asho-dâd*. I will here describe the terms (a) *Hamazor* and (b) *Ashôdâd* above referred to.

(a) Hamazor.

The *hamazor* (*hamâzor*) plays an important part in several ceremonies of the Parsees. It is a particular way in which, at the end of several ceremonies, one person passes his hands into the hands of another person. One person, say A, holds forth both his hands flattened out and in the position of the thumbs being uppermost and the palm of one hand facing parallel to the palm of the other. Another person B, with whom he makes the *hamazor*, similarly holds forth his hands, placing his flattened right hand between A's flattened hands. This process places the flattened right hand of A, in turn, between B's flattened hands. Thus, each holds the right hand of another in the folds of his hands. Having thus placed them, they, with a graceful movement withdraw the right hands and similarly pass their left hands in the folds [379] of the hands of another. After thus passing their hands into each other's hands they lift their hands towards their heads just as if to touch them with the tips of their fingers, which is the usual way of saluting elders or superiors. This graceful movement of hands is spoken of as "*hamazor karvi*" or "*hamazor levi*," i.e., "to make the *hamazor*" or "to take the *hamazor*."

The Ceremonies or occasions during which the *hamazor* is performed.

The following are the ceremonies at the end of which the *hamazor* is generally performed. 1. The Yajashne [Yasna]. 2. The Vendidad. 3. The Visperad. 4. The Afrinagan. 5. The recital of Niyayeshes jointly by a number of persons forming a congregation.

During the first three ceremonies, it is generally the two priests who take part in the ceremonies that perform the *hamazor*. In the case of the Vendidad when it is recited for the Nirangdin, the second priest, i.e., the Raspi, or the *Atravakhshi*, at the conclusion of the ceremony, performs the *hamazor* with other priests and laymen assembled to superintend and witness the ceremony.

In the case of the Afrinagan ceremony, the two priests, the Zoti and the *Atravakhshi*, perform the *hamazor* at the end of each Afrinagan, i.e., at the end of each *Kardeh* of the Afrinagan. If there is a large number of priests present and if there is a large congregation of laymen before which the ceremony is performed, at the end of the recital of the last *Kardeh* of the Afrinagan, the *Atravakhshi* goes round the assembly and performs *hamazor* with the other priests and

laymen. This custom of making *hamazor* with others is getting a little out of practice in Bombay, but is still in practice in the Parsee towns of Gujarat.

In the case of the recitals of the Niyayeshes jointly by no congregation, the *hamazor* is performed by the persons assembled with several persons standing next to them. For example, the Oothamnâ ceremony on the third day after death is such an occasion when there are joint recitals of the Khwarshed and Mihr Niyayeshes. There, after the recital of the Pazand Doa Nam Setayashne, which always follows the recital of the Niyayeshes, this [380] performance of the *hamazor* follows. Again, at some ceremonial gatherings, the Atash Niyayesh is jointly recited. There also the *hamazor* is performed after the recital of the Doa Nam-setayeshne.

In such religious and ceremonial gatherings, people generally take their stand according to their seniority or superiority. The Dastur or the Head Priest or a senior has his place generally in the middle and in the front. At the proper time, he performs the *hamazor* with a few near him, beginning with the next juniors, standing next to him. The latter continues it with those next to him, and so on. Thus, the whole assembly makes the *hamazor*, each person making it with the few round about him.

The *hamazor* of the Parsees and the Kiss of Peace of some of the Bene-Israels of India and of the Early Christians.

I think, that the *hamazor* of the Parsees resembles the Kiss of Peace of some of the Bene-Israels of India, and the Kiss of Peace of some of the Early Christians. Rev. J. H. Lord thus describes the Kiss of Peace of the Bene-Israels:

“Emanating from the chief minister, who bestows it on the elders nearest to him, it passes throughout the congregation. Each individual seeks it, as far as possible, from his senior or superior. Extending the arms with the hands flattened out, and in the position of the thumbs being uppermost, the person approached takes the hand between both of his own, similarly held, and the junior then probably places his remaining hand on the outside of one of those of the person already holding his other hand. The hands of each are then simultaneously released and each one immediately passes the tips of his fingers which have touched those of his neighbour to his mouth and kisses them. He then passes on to receive the same from, or to bestow the same on, another; and so on, till all in the Synagogue have saluted one another. Two or

three minutes may be occupied in the process. A movement is going on all through the Synagogue, and a distinctly audible sound of the lips is heard through the [381] building, till all is finished.”¹ As to the occasions when the Kiss of Peace is observed among the Bene-Israels, he says: “It is, of course, not difficult to believe in the possibility of the practice having been handed down amongst the Bene-Israels, and having been without break used by them on occasions of their meeting together at circumcisions, and for such other communal meetings as they may have kept up amongst themselves from the first.”

The points of similarity between the *hamazor* of the Parsees and the Kiss of Peace of the Bene-Israels, when observed in congregations, are the following: (a) The movements of hands is similar. (b) In both, they emanate from the chief minister. (c) In both, each makes it with, or bestows it upon, the elders nearest to him. (d) In both, they pass throughout the congregation.

The only point of difference is this, that, while among the Bene-Israels the process ends with a kissing of the tips of the fingers of the hands, among the Parsees, it ends with the taking of the tips of the fingers to the forehead with a gentle bow.

The meaning of the word *hamazor*.

The word *hama* in the word *hamazor* is Avesta, *hama*, Sanskrit *sam*, Latin *simul*, *similis*, English same. The word *zor* is Avesta *Zaothra* and comes from the root *zu*, to perform a ceremony. So, the word *hamazor* means “to be the same or to be one in ceremony.” One of the principal participants or performers of the ceremony, by passing his hands in the hands of others, symbolically makes them participate in the ceremony he had performed. The members of the congregation by performing the *hamazor* with one of the principal celebrants make themselves participants in the ceremony. After the performance of the *hamazor* and at the end of the ceremony, they subsequently make the *châshni*, i.e., they eat a little of the consecrated things and thereby further show themselves as participants in the advantages or good resulting from the ceremony. [382]

The formula recited while performing the *hamazor*.

While performing the *hamazor*, they recite the words “*hamazor*

1 The Jews in India and the Far East, by the Rev. J. H. Lord (1907) pp. 30-31. Vide my paper, “The Kiss of Peace among the Bene-Israels of Bombay and the Hamazor among the Parsees” (Journal of the Anthropological Society of Bombay, Vol. VIII, No. 2, pp. 84-95. Vide my *Anthropological Papers*, Part I, pp. 283-94).

hamâ asho bêd,” i.e. “May you be one (with us) in the ceremony and may you be *ashô* or righteous, The recital of the words signify and emphasize the object and aim of the performance of the *hamazor* ceremony. The ultimate object of all ceremonies, rites and sacrifices is to elevate the mind of the performers or the worshippers. A “sacrifice” does not fulfil its object unless it makes the participant “sacred,” unless it elevates his thoughts, and makes him a better man. So, after performing the sacrificial service, one of the principal celebrants passes his hands into those of the other members of the congregation and lets them pass theirs into his, and by this symbolic mixing of hands, makes them participants in the ceremony and wishes them or rather asks them to be *ashô*, i.e., righteous.

The *hamazor* on a New Year’s day.

From the fact, that a *hamazor* was performed in the Liturgical Services with a view to signify participation and unity and with a wish that the person with whom it was performed may be righteous, the *hamazor* has come to signify a religious or solemn way of communicating one another’s good wishes on the Nawruz or the New Year’s day. To the laymen, it is best known in connection with thla New Year’s day. Early in the morning of that day, after washing and putting on new apparel, the male members of the family exchange this form of salutation and of expression of good wishes. Friends do the same when they meet one another. “Sâl mubâarak,” i.e., “May the year be auspicious,” and “*Dêr zi va shâd zi,*” i.e., “May you live long and may you live happy,” are other additional words, at times, uttered with this form of the exchange of salutations. Members of a family, or friends, if at variance, are expected to forget on the New Year’s day their differences and to unite and be friendly with the performance of the *hamazor*. A generation or two ago, it was a custom for the head of a family, i.e., the head, senior or elder member representing the block from which several chips had descended, to call a mijlas or a gathering at his place in the [383] morning of the New Year’s day for the purpose of the *hamazor*. All the members of the family met together and exchanged *hamazor*.

Spiritual *hamazor*.

We see from what is said above, that behind the outward passing of hands in the *hamazor* which signifies unity, harmony, participation, there lies the inner idea, which demands that the participants must unite in the works of righteousness. So, behind, what we may call, the “physical *hamazor*”, there is what we may term the “spiritual *hamazor*.” The participants in the ceremony, in the ritual, in the recital are asked to be one with the chief celebrant in

some religious acts which may lead to an increase of righteousness in the world. From this view of the ritual there is not only the *hamazor* — the physical *hamazor* — between Man and Man, but there is also a kind of *hamazor* — a kind of spiritual *hamazor* between Man and Nature, between Man and Nature's God. The Pazand Afrins recited in the above-described Afrinagan ceremonies are replete with expressions about this kind of *hamazor* with God and his Nature. For example, in the Afrin of Ardafarosh, there is a long list of *hamazor* — *hamazor* with Ahura Mazda and *hamazor* even with many abstract ideas, all leading to a conception of righteous moral life. The purport of this part of the Afrin is, that one must try to be one with the Harmony, Order, System established by God in Nature. The *hamazors* with the divisions of Time and the divisions of Space in the Great Infinity of Time and Space — divisions brought about by the movements of Heavenly bodies — are all intended with a view to that Harmony, Order, or System. Let man try to be one with that Harmony, Order, or System.

(b) Ashô-dâd.

Ashô-dâd literally means “what is given (*dâd*) to the righteous to the holy (*ashô*).” Hence the fees, or gifts given to the members of the Holy Order or the priesthood are generally spoken of as “*ashôdâd*.” Afterwards, now-a-days, the word is sometimes employed even [384] for the money-gift given at the temples to the Parsee poor, whether priests or laymen.

The *ashôdâd*, or the fees to the priests, does not only consist of payment in money, but also payment in kind. At the Uthamnâ ceremony, on the third day after death, besides payment in money, payment in cloth is made. A *sudre* or a sacred shirt is given to each priest invited for the ceremony. Again, the *drons* or sacred breads and the *myazd* offered in the Srosh Baj are taken by the family priest as a part payment. In some ceremonies, such as the Naojote and the Marriage, a part of the payment consists of grain. These grain payments are generally known as ‘*akhiânâ*.’ [385]

CHAPTER XVII. (II) THE FAROKHSHI.

Farokhshi.

The word Farokhshi is another form of Fravashi. The prayer recited under this name is so called because it is intended to remember, invoke, and praise the Fravashis of the dead. Like the Afrinagan, it is generally recited over fruits, flowers, milk, wine, water, etc., and before fire. Its recital consists of the recital of the *Satûm* and the Avesta portion of the Frawardin Yasht. At times, and that very rarely, the recital of the Frawardin Yasht is proceeded with the recital of the Yasna chapters of the Baj recital, which, in that case is spoken of as Baj *dharnu* (lit. holding the Baj) of the Farokhshi. It is recited by one priest and has very little of ritual. As Farokhshi is the recital of the prayers for the Fravashis, and as these Fravashis or Farohars plays very important part in the religion of the Parsees, and as many ritualistic ceremonies refer to the Fravashis, a description of the Fravashis is essential.

The Fravashis or the Farohars.

Fravashi is the original Avesta term and Farohar is its later form. The word is too technical to be sufficiently and properly rendered into English. Prof. Harlez says: It is difficult to determine their nature (leur nature paraît assez difficile à déterminer).¹ Rev. Dr. Oasartelli says: “Il y a peu de sujets qui presentent plus de difficulté, tant dans le système avestique que dans celui du mazdéisme plus récent, que celui des esprits appelés *fravâhars*, *farôhars*, *fravash* ou *frôhars*. L’embarras principal provient de ce que le nom est appliqué à une faculté de l’âme humaine unie au corps pendant la vie, et à cette faculté détachée du corps et menant la vie, Indépendante d’un esprit céleste.”² The word Fravashi comes from Avesta prefix *fra*, Sans. *pra*, Pers. *far*, Lat. *pro*, German *vor*, Eng. *forth*, meaning forward, and the Avesta root *vakhsh*, Sans. वक्ष् *vakhsh* Pers. *vakhshidan*, Germ. *waschen*, Eng. *wax*, meaning [386] to “grow.” So Fravashi is that power or spiritual essence in a substance which enables it to grow. Neryosang in his Sanskrit translation, renders the word by *vrudhdhi*, i.e., increase. The proper name Frawartish which we come across in the Cuneiform Inscriptions (Behistun II, 5) and the name Phraortes which we find in Herodotus (Bk. I, 73, 102) are derived from the word Fravashi. We learn from the etymological meaning of the word and from all that is written about it in the Avesta books, that Fravashi is a

1 *Avesta, Livre Sacré du Zoroastrisme*: Introduction p. CXIX.

2 *Le Philosophie Religieuse du Mazdéisme sous les Sassanides*, par C. Casartelli, pp. 76-77.

spirit, a guardian spirit, inherent in everything, animate or inanimate which protects it from decay and enables it to grow, flourish and prosper. Every good object in Nature has its Fravashi which protects it and helps its development. Dr. Haug's definition gives some idea of what it is, though I would rather use the word "spirit" in place of "angel." He says, "these Frohars or protectors, who are numberless, are believed to be angels, stationed everywhere by Ahura Mazda for keeping the good creation in order, preserving it, and guarding it against the constant attacks of fiendish powers. Every being of the good creation, whether living, or deceased, or still unborn, has its own Fravashi or guardian angel who has existed from the beginning. Hence they are a kind of prototypes and may be best compared to the "ideas" of Plato who supposed everything to have a double existence, first in idea, secondly in reality."¹

All the Farohars were created by God before the creation of the Universe (Frawardin Yasht, 13:76). The Frawardin Yasht (Yasht 13:59-62) gives their number to be 99,999. But one must understand from that number, that, in the Avesta, it gives an idea of being innumerable. In this Yasht. 99,999 Fravashis or individual spiritual essences are spoken of as protecting and looking after the sea Vourukasha (the Caspian). The same number looks after the constellation of Haptoring (Ursa Major), the body of Kersasp, and the seed of Zoroaster. So their number is innumerable. As the grand universe, the whole Nature is made up of innumerable objects, animate or inanimate, large or small, and as each object has its own Fravashi or some individual inherent spiritual essence which maintains and [387] supports it, it is evident that there are innumerable such spiritual essences all emanating from that Great Divine Essence of God who has created them, and who has made use of them.

The Fravashis are Spiritual Essences. Their Relation to the other Higher Intelligences.

Ahura Mazda is the Great Architect of the Universe. He is the Creator of the Material as well as the Spiritual world. The Fravashis form the creation of the Spiritual world. In the spiritual hierarchy, they stand, as it were, fourth in the order of supremacy. There is believed to exist a beautiful relation between the different Higher Intelligences of the Hierarchy.

1. Ahura Mazda (The Omniscient Self-existent Lord) is at the head of all.

2. Next come his Amesha Spentas (The Bountiful Immortals) who

¹ Haug's *Essays on the Parsees*, second edition, p, 206.

are his own creation (Ohrmazd Yasht, Yasht 1:25). Ahura Mazda who is self-created (*Khadhâta*, *Khudâ*) is himself one of the Amesha Spentas (Yasht 1:3; Yasht 3:1).

3. Then come the Yazatas (lit., those who are worthy of being worshipped). The Amesha Spentas who stand higher in the order and Ahura Mazda himself who stands at the top are also included in the list of the Yazatas. They stand first in the list of the Yazatas. In later books, Ahura Mazda is spoken of as *Yazdân*, i.e., the *Yazds* in the plural, or the Yazata of the Yazatas.

4. Then come the Fravashis (i.e., the guarding or protecting spirits). Now, each of the Yazatas, who precede the Fravashia in the above order of hierarchy, has his own Fravashi. The Amesha Spentas who stand higher have each their own Fravashis, Then Ahura Mazda who stands at the top has his own Fravashi (Yasna 23:2; 26:2, 3).

The Work of the Fravashis in the creation of the Universe.

Ahura Mazda, the Omniscient Lord, has allotted to the Fravashis the work of helping the creation, (Frawardin Yasht; Yasht 13:1, 19). They help in sustaining the sky (*Ibid*, 2, 22, 28, 29; Yasna 23:1), in letting the great river Aredvi Sura flow (Yasht 13:4), in supporting the earth (Yasht 13:9, 22, 28; Yasna 23:1). They help mothers in maintaining the children in the [388] womb and in the work of delivery (Yasht 13:11, 22, 28; Yasna, 23:1, 15). It is these spiritual essences, these guiding and guarding spirits that help the waters to flow (Yasht 13:14, 22; 28; Yasna 23:1), the trees to grow, the winds to blow (Yasht 13:14, 22, 28), the Sun, the Moon and the Stars to move in their orbits (Yasht 13:16). To them, the cattle owe their growth and spread (Yasna 23:1, 12). The purport of all this is, that there is the Divine hand of God in everything. Through His Fravashis or the protecting, guiding and guarding Spirits, He maintains all and rules over all.

Two classes of Fravashis.

We learn from the Frawardin Yasht, that all the objects of Nature have their Fravashis, but artificial objects have none. Ahura Mazda and the Amesha Spentas have their Fravashis (Yasht 13; Yasna 23:2-4; 26:2-3). The Yazatas and mankind have their Fravashis (Yasht 13, Yasna 23:2-4). The sky, waters, earth, fire, trees, cattle, all have their Fravashis (Yasht 13:2). All the objects of Nature, as divided into three classes, 1. the Vegetable world, 2. the Mineral world, and 3. the Animal world, have their Fravashis.

From what is said above we may divide the Fravashis into two classes:

- (1) The Fravashis of Natural objects, i.e., the transcendental

essences of the objects. (2) The Fravashis of men.

(I) The Fravashis, or Transcendental Essences of natural objects.

According to the Avesta, all natural objects have their Fravashis, but not the objects that have been made from those natural objects. For example, the trees have their Fravashis, but not the chair or the table that has been made from the wood of the tree. God has created the Fravashis of these natural objects from the very beginning of creation. Before the creation of the object, there existed the Fravashi of that object, perfect, complete and correct. This conception of the Fravashi leads us to think that the Almighty had conceived the creation of every object in the Universe from the very beginning. In fact, he had conceived a complete, perfect, and correct idea of the whole [389] Universe before its creation. He had created or formed the transcendental spiritual essences of all objects before He created the objects themselves. The spiritual essences existed at first, and then the objects resulted from them. For example, the Avesta says that the earth itself has a Fravashi. Now, as it also says that the Fravashi existed before the creation of the object itself, it follows, that the Fravashi of the Earth existed or was created by God before He created the Earth itself. What does that mean in common parlance? It means that God had conceived beforehand a complete, perfect, correct, harmonious, orderly system of the Earth. From that perfect conception, that correct idea, proceeded the creation of the earth. It existed in spirit before it existed, in body. The earth, as we see it now, is not a haphazard result of some kind of creation or formation, but it is the result of a correct order, a perfect system, which was conceived before the earth came into existence. Again, take the case of the Heaven which also has, according to the Avesta, its Fravashi or a transcendental spiritual essence which existed before the creation of the Heaven. This also signifies that the Heaven also is not the result of some haphazard chance of circumstances. No, the Almighty had created its Fravashi beforehand and had thus conceived a perfect system of its creation, evolution and development. The Heavens, as we see them now, are a result of such Omniscient Intelligence.

The Zoroastrian belief about the Fravashis is connected with the idea of Eternity. Ahura Mazda is omniscient, omnipresent and omnipotent, and his omniscience, omnipresence and omnipotence consist in this, that he conceived, from the very beginning of beginnings, if we may say so, from time unlimited (*zravâna akarêna*), a most complete, a most correct, a most harmonious, a most orderly system of the universe. The Fravashis or the Farohars played an important part in this conception, because the Fravashis of the Universe and its objects were the transcendental spiritual essences

from which God evolved gradually the great universe.

This view of the Fravashis as propounded in the Avesta shows beautifully the power and the wisdom of God. Take, for [390] example, a tree. It has its Fravashi, *i.e.*, a transcendental spiritual essence, pure and perfect, which existed somewhere before the tree came into existence or assumed its present form and shape. With the birth, if we may so call it, of the tree, its Fravashi continues with it. It is its guiding spirit. After a certain time, the tree dies, but not the Fravashi. It continues to exist somewhere in nature as a perfect and pure transcendental essence. This Avestaic view of the Fravashis teaches several facts.

1. That there is something real, substantial, true, correct perfect, undying, behind the form and the figure of a thing which is always changing. That something real is always existing, is eternal.

2. That God is omnipresent, omniscient, omnipotent and his omnipresence, omniscience, omnipotence consist in this system of the Universe which has come from eternity, which exists at present for eternity, and which will continue to exist for eternity. There is nothing spontaneous. Everything evolves from something, from transcendental essence which is something connected with the very essence of the Almighty.

The Fravashis of the Avesta, (a) the Ideas of Plato and (b) the Patterns of the Bible.

(a) The Fravashis of the Avesta remind us, as pointed out by Haug, of the ideas of Plato and of the patterns of the Bible. Ideas or the transcendental spiritual essences formed an important part of the system of Plato's philosophy. According to him, the material and phenomenal world is the result of some pre-conceived ideas. Matter existed from times eternal. That matter took form at some certain time, but that form existed somewhere, long before the matter took that form. These forms were Plato's ideas. The ideas are eternal, invisible, and imperishable, but the substances which take forms are subject to frequent changes. For example, just as, according to the Avesta, the Earth has its Fravashi, according to Plato it has its idea. The "idea" of the Earth existed before the Earth itself. It was with that "idea" before Him, with the help, as it [391] were of the "idea," that God created the world out of chaos. Milton uses the word "idea" in that sense in the following lines:

"Thence to behold the new-created world
The addition of his empire, how it showed
In prospect from his throne, how good, how fair
Answering his great idea." (*Paradise Lost*, Book VII, ll.

554-557.)

(b) Again, according to Dr. Haug, the Fravashis of the Avesta resemble the patterns of the Bible. That resemblance is not very great, but it does hold to a certain extent. God shows to Moses the pattern of the tabernacle which he wishes the Israelites to construct. He says: "According to all that I show thee, after the pattern of the tabernacle, and the pattern of all the instruments thereof, even so shall ye make it." (Exodus, 25:9). These patterns shown by God to Moses are the ideas or spiritual essences which led to the construction of the objects. The reference to the patterns in the New Testament more vividly suggests the "ideas." In the Epistle to the Hebrews by the apostle Paul, we read: "It was therefore necessary that the patterns of things in the heavens should be purified with these" (Hebrew 9:23).

(2) The Fravashis of man.

Burnouf's definition of the Fravashi, as understood by the Parsees, gives a correct idea of the Fravashi of man. He says: "By the Farohar, the Parsees understand the divine type of every being endowed with intelligence, his "idea" in the thought of Ohrmuzd, the superior genius which inspires him and which watches over him." (Par Ferouer les Parses entendent le type divin de chacun des êtres doués d'intelligence, son *idée* dans la pensée d'Ormuzd, le génie supérieur qui l'inspire et veille sur lui" (Burnouf: *Commentaire sur le Yaçna*, p. 270).

As every object of Nature has its Fravashi, so every man has his Fravashi, which God had created before the creation and which therefore existed somewhere before his birth. Thus, the birth of a child today is, in one respect, not a new phenomenon or event. It is an event which God had conceived at the very [392] beginning of creation. The Fravashi of the child was created by God, milleniums before the date of the birth of the child. It existed from the very beginning, but it associated itself with the soul (*urvan* or *ravân*) of the child at its birth in this world. It will continue to remain with the child or rather with the soul of the child as long as the child enjoys life (*gaya*, *ahu*, or *ushtâna*). On the death of the child, whether as a child or as a man, it will continue to exist as perfect, as pure, as sound, and as innocent, as when it was first created. On death, it will separate itself from the body (*tanu* or *asta*, lit., bones) and from the soul (*urvan*) of the child and mix itself among all the holy Fravashis (*hamâ ashô Farohar*). Thus, in the matter of the Eternity of Existence, the Fravashi of a man may be said to have three periods of existence, though a continuous existence: (A) Before the birth of a man, his Fravashi had a "pre-existence." (B) With his birth, it has "co-existence" or what may be

termed “earthly conscious existence.” (C) After his death, it has before it an eternal “future existence.” Under these forms the Fravashis of men are spoken of as

- (A) Those of unborn persons (*fravashayô a-Zâtanâm*).
- (B) Those of born persons (*fravashayô Zâtanâm* or *Zavantâm*).
- (C) Those of the dead (*fravashayô irirathushâm*).

The work of the Fravashi of a man under the three states.

Now what part does the Fravashi of a man play in connection with man. What work has it to do?

A. The Fravashi of an unborn man.

As to what the Fravashi did in what we have termed its pre-existence, we know simply this, that, like the innumerable Fravashis, it did its work in the field of evolution. The world, or rather the universe as it is, is the result of development, of evolution, in which all the Fravashis take their part; so, with all the other Fravashis, the Fravashi of a particular man in its unborn (*a-zâtanâm*) state had to do its work. [393]

B. The fravashi of a born man. Difference between *Urvan* and Fravashi (Soul and Spirit.)

Then, with the birth into this world of the man whose special Fravashi it is, its special work begins. To understand that work, one must understand the relation between a man’s *urvan* or *ravân* and his Fravashi, or to speak in ordinary parlance, between his soul and guiding spirit. According to the Avesta, a man’s soul (*urvan*) is different from his guiding spirit (Fravashi). Several facts lead to show this.

(a) In the Khwarshed and Mihr Niyayeshes, a man invokes separately his soul and spirit (*Haôm urvânem yazamaidâ. Haem Fravashîm yazamaidê*). (b) *Urvan* is masculine. Fravashi is conceived as feminine. (c) In, the Frawardin Yasht, not only the *Urvan* and the Fravashi are considered to be separate spiritual parts of a man, but other spiritual parts, such as *Daena* (Conscience), and *Baodha* (Intelligence) are spoken of as separate spiritual parts (*Ahumcha Daênâmcha, Baodhascha, Urvânemcha, Fravashîmcha Yazamaidê*. Yasna 26:4). (d) The Yasna. (23:4) speaks of each *urvan* (soul) having a separate Fravashi. There, it is said: “I invoke the Fravashi of my own soul” (*âyasê yêshti havahê uruno Fravashêê*). (e) The Pahlavi books like the Arda Viraf Nameh, the Menog-i Khrad, the Bundahishn, the Ganj-i-Shayagan, all speak of them as two separate parts.

Now the relation subsisting between the soul and its Fravashi will be better understood by comprehending what we may call the “spiritual constitution of man.”

The spiritual constitution of man.

A man is made up of physical and spiritual parts. His *urvan* (soul) and Fravashi form his spiritual parts. *Ushtëna*, i.e., the animal life keeps up his body. The animal life is kept up by the five senses. A moderate use of all the five senses is good for keeping up animal life. An immoderate use of the senses turns into a passion and is bad. The attachment of the soul to the body is a trial, an ordeal for the soul. As the enjoyment of the five senses is necessary and unavoidable to keep up animal life, the soul, while associating itself with the bodily life of a [394] person, must look very sharp, lest an immoderate or undue use of the senses may contaminate it. It is good if the soul of a man separates itself in a pure, unalloyed uncontaminated state at the time when the animal life becomes extinct. If it does so, it is said to have passed the trial of this world well. One has to think, that the body is to be fed with the enjoyment of the senses in order to live and that it is not to be kept living in order to be fed. One must eat to live and not live to eat.

Now it is the Work of the Fravashi or the Farohar of a man to guide the *urvan* or soul and not let it be contaminated by an immoderate enjoyment of the senses. The Fravashi has to guide the *Urvan* or the soul through the *Baodha* or the *Budhi* or the spirit of intelligence. Just as a guide leads a wayfarer, so the Farohar guides the soul of a man. A man or a soul who accepts that guidance is a wise man. If one were to ask from this point of view “Who is the most fortunate man in this world?” We may reply in the spirit of the above quoted passage (*ahumcha daenâmcha baodhascha urvânemcha fravashîmcha yazamaidê*) that “A fortunate man is he, who accepts the guidance of his Fravashi, communicated to him through his intelligence (*Baodha*), and accepting the guidance, makes such an use of his five senses which lead to support his life (*ahu*) as would keep his soul (*urvan*) pure and uncontaminated, so that when he has to pass on to the other world, he can present himself before his God with a pure conscience (*daena*).”

The Fravashi of a man in the Avesta, and the Genius of the Romans.

The Fravashi of a living man among the Zoroastrians resembles, in good many points, the Genius of the ancient Romans. The roots of both the words signify well nigh the same thing. Fravashi comes from a root which signifies “to increase.” Genius comes from a root

gignere, to generate. Dr. William Smith says:

“The genii of the Romans are the powers which produce life (*dii genitales*) and accompany man through it as his second or spiritual self. They were further not confined to man, but every living being, animal as well as man, and every place had its genius. Every human being at his birth obtained (*sortitur*) a genius, whom he worshipped [395] as *sanctus et sanctissimus deus*, especially on his birthday, with libations of wine, incense, and garlands of flowers. The bridal bed was sacred to the genius, on account of his connection with generation, and the bed itself was called *lectus genialis*. On other merry occasions, also, sacrifices were offered to the genius.... He (Genius) was worshipped on sad as well as joyous occasions.... The genii are usually represented in work of art as winged beings.” (*Classical Dictionary*, word Genius.)

This passage shows that there are many points common to the Fravashis of the Zoroastrians and the genii of the Romans. (a) As among the Romans, so among the Zoroastrians, the Fravashis were invoked on both, sad as well as joyous, occasions. (b) The Fravashis also, are, like the Roman genii, represented in old-Persian works of art as winged beings. In the Frawardin Yasht (Yasht 13:70) they are represented as coming from the heaven like birds (*Yatha nâ mērêgo hupêrêno*). (c) Among the Zoroastrians, as among the Romans also, the Fravashis are invoked on bridal occasions. (d) They are represented as helping women in their labour of delivery (Yasht 13:15). (e) Flowers, incense, and wine are used among the Zoroastrians as among the Romans in the ceremonies invoking the Fravashis.

The Fravashis of the Zoroastrians and the Daimons of the Greeks.

The Fravashis of the Avesta resemble the *daimons* of the Greeks in several respects. The Greeks took the Daimon to be a protecting spirit. Plato said that “daimons are assigned to men at the moment of their birth, that they accompany men through life, and after death conduct their souls to Hades.” Pinder spoke of the daimon as “the spirit watching over the fate of man from the hour of his birth.” The daimons are further described as “the ministers and companions of the Gods who carry the prayers of men to the Gods, and the gifts of the Gods to men.” In the Frawardin Yasht the Fravashis also are represented as doing a similar errand (Yasht 13:151).

(C) The Fravashis of the Dead. Future Life or the Destiny of Soul after death.

Almost all nations, whether old or new, of the East or the West, the educated or the uneducated, have one form or another of venerating the dead. This veneration is connected with the belief in Future Life. Zoroastrianism believes in [396] the immortality of the soul. The Avesta writings of the Hadokht Nask and the 19th chapter of the Vendidad and the Pahlavi books of the *Menog-i Khrad* and the *Arda Viraf Nameh* treat of the fate of the soul after death. The last mentioned book contains an account of the journey of Arda Viraf through the heavenly regions. This account corresponds to that of the ascension of the prophet, Isaiah. Its notions about Heaven and Hell correspond to some extent to the Christian notions about them.¹

A plant called the *Hom-i-saphid* or white Haoma, a name corresponding to the Indian Soma of the Hindus, is held to be the emblem of the immortality of the soul. According to Dr. Windischmann and Professor Max Muller, this plant reminds us of the "Tree of Life" in the garden of Eden. As in the Christian scriptures the way to the Tree of Life is strictly guarded by the Cherubim, so in the Zoroastrian scriptures, the *Hom-i-saphid*, or the plant which is the emblem of immortality, is guarded by innumerable Fravashis or guardian spirits whose number, as given in various books, is 99,999. A good deal of importance is attached in the Avesta and in the later Pahlavi writings to this question of the immortality of the soul, because a belief in this dogma is essential to the structure of moral principles. The whole edifice of our moral nature rests upon its ground work. Dr. Geiger says on this point: "Nowhere, I think, does the belief in the future life after death stand out more prominently, nowhere are the ideas respecting it expressed more decidedly and carried out in all their details more fully, than among the Avesta people. Here the doctrine of immortality and of compensating justice in the next world forms a fundamental dogma of the whole system. Without it the Zoroastrian religion is in fact unintelligible."² [397]

Again, Zoroastrianism believes in Heaven and Hell. Heaven is called *Vahishta-ahu* in the Avesta books. It literally means the "best life." This word *Vahishta* has passed into Persian as "*behesht*," which is the superlative form of "*veh*," meaning "good," and it corresponds exactly with our English word "best." Hell is known by the name of

1 *Vide* my papers before the Bombay Branch of the Royal Asiatic Society, Vol. XVIII pp. 192-205 and Vol. XXIII pp. 189-216, on "The Divine Comedy of Dante and the Virâf-nâmeh of Ardâi Virâf," and on "An Iranian Precursor of Dante and an Irish precursor (Adamnan) of Dante." *Vide My Dante Papers*.

2 Dastur Darab Peshotan's Translation, *Civilization of the Eastern Iranians in Ancient times*. Vol. I, p. 98.

“*Achishta-ahu*,” i.e., “the worst life.” Heaven is represented as a place of radiance, splendour, and glory, and Hell as that of gloom, darkness, and stench. Between heaven and this world, there is supposed to be a bridge, named “chinwad.” This word — from the Aryan root “*chi*,” meaning to pick up, to collect, — means the place where a man’s soul has to present a collective account of the actions done in the past life.¹ For three days after a man’s death, his soul remains within the limits of this world under the guidance of the angel Srosh. If the deceased be a pious man or a man who led a virtuous life, his soul utters the words “*Ushtâ ahmâi yahmâi ushtâ-kahmâi-chit*.” i.e., “Blessedness to him, by whom that which is his benefit becomes the benefit of anyone else.” If he be a wicked man or one who led an evil life, his soul utters these plaintive words: “*Kâm nemoi Zâm? Kuthrâ nemo ayeni?*” i.e., “To which land shall I turn? Whither shall I go?”

On the dawn of the third night, the departed souls appear at the “Chinwad Bridge.” This bridge is guarded by the angel Mihr² Davar, i.e., Mihr the Judge. He presides there as a judge assisted by the angels Rashnu and Astad, the former representing Justice and the latter Truth. At this bridge, and before this angel Mihr, the soul of every man has to give an account of its doing in the past life. Mihr Davar, the judge, weighs a man’s actions by a scale-pan. If a man’s good actions outweigh his evil ones, even by a small particle, he is allowed to pass from the bridge to the other end and thence to heaven. If his evil actions outweigh his good ones, even by a small weight, he is not allowed to pass over the bridge, but is hurled down [398] into the deep abyss of hell. If his meritorious and evil deeds counterbalance each other, he is sent to a place known as “*Hamastgehân*,” somewhat corresponding to the Christian “Purgatory” and the Mahomedan “*Aerâf*.” His meritorious deeds done in the past life would prevent him from going to hell and his evil actions would not let him go to heaven.

Again Zoroastrian books say that the meritoriousness of good deeds and the sin of evil ones, increase with the growth of time. As capital increases with interest, so good and bad actions done by a man in his life increase, as it were, with interest in their effects. Thus a meritorious deed done in young age is more effective than that very deed done in advanced age. For example, let that meritorious deed be valued in money. Let two friends, A and B, at the age of twenty-five, propose doing an act of charity, viz., a donation of £1,000 to a

1 The “Chinwad” bridge of the Parsees reminds one of the “Sirat” of the Arabs, the “Wogho” of the Chinese, and the “Gioell” and “Bifrost” of the Scandinavians.

2 Cf. my paper on “Mithra, the Yazata of the Zoroastrians and Michael, the saint of the Christians.”

charitable institution. A immediately gives the amount, and B postpones the act for some time and does it at the age of fifty. Calculating at the rate of four per cent., A's gift of £1,000 at the age of twenty-five is worth twice that of B at the age of fifty, *i.e.*, twenty-five years later. Thus, the *Dadestan-e Denig* recommends man to follow the path of virtue from his very young age. A virtuous act performed by a young man is more meritorious than the same act performed by an old man. A man must begin practicing virtue from his very young age. As in the case of good deeds and their meritoriousness, so in the case of evil actions and their sins. The burden of the sin of an evil action increases, as it were, with interest. A young man doing an evil act has long time and opportunities at his disposal to wash off, as it were, the effect of that act, either by repentance or by good deeds in return. If he does not take advantage of these opportunities, the burden of those evil deeds increases with time.¹ [399]

Relation existing between the living and the dead through the Fravashi.

Now, the veneration for the dead among the Zoroastrians, rests on the belief, that the dead have a future existence somewhere and that there exists some relation, though invisible and spiritual, between the dead and the living (Yt. 13:49-52, 156-57). A father who did all his best to look after the welfare of his children does not cease to do so altogether after his death. He continues to do so in an invisible or spiritual way. On the other hand, the living who were loved and looked after by the deceased father do not and must not, forget the dead altogether. There exists some relation between the living and the dead. The channel through which this relation continues is the Fravashis of the departed ones. We saw above, that on the death of a person, his soul (*urvan* or *ravân*) meets with justice according to his merits or demerits. If he has deserved well, he goes to heaven, if not, to hell. His Fravashi, which guided him through life as a guiding spirit, parts from his soul and goes to its abode or place among all the Fravashis. It is the soul (*urvan*) that meets with good or evil consequences of its actions. The Fravashi or the guiding spirit, was pure and perfect, unalloyed and uncontaminated from the beginning and has passed away as such. So it is this pure and perfect spiritual entity, the Fravashi, that is the medium, as it were, of the continued relation between the living and the dead. After the third day after

¹ The belief of the ancient Egyptians about the future of the soul after death, was similar to that of the ancient Persians in several points. There was some similarity between the Fravashi of the Zoroastrians and the Ka of the Egyptians. For further particulars, *vide* my paper on "The Belief about the Future of the soul among the ancient Egyptians and Iranians" (Journal B. B. R. A. S. XIX, pp. 365-374, *vide* my *Asiatic Papers*, Part I, pp. 37-46.)

death, the Fravashi of the departed dear one is invoked. It is the Fravashi of the deceased that comes to the help of the living dear ones, provided they live a pure virtuous life and hold their departed dear ones in veneration.

Nature of the relation.

The relation subsisting between the two is, according to the Avesta, reciprocal. The dead expect to be remembered by their living dear ones, and in their turn offer their help and assistance. We learn from the Frawardin Yasht what the wishes of the Fravashis of the departed ones are. They exclaim: "Who will praise us? Who will offer us a sacrifice? Who will meditate upon us? Who will bless us? Who will receive us with meat and clothes in his hand and with a prayer worthy of bliss? Of which of us will [400] the name be taken for invocation?"¹ These words of the Fravashis then show, what they expect from the living dear ones. They expect to be remembered and held in esteem and respect. In return, they offer the following blessings: "May there be in this house flocks of animals and men! May there be a swift horse and a solid chariot."² Bearing in mind, that in those early days the cattle and the horse formed the wealth of a person, we understand by this, that the Fravashis in their turn offer to pray to God to give to their living dear ones prosperity and a progeny of children. Again, we read: "May these Fravashis come satisfied into this house; may they walk satisfied through this house! May they, being satisfied, bless this house, with the presence of the kind Ashi Vaughuhi! May they leave this house satisfied! May they carry back from here hymns and worship to the Maker, Ahura Mazda, and the Amesha Spentas! May they not leave this house of us, the worshippers of Mazda, complaining!"³ (Yasht 13:156-57.) Again, we read that those who "treat the Fravashis of the faithful well"⁴ become independent and happy, their difficulties are got rid of,⁵ they are rewarded with success, health and glory,⁶ and with an earnest desire to help the good and the virtuous⁷ and to break the power of those who oppress the poor and the innocent.⁸

1 S. B. E. Vol. XXIII, p. 192. (Yasht 13:49).

2 *Ibid*, p, 193.

3 *Ibid*, p. 184: Yasht 13:18.

4 *Ibid*, p. 230.

5 Yasht 13:20.

6 Yasht 13:24.

7 *Ibid*, 25, 39.

8 *Ibid*, 31, 33, 39.

Here, we see the relation supposed to subsist between the good that are living and the good that are dead. Those that are gone wish and expect to be held in esteem and regard and to be remembered and respected. The living, on their part, also desire that the dead may be remembered in their houses well and worthily and that they may return satisfied and contented. The Fravashis of the dead on their part pray for and offer blessings to the living that they may be blessed with worldly and spiritual wealth, that they may be happy and virtuous, that they may help the virtuous and punish the vicious. So, in short, the relation between the living and the dead is respect, regard, remembrance and esteem from one side and blessings from the other. [401]

The one essential thing for the living to receive the blessings of the good dead who are gone is, that they should be *ashavan*, i.e., righteous. When the Fravashis are invoked in a house, they feel satisfied and contented if they see piety, virtue, righteousness in the house. If they do not see that, they return unsatisfied and distressed. All the prayers recited in the house in honour of the dead must be prayers that “reach righteousness” (*asha nâsa nemangha*). The Yasna (Ha 16) again says, that “the dead rejoice at the brilliant deeds of righteousness, by the living.” If they will find the house virtuous, they will move therein, as it were, with pleasure and satisfaction, and bless the house with the gift of Ashi Vanghu. If they will find the contrary, they will leave the house “complaining.” Righteousness in the house is the *sina qua non* of their hearty, good reception. If that is not seen in the house, hundred other things done for them go for nothing. If they will receive satisfaction from the house in point of righteousness they will be the means of carrying the prayers of the living to the throne of Ahura Mazda. In that case, they (the Fravashis) will carry to the house¹ “the healing virtues of (their) blessed gifts as wide-spread as the earth, as far-spread as the rivers, as high-reaching as the sun, for the furtherance of the better men, for the hindrance of the hostile, and for the abundant growth of riches and of glory.”² [402]

1 S. B. E. Vol. XXXI, p. 311: Yasna 60:4.

2 The veneration of the dead among the Zoroastrians, resembles, in some points, the veneration of the Manes of the dead among the Romans. The word “Manes” comes from Latin *manus*, good, and the Fravashis of the Avesta are also spoken of always as “the good” (*vanghuish*). The Manes of the virtuous were known as the Lares. The Fravashis in the Avesta are spoken of as those of the house, of the street, of the village, of the country, (*nmânayâo*, *visyâo*, *zantumâo*, *dakhyumâo*), I think somewhat similar division or nomenclature seems to have been made in the case of the Manes of the Romans. The Fravashis of the house (*Fravashayo nmânayâo* from *nmâna*, house) correspond to the Lares domestici (*domus*, house) of the Romans: The Fravashis of the street *Fravashayo visyâo* (from “*vis*”, street) correspond to the Lares compitales (parts of a city marked out with *campita* or dots) of the Romans. The Fravashis of the village (*Fravashayo Zântumâo* from *Zantu*, village)

CHAPTER XVIII. (III) THE SATÛM.

Satum, a Hymn of Praise for the dead.

The word *Satûm* means "praise." It comes from Avesta *stu*, Sanskrit *stu*, to praise. It is a prayer recited on meals in honour of the dead. It is so called from the word "*staomi*" which occurs in the commencement of the 26th chapter of the Yasna which is recited in the the prayer of the Satum as its principal portion. The Chapter opens with the words "I praise (*Staomi*), remember, and extol, the good, brave, and beneficent Fravashis of the pious." The word *Satûm* corresponds to the Sanskrit *stom* which means a "hymn of praise," as well as "a sacrifice, an oblation." Thus the word *Satûm* means a "Hymn of Praise."

As seen from the sentence quoted above (Yasna 26:1) it is a hymn of praise for all the Fravashis. At first, the Fravashis of all the Holy ones are invoked generally and then specially those of Ahura Mazda, His Amesha Spentas, of the pious *Poiryô-tkaeshân*, i.e., of the Mazda-worshippers who preceded the time of Zoroaster, of Gayomard the first man, of Zoroaster, of King Gushtasp in whose reign Zoroaster flourished, of Isad-vaster, a son of Zoroaster who was a chief priest. of the Nabânazishtas, i.e., of the contemporaries of Zoroaster who worshipped one God, of all pious souls, of all who were profound in religious lore and of all who were still acquiring that lore, and of all the pious, whether males or females, whether adults or minors.

The praise consists in remembering the dead, in remembering their good deeds and actions. But a most praise-worthy praise consists in your acting up to the high standard of the person or being whom you praise. So, in the Pazand Dibache which is recited after the recital of the above chapter of the Yasna which is known as "Satûm nô Kardo," i.e., "the section of Satûm," the worshipper expresses a desire to that effect and says, "May my Humata, Hukhta, Hvarshta, i.e., good thoughts, good words, and good deeds, go to delight the Fravashis of the holy." Thus the worshipper is enjoined to act up to the standard which Hana More points out in the lines. [403]

"Sweet is the breath of praise when
given by those
Whose own high merit claims the
praise they give."

correspond to Lares rurales (*rus, ruris*, the country) of the Romans. Lastly, the Fravashis of the whole country (*Fravashayo dakhyumâo*) correspond to the Lares præstites of the Romans. The Lares publicii of the Romans correspond to the Fravashis of the public benefactors remembered in the Frawardin Yasht (*vide* my paper in Gujarati on Farohars in my "Anahita and Farohar").

To praise the dead is more praise-worthy than to praise the living, because in the latter case, it may be, that you perhaps expect something substantial from them in return, but in the former case, you expect nothing substantial from the dead. What little you do is a kind of self-sacrifice. A Hymn of pure praise is better than a prayer wherein you want something from the Higher Powers.

Satûm recited over meals.

The Satum prayer is generally recited over meals. In the Haoma Yasht (Yasna 10:18) we read: "O Haoma! these Gathas are for thee, these *satums* (*staomayô*) are for thee, these meals (*chichashânâo*) are for thee, these words of truth are for thee." Hence the custom seems to have arisen to have a meal placed in a tray and then to recite the Satum prayer over it. The presentation of the meals is symbolic, showing that there exists a kind of communion, mental or spiritual between the living and the unseen higher intelligences of the dead. In the case of the dead, the living present their meals, as it were, to the memory of the dead, and, while presenting them as an offering for them, offer at the same time, as said above, an expression of their will to offer their good thoughts, good words, and good deeds,

The meals are prepared carefully with an idea of purity and cleanliness. If in a Parsee household the daily meals are prepared by a non-Parsee cook, in the case of a meal prepared for the *Satûm* prayer, the members of the family carefully wash the utensils clean, and prepare the meal themselves or engage a Parsee cook for the purpose. One or more dishes prepared according to the means of the family are arranged in a tray. A pot of pure water and a glass of wine are also placed in the tray. Then a vase of fire is placed in the front between the tray and the priest who recites the *Satûm* prayer. The priest, while reciting the *Satûm*, burns sandalwood and frankincense on the fire. In the recital of the Pazand Dibache, he mentions the name of the particular person in whose memory the *Satûm* is [404] recited. Together with his name the names of the other departed ones of the family may also be remembered.

When the recital is finished, one or more members of the family place frankincense on the fire referred to above. *Lobân mukvun*, i.e., to place the frankincense, is a part of the ceremony in which the ladies of the family take a special consolation for the separation of their dear ones. They remember the name of the particular dear one or dear ones whose memory they wish to honour, and, while doing so, place frankincense over the fire.

The morsel of the dog.

Before the large tray containing the meals, there is a small plate containing a part of the meals, not necessarily a part of all the dishes. This plate is for what is called *Kutrâ no bûck*,¹ *i.e.*, a morsel (lit. share) for the dog. It reminds one of olden times, when every Parsee street had a dog, not only for religious purposes as the *sagdid* but for Police purposes as well. Even now in a Parsee town like Naosari, some people feed, on some occasions, the dogs of the street. Up to a few years ago, it was a practice, even in Bombay, to send a bread or breads to the Towers when a corpse was carried there, to feed the dogs kept there for the *sagdid*. After the recital of the *Satûm*, this plate of meals is given to the dog or dogs of the street for food. When there are no such dogs, it may be given to the poor as charity, or to young children of the family, on the principle, perhaps, that “charity begins at home.”

Occasions for reciting the Satûm.

The occasions of the monthly Baj, *i.e.*, the monthly day during the first year after death on which a person died, and of the anniversaries of death are the principal occasions for the *Satûm*. It is also recited on other religious holidays like the Gahambars, the Frawardegan holidays, the Jashans, etc. Its recital is not necessarily connected with the dead. It may be recited even on joyous occasions. [405]

1 The word *bûch* ବୁଚ୍ଚ now used by the Parsees seems to be Av. aGab *baga* (Guj. ବାଗା from Av. jab Sans. ବାଞ୍ଚ Lat. frangere to break) a broken piece. Or, perhaps it may be the Arabic word used in Persian, بک buk meaning “having little milk” (Steingass). It is a practice with some to give to a dog, on such an occasion, a little milk, and a meal may be a substitute for such milk.

CHAPTER XIX. COMBINED GROUPS OF LITURGICAL CEREMONIES.

Having described at some length, the liturgical services individually, I will now describe certain ceremonies or rather groups of ceremonies which are observed by celebrating a certain number of the different services. Among such groups of services are the following:—

1. The Hamâyasht or Homâsht.
2. The Geti-Kharîd.
3. The Sarosh.
4. The Zindeh-ravân.
5. The Nirangdin.
6. The Gahambar.
7. The Jashan.
8. The Frawardigan.
9. The Farestâ.

1. HAMÂYASHT OR HOMÂSHT.

The word “*Hamâ Yasht*” means the praise or celebration (*Yasht*) of all (*hamâ*) Yazatas or angels. The ceremony consists of several celebrations of the *Yasna* and the *Vendidad*. It is performed in honour or in memory of women either living or dead. The belief is, that women are, in their state of menstruation, and accouchement, enjoined to observe certain observances (*Vide* Purification ceremonies). There may have been or there may be derelictions in the observance of those customs or in other worldly or religious duties. So, the performance of these ceremonies act, as it were, as some means to make up for the deficiencies in the observance of the customs.

The Hamâyasht consists of 12 *kardas* or sections. Each *Karda* or section consists of twelve recitals in honour of one particular Yazata. The recital varies according to the nature of the Hamâyasht. There are two kinds of the Hamâyasht:—

- (a) Moti (𑬨𑬀𑬱𑬀𑬎) or the great Hamâyasht.
- (b) Nâni (𑬀𑬎𑬀𑬎) or the small Hamâyasht. [406]

(a) The first, *i.e.*, the great Hamâyasht consists in the recital of 144 *Yasnas* and 144 *Vendidads* with their rituals. The 144 *Yasnas* and *Vendidads* are recited in honour or with the *Khshnuman* of 12 *Yazatas* or angels, *i.e.*, 12 *Yasnas* and 12 *Vendidads* are celebrated in honour of each *Yazata*. These 12 *Yazatas* are the following:— 1. Ahura Mazda. 2.

Tishtar. 3. Khwarshed. 4. Mihr. 5. Aban. 6. Adar. 7. Hordad. 8. Amurdad, 9. Spendarmad. 10. Gowad. 11. Srosh. 12. Ardafravash (Frawardin). The above list is given in the order in which the celebrations in honour of each Yazata are performed.

If one pair of priests, *i.e.*, two priests, would perform the whole ceremony, it would take 144 days, *i.e.*, about 5 months to complete it, as only one Yasna and one Vendidad can be recited every day. More than one Yasna can be recited by two priests during the Hawan gah or the morning hours of the day, but, as only one Vendidad can be recited during the Ushahin gah or the hours after midnight, one Yasna and Vendidad only can be celebrated per day. So, if one wishes the ceremony to be finished during a shorter period, one or more *Jôrs* or pairs of priests can be engaged for the service. While the ceremony lasts an Afrinagan and a Baj in honour of the same Yazata in whose honour the Yasna and the Vendidad are recited, are also performed.

(b) The smaller Hamâyaht consists of the recital of 144 Yasnas and 12 Vendidads. At the end of each *Karda* or section, *i.e.*, at the end of the recital of 12 Yasnas in honour of one Yazata, one Vendidad is recited in his honour. Now, as one pair of priests can celebrate during a day more than one Yasna and as the Vendidad is to be recited at the end of each *Karda* of 12 Yasnas, the smaller Hamâyasht can be finished sooner than the larger one. Again, if more than one pair of priests are employed, it can be finished much sooner.

2. THE GETI-KHARÎD.

The word *Geti-kharîd* literally means, “the purchase (*Kharid*) of the world (*geti*).” It corresponds, to a certain [407] extent, to the Christian word “Redemption” which also comes from a root *emere*, meaning to buy. It is intended to be a ceremony for seeking salvation from the sins of the world. The original idea suggested by the name seems to be, that one should redeem his time and make the best use of it so as to save himself. It was something like that suggested by the following words of St. Paul in his Epistle to the Ephesians (Chap. 5:15-16) : “See then that ye walk circumspectly, not as fools, but as wise. Redeeming the time, because the days are evil.” As the Patet says it is not money with which one has to purchase his salvation, but with his heart. One has to give away the money which he has when required for the good of others. He is to sacrifice even his life for the sake of truth. We read in the Patet (*Karda* 1): “The whole powers which I possess, I possess in dependence on the Yazatas (*Yazdân*, *i.e.*, God). To possess in dependence upon the Yazatas means (as much as) this: if anything happens, so that it behoves to give the body for the sake of

the soul, I give it to them.”¹ So, the original idea is that of self-sacrifice.

The ceremony that is now known by this name consists in the recital of nine Yazashnas or Yasnas. The first six Yazashnas are those of Mino-nawar. They are performed for six days, one at a day, each of the two priests who perform them serving as *Zaota* alternately. Then, on the sixth and the seventh or the seventh and the eighth day, they perform three more Yazashnas, one in honour of Srosh, another that of the Siroza, and the third the Visperad.

3. SAROSH.

Sarosh ni Kriya, i.e., the Ceremonies of Sraosha.

By the name Sarosh are known the funeral ceremonies that are generally performed in honour of a deceased person during the first three days after death. At times some repeat these ceremonies even some time after death, even after months or years after death. These ceremonies are known by the name of Sarosh, because the prayers therein are recited in honour of, [408] or with the Khshnuman of, Sraosha. We will here shortly describe the functions of Sraosha, the Yazata or angel, which will enable one to see why the prayers are recited with his Khshnuman.

Sraosha, the Yazata.

In Zoroastrian angelology, Sraosha (Srosh) occupies a very high position. As said by Dr. Geiger, he is a “characteristic figure in the Avesta religion” and “exemplifies clearly the ethico-philosophical spirit which predominates in the Zoroastrian system.”²

The word comes from the root *sru*, Sanskrit *shru*, to hear, or to cause to hear, and thence to obey. So he presides over the abstract idea of obedience, — obedience to God. Obedience implies hearing. So he is the Yazata who hears from God, communicates to Man what he hears from God and asks Man to obey God’s message which he communicates. Hence he plays, to a certain extent, the same part in the Parsee books, as that which Gabriel plays in Christian books. He is a messenger of God communicating to Man the wishes and orders of God. It is generally through him that prophets and even righteous men are inspired by God. He protects the souls of men both during the day and during the night. His protection is greater at night. Hence it is that the Yashts in his praise (Yasht 11 and Yasna 57.) are specially

1 Spiegel, translated by Bleeck, Vol. III. p. 153.

2 *Civilization of the Eastern Iranians in Ancient Times*, Introduction, translated by Dastur Darab P. Sanjana, Vol. I, p. LI.

recited at night. The dog, who watches a house at night, and the cock, that crows during the last part of the night and wakes men from sleep, are therefore the animals that are associated with his work. (*Bundahishn*, Chap. 19:33). He protects man against the evils of ignorance, anger, sloth, and intoxication. The pith of all that is said of him in the Avesta and Pahlavi books is this: By obedience to the Commands of God, by conformity to His laws as seen in Nature, man protects his soul and moves in the proper path. Obedience to the Laws of God, as seen in his Nature over which Sraosha presides is everything. As M. Harlez says: "L'accomplissement de la loi est la source de toute la prospérité."¹ [409]

From all this we see that Sraosha is the guardian angel who protects the soul of man. He protects the soul of man not only during life but even after death (*Yasna* 57:25). His help or co-operation is required by the soul during its passage to the next world, especially during the first three days, when it is passing to a new plane of activity from the plane of this world to that of another. We read in the *Menog-i Khrad* (Chap. 2:115): "The fourth day in the light of dawn—with the co-operation of Srosh the righteous, Vâê the good, and Warharan, the strong (the soul) goes up to the awful, lofty Chinwad bridge to which everyone, righteous and wicked is coming."² "And the righteous soul passes over with the co-operation of Srosh the righteous" (Chap. 2:124).³ (*Vide* also *Shayesht Ne-Shayest*, 17:3; *Dadestan-e Denig*, 28:6-7). Thus, we see that the ceremonies are performed with the Khshnuman of Sraosha, because the soul in its passage to the next world has his help and guidance. So, the Sarosh ceremonies are on the one hand intended to signify thanksgiving to Sraosha for the protection that he had offered to the soul during his life-time and that he offers after death. They are at the same time intended to pray, that he (Sraosha) may continue that protection after death. After separation from the body, the soul, finding itself, as it were, on a quite new plane, in other spheres of activity, is in more need of help and protection.

The Sarosh ceremonies consist of the following:— (The Pahlavi *Vendidad* 8:22 refers to some of these ceremonies).

1. The recital of 3 Yasnas with the Khshnuman of the angel Srosh during the morning hours. This recital is indispensable. For a child under seven, one Yasna is permissible. (*Ibid.*)
2. The recital of the *Vendidad* at midnight from one to three in

1 *Le Zend Avesta*: Introduction, CXV.

2 S. B. E., XXIV, p. 17.

3 *Ibid.* p. 19.

- number. This is not necessary; it may or may not be made.
3. The recital of the Srosh Baj during each of the 5 *gahs* or periods of the day during the first 3 days. This recital is not indispensably necessary, but it is generally made. [410]
 4. The recital of the Afrinagan of Sraosh (Yasna 57:15-18) in the first part of the night (Aiwisruthrem gah). This is indispensably necessary. It is generally recited in the house near the spot where the remains were placed before being carried to the Towers. This recital is ordinarily spoken of as "Sarosh no Kardo, *i.e.*, the particular section in honour of Sraosha.
 5. The recital of the Niyayeshes and Yashts in each of the five *gahs* or periods of the day. During the three periods of the day, the smaller Srosh Baj, *gahs*, the Khwarshed and Mihr Niyayeshes and Patet are recited; and, during the night, the smaller Srosh Baj, the *gahs*, the Yashts (Yasna 57 and Yasht 11) and the Patet are recited. These recitals are not indispensably necessary.
 6. The recitals at the Uthamnâ ceremony. They are necessary. Some perform this ceremony twice, once during the afternoon of the third day and the second time at the end of the third night. Only one of these two is necessary, and especially that at the end of the third night.
 7. The recitals of the Four Bajs with a *Siâv* or suit of clothes during the latter part of the third night, (*Vide* Baj for the description of these).
 8. The recital of the Afrinagan of Daham on the dawn of the third night.
 9. The Chehârum, or the fourth day ceremony.

All the different ceremonies which make up the Sarosh ceremonies do not require any fuller explanation, as they have been treated under their respective headings, but the Uthamnâ and the Chehârum require a special mention. We will describe them at the end of the article on Sarosh.

Jorâni Kriyâ.

In the matter of the Sarosh ceremonies for the first three days after death, and subsequent ceremonies during the first [411] year or even after the first year, the practice is that if the deceased is a married person, the ceremonies—if not all, the principal according to one's means—were performed not only in the name and in honour of the deceased but also in the name of his or her partner, *i.e.*, of the husband if the deceased is a female, and of the wife if he is a male, whether the partner be living or dead. The performance of this double

set of ceremonies is spoken of as “Jorâni, Զլըլեի,” *i.e.*, ceremonies of the pair. This double performance is not referred to in old books and seems to be a later introduction. In case the deceased has gone through a second marriage, the ceremonies are threefold. For example, if A dies and had married a second wife C after the death of his first wife B, then on his demise, some of the ceremonies are performed in the name of all three A, B, and C. This is not a general practice, but is resorted to by those able to afford. The custom of this double set of some ceremonies seems to have arisen from the belief that a pair once married is married for life and death.

Expenses of the funeral ceremonies for the first four days.

The Trustees of the Funds and properties of the Parsee Panchayet pay the funeral expenses of the poor of their community who are not able to defray them. In case of those that have died utterly destitute and without anybody to perform the funeral ceremonies after them, they (the Trustees) get the ceremonies performed in a Fire-temple under the charge of a head-priest. I give below a list of the charges which will give one an idea, not only of the expenses, but also of the ceremonies that are thought to be absolutely and indispensably necessary. The total cost paid for the poor in Bombay, which is a big and rather expensive city is Rs. 45.

	Rs.	a.	p.
Fees received at the Tower of Silence for the wages of the 2 corpse bearers, etc., in the vase of poor persons ...	4	0	
Fees of two priests who perform the <i>Get Srnâ</i> ceremony 3 before the removal of the corpse ...	0	0	
Recital of the three Yasnas of Srosh ...	6	0	0 [412]
Recital of the Ardafrawash on the Chehârum, <i>i.e.</i> , 4th 2 day ...	0	0	
Recital of four Bajis on the third day after midnight ...	2	0	0
Recital of the Karda of Srosh for three nights ...	3	0	0
The Uthamnâ and the Afrinagan on the dawn of the fourth 4 day ...	0	0	
The Afrinagan Baj of Chehârum on the 4th day Fruit, 6 flowers, flour, sandalwood, etc., ...	8	0	
The meal for the Satum on the Chehârum day ...	1	0	0
<i>Siâv vâsan</i> (<i>i.e.</i> , a suit of clothes, utensils, &c.) to be 7 consecrated at the recital of the four Bajis on the third day ...	4	0	
Total ...	40	0	0

Uthamnâ ceremony.

The word *Uthamnâ* comes from an Indian verb “*uthvun*” meaning

“to get up, to depart.” According to the Parsee books, on the death of a person, his soul remains within the precincts of this world, generally at the place where he died, or at the place where his body had its last resting place. It is at the dawn of the third night, it gets up, as it were, and departs from this world to the world above. So, the ceremony performed on the third day after death is called “Uthamnâ,” *i.e.*, the ceremony of the day of the departure” of the soul from this world.¹ The most proper occasion for the ceremony is the dawn of the third night when the soul is believed to depart from the precincts of this world. The ceremony is performed at that time, but generally the custom is, that it is also performed in the afternoon of the third day in order to make it convenient for the friends and relations to attend at, and participate in, the ceremony.

Friends and relations and the invited priests assemble at about 3 p.m. at the place where the ceremony is to be performed. [413] The place may be either the house of the deceased, if it is convenient to accommodate the assembly there, or at an adjoining Fire-temple or another kind of public place. At three o'clock when the *gah* (Uzerin) changes, most of the persons assembled perform their ablutions and perform the Kusti Padyab. They then stand turning to the West and recite the Khwarshed, Mihr Niyayeshes, the *Doa nam Setayashna* and the *nemô-aônghâm* prayer known as the *nemâz* of the four quarters of the world (Yasna 1:16). The Khwarshed and the Mihr Niyayeshes are repeated twice. It is considered to be the duty of every Zoroastrian to say his Khwarshed Mihr Niyayeshes three times (Hawan/morning, Rapithwin/noon, and Uzerin/afternoon) during the day. So, the first set of the Niyayeshes is recited with a view to do their own duty. The second is believed to be recited out of their duty and respect towards the dead. After the conclusion of the above prayers, all assembled perform the Hamazor with one another. They then sit down on the carpet and recite Uzerin gah and Srosh Hadokht (Yasht 11). They then recite the Patet or the prayer of repentance mentioning the name of the deceased person in the last *Kardeh* or section. In all these prayers, the head or the senior priest leads the recital. During the recital of the Patet by the whole assembly, a priest standing before the fire, which burns in a vase, and with trays of fragrant flowers and of pots or vessels containing rose water and other perfumes before him, recites the Dhup-nirang (see below) mentioning the name of the deceased person. If the deceased person is married, two priests say the Dhup-nirang prayer. In that case the ceremony is said to be that of *Jorâni Kriyâ*, *i.e.*, the ceremony of the married pair.

1 Some say that it is so called because, after its celebration, members of the family, get up from their deep mourning and go out for their usual avocations.

Sôsh.

At the conclusion of the *Dhup-nirang* prayer, one of the heirs of the deceased, generally the eldest son or a near relation is presented before the senior priest who makes him recite a form of obligation which is spoken of as “*Sôsh bhanâvvi*” wherein a son or a near relation undertakes to perform certain religious ceremonies in honour of the deceased. The word *Sôsh* seems to be a corruption of *Srosh* which is the principal ceremony for the dead. The obligation is to get the following recited or done:— [414]

(a) *Lâkh bhanâvvi*, i.e., to get recited one lac, five hundred Ahunwars.

(b) Three Yasnas.

(c) Three Vendidads.

(d) Twenty-four Drons.

(e) Ashodâd, i.e., the gift to the righteous.

This obligation nowadays has become well nigh stereotyped. It seems that formerly the obligation was only for the ceremonies which the surviving relations wished to be performed.

Then, if the deceased is a male of the age of 15 or above. an announcement is made as to who has been adopted as his son. Donations in charity in honour or in memory of the deceased are then announced. Then the assembly recites the Tandarosti prayer praying for blessings upon the surviving head of the family. Consecrated flowers are then distributed among, and rose-water besprinkled upon, the persons assembled.

Lastly, the family priest goes round among the persons assembled and makes *salâms* or salutations. This is the way of thanking the people for their kind presence on the occasion. Formerly, the head of the family also followed the family priest in bidding the salutation. But that custom is not observed generally, though it is prevalent even now in mofussil towns like Naosari.

The Ahunwar or Yatha Ahu Vairyo is a short prayer like the Paternoster of the Christians. The relations undertook to get one lac (*lâkh*) and five hundred Ahunwars recited in honour of the deceased. They need not and cannot be recited at once. They can be recited at convenience during the first year after death. They may be recited by a priest or may be recited by a member of the family.¹

¹ For a fuller description of this ceremony, *vide* my paper on “the use of Rosaries among the Zoroastrians” in the *Sir J. J. Zarthoshti Madressa Jubilee volume*. *Vide my Memorial Papers*, pp. 63-64.

(b) (c) (d). The recital of the Yasna and the Vendidad refer to the recitals of these ceremonies during the first three days. The 24 Drons refer to the sacred breads in the Baj ceremony performed at the latter part of the third night. [415]

The Ashodâd.

The word *Ashô-dâd* means gifts to the righteous. The voluntary payments to the priests are generally known by that name now. In the *Uthamna* ceremony, at the end, the head of the family or somebody in his behalf pays the priests their fees. The sums given vary according to the means of the family. The head or the senior priest is paid more than others according to his status in his profession. Besides payment in money, each priest is generally given a *sudra* or sacred shirt. The suit of clothes that is consecrated with the four Bajis on the third day after midnight and which is known as *Siâv* is also spoken of as *Jameh Ashodâd*, i.e., the clothes to be given as gift to the righteous poor. This suit of clothes is generally given to the family priest.

Gâe bhanâvvi.

It seems that formerly the family priest was given a cow in addition to payment in money and clothes. This custom seems to have arisen in India where Hindus presented cows to their Brahmins. Though the custom of giving a cow is no longer observed, its remnant has remained in a money payment to the family priest which is called the fee for *Gâe bhanâvvi*, i.e., the declaration in prayer for the gift of a cow. He is now given a sum varying from one Rupee to 5 Rupees under that name. As this fee is now given at the time when the above referred to Shos (or Sraosha) declaration or obligation is made, it is at times called the fee of *sôsh* (Srosh) *bhanâvvi*.

Dhup-sârvi.

Dhup is an Indian word (Sanskrit *dhup*) meaning perfume. Dhup saroi is the modern Indian name of the ceremony, of which the ancient Persian name is *nirang-i-bui dâdan*, i.e., the ceremony of giving or distributing the perfumes. The ceremony is so called because during the performance of this ceremony, fragrant flowers, rose-water, and other perfumes are placed in trays on carpets on which the assembly is seated. At the end of the ceremony these flowers are distributed and the rose-water sprinkled among the [416] persons assembled. Again, during the performance of the ceremony, fragrant wood like sandalwood and the agar and fragrant incense like frankincense, are burned.

Now, what do these perfumes of the fragrant flowers, rose-water and other odoriferous liquids seem to signify and symbolize? The

ceremony seems to signify that the path of the righteous (*ashavan*) souls in the next world is besprinkled with fragrance and joy. It moralises and says, as it were, to the people assembled: "A righteous soul that passes away to the next world has his way beset with fragrance and joy. Let us all think of that and bear that in mind and let us all so behave, that when our turn of departure comes, our way also may be so perfumed with fragrance and joy." The *Arda Viraf Nameh*, which, like the Divine Comedy of Dante gives a picture of what the righteous soul meets on his way to the next world, says that "on the dawn of the third day the righteous soul moves about in the midst of fragrant plants" (*Arda Viraf Nameh*, Chap. 4:15). So, the occasion when this Dhup ceremony is performed being that of the *Uthamnâ*. (*q. v.*) or the ceremony of the third day after death, fragrant flowers, and perfumes are presented as symbols.

The Dhup ceremony forms a part of the *Uthamnâ* ceremony. It consists in the recital of the Pazand Dibache, which precedes the recital of the Afrinagan ceremony. The Dibache is preceded by a few additional words in the commencement (*az hamâ gunâh patet pashemânum. Ashem*, etc.) expressing repentance of sins, if any. It ends with a few more sentences expressive of good wishes for the deceased and for the living creation.

The recital of the Dibache is spoken of as "*Dhup sârvi*." There are three ceremonies with which the verb "*sârvi*" is connected. The verb "*sârvi*" is Persian "*Sarâidan*" which means "to cause to hear, to chant, to sing." It is the Avesta "*Srâvaya*" which is the causal form of "*sru*," Sanskrit "*sru*," a root from which come the English words "celebrate" and "laudation." The two other ceremonies with which this verb is connected are the Ashirvad or marriage ceremony and the Geh sârânâ ceremony or the recital of the Gatha over the dead body before its removal [417] to the Tower. One is spoken of as "*Ashirvad Sârvi*." and the other as "*Geh Sârvi*." The use of this verb suggests that the recital of the prayers at these three ceremonies must necessarily be with a loud voice so as to be heard aloud by all the persons who assemble on the occasions.

Chehârum.

The word *Chehârum* means "the fourth." The fourth day and the ceremonies of the fourth day are known by that name. Though this day's ceremonies do not strictly belong to the Sarosh ceremonies properly so called, they are generally considered to form a part of these ceremonies. They consist of the recital of an Yasna, an Afrinagan, and Baj, known as *Chehârum ni Ardâfarosh*, (*i.e.* the recital of the Yasna in honour of the Farohars or Fravashis on the

fourth day) and *Chehârum nu Âfringân Baj*. The recital of the “Satum” at about midday on the mid-day meal generally completes the ceremonies of the day. The priests who had been performing the Sarosh ceremonies for the preceding three days at the Fire-temple or Dar-e Mihr are generally invited to dine at this Chehârum midday meals. They partake of this solemn dinner with the recital of a Baj or prayer of grace mentioning the name of the deceased in the Dibache of the Baj. At the end of the meals the priests are given some small money gifts. For the first three days after death, meat is prohibited. It is allowable from the fourth day. Wine is considered necessary in its celebration (*Vide* Pahlavi Vendidad 8:22 for the Chehârum ceremony).

4. ZINDA-RAWAN.

The word *Zinda-rawan* means a living soul and is opposed to *Anosheh-rawan*, i.e., the dead (lit., immortal) soul. All the Parsee liturgical ceremonies are performed both in honour of the living and of the dead. As far as the recital of the prayers goes, the prayer is the same except this, that at that part of the prayer where the name of the person, in whose honour the ceremony is performed, is mentioned in the Dibache, if he is living, the word *Zinda-rawan* is mentioned as an epithet before his name (e.g., *Zinda-rawan A or B*), and if he is dead, the word *anosheh-rawan* is mentioned. [418]

Zinda-rawan, the name of a ceremony.

The word *Zinda-rawan* has come to assume a technical name for a ceremony. It is the ceremony in honour of Srosh. On the death of a person, the funeral religious ceremonies are performed with the Khshnuman of the Yazata Srosh who is believed to be the angel protecting the souls of men. It is not only the souls of the dead that he protects but also the souls of the living. So, a Zoroastrian gets the Sarosh ceremony performed in his life-time. This Sarosh ceremony thus performed for one in his life-time is called his “Zinda-rawan.” So the Zinda-rawan is the Sarosh ceremonies performed in one’s life-time. At times, it is continued for the whole year, i.e., all the religious ceremonies during the first year—like the Chehârum, i.e., the Fourth day, the Dehum or Dasmu, i.e., the Tenth day, the Sirouz, i.e., the thirtieth day, and each subsequent 30th day or monthly day and the Salrouz or the anniversary—are performed for a year. It is the ladies who generally get their *Zinda-rawan* performed. During the last generation, Parsee ladies, when they got their *Zinda-rawan* performed, looked to the event with satisfaction as having done a necessary righteous work in their life. They looked to the event with satisfaction from the point of view, that, if on their death the

necessary Sarosh ceremonies were not performed in their names by their relatives, or if some mishap—*e.g.*, that of dying in an out of the place locality where there was not sufficient convenience for getting the ceremony performed—prevented their being performed, the *Zinda-rawan* as the funeral ceremonies in honour of Srosh performed in their life-time would stand them in good stead and would have his protecting or beneficial effect.

One hears here and there the story of an orthodox Parsee of the last generation taking so serious a view of the matter that he not only got the funeral ceremony of Sarosh performed but also got the ceremony of *gêh sârnâ* performed, *i.e.*, he washed and laid himself on an iron bier as if dead and got a couple of priests to say the funeral service.

This reminds one of one of the Kings of France—it was one Louis—who is said to have got a solemn funeral service performed [419] over himself, and this to such an extent, that he was carried to the graveyard and there laid in a grave, where the last of the services was performed, in which he himself joined solemnly. He then left the grave after all others had departed.

The object of this ceremony was that it enabled one to take a serious view of life, and to consider, that in life he was in the midst of death, and that therefore it behoved him to lead a good settled virtuous life.

5. THE NIRANGDIN.

Nirangdin is the name of the ceremony which consecrates the *gomez* or the urine of the bull for ceremonial purposes. It consists of a Barashnom ceremony by two priests, then the Khub ceremony, then the six Gewrâs, and then the final Vendidad. (*Vide* above (pp. 253-57), the Consecration Ceremonies for details).

6. THE GAHAMBAR CEREMONY.

Gahambars, their importance from two points of view.

The Gahambars are six holidays or periods of holidays, each of the duration of 5 days, that occur at stated times of the year. They derive their importance from two points of view.— (A) Agricultural or seasonal.

(B) Cosmogonical.

The Avesta itself refers to them as agricultural or seasonal. The later writings connect them also with cosmogony. We will speak here

of these two points.

A. Gahambars as season festivals.

There are three facts which lead to show that the Gahambars are season festivals. They are the following.

(a) The root and the meaning of the word.

(b) The meanings of the words which bear the names of the six Gahambars.

(c) The description of the Gahambars found in the Parsee books. [420]

(a) Root and meaning of the word Gahambar.

Gahambar is a later word, the exact corresponding word for which is not found in the extant Avesta. If one were to coin a corresponding word, it would be "*Gâtuhâmbâr*." But the Avesta word which carries the meaning borne by the word Gahambar is "*Yâiryâ*" (Yasna 1:9). The word "*Yâiryâ*" comes from "*Yâré*" which is the same as English "year." "*Yâiryâ*" means "seasonal divisions of the year." The word Gahambar itself is the Pahlavi *Gâsânbâr*. As the word "*Yâiryâ* (*Yâre*, English *year*) comes from the root "*yâ*" to go, so the word *gâs* in *gâsânbâr* and *gâh* in Gahambar comes from the root *gâ*, to go.

Dastur Peshotan gives the meaning of the word as "prayer (*gâthâ*) or the gift (*bâr*, *bar*) of God." Mr. K. R. Cama thinks the last part of the word "*bâr*" to be the same as "-ber" in September, October, etc. and understands it to mean "time" (cf. the Gujarati word *vâr*). He takes the whole word to mean "the time for singing the Gathas." He thinks that the word may also mean an assembly (*ambâr*, Avesta *hâm-bairya*) of a particular time or place (*gâs* or *gâtu*). I think the word means "collection (*ambâr*) of time (*gâh*)," i.e., "the full time," "the proper (season) time."

(b) The six Gahambars and the meaning of their names.

The Gahambars are six in number. Their very names signify that they are season festivals.

1. The first Gahambar, which occurs from the 41st to the 46th day after Nawruz or the New Year's day, is Maidyozarem. Its name signifies "Midspring." (*maidhya*, middle and *zaremya*, spring from *zar*, Sanskrit *har* to be green.)

2. The second from the 101st to 105th day is Maidyoshahem i.e., Mid-summer (*shem*, Sanskrit, *samâ*, summer).

3. The third from the 176th to 180th day is Paitishahem. The word comes from *paiti* and *hahya*, Sanskrit *sasya*, corn and means "the

time of reaping the harvest.” It is the time of autumn.

4. The fourth from the 206th to 210th day is Ayathrem. The meaning of the word is not clear. It is thought to be the [421] time of prosperity and nourishment (*thrima* from *thrâ* to thrive). It is thought to be the breeding season of the cattle.

5. The fifth from the 286th to 290th day is Maidyarem, *i.e.*, the season of Mid-winter. The word means “the midst of *airya*” *i.e.*, rest. Mid-winter is the time when, owing to extreme cold, all agricultural work generally ceases.

6. The sixth from the 361st to the 365th day is Hamaspathmaedyem. It seems to signify the time when the path (*pathan*) of the year is the same (*hama*) or in the middle (*madha*). It is the time of the Vernal Equinox when the days and nights are equal, when the heat and the cold are the same, *i.e.*, moderate.

Though each of these six Gahambars lasts for 5 days, the principal day of the Gahambar is the last day. The preceding four days are as it were, of preliminary preparation and enjoyment.

(c) The description of the Gahambars in the Parsee books.

The description of the Gahambars as given in the Parsee books also tends to show that they are season festivals. The principal description of this is found in the Visperad (1:2). The *Bundahishn* also refers to this fact. (Chap. 25.)

B. Gahambars, as connected with Cosmogony.

In the Pahlavi Commentary of the Afrinagan of Gahambar, and in the Afrin of the Gahambar, these holidays are connected with the following six principal creations of God:—

1. The Heavens. 2. Water. 3. Earth. 4. Vegetable Creation. 5. Animal Creation. 6. Man.

The object of celebrating the Gahambars.

The consideration of the above facts shows that the principal and the first object of the celebration of the Gahambars was to offer thanksgiving to God for the institution of the different seasons, on the regularity of which depended the prosperity of the world. To this primary object was latterly added the object of offering thanks for the creation of the six best and grand objects of Nature. The *Menog-i Khrad* (Chap. 4) speaks of [422] seven principal acts of righteousness. Among these Charity (*râdih*) is placed first; then Truth (*râstih*) and then the celebration of the Gahambar. There it is said, that Gahambars or the phenomena of the seasons are one of the great acts

of Wisdom worthy of the Omniscient Lord.

The *Shayest Na-Shayest* (Chap. 12:31) enumerates some liturgical ceremonies which a Zoroastrian should celebrate. Among them the celebration of the Gahambars stands first. The *Sad Dar* (Chap. 6:1-2) also places the celebration of the Gahambars at the head of a list of six religious acts. The Vohuman Yasht (2:45) prophesies that the non-celebration of the Gahambars will be an evil day for the world. To put it into ordinary language, what it means is this, that it will be an evil day when man will cease to offer thanks to God for the creation of the phenomena of the seasons and for the different gifts that result from the phenomena. King Jamshed is said to be the first monarch of Persia who celebrated the Gahambars.

The two principal functions in the Gahambars.

There are two principal functions in the celebration of the Gahambars.

(A) The performance of the Liturgical services relating to the Gahambars.

(B) Solemn feasts accompanying the services. Of these two, though the first is more important it is the latter that has appealed and appeals most to the generality of people. We will here describe these two functions.

(A) The different Liturgical services of the Gahambar ceremony.

The following are the Liturgical services that are generally celebrated on the occasions of the Gahambars:

1. The Afrinagan of Gahambar.
2. The Baj of Gahambar.
3. The Yasna of Gahambar, known as the Visperad.
4. The Pâvi of Gahambar.

Of these four, the first two form the necessary services. The next two may not be celebrated. Of these four, the first [423] three have been referred to under the heading of Afrinagan, Baj, and Visperad. So, we will describe the *Pâvi* here.

The Pâvi of the Gahambar.

Two or more priests take part in this ceremony. One of the priests must have recited beforehand the Baj of the Gahambar with Barsom. (*Vide* above pp. 369 and 371). The other priests then *take* the Baj, *i.e.*, recite the first part of the second Baj of meals or grace. (*Vide* above p. 371.) They then recite in Baj the Dibache three times. (*Vide* above p. 377.)

In the first recital of the Dibache they mention the Khshnuman of the Gahambars, mentioning, out of the six names of the Gahambars, the name of the particular Gahambar during the period of which the service is being celebrated. During the second recital, the Khshnuman of the particular Hamkara is mentioned. During the third, the Khshnuman of Srosh is mentioned. In each of these recitals, the *Yâd* (p. 381) is made in the name of the person, for whom or in whose *niyat* or memory the Gahambar is performed. During these recitals, especially during the second and the third, the whole of the Dibache need not be recited. Half of it, up to the part where the names of the persons are commemorated, is generally recited.

In the ceremony of the *Pâvi*, no fruits or flowers are required. The only thing required is milk. Each priest has before him a small metallic cup or glass in which, at each recital of the Dibache a little milk is poured. Thus, all the recitals are made over milk. After this recital of the three Dibaches by all the priests, the particular priest who has performed the ceremony of the Baj of Gahambar recites alone the Dibache again. At the end of each sentence of the Dibache, the other priests say in chorus "*aidun-bâd*," i.e. "Amen."

Between the first three recitals of the Dibache by all the priests together and this fourth by the priest who had recited the Baj of Gahambar, there are two points of difference.

1. During the first three recitals the three Khshnumans of of (a) the particular Gahambar, (b) the Hamkara of the day, and (c) Srosh, are recited separately, each in each of the three [424] Dibaches, but in the fourth recital, all the three Khshnumans are recited together.

2. During the first three recitals. the sacred thing offered or produced is milk. Some make the recital on wine also. But in the case of the fourth recital it is made over pure water which the priest makes *pâv*, i.e., ceremoniously pure before the recital.

The reason why thil ritual is called *Pâvi*.

The reason why this ceremony is called "*Pâvi*" would, at first sight, seem to be that during its performance, the priest while reciting the fourth Dibache commences by making the ceremonial water *pâv* or ceremoniously pure. But the proper reason seems to be, that the ceremony was, in former times, performed in an enclosed space which is known as *pâvi*.¹ Of course, many liturgical services performed by the priests observing the Barashnom are performed within a *pâvi*, but as distinguished from these, this particular ceremony is called and specialized as *pâvi*. because while in those other services, the priests

1 *Vide* the word *Pâvi* in the chapter of Purification of ceremonies.

only take part in this ceremony of the *pâvi*, the laity also take part.

As a matter of fact, now-a-days the ceremony is not performed within an enclosed space or *pâvi*. So the name *pâvi* would seem to be a misnomer. But, it appears that though it may seem so now, it was not so formerly. It appears from Anquetil Du Perron, that as late as about 160 years ago, the ceremony was performed in a *pâvi* or an enclosed space. Anquetil, while describing this ceremony says:

“Les Parses étant rassemblés dans un jardin, et placés dans un endroit entouré d’un *keisch*, disent le *Vadj Khordan*, (i.e. the prayer of grace): et l’Herbed après avoir béni trois *Navés* (vases qui contiennent ce qu’on va boire ou manger), prononce au milieu de l’assemblée cet *Âfrin du Roi Gahambar*” (*Le Zend Avesta*, Vol. II, pp. 121-122).

B. The second function of the Gahambars: the solemn feast.

The Gahambars are generally accompanied with solemn feasts, wherein members of the family, or residents of a street, or a town participate. “Gahambar-ni-chashni,” i.e., the ceremonial and communal eating of the things offered in [425] the Gahambar ceremonies, forms an important part in the Gahambar celebration.

How to celebrate the Gahambars.

As said above, it was considered to be the duty of a Zoroastrian to celebrate the Gahambars. Then how were the poor to celebrate these? The Afrinagan of the Gahambar suggests a way for that. It says that all may participate in the public Gahambars and pay their mite, however poor, according to their means. Every Zoroastrian need not celebrate separately a Gahambar. There may be public Gahambars, celebrated by the members of a family or by the inhabitants of a particular street in a town or by those of a particular village or town. All may participate in these public Gahambars. If one can afford, he may pay his mite in money or in kind. For example, the Afrinagan says, if one can afford, he may offer as his mite, a fat healthy goat or sheep or the public feast. If he cannot afford to do that, he may give a quantity of wine. If one cannot afford even to do that, he may give a bundle of dry wood or fuel for cooking the food. If one cannot afford to do that even, let him give even one piece of fuel. If a poor man cannot afford to give even this small thing, never mind, let him go there and participate in the celebration by remembering his God there. He may join the celebration, say his prayer, and participate in the feast of the Gahambar. The four words used in the Afrin of Gahambar—*Yazad*, *sâzad*, *khurad*, *dehad*, i.e., pray, perform, eat, or give—seem to

suggest the different ways in which one can participate in the celebration of the Gahambar or season festivals to which a good deal of importance is attached in Parsee books. The ways are the following:

1. One may join in the prayers recited and pray.
2. One may do some manual service.
3. One may participate in the feast by offering some article of food.
4. One may give something in kind or money.

The *Shayesht Ne-Shayest* (Chap. 19:4) enjoins, that in returning from a Gahambar feast one must say four Yatha Ahu Vairyos. [426] This injunction seems to have been suggested by the fact of the recital of four Yatha Ahu Vairyos at the commencement of the Afrinagan of Gahambar, and, I think, this number four symbolizes the above four ways in which one can participate in a Gahambar.

Gahambar feasts of the Zoroastrians and the sacred feasts of the ancient Jews.

The above description of the celebration of the Gahambar in ancient Iran reminds us of the following description of similar sacred feasts of the ancient Hebrews as described in the Old Testament (Deuteronomy 12:6-7, 12):

6. And thither ye shall bring your burnt offerings, and your sacrifices, and your tithes, and heave offerings of your hand, and your vows, and your freewill offerings, and the firstlings of your herds and of your flocks.

7. And there ye shall eat before the Lord your God, and ye shall rejoice in all that ye put your hand into, ye and your households, wherein the Lord thy God hath blessed thee.....

12. "And ye shall rejoice before the Lord your God, ye, and your sons, and your daughters, and your men servants, and your maidservants, and the Levite that is within your gates; for as much as he hath no part nor inheritance with you."

The washing of the hand in such solemn feasts.

One of the solemnities observed in solemn feasts like those of the Gahambar is that of washing the hands before the meals. Though this custom is now-a-days not generally observed by the laity, the clergy do observe it still. A servant passes round with a water-pot and

a large vessel and lets the guests wash their hands before the meals. It is this custom that is alluded to in the Bible where we read:

1. Then came together upon him the Pharisees, and certain of the scribes, which came from Jerusalem.
2. And when they saw some of his disciples eat bread with defiled, that is to say, with unwashen hands, they found fault.
3. For the Pharisees, and all the Jews, except they wash their hands oft, eat not, holding the tradition of the elders. [427]
4. And when they come from the market, except they wash, they eat not” (Mark 7:1-4).

The present practice of celebrating the Gahambars.

At present, private individuals or families celebrate these Gahambars. In the case of families, they generally celebrate the six Gahambars of the year during the first year of one’s death in the family circle. They celebrate the Gahambars with the *Yâd* or remembrance of his or her name in the recitals of the prayers. But, besides these private celebrations, there are public celebrations in almost all Parsee towns. In some places, there are, what may be called, “Subscription Gahambars,” where only those who pay their mite, as fixed and arranged, may join. In some places, there are generous donors who celebrate public Gahambars and invite all Parsees of the town to the feast. In case of subscription Gahambars, at times, there are Gahambars of different tradesmen. For example, the Parsee cloth-merchants of Bombay have their own Gahambars. Different Parsee offices have their own Gahambars.

Public Gahambars in Bombay.

In Bombay, the Trustees of the funds and properties of the Parsee Panchayet hold a fund of about Rs. 150,000 made up by public subscriptions. From the income of this fund they celebrate six public Gahambars. They spend Rs. 780 for the celebration of each of the Gahambars. About Rs. 20 to Rs. 25 go for the religious or ceremonial part, and the rest goes in giving a public dinner, called *Niât* (*lit.* caste dinner, to the whole community). A public invitation goes round and from about two to three thousand people take part in the dinner. The first Sir Jamsetjee Jejeebhoy Bart. had great faith in the celebration of the Gahambars. He has set apart a large fund for the celebration of these Gahambars, not only in Bombay but in some of the big Moffusil Parsee centres like Surat, Naosari, Broach, etc.

Gahambars, occasions of communal gatherings.

Of all ceremonial occasions, the Gahambars were considered to be

the principal occasions for ceremonial gatherings. Universal Brotherhood which we often hear spoken of, was one of the [428] principal objects aimed at in the public Gahambar. The rich and the poor—rich and poor not only in wealth but in intellectual knowledge—of the town were expected to meet together and to learn from each other's company what was best in it. The inferiors coming into contact with the superiors learnt from them good manners and the traits of their nobility. The rich came to know the wants of the poor and pondered over their shortcomings which they thought of removing.

7. JASHAN.

Meaning of the word Jashan.

The celebration of an important event or occasion, whether joyful or melancholy, in a religious and solemn way with liturgical services, is known as Jashan. The Jashans are known by special designations according to the occasions which require their celebration. For example, if it is to celebrate the anniversary of the death of a person, it is said to be the "Jashan of A or B's Baj." If it is to celebrate the anniversary of the foundation of a Fire-temple, it is said to be the "Jashan of the Sal-gireh, *i.e.*, anniversary of the Fire-temple." If it is to celebrate a Gahambar or season festival, it is said to be the "Jashan of the Gahambar." The Parsees have celebrated by Jashans, important events like the Golden and Diamond Jubilees of Her late Majesty, Queen Victoria, and the Coronation of Emperor, Edward VII. Similarly they have celebrated Jashans to pray for the suppression of scourges like those of famine and pestilence, mutiny and war.

The word Jashan is another form of Yazashna or Ijashna meaning an homage of praise, from the root *yaz* to praise, to worship. Some derive the word from "*chash*" to taste, to eat, from the fact that the Jashans end by a kind of communion, wherein all the persons assembled partake of the *dron*, the consecrated bread, and *myazda*, the consecrated fruits, and other eatables. Some later Mahomedan authors give the word as "*chashan*" instead of "Jashan," thus suggesting the above derivation of the word from "*chash*" to taste.

What Southey says of Festivals generally is specially true of Parsee Jashans. They, "when duly observed, attach men to [429] the civil and religious institutions of their country; it is an evil, therefore, when they fall into disuse."

The liturgical ceremonies which are generally performed in a Jashan are the following:—1. The Afrinagan. 2. The Baj. 3. The Yasna. 4. The Farokhshi. 5. The Satum.

The last three, or anyone or more of them, may or may not be performed. But the first two are generally performed. Out of these two, the first, *i.e.*, the Afrinagan is indispensably necessary. In fact it is the ceremony of the Jashan or it is the Jashan proper. It is generally performed in a large hall where many people can assemble and witness the ceremony.

Three *kardas* or sections are generally recited in the Afrinagans of the Jashans. Of these three, two that are invariably recited always (except during the 5 days of the Gathas which are the last 5 intercalary days of the year when the Daham Afrinagan is not recited) at the end are the Afrinagans of Daham and Srosh. The first *karda* varies according to the occasion of the Jashan. If the Jashan is for the anniversary of a deceased person, the *karda* of the Afrinagan of Ardafrawash is recited. If it is the anniversary of a Fire-temple or any such institution, the Afrinagan with the Khshnuman of the Yazata, Warharan (who presides over Victory) or with the Khshnuman of the particular Yazata which presides over the day is recited. If it is the Jashan of Gahambar, the Afrinagan of Gahambar is recited. If it is the Jashan of Rapithwin, the Afrinagan of Rapithwin is recited, and so on.

Jashan Holidays.

There are particular Holidays in the year which are specially known as the Jashan Holidays and they are specially known as the Jashans. These Jashans or special Holidays can be divided into three classes.

I. Jashans connected with seasons or season festivals. Under this class fall the Jashans like those of (a) the Gahambars, (b) the Jamshedi Naoroz, (c) Mihragan, (d) Rapithwin, (e) Tiragan, (f) Khordad-Sal. [430]

II. Jashans in honour of the dead. Under this class are included Jashans like those of—(a) The 10 days of the Frawardegan Holidays. (b) the Frawardin Jashans, *i.e.*, the Jashans of ruz Frawardin (the 19th day) and mah Frawardin (the first month). The 19th day Frawardin of each month also is held sacred to the dead, though not to such an extent as the 19th day of the first month and the 19th day of the 9th month (Adar). (c) the Jashans of the 4th, 10th, 30th, and the anniversary day after one's death (Pahl. Vendidad 8:22).

III. The Jashans that have some connection with some historical events in ancient Iran. Some of the Jashans that fall under the first head fall also under this head, *e.g.*, (a) the Jamshedi Nawruz, (b) the Mihragan, (c) the Tiragan.

The object of the public Jashans.

Firstly, the object of most of the public Jashans, *e.g.*, the Jashans of the Season Festivals is to offer thanks to the Almighty for His bountiful blessings and to pray for a continuance of the same. To a great extent they are thanksgiving services.

Secondly, the public Jaahans are intended to cement the tie of brotherhood. They aim at not only physical brotherhood, but spiritual brotherhood. The celebrant says in the recital of the Dibache that the reward of all his prayers may go to the treasury of Ahura Mazda, *i.e.*, for the good of all his fellow creatures. This is what one may call "spiritual socialism."

The Jashan days in a Parsee year.

The following are the Jashan holidays during the year among the Parsees.

I. During the first month FRAWARDIN:

1. Nawruz or the New Year's day. This day corresponded at one time with the Jamshedi Nawruz day (the 21st of March, the day of the Vernal Equinox), but as the Parsees have ceased to observe intercalation since their immigration to India, this Nawruz does not fall on the 21st of March. It is known as the Jamshedi Nawruz day, because, according to Firdausi, king Jamshed of the Peshdadian dynasty first observed it with éclat on the Vernal Equinox day (M. Mohl. I, p. 53). On this day. the Parsees, when meeting each other, perform the hamazor. [431]

2. Rapithwin. On the 3rd day. The word, means the pith (*pithwa*) or the middle portion of the day, the midday being the hottest part of the day. The Jashan day at the season when the sun begins to be hot is called the Rapithwin day. From the New Year's day (the Vernal Equinox), the winter being over, spring sets in and the sun begins to be hotter. The Rapithwin Gah prayer is recited from that day. So, the first of the month would be the proper day for the observation of the Rapithwin Jashan, but the third day Ardwhisht is observed as the day for the celebration, because Ardwhisht is associated with Fire which is the visible form on the surface of the Earth of the heat of the sun.

3. Khordad Sal: 6th day. This day is spoken of in some old books as the Nawruz-i khaç, *i.e.*, the special New Year's day, while the real New Year's day was known as Nawruz-i Âm, *i.e.*, common New Year's day. It was specially (*Khâç*) observed by the King and his nobility. It is said to be the day on which many historical events of old Iran are said

to have happened.¹

4. Jashan of Frawardigan. Frawardin, the 19th day of the first month Frawardin is a Jashan day in honour of all the dead. The Yazata Frawardin presides over the Fravashis or Farohars. So, the day bearing the name of that Yazata occurring in the month which also bears the name of that Yazata is sacred to the memory of the Fravashis of all the dead.² [432]

II. ARDWAHISHT MONTH.

1. Ardwhahisht Jashan. The third day of the second month. Each of the 30 days of the Parsee month bears the name of the Yazata which is believed to preside on that day. Again, each of the 12 months bears the name of the Yazata which is believed to preside on that month. So, that day of the month which bears the name of the Yazata who presides also over the month or whose name is also borne by the month, is held as a sacred Jashan day. So the third day, Ardwhahisht, of the second month Ardwhahisht is the Jashan day of Ardwhahisht.

2. Maidhyozarem Gahambar Jashan days. From the 11th to the 15th day. *Vide* above, Maidhyozarem, in the article on Gahambar.

III. MONTH HORDAD.

Hordad ruz Jashan. The 6th day Hordad of the 3rd month Hordad is the ordinary Jashan day.

IV. MONTH TIR.

1. Maidhyoshahem Gahambar. From the 11th to the 15th day. *Vide* Maidhyoshahem in the article on Gahambars.

2. Tiragan [Tiryân]. On the 13th day Tir of the 4th month Tir. This day is also connected with an historical event in the reign of King Minocheher, when a dispute about the boundary of Iran and Turan was decided by the throwing of an arrow (Tir) by an archer Erekhsha.

1 *Vide K. R. Cama Memorial Volume*, p. 122-29. Dastur Kaikhusrû's paper.

2 It is something like the day of "All soul's day" of the Christians which falls on the second of November. I remember having visited the cemetery of "Pée la Chaise" in Paris on the 1st of November 1887, the day of all saints (Tous saints). What I saw there reminded me of the Frawardigan Jashan of the Parsees of Bombay. I saw hundreds, nay thousands, going to the above cemetery with wreaths and crowns of flowers, real and artificial. In Bombay you see hundreds of Parsees going to the Towers of Silence, which, like the above cemetery of Paris, are situated on a hill, with pieces of sandalwood for the sacred fire burning in a temple on the hill. Hundreds of priests go up the hill with fruits and flowers for the Afrinagan ceremony to be performed there. In Paris I saw a number of Parisians giving their candles to be ignited at the altar. In Bombay, a number of Parsees give pieces of sandalwood to be ignited on the sacred fire.

V. AMURDAD.

Amurdad Jashan. On the 7th day Amurdad of the 5th month Amurdad.

VI. SHAHREWAR.

1. Shahrewar Jashan. On the 4th day Shahrewar of the 6th month Shahrewar.

2. Paitishahem Gahambar. From the 26th day to the 30th day. *Vide* Paitishahem in the article on Gahambars.

VII. MIHR.

1. Mihragan. On the 16th day Mihr of the 7th month Mihr. It is also connected with an event in the reign of [433] Faridoon. It was on this day that he took Zohak prisoner and ascended the throne of Persia.

2. Ayathrem Gahambar. From the 26th to the 30th day. *Vide* Ayathrem in the article on Gahambars.

VIII. ABAN.

Aban Jashan. On the 10th day (Aban) of the 8th month Aban. It is a festival in honour of the Yazata presiding over waters. Hundreds of persons, especially the ladies, go to the sea-shore, to the banks of rivers and say prayers in honour of Aban who presides over water.

IX. ADAR.

1. Adargan. On the 9th day Adar of the 9th month Adar. It is a festival in honour of the Yazata presiding over Fire. Hundreds of persons go to the Fire temples and recite Atash Niyayesh in honour of Adar, the Yazata that presides over Fire.

2. Second Frawardigan Jashan. This second Frawardigan Jashan occurs on ruz Frawardin, the 19th day of Adar, the 9th month. On that day, a number of Parsees go to the Hill where the Towers are built, present pieces of sandalwood to be burnt on the sacred fire there and say their prayers. The priests recite the Afrinagan prayers. This is a day for the remembrance of the memory of all the dead.

This day is important in connection with the dead in another way. When a person dies in a way as would not enable his relations to know the date of the Parsee month on which he died, then the ruz Frawardin, *i.e.*, the 19th of the month is taken to be the date of his death. When even the month is not known, then the 9th month, the Adar, is taken to be the month. For example, suppose a man goes on a voyage and his boat founders and he is lost, and his relatives do not

know the date on which the ship or boat foundered and he died. Then, for the observance of the day and for the performance of the obsequies, they assume Frawardin the 19th day of the month to be the date of the month of his death. Suppose even the month of his death is [434] not known;¹ then they assume Adar, the 9th month, to be the month of his death. So, in such cases they take the 19th of the 9th month to be the anniversaries of the deaths of persons whose date and month of death are not known, (Pahlavi Vendidad, Chap. 8:22). The reason why the month of Adar and not any other month, was assumed to be the month of death. is said to be this that the injunction was made at a time, when, owing to the fact of an intercalary month being added in turn at the end of every 120 years, Adar was considered to be the last month of the year. In the case of persons dying on one of the five Gatha days, *i.e.*, the intercalary days at the end of the year, there being no corresponding day for that day in the subsequent months, the day Frawardin is taken to be the day of his month and the monthly religious ceremonies are enjoined to be performed on that day every month.

X. DAY/DEH.

1-4. Day/Deh-Dadar Jashans. The 10th month Day/Deh is sacred to Ahura Mazda himself. Day-pa-Adar, Day-pa-Mihr, and Day-pa-Den are the *Hamkars* (*lit.* co-workers) of Ohrmazd. So the 1st, the 8th, the 15th, and the 23rd days of the month which bear the names Ohrmazd, Day-pa-Adar, Day-pa-Mihr, and Day-pa-Den are held as the sacred Jashan days of Day/Deh Dadar.

5. Zartosht-no-Diso [Jarthoshtno-Diso]. The 11th day Khwarshed of the 10th month Day/Deh is held to be the anniversary of the death of Zoroaster. So, this day (*diso*) is observed as a Jashan day.

6. Maidyarem Gahambar. From the 16th to the 20th day. **Vide** the word Maidyarem in the article on Gahambars.

XI. VOHUMAN [BAHMAN].

Bahmangan. On the 2nd day (Vohuman) of the 11th month Vohuman. Vohuman being the Yazata that presides over cattle, the Parsees abstain from meat diet on this day and also on the *Hamkar* days of Vohuman during the month, *i.e.*, on the 12th (Mah [Mohor]), 14th (Goshorun) and 21st (Ram) days. [435]

XII. SPANDARMAD.

1. Spandarmad Jashan. On the 5th day (Spandarmad) of the 12th

1 In these days of fast and better travelling and voyaging, such a contingency hardly arises, but in old Iran it very frequently arose.

month Spandarmad. Spandarmad is the Yazata presiding over earth. On this day the Parsees used to get particular Avesta Pahlavi passages written on pieces of paper which were meant as charms for the destruction of small insects like, ants, serpents, etc.¹ They fixed these charm papers on the doors of their houses on this day, so that the house may be free during the year from the pest of these insects. It is also known as Jashan-i-Burzigaran (cultivators), because they used to use the charm for their fields.

2. Avardad Sal gah. On the 6th day (Hordad) of the month Spandarmad. It is said that at one time, when the Parsees of some part of Persia observed intercalation at the end of every fourth year, they added a day at the end of every fourth year and called it by that name. Since they ceased observing intercalation, the Jashan has been attached to the sixth day (Hordad) of this last month, because Hordad is associated with time.

3. Mukhtad Jashan Holidays. From the 26th day to the 5th Gatha day. (*Vide* Frawardigan).

4. Mino-Mahraspand Jashan. On the 29th day. It was supposed to be the day when Zoroaster convinced Gushtasp about the truth of his new religion.

Jashans mentioned by Firdausi.

Firdausi often mentions three principal Jashans of the ancient Iranians. They are:

1. The Nawruz, *i.e.*, the New Year's day, the first day of the first month Frawardin.
2. The Mihragan. Properly speaking, this Jashan, which is that of the autumnal equinox, must fall on the 1st day of the seventh month, *i.e.*, exactly six months after the Jashan of the Vernal Equinox which fell on the 1st day of the 1st [436] month. But the month being Mihr, it was thought proper to celebrate the Jashan on the day which bears the name (Mihr) of the month. Hence it is, that it is celebrated on the 16th day of the month Mihr. It is the Jashan latterly shown as the feast of Mithras.
3. Jashan-i-Sada [Sadeh]. On the 10th day (Aban) of the 10th month Day/Deh, They say that a large fire was kindled in the fields on this day to symbolize the approach of winter which necessitated the kindling of fires.

¹ *Vide* my paper on "Nirang-i-Jashan-i-Burzigaran (*Journal of the Anthropological Society of Bombay*. Vol. V, pp. 398-405). *Vide* my *Anthropological Papers*, Part I., pp. 122-130.

Special Buildings for the celebration of these Jashans.

According to Firdausi, the ancient Iranian Kings took pride in celebrating these Jashans with great eclat. In the years succeeding great wars and victories, the Jashans were celebrated with greater eclat to commemorate the events of victories. Other great events of a King's reign were also commemorated by observing the Jashans of the year with great eclat. There were special spacious buildings attached to Fire temples for the celebration of these Jashans. For example, there were the "Aiwan-i-Nawruz," *i.e.*, The Hall for (celebrating) the Nawruz Jashan, and the Kâkh-i-Sada, *i.e.*, the Mansion for (celebrating) the Jashan of Sada (M. Mohl V. p. 356, 558; VI p. 140, VII p. 36, 402). Kings Shapor I, Behramgore (Bahram V), Noshirvan the Just (Chosroes I), Khosro Parviz (Chosroes II) and Shirin, the queen of Khosro Parvis, are mentioned by Firdausi as celebrating the Jashans of Nawruz and Sada and as endowing the Halls for the celebration of these Jashans (*Ibid.*). The Kings had a public audience of the great men of their country, even of state prisoners, on these Jashan days.

The Jashans of Iran according to Masoudi.

Masoudi mentions the following Jashans of ancient Iran:—1. Nawruz. 2. Mihragan. 3. Abangan. 4. Kaosaj. 5. Azerkhoosh.

The first three are mentioned above. The fourth is not referred to in old Parsee books, but it seems to be a later celebration to mark the departure of winter. The fifth Jashan seems to be, as indicated by its name (Azer), some Jashan connected with fire. [437]

Jashans as described by Al-Biruni.

Al-Biruni's list of Jashans includes most of the Jashans enumerated above. The following are the principal of some of those mentioned for the first time.

1. On ruz Srosh (17th) mah Frawardin (1st month). Albiruni says that the custom of saying grace at meals and eating in silence first came into practice on this day.

2. Jashan-i-Nilofâr, *i.e.*, the Jashan of the Water-lily, on ruz 11th of the 4th month (Tir).

3. The great Mihragan, or ruz 21st of month Mihr, *i.e.*, 5 days after the ordinary Mihragan.

4. Bâhâr Jashan, *i.e.*, the Jashan to mark the approach of spring. It was on the first day of the 9th month Adar. It seems to be the same as that of the Kaosaj of Masoudi.

5. Jashan of Khurram ruz, on the 1st day of the month Day/Deh

which was also called Khur Mah.

Jashans according to other authors.

Various other authors, and among them, Tabari and Mirkhond and the writers of the *Dabestan* and the *Ain-i-Akbari*, refer to the Jashans of the Iranians. Malcolm and Ousely describe at some length the Jashan of Nawruz as observed even now in Persia. (*Vide* my Lecture on અસલી ઇરાની જશને i.e., Ancient Iranian Festivals in my જરથોશ્તી ધર્મ સંબંધી ભાષણો અને વાચ્યો, *Lectures and Sermons on Zoroastrian subjects*, Part III, pp. 121-145).

8. FRAWARDIGAN OR MUKHTAD CEREMONIES.

Frawardigan or Mukhtad Holidays.

The last ten days of the Parsee Year from ruz Ashtad, the 26th day of the last month Spandarmad, to the day of the Wahishtoisht Gatha, are known as the Frawardigan or the Mukhtad Holidays. They are the principal holy days for the remembrance of the dead. In the case of the death of a member of a family during a year, these holidays are particularly observed ceremoniously by the family during the first year. In other years, the ceremonies are often performed in turn jointly by several families [438] that are chips of the same block. For example, A has left behind him three sons, B, C, D. After the death of A, the three sons observe the holidays ceremoniously and perform all religious ceremonies in turn every year in their own houses. In case B has a death in his family in a particular year, he generally prefers to perform the ceremonies at his house, though it be not his turn, because it is the first year of the death of a member of his family. In the case where ceremonies are performed in turns, the others pay their mite as a part of the expenses. For example, if it is B's turn, then C and D pay, a certain sum as their mite for the expenses.

These holidays are known by the following two names of which the first is the older name:—1. The Frawardigan Holidays. 2. The Mukhtad Holidays.

1. Meaning of the word Frawardigan.

The word Frawardigan is the plural of the word *Fraward* which is another form of *fravart* or *fravarti* which word, in its turn, is another form of Avesta *Fravashi*. So the word Frawardigan means the ceremony in honour of the Fravashis, the Farohars or the guardian spirits (*vide* Fravashis). This is the proper Iranian name of the Holidays, as referred to in old Parsee books.

2. Meaning of the word Mukhtad.

At one time, I was inclined to think that the word Mukhtad is a Sanskrit word and that it came to be used in India since the time of the Sanskrit translation of the Avesta texts by Dastur Neryosang Dhaval who lived in about the 12th Century. Neryosang translated the words “*ashaônâm fravashinâm*,” which often occur in the Avesta, by the Sanskrit words “*muktâtmânâ vrudhdhi*” the word *muktâtmâ* in this phrase is supposed to have given to the holidays its name “Mukhtad.” As the last ten days of the year are the days for the remembrance of the Holy Fravashis or Farohars, *i.e.* the guardian spirits of the dead and are therefore called Frawardigan days. so they were also thought to have been known as Mukhtad days from the word *Muktâtmâ*, the Indian or Sanskrit equivalent of the Avesta “*ashaônâm Fravashinâm*.” The Mukhtad holidays were thought [439] to be the days for the remembrance of the Holy souls that have got their *Mukhti* or salvation.

But a Persian Rivayat, known as Nariman Hoshung’s Rivayat leads us to think that the word Mukhtad is a corrupted form of Persian *Mukhtâr*, *i.e.*, supreme, highest, choice. The Holidays are called Mukhtar, *i.e.*, the supreme or the highest, because they are the most principal among all Parsee holidays.

The number of Frawardigan days.

The Frawardin Yasht, (Yasht 13:49), the Denkard (Bk. 8, Chap. 7:10-13),¹ the Din-i-Vajarkard,² the Vajakard-i-Dini,³ the Pahlavi Vendidad (8:22),⁴ the Pahlavi Rivayat, the Nirangistan,⁵ the Sad-dar,⁶ the Persian Rivayats,⁷ and other later books all give 10 as the number of Frawardigan Holidays. *Vide* for the original passages my Gujarati book *An Inquiry from Pahlavi Persian and other Works on the*

1 S. B. E. XXXVII, p. 17.

2 *Ibid.*, p., 440.

3 Dastur Peshotan B. Sanjana’s Text, p, 56.

4 Spiegel’s *Pahlavi Vendidad*, p. 111, l. 4.; Dastur Jamasji’s Gujarati Text, p. 68; Dastur Hoshang’s Text p. 321.

5 Photo-zinco Manuscript, edited by Dastur Darab P. Sanjana, folio 52a, folio 122a. *Le Zend Avesta*, par Darmesteter, Vol. III, p. 99. *The Nirangstan*, translated by Mr. Bulsara, pp. 111-114; Ervad Dhabhar’s Text.

6 (a) The Sad-dar Bundahishn. *Vide* the lithographed Rivayat of Mr. Maneckji R. Unvala, Vol. II. p. 500. (b) The Sad-dar-i-Nazam (chap 41). (c) The Sad-dar-i-Behar-i-Tavil (Chap. 41. Dastur Jamasji’s Gujarati Translation, p. 216). (d) The Sad-dar-i-Nasar (Chap. 37, Mr. Maneckji R. Unvala’s lithographed Rivayat, vol. II, p. 494). *Vide* S. B. E. XXI V, p. 298.

7 (a) Nariman Hoshang’s Rivayat, S. B. E. XXXVII, p. 429. (b) Kama Bohra’a Rivayat. Mr. Maneckji R. Unvalas lithographed Rivayat, Vol II, p. 609.

subject of the Number of Days of the Frawardigan.

Menander Protector, the Byzantine historian, who had lived in the reign of king Mauricius (Mauricius Flavius Tiberius, 582-602) and who refers to these holidays as Furdigan, also [440] gives ten as the number of these holidays.¹ Al-Biruni² (973-1048) also gives the number as ten. Anquetil Du Perron³ who was in India from 1755 to 1761 also says that the Parsees at Surat observed 10 days as the Frawardigan holidays.

Though all the old authorities give 10 days as the period of the Frawardigan holidays, the Parsees seem to have extended the period to 18. They seem to have added at first to the period of 10 days, the day preceding the first day, which was held as a day of preparation for the Holidays. Again during the next seven days, *i.e.*, the seven days of the New Year, there occurred some other great holidays, like the New Year's day or the first day of the New Year, the Rapithwin Jashan on the 3rd day, the Khordad Sal on the 6th day. So these days and the intervening days were subsequently added to the Frawardigan holidays. Then the seventh day seems to have been subsequently added as the Amurdadsal holiday. So now, generally 18 days are observed as the Frawardigan days, though there are families who have reverted to the custom of observing only the original 10 days.

As to what the Fravashis or Farohars are, for whose remembrance the 10 days of the Fravardegan are appointed, see the word Fravashi.

The first five of these 10 days are known as the *Panj-i-keh*, *i.e.*, the lesser five days and the second five, which are the Gatha Gahambar intercalary days, as the *panj-i-meh*, *i.e.*, the greater five days. The latter are held in higher veneration than the first five from the fact (*a*) that they happen to be the last five days of the year, (*b*) that they are, in addition, the days of one of the Gahambers, (*c*) and that they are the intercalary days known as the Gatha days.

The Frawardigan holidays are especially for invoking the Fravashis of the dead.

Though according to the literal meaning of the word, they are the holidays for the invocation of all Fravashis, they are principally for the invocation and remembrance of the Fravashis of the dead (*Vide* the word Fravashi). The [441] Frawardin Yasht (Yasht 13:49) connects them with the dead. They reminded us of the Lerentalia, the Ferolia or the Parentolia of the ancient Romans and the Anthesterion of the

1 *Vide* Darmesteter's *Le Zend Avesta*, Vol. II, p. 503, n. 11.

2 *Albiruni's Chronology of Ancient Nations* translated by Sachau, p. 210.

3 *Zend Avesta*, Tome II. p. 576.

Greeks.

The object of the Holidays.

The object of these Frawardigan holidays is to remember and honour the Farohars or the spirits of the departed dear ones. Of course, the survivors do so on particular occasions like that of the anniversaries of their death, but the Frawardigan days are general holidays for the remembrance of all the departed ones. The Frawardin Yasht which treats of the subject of the Farohars in whose honour the Frawardigan holidays are observed and the Frawardigan ceremonies are performed, thus refers to the subject of remembering the spirits of the dead in these last ten days of the year. It says: "We worship the good, strong, beneficent Fravashis of the faithful, who come and go through the borough at the time of the Hamaspathmaidyem; they go along there for ten nights, asking thus: 'Who will praise us? Who will offer us a sacrifice? Who will meditate upon us? Who will bless us? Who will receive us with meat and clothes in his hand and with a prayer worthy of bliss? Of which of us will the name be taken for invocation? Of which of you will the soul be worshipped by you with a sacrifice? To whom will this gift of ours be given, that he may have never-failing food for ever and ever.'"¹

From the above passage of the Frawardin Yasht (Yasht 13:49-50), we learn that the Fravashis of the dead expect to be invoked by their names being mentioned in the ceremony. Hence it is a custom that in the recital of some of the liturgical ceremonies, especially the Afrinagan ceremony, the names of the deceased members of a family are recited from a list called *nâm-grahan*.

Nam-grahan.

The word *nâm-grahan* comes from Avesta *nâman*, name and *garew*, Sanskrit *grah*, German *ergreifen*, to gripe or take. So *nâm-grahan* means "taking or remembering the names." Every family has a manuscript book or list known by that name. It contains the [442] names of the departed ones of the family. Those who have died lately head the list. The priest while reciting the Pazand Dibache in the Afrinagan, Satum, Farokhshi, etc., recites all the names in this list. At first he mentions or invokes the name of the particular deceased in whose honour the ceremony is performed and then the names of other deceased of the family. He then recites also the names of some of the departed Zoroastrian worthies of ancient Iran and of India who have done valuable services to their community.

¹ S. B. E. XXIII, p. 192: Yasht 13:49-50.

The Holidays just before the Spring.

In ancient Iran, the holidays, which occur at the end of the year on the Hamaspathmaidyem Gahambar days, happened to come just before the setting in of the season of spring. On the expiry of these 10 holidays, the New Year began with the Vernal equinox. It is not so now because since the Arab conquest of Persia, the Parsees have not been regularly keeping the leap year and so they are now much backward in their calculation of time. Among the Romans and the Greeks also their holidays to commemorate their dead occurred just before the commencement of the spring. As Prof. Darmesteter says: "The souls of the dead were supposed to partake of the new life then beginning to circulate through nature that had also been dead during the long months of winter."¹

Importance of the Holidays.

Memory and Hope both render these holidays very important—Memory for the dead and Hope for our future. They are the days for keeping green the memory of those who have departed and have laid us under some obligation either by their love and affection or by their services—services physical, mental, or pecuniary. People march and march during the whole of the year in their different avocations and walks of life. The arrival of these days calls upon the Zoroastrians to halt in their march, to cast an eye over the past and to look to the future. Looking to the past, they have not only to remember with respect, esteem, and gratitude their departed dear ones and their departed worthies, but to remember or to take stock of their actions [443] during the year and then to hope for the better in the future. They have to reflect that as they have to remember with esteem and gratitude their departed dear ones, a time will come in future when they in their turn will expect to be remembered by their surviving dear ones. So, it would be well if they behaved in a way as would enable them to be remembered. with esteem and gratitude.

The principal observance during the Holidays.

The principal observance during the holidays in several Parsee families is that known as *Mukhtad-mâldvâ*, i.e., to arrange or lay the *Mukhtad*, signifying thereby to make arrangement for remembering the pious souls of the dead. The house is cleaned and generally white-washed before the holidays. If not the whole house, at least a room where the ceremony is to be performed is washed clean with water and white-washed. Then on an iron stand or on a table, water pots or flower-vases containing water and flowers are arranged. The place where the ceremonies are performed is lit up at night. Fire is kept

1 S. B. E. XXIII, p. 192 n. 1.

burning with fragrant sandalwood and frankincense for a great part of the day. Visitors at the house during the holidays feed the fire with their own hands and remember at the same time the particular departed ones, to pay homage to whose memory they have paid the visit. The whole process is spoken of in the *Vajarkard-i-Dini* as “*Hurak itibunashna*”, *i.e.*, “to get a *hurak* seated.” The Rivayats speak of it as “*hurak nashândan*” which is a Persian rendering of the Pahlavi expression. In ordinary phraseology, one hears the word “*Doslâ mâdvâ*,” *i.e.*, to arrange for the *Dosla* or the *Dosâ*, *i.e.*, the old because it is the old who generally form a large number of the dead.

The *Vajarkard-i-Dini* thus refers to the subject: “During these ten days, in the house or in the Fire-temple a clean and decent place may be chosen, away from the place where women seclude themselves during their menses. There a “*hurak*” may be arranged and it is necessary that a good deal of the Avesta may be recited there. For the first 5 days, the Yasna in honour of Srosh must be recited. The chapter of *Frâ-mraôt*, which is [444] one of the chapters of the Yasna,¹ must be recited during the first five days with the Baj of Ardafarosh. If that is not possible, *i.e.*, if one cannot recite the chapter, he must recite 1,200 Ashem Vohus with the Baj of Ardafarosh. During the five days of the Gatha, the Has or chapter of the Gathas must be recited If that is not possible, there is no help for it, and one must recite 1,200 Yatha Ahu Vairyos.”²

The *Sad-dar-i-Bundahishn* says: “During the Frawardigan holidays, the spirits of the dead revisit this world. They go to their respective houses.... There it is necessary for men to burn fragrance over fire during these ten days and remember their dear departed ones. They must perform the Dron, Myazd, and Afrinagan ceremonies and recite the Avesta. The spirits of the dead are thereby felicitated and pleased and they bless (the living ones). Again it is necessary that during these ten days men must perform works of charity and be free from other ordinary work. The spirits of the dead thereby return (to their mansions in heaven) much pleased and they bless (their living dear ones).”³

Al-Biruni's reference to the custom.

Al-Biruni describes what was done in Persia during the holidays about 900 years ago. His description, though not quite correct, gives one an idea of what was done and is still being done. He says: “During

1 Ha 20.

2 Translated from Dastur Peshotan's Text, p. 66.

3 Translated from the *Sad-dar* in the lithographed Rivayat, by Mr. M. R. Unvala , Vol. II p. 500.

this time, people put food in the hall of the dead.... They fumigate their houses with juniper, that the dead may enjoy its smell. The spirits of the pious men dwell among their families, children, and relations, and occupy themselves with their affairs, although invisible to them.”¹

Anquetil’s reference to the custom at Surat.

Anquetil Du Perron refers to these holidays as observed by the Parsees of Surat 150 years ago, and says, that “they give them (the Fravashis) the most magnificent reception. The houses are purified and decorated. They do not go out of the houses.”² [445]

With reference to the custom referred to by Anquetil of not going out of the house during the ten days, we find, that that was due to the injunction, that these days may be best spent in prayers and works of charity. We learn from Menander, referred to above, that it was for this reason, that Noshirvan (Chosroes I) had postponed the reception of the embassy of the Roman Emperor.

Technical terms about the arrangement of flowers, etc.

One comes across the following words in the matter of the observation of the Frawardigan Holidays:—

1. Hurak.	3. Tâkchê
2. Mâchi.	4. Behrun.

We will explain these words and the observances connected with them.

Hurak.

The whole ceremony and process of arranging stands or platforms on which flowerpots or vases are arranged to hold water and flowers is spoken of as “*hurak itibunashna*,” in the Pahlavi *Vajarkard-i-Dini* and “*hurak nishândan*” in the Rivayat. The expression means “to get the hurac seated, arranged or placed.” The signification of the word “*hurak*” is not clear. It seems to be the diminutive of Persian *hur*, *i.e.*, the sun. As the place is decorated with flowers and kept perfumed with burning fragrant sandalwood and frankincense, it was perhaps thought to be a place reminding of the heavens wherein the sun moved, and so it was perhaps taken as a small model of the paradise. The Parsee books speak of several paradises one of which was *Khwarshed-paya*, *i.e.*, of the dignity or the place of the sun. In this connection, one must remember that in the preparation and

1 *Albiruni’s Chronology of the Ancient Nations*, by Dr. Sachau, p. 210.

2 Tome II, p. 574.

arrangement of the stand for the flower-pots, etc., some give a part of the stand the form of a *gumbad*, or the dome of the sky.

Mâchi or the stand for the Mukhtad ceremony.

The metallic stand on which the flower-pots or vases are arranged is called *mâchi*, a word that comes from Sanskrit *manch* meaning “a raised seat, a dias, a platform, a seat of honour, or a throne.” It is so-called because it is generally on a raised [446] stand that the flower-pots are arranged. The flowers, fruits, and the water of the vases may be, and are generally, changed every day, but they must be changed at least at the interval of every five days. Each of those days when they must be changed is also called a *mâchi* from the fact that all the things on the *mâchi* or stand have to be changed on that day. So, during the period of the 18 days of Mukhtad as now observed by most of the Parsees, there are three such *Mâchis* or days for the change of the fruits, flowers, etc. As observed generally now, the holidays begin on the 25th of the last month of the Parsee year. So, the first *mâchi* is five days after that, *i.e.*, on the 30th day of that month. The next *mâchi* called *vachli mâchi*, *i.e.*, the middle *mâchi* falls on the Wahishtoish Gatha, the last of the five intercalary days. The last *mâchi* occurs on the fifth day of the first month of the new year.

The short prayer recited in honour of the Fravashis at the place for the Mukhtad ceremonies is known in some books as *mâchi nô nemaz* or *namaskâr*, *i.e.*, the prayer of homage of the *mâchi*. The formula recited is very short. It says: “I repent of all my sins. We praise the good, brave, beneficent Fravashis of the holy.”

Tâk or Tâkchê.

In former times and even now in some houses, they arranged the flower-pots, etc., in a large niche in a wall. Some houses formerly had a special room built for the purpose of the Frawardigan ceremonies wherein was provided a large arch-like niche with a platform. This arrangement was called a *tâk*, *i.e.*, an arch. The word *tâkchê* occasionally used is a diminutive of the word *tâk*, as *bâgichê* of *bâg* (garden).

Behrê or the quota for each Fravashi.

The Mukhtad ceremonies are generally performed, as said above, in one branch of the different branches of the chief stock. For example, A dies leaving three sons B, C, and D. Then the three sons, B, C, and D generally perform the mukhtad ceremonies in turn every year. If it is B's turn, he performs the ceremonies at his house, and C and D generally pay their share of the expenses. [447] One whose turn it is to perform the ceremonies generally bears the brunt of the

expenses, the others merely paying a fixed sum as their share. Now for each dead of the family, there is at present the custom to place a separate vase or flower-pot for several number of years after death. For example, suppose a family has lost two persons during a year, say E. and F. Then two separate vases each in memory of E. and of F. are provided and placed on the stand or on the platform. That particular flower-pot or vase is said to be E or F's *Behru*. Some say that the word comes from Gujarati *be*, *i.e.*, two and means a pair, because the flower-pots in honour of each dead are generally two or more, one placed over the other. But I think, that the word is Persian "*behreh*" meaning "share." The head of that branch of the family in which death has occurred during the year has to pay his quota in the general expenses. He pays that either in money or in kind, by sending some articles of food. etc. He likewise provides a flower-pot which also is considered something like paying in kind. It is the payment of a pot for putting the flowers in. So it is called *Behreh*, *i.e.*, share. After a certain number of years after, one's death, which is not fixed, they discontinue providing a separate flower-pot for each particular deceased.

During these holidays, the family is visited by near friends and relatives. They carry strings of flowers called *jâri* with them and place them upon the *behrân*, *i.e.*, flower-pot or pots of the particular departed whom they wish to honour. This is particularly done during the first year after the death of a person.

Flowers and the Memory of the Dead.

Flowers play a very important part in all Parsee religious ceremonies. In the ceremonies for the dead, they are necessary in the Afrinagan ceremony. During the Mukhtad holidays flowers are kept day and night at a separate place of room in the house set apart, as said above, for the purpose of the ceremony. Almost all nations connect the memory of the dead with flowers. One of the objects of the ceremonies in honour of the dead is to keep their memory "green." So, the flowers are the best medium which could symbolically help men to keep the memory green. [448]

(a) In the Frawardin Yasht which treats of the Fravashis, the Fravashis or the spirits of the holy dead are associated with water and trees (Yasht 13:147). There we read:

"May the good waters and the plants and the Fravashis of the faithful abide down here! May you be rejoiced and well received in this house! Here are the Athravans of the countries, thinking of good holiness. Our hands are lifted up for asking help, and for offering a sacrifice unto you,

O most beneficent Fravashis!"¹

In this passage we find, as it were, the origin of the Mukhtad ceremonies in which water and flowers are placed in a particular clean part of the house, where they are invoked and praised by the Athravans or Fire-priests in the presence of fire and where the members of the family, offering flowers and fruits, ask the blessings of their dear departed ones.

(b) Water, flowers or plants, and the holy Fravashis are associated together in the Ohrmazd Yasht also (Yasht 1:9). There, we find Ahura Mazda saying: "Worship me, O Zarathushtra, by day and by night, with offerings of libations well accepted. I will come unto thee for help and joy, I, Ahura Mazda; the good holy Sraosha will come unto thee for help and joy; the waters, the plants, and the Fravashis of the holy ones will come unto thee for help and joy."² There are several passages in the Avesta that point to water and flowers as the objects of nature with which the Fravashis of the dead are pleasantly associated.

(c) In the *Arda Viraf-Nameh*, the souls of the departed are represented as moving in the midst of fragrant trees on the third dawn after death. There we read: "On the third dawn, that pious soul moved about in the midst of sweet-scented trees" (Viraf-Nameh, 4:15). The fruits, flowers, water, etc., that are offered and over which the prayers are recited form the myazd, in the midst of which the Fravashis take delight to move about. We read in the Frawardin Yasht (Yasht 13:64): "We worship the good, strong, beneficent Fravashis of the faithful. ... who run by tens of thousands into the midst of the Myazdas."³ [449]

The Frawardigan ceremonies symbolize some religious ideas.

Just as the Christmas tree and the representation of the stable and the farm-yard during the Christmas holidays remind one of the events of Christ's life, the decoration of flowers, etc. at the place of the Mukhtad and the remembrance of the Fravashis of the dear departed ones in connection with the fragrant flowers reminds the survivors of the past righteous deeds of some of their fore-fathers, deeds which have spread moral and spiritual perfume as strong or rather stronger than that of the flowers there.

The prayers recited at the place during the holidays.

During these holidays the prayers that are generally recited by the

1 S. B. E. XXIII, p. 228; Yasht 13:147.

2 S. B. E. XXIII, pp. 25-26.

3 S. B. E. XXIII, pp. 195-196.

priests at the house of the laymen where the Mukhtad ceremonies are observed are: (1) The Afrinagan, (2) the Satum, and (3) the Farokhshi. In the Fire-temple, they perform the Baj ceremony. The Yasna, the Visperad, and the Vendidad ceremonies are not performed in all cases but only in those where the family is able to afford to pay for them. The laymen are required to recite during the first 5 days. the Ha of Framraot (Yasna Ha. 20) If a person is illiterate and is not able to recite that Ha, he may recite the short Ashem Vohu prayer 1,200 times with its Baj.

During the next 5 days of the Gathas, the laymen are required to recite the *Gâthâ nâ Hâ*, i.e., the chapters of the Gathas, each Gatha having to be recited on the particular day which bears its name. For example, on the first of the second batch of 5 days, which is the Ahunwad Gatha day, they are to recite the seven chapters of the Ahunavaiti Gatha, and so on. If a layman is unable to recite these Gathas, he may recite the Yatha Ahu Vairyō prayer 1,200 times with the proper Baj.

Frawardiân [Fravardian].

Again there is another ceremony known as *Frawardiân*, a word which is another form of Fravardigan, which is at times performed during the Fravardigan holidays by the priests at the Fire temples in honour of a particular dead person. The ceremony consists in the recital and the performance of the following prayers and ceremonies: [450]

(a) The recital of two Yasnas by the priests at the Fire-temple during each of the ten days. During the first five days (*panj-i-keh*), except that on the fourth day (ruz Mahraspand), one of the two recitals is in honour of Srosh and the other in honour of Ardafarosh. On the fourth day, one is in honour of Srosh and the other in honour of the Yazata Mahraspand. During the second five days, (the *panj-i-meh*) one of the two recitals is in honour of Srosh and the other, for any four days, in honour of the Gathas, but on one of the days in honour of the Gahambar (the Visperad).

(b) The recital of 5 Vendidads on the following days:

1. Ruz Ashtad, the 26th day of the last month; the first of the 10 days.
2. Ruz Mahraspand, the fourth of the 10 days.
3. Gatha Ahunawad, the 6th of the 10 days.
4. Gatha Wohukhshathra, the 9th of the 10 days.
5. On ruz Spandarmad, the fifth in the new year.

Then, there are the further recitals of one Yasna, the Yasna of Rapithwin on the 3rd of the 1st month Frawardin, of two on the 5th day and of one on the 6th day.

IX. FIRESHTE [FARESTÂ].

Meaning of the word *Fireshte*.

Fireshte is Persian *Firasta* or *Firashta*, lit., one who is sent, meaning a messenger. and then an angel. Fireshte or more correctly Firasta is the later name of the Avesta word Yazata. Fireshte is the name given to a ceremony wherein all the angels (Firastas), or more properly, all the Yazatas are invoked. There are a large number of Yazatas, but 33 are specialized. Of these thirty-three, thirty are those that preside over the 30 days of the month and three are extra. The Fireshte ceremony consists in reciting 33 Afrinagans and 33 Bajs with their proper ritual in honour of, and with the Khshnuman of, these 33 Yazatas or angels. It would take very long for one pair of priests, who ordinarily perform the Afrinagan ceremony, to recite the 33 *kardas* or sections of the Afrinagans for 33 Yazatas, so more than [451] one pair, generally two, are engaged to perform the ceremony. The same is the case with the Baj. More than one priest, generally three or four, are engaged in reciting, with its ritual, the Baj in honour of and with the Khshnuman of these 33 Yazatas.

The Fireshta ceremony is almost always performed on merry occasions, like marriage, birthday, Naojote, the occupation of a newly built house, the fulfilment of a long cherished object. The ceremony is intended either as thanksgiving for desires fulfilled or for invoking blessings of the Almighty and His Higher Intelligences upon particular events of a man's life or his undertakings. We will here shortly describe what a Yazata is and then enumerate them.

Yazata.

The word Yazata comes from the Avesta root *yaz*, Sanskrit *yaj*, "to praise, to invoke." So it means, "one worthy of being praised." These Yazatas are all believed to be spiritual beings. Zoroaster was the only man, who, in the literal sense of the word "Yazata," was considered to be worthy of being praised, adored or invoked. So he is considered to be an Yazata (Yasna 16:12), a great and known Yazata (Yasna 7:21; 3:21). In some later writings, supposed to serve as Avesta amulets, even King Faridoon, who was supposed to be a great physician has been raised to the rank of Yazata (Westergaard, Text of the Avesta, p. 331: Miscellaneous Fragments II).¹

1 Vide my paper on "An Avesta amulet." *Journal of the Anthropological Society of*

The classes of the Yazatas according to the Avesta.

The Avesta speaks of two classes of the Yazatas: I. The Yazatas of the spiritual world (*Yazatanâm mainyavanâm*: Yasna 3:4). II. The Yazatas of the physical world (*Yazatanâm gaêthyânâm*: Yasna 3:4).

The Yazatas of the spiritual world.

All Yazatas are spiritual beings. So, by the phrase “the Yazatas of the Physical World” are meant those that are believed to preside over grand physical objects of Nature. The 30 Yazatas, [452] whose names are borne by the 30 days of the months, may be divided into these two classes as follows:—

I. Yazatas of the Spiritual World.*	II. Yazatas of the Physical World.
1. Ohrmazd.	9. Adar.
2. Vohuman.	10. Aban.
3. Ardwhisht.	11. Khwarshed.
4. Shahrewar.	12. Mah.
5. Spandarmad.	13. Tir/Tishtar.
6. Hordad.	14. Goshorun.
7. Amurdad.	16. Mihr.
8. Day-pa-Adar.	19. Frawardin.
15. Day-pa-Mihr.	21. Ram.
17. Srosh.	22. Wad/Gowad.
18. Rashnu.	27. Asman.
20. Warharan.	28. Zam.
23. Day-pa-Den.	30. Anagran.
24. Den.	
25. Ard.	
26. Ashtad.	
29. Mahraspand.	

* The figures before these names give the number of their position in the regular order in which they give their names to the 30 days of the month.

The Yazatas of this class are those that preside over abstract ideas, most of which are moral characteristics. The first seven Yazatas of this class stand higher in the rank of the Yazata and are also called the Amesha-Spentas.

The Amesha-Spentas.

The word literally means the “Immortal Bountiful ones.” They are seven in number including Ahura Mazda himself who is one of them. As archangels, their number corresponds to that of the seven Shadim or archangels of the Jews. Dr. Kohut says on this subject: “It is

Bombay, Vol V. No.7, pp. 418-21. *Vide my Anthropological Papers*, Part I.

worthwhile observing that the fluctuation between the number six or seven of the Amesha Spentas, indeed, according [453] as Ahuramazdao is counted or not in the class of the Amesha Spentas of Yst. I, 36; 2, 1-6, recurs also in the Jewish scriptures. Thus the so-called Jerusalem Targum to Deuter. 34, 6 and the book of Enoch C. 20, where the list of "watching angels" is counted up — gives only six; the book of Tobit 12, 15 and of Enoch C. 90, 21 gives seven as the number of the Archangels."¹

The Christian Scriptures also speak of seven Archangels or the Seven Spirits of God. We read in the Revelation (5:6): "And I beheld, and, lo, in the midst of the throne and of the four beasts, and in the midst of the elders, stood a Lamb as it had been slain, having seven horns and seven eyes, which are the seven Spirits of God sent forth into all the earth." (*Vide* also, *Ibid.* XV, 1 and 6-7 ; XIII, 2; XVI, 1; Zechariah 4:10). The Apocryphal Book (Tobit ch. 12:15) also speaks of "The seven holy angels which go in and out before the glory of the Holy one." So Milton sings:

The seven who in God's presence nearest to His throne
Stand ready at command.

The "Divine Powers" of the Neo-Platonic philosophy of Philo Judæus, who also corresponded to the Amesha Spenta of the Avesta and who stood "closest to the self-existent,"² were six in number. Including the self-existent, their number was seven. The Gnostics also said that "the universe was created by the Seven Great Angels."

These seven Amesha Spentas had the rest of the Yazatas with them as their Hamkars, *i.e.*, Co-operators or Co-laborateurs.

Hamkars. Their groups.

The word *Hamkar* means co-laborateur. The thirty Yazatas or angels that preside over the 30 days of the month are said to be the Hamkars of the first seven of those who are the Amesha Spentas or the Archangels. They are grouped as Hamkars or co-laborateurs, [454] because, to a certain extent, in their sphere of work, they are supposed to have some connection. The following list gives the groups of these Hamkars:—

Ohrmazd—	Day-pa-Adar, Day-pa-Mihr, Day-pa-Den.
Vohuman—	Mah, Goshorun, Ram.

1 The Jewish Angelology and Demonology based upon Parsiism translated from the German of Dr. Kohut by K. R. Cama, p. 4, n.

2 Drummond, James. *Philo Judæus; Or, The Jewish-Alexandrian Philosophy in Its Development and Completion*, Vol. II. London: Williams and Norgate, 1888, pp. 82-83.

Ardwahisht—	Adar, Srosh, Warharan.
Shahrewar—	Khwarshed, Mihr, Asman, Anagran.
Spandarmad—	Aban, Den, Ard (Ashisang), Mahraspand.
Hordad—	Tir/Teshtar, Ardafravash (Frawardin), Wad/Gowas.
Amurdad—	Rashnu, Ashtad, Zam (Zamyad).

Thus, Day-pa-Adar, Day-pa-Mihr, Day-pa-Den are spoken of as the Hamkars or co-labourateurs of Ohrmazd; Mah, Goshorun, Ram of Vohuman and so on. This Hamkarship of co-labour is, as it were, recognized even in practice. For example, the Ameshaspand Vohuman, presides over cattle. So many an orthodox Parsee, out of respect as it were for this Ameshaspand, abstains from meat diet not only on the ruz Vohuman, *i.e.*, the second day of each month, but also on the days of his co-labourateurs, Mah, Goshorun, Ram, *i.e.*, the 12th, 14th and 21st days of each month. Some abstain from meat diet also on the days next to these four, *i.e.*, the 3rd (Ardwahisht), the 13th (Tir/Teshgtar), the 15th (Day-pa-Mihr) and the 22nd (Wad/Gowad), because in a big city like Bombay, they know that the goats or sheep are slaughtered a day previous. If they were to eat meat on, say, ruz Ardwhisht (the 3rd day) they would virtually be eating the meat of the cattle slaughtered on ruz Vohuman (the 2nd day), for the Yazata presiding on which they wanted to show their respect. Some abstain from meat diet during all the 30 days of the 11th month which bears the name Vohuman.

Take another practical example of Hamkarship. The Ameshaspand Ardwhisht, presides over Fire. So, the third day of every month is held sacred to fire. The Fire-temples are lighted more than usual on that day and the sacred fire is at times fed with a larger quantity of sandalwood. The temples are visited in a greater number on that day than usual by the [455] worshippers. Many an orthodox family abstains on that day from frying dried fish which gives a little stench when placed on fire. Now all those observances are also observed on the days Adar, Srosh, and Warharan (the 9th, 17th, and the 20th day) which bear the names of the Yazatas that are the Hamkars or co-labourateurs of Ardwhisht. In the Afrinagan of Dahman and in the Afrin of Dahman, these Hamkars or the Yazatas that are supposed to be co-labourateurs are remembered and commemorated together.

Hamkar, a technical term for the priestly class.

The word Hamkar has come to assume a technical meaning in a town like Naosari which is the head quarters of the priesthood. There, all the qualified priests are spoken of as Hamkars or co-labourateurs. Really speaking, members of all professions are the Hamkars of that

profession, but in Naosari, the headquarters of the priests, the members of the priestly profession are particularized as Hamkars. On certain solemn occasions, solemn dinners are given to all the qualified priests (Hamkars) of the town. These dinners also have therefore come to assume the name of *Hamkâr* or of *Hamkâr-sâth*, i.e., the whole company of co-laborateurs. In Naosari, when one says "There is *Hamkâr-sâth* today," he means "There is a dinner for all the qualified priests today."
